BYTE®

the small systems journal

APRIL 1982 Vol. 7, No. 4
$2.95 in USA
$3.50 in Canada/£1.85 in U.K.
A McGraw-Hill Publication

ACCESS CENTER

IXO TELECOMPUTING SYSTEM


HUMAN FACTORS ENGINEERING

IXO TELECOMPUTING SYSTEM

A new small computer that won't limit you tomorrow



New Cromemco System One shown with our high-capability terminal and printer.



Expandability

Here's a low-priced computer that won't run out of memory capacity or expandability halfway through your project.

Typically, computer usage tends to grow, requiring more capability, more memory, more storage. Without a lot of capability and expandability, your computer can be obsolete from the start.

The new System One is a real building-block machine. It has capability and expandability by the carload.

Look at these features:

- **Z80-A processor**
- **64K of RAM**
- **780K of disk storage**
- **CRT and printer interfaces**
- **Eight S-100 card slots, allowing expansion with**
  - **color graphics**
  - **additional memory**
  - **additional interfaces for telecommunications, data acquisition, etc.**
- **Small size**

GENEROUS DISK STORAGE

The 780K of disk storage in the System One Model CS-1 is much greater than what is typically available in small computers. But here, too, you have a choice since a second version, Model CS-1H, has a 5″ Winchester drive that gives you **5 megabytes** of disk storage.

MULTI-USER, MULTI-TASKING CAPABILITY

Believe it or not, this new computer even offers multi-user capability when used with our advanced CROMIX* operating system option. Not only does this outstanding O/S support multiple users on this computer but does so with powerful features like multiple directories, file protection and record level lock. CROMIX lets you run multiple jobs as well.

In addition to our highly-acclaimed CROMIX, there is our CDOS*. This is an enhanced CP/M† type system designed for single-user applications. CP/M and a wealth of CP/M-compatible software are also available for the new System One through third-party vendors.

COLOR GRAPHICS/WORD PROCESSING

This small computer even gives you the option of outstanding high-resolution color graphics with our Model SDI interface and two-port RAM cards.

Then there's our tremendously wide range of Cromemco software including packages for word processing, business, and much more, all usable with the new System One.

ANTI-OBSOLESCENCE/LOW-PRICED

As you can see, the new One offers you a lot of performance. It's obviously designed with anti-obsolescence in mind.

What's more, it's priced at only $3,995. That's considerably less than many machines with much less capability. And it's not that much more than many machines that have little or nothing in the way of expandability.

Physically, the One is small — 7″ high. And it's all-metal in construction. It's only $14\frac{1}{8}$″ wide, ideal for desk top use. A rack mount option is also available.

CONTACT YOUR REP NOW


Get all the details on this important building-block computer. Get in touch with your Cromemco rep now. He'll show you how the new System One can grow with your task.


*CROMIX and CDOS are trademarks of Cromemco Inc.
†CP/M is a trademark of Digital Research



Circle 469 on Inquiry card.







CROMIX*— Cromemco's outstanding UNIX†–like operating system

CROMIX is just the kind of major development you've come to expect from Cromemco. After all, we're already well-known for the most respected software in the microcomputer field.

And now we've come up with the industry's first UNIX-lookalike for microcomputers. It's a tried and proven operating system. It's available on both 5" and 8" diskettes for Cromemco systems with 128K or more of memory.

Here are just some of the features you get in this powerful Cromemco system:

- Multi-user and multi-tasking capability
- Hierarchical directories
- Completely compatible file, device, and interprocess I/O
- Extensive subsystem support

FILE SYSTEM

One of the important features of our CROMIX is its file system comprised of hierarchical directories. It's a tree structure of three types of files: data files, directories, and device files. File, device, and interprocess I/O are compatible among these file types (input and output may be redirected interchangeably from and to any source or destination).

The tree structure allows different directories to be maintained for different users or functions with no chance of conflict.

PROTECTED FILES

Because of the hierarchical structure of the file system, CROMIX maintains separate ownership of every file and directory. All files can thus be protected from access by other users of the system. In fact, each file is protected by **four separate access privileges** in each of the three user categories.

TREMENDOUS ADDRESS SPACE, FAST ACCESS

The flexible file system and generalized disk structure of CROMIX give a disk address space in excess of one gigabyte per volume — file size is limited only by available disk capacity.

Speed of access to disk files has also been optimized. Average access speeds far surpass any yet implemented on microcomputers.

'C' COMPILER AVAILABLE, TOO

Cromemco offers a wide range of languages that operate under CROMIX. These include a high-level command process language and extensive subsystem support such as COBOL, FORTRAN IV, RATFOR, LISP, and 32K and 16K BASICs.

There is even our highly-acclaimed 'C' compiler which allows a programmer fingertip access to CROMIX system calls.

THE STANDARD O-S FOR THE FUTURE

The power and breadth of its features make CROMIX the standard for the next generation of microcomputer operating systems.

And yet it is available for a surprisingly low $595.

The thing to do is to get all this capability working for you now. Get in touch with your Cromemco rep today.

*CROMIX is a trademark of Cromemco, Inc.
†UNIX is a trademark of Bell Telephone Laboratories



Circle 470 on inquiry card.


In The Queue


BYTE Volume 7, Number 4 April 1982

Features

Reviews


Nucleus


Page 40



Page 50



Page 56


Page 76





In This Issue

As computer technology continues to make inroads into our lives, the man/machine interface assumes greater importance in the total system design. Human-factors engineering, our theme this month, is the discipline concerned with the need for friendly computers. Our cover, photographed by Paul Avis, features a new, user-friendly product, the IXO Telecomputing System. For a detailed description of this hand-held terminal see Chris Morgan's editorial.


To help you make your systems user-friendly, we present "A Human-Factors Style Guide for Program Design" by Henry Simpson and "Designing the Star User Interface" by Dr. David Canfield Smith, Charles Irby, Ralph Kimball, Bill Verplank and Eric Harslem. In "A Human-Factors Case Study Based on the IBM Personal Computer," Robert G. Cooper Jr., Paul Thain Marston, John Durrett, and Theron Stimmel discuss the Personal Computer from a human-factors perspective. Steve Ciarcia demonstrates how to use infrared systems, William Barden Jr. presents a collection of projects for the TRS-80 Color Computer, Gregg Williams treats us to a sneak preview of Epson's new portable computer, and Bob Katz reviews the Hewlett-Packard Interface Loop.

BYTE is published monthly by BYTE Publications Inc, 70 Main St, Peterborough NH 03458, phone (603) 924-9281, a wholly-owned subsidiary of McGraw-Hill, Inc. Address subscriptions, change of address, USPS Form 3579, and fulfillment questions to BYTE Subscriptions, POB 590, Martinsville NJ 08836. Second class postage paid at Waseca, Minnesota 56093 - USPS Publication No. 528890 (ISSN 0360-5280). Canadian second class registration number 9321. Subscriptions are $19 for one year, $34 for two years, and $49 for three years in the USA and its possessions. In Canada and Mexico, $21 for one year, $38 for two years, $55 for three years. $43 for one year air delivery to Europe. $35 surface delivery elsewhere. Air delivery to selected areas at additional rates upon request. Single copy price is $2.95 in the USA and its possessions, $3.50 in Canada and Mexico, $4.50 in Europe, and $5.00 elsewhere. Foreign subscriptions and sales should be remitted in United States funds drawn on a US bank. Printed in United States of America.

BYTE® is available in microform from University Microfilms International, 300 N Zeeb Rd, Dept PR, Ann Arbor MI 48106 USA or 18 Bedford Row, Dept PR, London WC1R 4EJ England.



Office hours: Mon-Thur 8:30 AM - 4:30 PM, Friday 8:30 AM - Noon, Eastern Time





"...stands well above other S-100 graphics displays in its price and performance range."
BYTE, Product Review



"...better monochromatic ...display...."
ELECTRONIC DESIGN, 1981 Technology Forecast

MICROANGELO

HIGH RESOLUTION GRAPHICS SINGLE BOARD COMPUTER
512 x 480 resolution black and white **and** vivid color displays

RS-170 composite or direct drive output


Local or external sync generation

4 Mhz Z80 microprocessor

60 hertz real-time clock

8 level interrupt tie-in

IEEE S100 bus compatible



Light pen interface

Time multiplexed refresh

4K resident Screenware™ Pak I operating system

32K RAM isolated from host address space

High speed communications over parallel bus ports

Screenware™ Pak I

A 4K byte operating system resident in PROM on MicroAngelo™. Pak I emulates an 85 character by 40 line graphics terminal and provides over 40 graphics commands. Provisions exist for user defined character sets and directly callable user extensions to Screenware™ Pak I.

Screenware™ Pak II

An optional software superset of Pak I which adds circle generation, polygon flood, programmable split screen for separate graphics and terminal I/O, relative coordinates, faster vector and character plotting, a macro facility, full UCSD Pascal compatibility, and more.

And now...COLOR!!

The new MicroAngelo™ Palette board treats from 2 to 8 MicroAngelos as "bit planes" at a full 512 x 480 resolution. Up to 256 colors may be chosen from 16.8 million through the programmable color lookup table. Overlays, bit plane precedence, fade-in, fade-out, gray levels, blinking bit plane, and a highly visual color editor are standard.

Ask about our multibus and RS-232 versions.



Circle 363 on inquiry card.

12310 Pinecrest Road • Reston, VA 22091 • (703) 476-6100 • TWX: 710-833-0684

Editorial

A Revolution in Your Pocket

by Chris Morgan, Editor in Chief

Imagine a terminal that costs about $500 and can:

- access the Source, Compuserve, Dow Jones, or other remote database or computer services
- automatically handle the protocols to access these services so that you need only enter your password to be online
- have a full ASCII character set
- have a built-in modem with autodialer and full- and half-duplex capability
- be able to emulate other terminals
- have an uninterruptible power supply
- fit in your pocket
- operate from a battery

Sounds amazing, doesn't it? Yet it's not fantasy; the product does exist. It's called the IXO Telecomputing System (hereafter referred to as the Telecomputer), and it's featured on our cover this month.




Photo 1: *The IXO Telecomputing System. It's a complete pocket terminal with built-in modem and autodialer that will sell for about $500. The phone number displayed is IXO's Access Center.*

PERCOM


YOU GET MORE OUT OF PERCOM DISK SYSTEMS.

EXPECT IT!

At Percom, our business is making disk storage systems for microcomputers — something we've been doing right, since 1977.

From the design of rock-solid drive controller circuitry to quality controls that include 100% life testing of every drive shipped, you can expect to get more out of Percom Disk Systems.

And Percom provides you with comprehensive after-sales service from our wholly owned, fully independent customer service center.



WINCHESTER 10-MEGABYTE DISK STORAGE SYSTEMS


Enormous storage capacity plus high speed. Percom 5¼ inch hard disk systems are 40 times faster than single-density floppy mini-disks, 20 times faster than double-density units. Systems include a smart, four-drive controller featuring state-of-the-art data encoding and separation, adaptable industry-standard disk interfacing. Plug-in-compatible version for TRS-80* Model III computer, available now. Watch for IBM PC, Apple II, Atari, and H/Z-89 versions. Prices start at under $3000, including software. Also available with 5 or 15-Mbyte drives.

Coming soon! Ten megabyte removable-disk cartridge drive.

FLOPPY MINI-DISK STORAGE SYSTEMS

40 or 80-track drives, single or dual-head, flippy or non-flippy — all double-density rated. Available in 1, 2 and 3-drive add-on units, 1 and 2-drive internal units, with full documentation and software support. Add-on drives from $399, complete systems from $459.95.

To learn more about quality Percom disk storage systems, mail the coupon today. Or, call toll-free 1-800-527-1222. Ask for booklet "D".



YES ... I'd like to know more about Percom disk systems. Please rush me booklet "D".

Send to: PERCOM DATA COMPANY, INC. Dept BD1
11220 Pagemill Road, Dallas TX 75243

name ______

street ______

city ______ state ______ zip ______

phone number ______

I'm interested in floppy disk storage for my...
TRS-80 ☐ Mdl III ☐ Mdl I ☐ IBM PC
☐ H/Z-89 ☐ H-8 ☐ AIM/KIM/SYM ☐ System-50

I'm interested in hard disk storage for my...
☐ IBM PC ☐ TRS-80 Mdl III ☐ Apple II ☐ Atari ☐ H/Z-89

Other computer? ______
(☐ floppy disk or ☐ hard disk?)



THE DRIVE PEOPLE

11220 Pagemill Road • Dallas TX • 75243 • (214) 340-7081

PRICES AND SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE.

*TRS-80 is a trademark of Tandy Radio Shack Corporation which has no relationship to Percom Data Company, Inc.

Editorial

I first saw the Telecomputer nearly a year and a half ago when I visited its inventors, husband-and-wife team Bob and Holly Doyle, at their Cambridge-based company, Macrocosmos. The Doyles conceived of a portable but powerful computer terminal, and with the aid of electronic-design wizards Michael Suchoff and Andy Barber, they built a limited number of prototypes. The Doyles later joined forces with former Mattel Electronics president Jeff Rochlis to form IXO Inc., the company that markets the Telecomputer. I received one of the prototypes for testing last year and I've been using it ever since. I'm still amazed at the features packed into its exceedingly small package.

This month's theme is human-factors engineering, and the IXO Telecomputer is an excellent example of a terminal designed with the user in mind. The Telecomputer, which will be generally available this summer, has a lot to offer in addition to its human factoring. It has, for instance, a sophisticated security-protection system and innovative, compact circuitry. I'll touch on these topics, but my main objective here is to discuss the implications of IXO's design philosophy.




Photo 2: *The Telecomputer is powered by a built-in Polaroid Polapulse flat battery.*




Photo 3: *The FCC-registered Telecomputer is designed to attach directly to a phone using a standard modular jack. When in use, the terminal draws all of its power from the phone line.*

Circle 220 on inquiry card. ⟶

Circle 160 on inquiry card.

Editorial




Photo 4: *Four peripherals for the Telecomputer (clockwise from upper left): an acoustic interface (not the same as an acoustic coupler because the modem circuitry is already contained inside the terminal); the RS-232C interface, a video interface; and a 20-column printer.*

The Telecomputer marks the beginning of a whole new "genus" of computer products: no-compromise portable computers that are truly user-friendly. Let's take a closer look at its features.

The Telecomputer comes in a small plastic case containing densely packed CMOS circuitry and a Polaroid Polapulse flat battery to drive it (see photo 2). The heart of the design is an NEC 4-bit microprocessor with 1K bytes of CMOS RAM (random access read/write memory).

The keyboard, which is slightly too small for extended typing sessions, contains several unusual keys to help the naive user (and sometimes the not-so-naive user). These include the YES, NO, DON'T KNOW, HELP, and PHONE keys. They are brightly colored to attract your attention. The HOLD, SLOW, FAST, REPT, GO BACK, CLR CHAR, and CLR ENTR keys are dark blue. The usual BREAK, ESCAPE, and CONTROL keys are gray. The blue and gray colors tend to keep the more complex keys in the background in order not to distract or intimidate the beginner.

A Session with the Telecomputer

After you remove the Telecomputer from its box and turn it on, you then connect it to your telephone line by plugging your telephone cord's modular jack into the female socket at the back of the terminal (see photo 3). At this point the Telecomputer begins to draw all of its power from the phone line while the phone is "off hook," i.e., while the phone is in use (a clever arrangement by the machine's designers). Since the phone companies require all phone devices to draw 20 milliamps to prove that the devices are using the lines anyway, this becomes a perfect source of power for CMOS circuitry! In fact, telephone devices are allowed to draw 5 microamps while "on hook," so it becomes theoretically possible to trickle-charge a battery.

Circle 380 on inquiry card. →

Every Apple Is Created Equal. But It Doesn't Have To Stay That Way.

An Apple™ is really something. But from now on, it's going to be something much more. How come? Simple. We're introducing three revolutionary new data communication packages, called Transend™, designed especially to make your Apple II™ rise above all others.

Our Transend data communications software provides access to information utilities; complete file transmission of charts, VisiCalc™ reports, and entire programs; as well as all electronic mail functions.

Transend comes in three different versions. You can begin economically with the simplest form, Transend 1, an intelligent terminal/file transfer system. As your needs increase, you can move up to two other Transend packages, without worrying about retraining or repurchasing. Transend 2 gives any Apple II intelligent terminal capabilities, plus file transfer with complete error detection and automatic retransmission for demanding business applications. Transend 3 incorporates electronic mail—with password security, text editing, mailbox with mailstop, unattended scheduling and receiving, automatic redialing, and much more.



SSM

The Transformation People

Transend's support of most popular Apple II "add-in" cards and modems lets you upgrade your Apple without hassle or unnecessary expense. And you'll immediately cut operating costs by as much as 30% with simple, easy-to-use menus, data compression and 1200-baud modem support.

Nobody on the personal computer scene today is offering the speed, flexibility, and reliability of Transend in a single upgradable software system.

Don't miss this chance to uplift your Apple II. Contact us or your dealer for all the delicious details.

SSM Microcomputer Products, Inc., 2190 Paragon Drive, San Jose, CA 95131, (408) 946-7400, Telex: 171171, TWX: 910-338-2077.

The disk drive that puts more byte into your Apple.



Introducing the first totally compatible Floppy Disk Drive.

Rana Systems has designed a totally compatible disk drive for Apple, that's better than Apple's. A high density, high capacity disk drive and controller that offers a myriad of features Apple never thought of. Unique advantages that get the maximum efficiency out of your existing Apple II® hardware and software.

At Rana, we knew you wanted more storage, so we went right to the core of the problem. Even our most economical model is designed to give you 15% more storage capacity than Apple's. Our top-of-the-line unit gives you 4 times the capacity of Apple's comparable unit. Even our design is far more dramatic than theirs. With lines that actually complement the sleek Apple II computer.

We're a step ahead of Apple because we have a faster step.

Holding more information is even more valuable when you can get it faster. The Rana System track positioning mechanism is engineered to access three to four times faster track to track, with greater accuracy than Apple's. Our disk drive offers safeguards like a stall provision to protect spin motor burnout,

Apple II is a registered trademark of Apple Computer Inc.


an advanced write protect feature that keeps your information where you put it, and an energy saving device that "powers down" when your disk drive is taking a break.

We even took a bite out of Apple's price.

Our most popular model is 25% more economical per byte than Apple's, providing you with maximum performance, superior cost efficiency, and totally compatible styling. It also comes with a free diskette containing all the optional software and supports you'll need to enhance the capacity and performance. And it's all backed up with an efficient service support system, and a full 90 day warranty.

The Rana System Floppy Disk Drive. Just plug it into your Apple and all those delicious extra bytes will be yours.

RanaSystems™



Circle 353 on inquiry card.

20620 South Leapwood Avenue, Carson, CA 90746 213-538-2353.
For dealer information call toll free: 1-800-421-2207.
In California only call: 1-800-262-1221. Source Number TCT-654.
See our booth at the West Coast Computer Faire Show.

Editorial

After you hit the ON switch, the unit's liquid-crystal one-line display begins presenting a series of questions in menu format. The first query you see is "ACCESS CENTER?" The best way to learn about the unit is to dial the Access Center, a remote computer resource center maintained by IXO to service Telecomputer customers. You simply type in the telephone number and the unit automatically dials it. The Telecomputer senses whether your phone line is Touch-Tone or rotary-dial and sends out the appropriate signals. Once online, you can experiment with the simulated services offered by the Access Center, including a checkbook-balancing program, a travel-agency simulation that demonstrates booking airline flights, a television guide database to help you find TV show times, and so on. The main purpose of this exercise is to illustrate the advantages of services using plain English dialogue back and forth between the user and the computer. In time, real versions of such computer services will be available. When connected to the Access Center, you can always press the HELP key if you get stuck and get a more detailed explanation of what to do next. You can also press the DON'T KNOW key if in doubt as to the correct reply to the computer's questions. (If only the existing databases had these features!) The Telecomputer's designers have been trying for some time to convince the people who run the databases to adopt these user-friendly approaches. Let's hope they do.

The most important feature of the Access Center is that it can download protocols for The Source, Compuserve, and Dow Jones into your terminal's RAM. (These were the three services available at the time I evaluated the unit; more will undoubtedly be added later.) Downloading protocols takes about 30 seconds and needs to be done only once because the information is permanently stored in the terminal as long as the battery holds up, which is at least a year—longer if you're "off-hook" frequently. Once you're connected, the Access Center asks you to type in a password that you must use in all future dealings with the Center and also asks for your name.


I was surprised the second time I called the center to find that it greeted me with "HELLO CHRIS. PASSWORD?" It's hard to convey the excitement of seeing a message like this on a miniature terminal connected directly to your phone line. Future shock, indeed.

The next time I used the terminal, I decided to get on the Dow Jones database and analyze some stocks. I powered up the Telecomputer, entered my password, and it immediately asked "DOW JONES?" The downloading had worked! Out of curiosity I pressed NO and the terminal stepped to the next item: "THE SOURCE?" NO again. "COMPUSERVE?" NO. "MANUAL ACCESS?" (The latter mode lets you dial any general database or computer by entering a telephone number.) I cycled around to "DOW JONES?" again and pressed YES. (Incidentally, you can type "yes", "Y", hit the YES key, or the ENTER key to tell the terminal yes. The designers have obviously thought of every possibility to

HOW TO USE YOUR EPSON WITHOUT WASTING COMPUTER TIME:

Your computer is capable of sending data at thousands of characters per second but the Epson can only print 80 characters per second.

This means your computer is forced to wait for the printer to finish one line before it can send the next. A waste of valuable time.



THE NEW MICROBUFFER™ ACCEPTS DATA AS FAST AS YOUR COMPUTER CAN SEND IT.

Microbuffer stores the data in its own memory buffer and then takes control of the printer. This frees your computer for more productive functions.

PARALLEL OR SERIAL.

Microbuffer model MBP-16K is a Centronics-compatible parallel interface with 16,384 bytes of on-board RAM for data buffering.

The MBS-8K is a full-featured RS-232C serial interface with both hardware and software (X-On/X-Off) handshaking, baud rates from 300 to 19,000 and an 8,192 byte RAM buffer.

SIMPLY PLUG IT IN.

Either model fits the existing auxiliary interface connector inside the Epson MX-80, MX-80 F/T or MX-100 without modification, and is compatible with standard Epson cables and printer control software, including GRAFTRAX-80.

JUST $159.00*

When you think how much time Microbuffer will save, can you afford *not* to have one? Call us for your nearest dealer.

PRACTICAL PERIPHERALS, INC.
31245 LA BAYA DRIVE, WESTLAKE VILLAGE, CA 91362 • (213) 991-8200

*Suggested retail price for either model.

James Martin, data-processing and futures expert, offers the following predictions about the role of the pocket terminal ten years in the future. The following excerpt is from his book, *Telematic Society: A Challenge for Tomorrow* (Prentice-Hall, 1981).

Pocket terminals mushroom in sales and drop in cost as fast as pocket calculators did a decade earlier. Most people who carried a pocket calculator now have a pocket terminal. The pocket terminal, however, has an almost endless range of applications. It can access many computers and data banks via the public data networks. The pocket terminal becomes a consumer product (as opposed to a product for businesspeople) on sale at supermarkets, with human factoring that is simple and often amusing. The public regard it as a companion which enables them to find good restaurants, display jokes on any subject, book airline and theatre seats, contact medical programs, check what their stockbroker computer has to say, send messages, and check their electronic mailbox.

Public data networks are ubiquitous and cheap, and accessible from every telephone. Their cost is independent of distance within most countries.

keep naive users from getting stuck.)

You've probably gone through the usual tedium of identifying your terminal, hitting carriage returns, and going through all the usual make-work dialogue required to get onto databases. The Telecomputer eliminates all that. Once the Access Center downloads its protocols to your terminal, your terminal automatically completes the dialogue with, say, Dow Jones. You need only enter your password and you're instantly online. It takes only a couple of seconds. If you regularly access several databases or electronic mail services, you'll appreciate not having to memorize a lot of annoying protocols. This sort of elegant engineering will help popularize computers.

Another useful feature is the pair of speed-control keys, labeled SLOW and FAST, that control the speed at which text scrolls across the display by sending XON and XOFF control characters to the remote computer. Every time you press one of the keys the display incrementally slows down or speeds up. You can slow the display down to transcribe messages or speed it up to quickly scan through material.


There's little more to add about the operation of the Telecomputer—it's that simple. The built-in autodialer remembers your local Tymnet and Telenet numbers after you enter them once. It even shuts itself off if not used for eight minutes, first giving you an audible warning. The machine is truly "goof-proof."

Peripherals for the Telecomputer (see photo 4), including an acoustic interface (not the same as an acoustic coupler because the modem circuitry is already contained inside the Telecomputer—therefore the price is lower); a 20-column thermal dot-matrix printer made by Olivetti; an RS-232C interface; and a video interface designed for use with both TV sets and video monitors, will be available by July.

Design Philosophy

It's no surprise that the Telecomputer takes a human-factors approach. Its designers come from strong backgrounds in consumer electronics. Bob and Holly Doyle have invented more than a dozen computer toys, including Parker Brothers' best-selling Merlin and Stop Thief. While at Mattel Electronics, Jeff Rochlis supervised the production of the Intellivision personal computer and hand-held games such as Brain Baffler (to which the Telecomputer bears a coincidental resemblance). Rochlis's four design goals were to make the Telecomputer cheap (it will sell for approximately $500 to $550); portable; easy to use (meaning both ease of access to databases and ease of use via plain English dialogues); and secure.

That last point deserves a volume in itself. Someone once said that today's electronic mail services are more like "postcard" services because the security measures are so lax that any half-competent programmer can crack them. The Telecomputer's three-way security keying system goes a long way to correcting this situation. The user



PEARL™!

Skeptics are still saying a program like PEARL won't be available until the mid-1980's

They're wrong, of course. PEARL is available now.

PEARL (Producing Error-free Automatic Rapid Logic) brings application generation software to microcomputer users at four user levels.

Very simply, PEARL means that anyone with a microcomputer with 48K memory can use one of the four PEARL programs to generate new applications software with a minimum of time, trouble and training.

PEARL runs under CP/M* and is designed as a powerful menu-driven tool. PEARL Level 1 provides non-programmers with the capability to program their own new applications automatically. Users respond to on-screen prompts as they define their system; no programming knowledge is required.

PEARL Levels 2 and 3, for experienced programmers, provide sophisticated processing for complex applications. In just fractions of the time it used to take to design, code, and test a program, PEARL will generate and compile a new application. PEARL Level 4, the most advanced of the PEARL packages, provides programmers with the capability to include many features normally associated with customized turnkey systems.

Introductory prices. Trade-in allowances for upgrade to higher levels.

PEARL Level 1	For Personal Computing	$ 90	
PEARL Level 2	The Business Assistant	$ 200	
PEARL Level 3	For Software Developers	$ 400	May 1980
PEARL Level 4	For Turnkey Systems Developers	$ 800	June 1980

evolutionary software for the 1980's

CPU International • 503-370-8653
P.O. Box 12892 • Salem, Oregon 97309

THIS AD MARKED THE BEGINNING OF A NEW ERA IN MICROCOMPUTER PROGRAMMING.

It announced PEARL™.

PEARL ushered in the era where programmers could free themselves from boring, routine and repetitive tasks. Because PEARL handles 60-70% of programming details, which permits programmers to spend their time more creatively, and more productively.

But that was two years ago.

Today, there's Personal PEARL – to be introduced at the West Coast Computer Fair. And it goes a giant step further. Personal PEARL makes the capabilities of the computer available to virtually anyone.

For its $295 price, even people without technical backgrounds can use it to visually create their own applications and reports on any computer.

So the ad you're reading now is announcing an even more important breakthrough in computer and personal productivity.

Just think about the possibilities. Then contact our Personal PEARL Product Manager.

RELATIONAL SYSTEMS INTERNATIONAL
P.O. Box 12892/Salem, Oregon 97309/(503) 363-8929

Circle 355 on Inquiry card.

CPU International is the former name of Relational Systems International. PEARL (Producing Error-Free Automatic Rapid Logic)

has a password, the terminal has a built-in password (unknown to the user), and the host computer has a password. (This is the proposed standard. Presently, only the IXO Access Center computer adheres to it.) The host computer combines its password with both the user's password and the terminal password in complex, randomized ways to make it virtually impossible for someone else to emulate your terminal with another terminal or computer, even if he knows your password. It's an admirable approach to securing data. I hope manufacturers will pay serious attention to it.

The Telegraphic Age

Rochlis likes to compare today's computer age to the telegraphic age of the nineteenth century. In many ways, he says, the technique of talking to computers is still in its "telegraphic" stage. Back when the telegraph was the chief means for long-distance communication, telegraph operators were required as intermediaries for all transactions. Unfortunately, they "spoke" a different language than their clients: Morse code. Today, most of the public at large do not know how to operate computer terminals and must rely on computer operators. The latter are in effect the most expensive "peripherals" of all. To bring computing power to the people, we must supply them with cheap *and* easy-to-use computers and terminals.

There is a trend this year toward the development of briefcase-sized computers and terminals. (See the report about Epson's new HX-20 portable computer on page 104.) And that's just the beginning: watch for a series of new, small computers from both America and Japan. But size and cost alone will not guarantee the success of these machines with the general public. Human engineering has to be our paramount concern in the personal-computing field; the IXO terminal is a major step in this direction.

* * *

Piracy Addendum

Many people have asked me to comment on the issues of software piracy raised in Jerry Pournelle's January column. (See "User's Column: Operating Systems, Languages, Statistics, Pirates, and the Lone Wolf," January 1982 BYTE, page 132.) My only comment is that, while I sympathize with many of the opinions expressed by Jerry's "mad friend" Mac Lean, my overall attitude toward copying software has not changed since I spoke out in the May 1981 editorial. Nevertheless, I think it's important to air opposing viewpoints in BYTE. The debate is healthy and being overly dogmatic serves no useful purpose. I'd like to hear more from readers about this issue.■

Letters

The Missing LINC

I keep seeing the "personal computer era" referred to as having begun in the mid-1970s, as if it required the microchip to make it possible to design hardware and software for a single-user computer. But there are important antecedents to this, dating back twenty years, and they were not hand-held calculators so much as proper computers with analog interfaces and mass storage—namely, lab computers.

In 1962, at MIT's Lincoln Labs, Wesley Clark and Charles Molnar designed the LINC (Laboratory INstrument Computer), to be used in a research lab in a manner analogous to an oscilloscope. It wasn't merely its display and analog-to-digital converters (hence joysticks and Spacewar) which made it unique: its software was designed to enable the scientist-user to program without a professional programming staff. Much of the design rationale was process-control oriented (hence interrupts) so that online data analysis could be performed during an experiment, allowing modification to the experimental protocol. But having such a friendly computer in the room, shared only with the other users of the same lab, created the atmosphere of "personal computing" a decade before mass-market economics extended it.

The first 24 LINCs (with their small memories and dual small-reel magnetic tapes—so-called LINCtapes—which were the forerunners of the floppies) were built under a government research grant and distributed around the country in 1963 to various physics, chemistry, and life sciences labs (they were especially important in my own field of neurobiology). With the plans in the public domain, several computer manufacturers began selling them (Digital Equipment Corporation's version cost $54,000—and in 1966 dollars, at that) and improving on the design (DEC's LINC-8 and PDP-12 were the major extensions). In essence, thousands of users experienced the personal computer revolution in the 1960s and helped shape its present philosophy.

It is curious how this heritage has been forgotten in the great expansion. One consequence is an excessive amount of reinventing the wheel. The interactive software packages developed by LINC users (especially at Washington University and the University of Wisconsin) were excellent—I have yet to see a statistics-and-plotting package for microcomputers which equals LINDSY for the LINC, and the LINC's text editor and operating system (LAP) puts CP/M to shame. And—another forerunner of the present microcomputer situation—the really good general-purpose software came from small groups, not manufacturers.

Most people tend to compare new microcomputer software to fancier mainframe versions, but it is often more appropriate to compare it to the lab computer antecedents, which shared a similar philosophy. It is the design philosophy for microcomputers that so sets them apart from the staffed mini- and main-frame computers, and it is that single-user-as-master philosophy that was so extensively developed by the LINC users.

William H. Calvin, Ph.D.
Associate Professor of Neurophysiology
Department of Neurological Surgery
RI-20
University of Washington
Seattle, WA 98195

Computer Scrabble*

We were pleased to see an article discussing the feasibility of a computer opponent for Selchow & Righter's popular Scrabble word game (see "Computer Scrabble," December 1981 BYTE, page 320). Others who are intrigued by this concept will appreciate knowing that the state of the art in microcomputer Scrabble has made a great leap forward. It is far beyond the boundaries that Mr. Roehrig tells us will not be broken by anything less than a new, superior generation of microcomputers.

"Monty plays the Scrabble Brand Crossword Game" (a computer-opponent program available on disk for the Apple II and TRS-80 Models I and III from Ritam Corporation for $39.95) demonstrates both speed and ability, within the constraints of today's microcomputers.

Monty spends an average of only 4½ minutes per move at the highest skill level, and yet it uses an extensive word list (over 50,000), based in part on the *Official Scrabble Players Dictionary.*

As for memory, the program requires no more than 48K bytes for Apple and 32K bytes for TRS-80 versions, much of which is devoted to machine-language graphics, music, and other user-interface requirements. The dictionary is accessed from disk and is stored in an average of only two bytes per word (with an average length of 6 or 7 letters) by use of advanced compression techniques. In addition, Monty is capable of challenging other players' words, based on linguistic analysis, without accessing the disk.

To give Mr. Roehrig's efforts due credit, the "game's complexities" do offer a challenge! It took us several major design breakthroughs, over four man-years of programming (for three different computers), and a lot of determination to develop "Monty plays Scrabble" without conceding to "certain constraints" on word length, search, and placement.

Although his conclusion that "improved computerized Scrabble will require a faster host computer with more memory capacity" has been disproved by example, we thank Mr. Roehrig for his article. It makes our endeavor seem quite worthwhile when we learn that we've achieved the impossible!

By the way, Mr. Roehrig neglected to properly acknowledge that Scrabble is a trademark of the Selchow & Righter Company, and to disclaim, as does Ritam, any sponsorship or endorsement by Selchow & Righter.

Robert Walls, President
Ritam Corporation
POB 921
Fairfield, IA 52556

* *Scrabble is a registered trademark of Selchow & Righter Company. We apologize for not acknowledging this in a prior article. . . .* MH

More Commbat

I would like to thank George Stewart for his excellent and perceptive review, "Commbat: A Tele-Game for Two," in the December 1981 BYTE (page 100). He captured my motivation for creating Commbat in the first paragraph.

The problems he mentioned of synchronizing both systems upon initial start-up


Videx INC.

897 N.W. Grant Ave. • Corvallis, Oregon 97330 • 503/758-0521


THE DAWN OF A NEW ERA FOR APPLE][®: THE ENHANCER][

Introducing the Enhancer][: a new Standard which is improving the relationship between Humans and Apples. The Enhancer][can help your Apple]['s keyboard become more sociable by remembering words or phrases which can be entered into the Apple by the mere touch of a key. Life can become even easier because the Enhancer][can remember what you typed while your Apple was busy talking to your disc (or doing other things). Naturally, it knows the difference between upper and lower case letters and what shift keys are supposed to do. It even knows to auto repeat any key held down. The Enhancer][replaces the encoder board making installation simple.

Suggested retail price: $149.00.



■ VIDEOTERM




The time tested Videoterm 80 column card:

- 80 characters × 24 lines
- True decenders
- 7 × 9 character resolution
- Low power consumption
- Compatible with most word processors
- Softcard and CP/M compatible
- Modem compatible
- Most popular character set of any 80 column card
- Alternate character fonts available


Suggested retail price $345.00

■ SOFT VIDEO SWITCH



The Soft Video Switch is an automatic version of the popular Switch-plate. It knows whether it should display 40 or 80 columns or Apple graphics. It does the tedious work of switching video-out signals so you don't have to. The Soft Video Switch can be controlled by software. Any Videoterm with Firmware 2.0 or greater may be used with the Soft Video Switch. The single wire shift mod is also supported. Package price is $35.00.

■ KEYBOARD AND DISPLAY ENHANCER



The original Keyboard and Display Enhancer is still available for Revision 0-6 Apples (on which the new Enhancer][will not fit). These Apples have memory select sockets at chip locations D1, E1 & F1. The Keyboard and Display Enhancer allows entry and display of upper & lower case letters with fully functional shift keys. It does NOT have user definable keys nor a type ahead buffer. The price is $129.00.

■ ACCESSORIES:

Videoterm Utilities Disc $37.00 (includes)

- Font Editor
- Pascal Mid-Res Graphics
- Applesoft Read Screen Utility
- Top & Bottom Scrolling
- Pascal Vidpatch
- Graphics Template

Character Set EPROMs $29.00 ea

- Half Intensity
- Inverse
- German
- Katakana (Japanese)
- Line Drawing Graphics (Expanded)
- Spanish
- French
- Math & Greek Symbols
- Super & Subscript

Dvorak EPROM (Enhancer) $29.00

Lower Case Chip $29.00

and keyboard sluggishness are a result of accommodating the TRS-80 Model I's RS-232 port. It cannot interrupt the processor when it has a character, so it must be operated in a polled-loop configuration in order not to lose data. As long as Model Is or their look-alikes are a significant part of the market this 'problem' will be necessary. I believe the first release of Commbat was the one reviewed. As a result of the synchronization problem, the current release, Commbat Version 2.1, has a split-screen dumb-terminal option that is presented to the user upon start-up. This mode can be entered without any particular worries as to timing by both participants, and when both are communicating they can exit to the game. This mode also allows communications to be established through some of the dial-up services that can handle pass-through communications between users.

At last report, the Atari version of this game was in production and should be available soon from Adventure International, and an Apple version is on the way. The major feature of these different versions is that they will all play against each other. My intention is to keep Commbat system independent; as other systems become a significant portion of the market they will get their own compatible version. Anyone who buys Commbat will be able to play anyone else who has ever bought it, regardless of equipment.

The second game of this planned series is finished and will be marketed in the near future, and the third is coming along well.

Robert A. Schilling
725 SE Vance Circle
Palm Bay, FL 32905

No Contest

Despite the "battle" for dominance portrayed in the "Unix vs. CP/M" item in the November 1981 BYTELINES column (page 306), the position of the apologists for CP/M has become all but untenable. The implication that Unix and CP/M can be compared on the same terms is wholly misleading. Unix is a full-featured operating system which is widely regarded as the finest ever written, while CP/M is little more than a program loader.

The only reason for the continuing popularity of CP/M is summed up in the column's last sentence: "CP/M appears to have much more public-domain and commercial software for it than does Unix." As the computer community recognizes that Unix is bound to become the standard 16-bit microcomputer operating system, commercial applications software for it will inevitably begin to appear. And, since most Unix software is written in the powerful C programming language rather than in assembly language or some dialect of BASIC, we can be sure that the commercial software which will eventually be available under Unix will be of higher quality than that found in the CP/M market.

John Lynn Roseman
Urban Software Corporation
11 West 34th St.
New York, NY 10001

Toward a Structured Assembler

I have just finished reading the two-part article "Toward a Structured 6809 Assembly Language" (November 1981 BYTE, page 370, and December 1981 BYTE, page 198). I found the article quite interesting, especially since I have been selling a structured assembler (STASM09) package since 1980. STASM09 uses a pre-/post-processor to generate the appropriate internal labels and to modify the listing to provide automatic indentation of the listing. (The indentation of the code provides graphic display of the structure of the program module.)

STASM09 provides the IF. . .ELSE. . . ENDIF but not the WHILE. . .ENDWH or REPEAT. . .UNTIL constructs described by Mr. Walker in his article. Instead, STASM09 provides a more general DO. . .ENDO construct with several methods to BREAK out of the loop. This allows both the WHILE and REPEAT functions to be implemented. In addition, STASM09 provides a COUNT function that can be used to control the number of times a loop is traversed.

STASM09 is designed to run under the FLEX operating system from Technical Systems Consultants rather than the more industrially oriented Motorola operating system. STASM09 is available on a 5¼-inch, single-density disk for $49.95, including shipping and handling, from Sansaska Systems, 3311 Concord Blvd., Concord, CA 94519.

NOW!
MORE THAN EVER

When You Have To Face A Deadline…


Since its introduction, Pascal/MT + ® has been used to produce thousands of professional solutions to industrial, business and systems level application problems. In addition to implementing the complete ISO STANDARD, Pascal/MT + ® contains a host of powerful features and facilities which make program construction a snap!

Pascal/MT + ® is a total programming system including our native machine code compiler, linker, Pascal-level debugger, disassembler, run-time subroutine library and the exclusive SpeedProgramming™ Package.

With the advent of 16-bit machines and increasing customers demands, you can no longer afford to write programs in anything but a professionally constructed and professionally supported package like Pascal/MT + ®. MT MicroSYSTEMS has demonstrated its commitment to keeping your programs and programmers productive with our recent introduction of Pascal/MT + 86 and Pascal/MT + 68K for the 8086. While Pascal/MT + ® provides the capability to write non-portable programs when the need arises, true portability between radically different machines is a reality while still translating into efficient, optimized native machine code.

Our Pascal/MT + ® compilers and SpeedProgramming Package are available on a wide variety of processors and operating systems, with more to come! We are continually working to provide innovative solutions to the ever present problem of translating your ideas into software solutions.

The Pascal/MT + ® System

Compiler:

Generates ROMable Native Code • Complete ISO Standard (superset of Jensen & Wirth).

Powerful Extensions Include:

Modular Compilation, Direct production of binary relocatable modules • Dynamic strings • Chaining • Powerful Overlay system • Address and Size returning functions • Bit manipulation (test, set, clear, shifts) • Byte manipulation (high, low, swap) • Imbedded assembly language • Easy linkage to external assembly language • Full NEW and DISPOSE procedures • Direct access to I/O ports • Fast floating point, both software and AMD 9511 • Accurate 18 digit BCD (fixed point, 14,4) • Include files • Hex literal numbers • and more…

...Arm Yourself With Pascal/MT+®



Linker:
Combines relocatable modules into executable files • Can generate Hex format for use with PROM programming.

Interactive Symbolic Debugger:
Variable display • High-level breakpoints by procedure/function name • Tracing/single step by Pascal statement • Procedure/function entry and exit trace available.

Disassembler:
Combines a relocatable module with its listing file to produce interleaved Pascal and approximate assembly language code.

The SpeedProgramming Package™:
The SpeedProgramming Package is an integrated set of tools which allows you to create Pascal/MT+® programs, check them for correct syntax and undefined identifiers, format them to display flow of control, and do this all within the editing environment before you ever invoke the compiler. Programmers like SpeedProgramming because it frees them from the time consuming chore of repeated compilations to correct simple syntactic and typing errors. Managers find that SpeedProgramming improves productivity, thereby reducing development costs. SpeedProgramming combined with our field tested Pascal/MT+® package gives you a comfortable, powerful, interactive programming environment in which to create your professional quality software. Your products demand production quality tools. Order Pascal/MT+® with SpeedProgramming today!

Screen Editor:
User configurable • Standard random cursor movement; file access, search and replace, insert, delete, exchange, etc. • Structured language editing features such as automatic indent, line adjustment, reading from and writing to a file, block text insertion and duplication. • Requires: 24 x 80 CRT (or larger). ASCII Keyboard (7 bit data), random cursor addressing.

Interactive Syntax Scanner:
Finds syntax errors in text being edited • Enters SPEED, puts cursor at error, prints error text.

Variable Checker:
Catches undefined and mis-spelled variables before the compiler is invoked.

On-Line Reformatter:
Beautify programs in seconds • Clearly shows structure and program flow.

Source Code Management Tools:
Automatic Modification Log and Backup utility program.

PRICING: *Read carefully, some systems do not include the SpeedProgramming Package but do include the compiler, linker, disassembler, debugger and other utilities.

AVAILABLE NOW!

*8080/8085/Z80 without SpeedProgramming 56K or larger CP/M	Price $350.00
8080/8085/Z80 complete including SpeedProgramming 56K or larger CP/M	Price $475.00
8080/8085/Z80 for special MP/M environments	Contact Factory
*8086/8088 without SpeedProgramming CP/M-86 or MP/M-86, requires 116K program area	Price $600.00
8086/8088 complete including SpeedProgramming	Price $800.00

All 8086/8088 packages include 9511 and 8087 support and program to convert MT object files into Intel OBJ 8086 files.

Digital Research, Inc. is now the sole distributor for Pascal/MT+, and is proud to add it to the Digital Research family of operating systems, languages and utilities.

Available on 8" (3740) Single Density Disks. Contact Distributors For Other Formats.

Pascal/MT+, CP/M, MP/M are trademarks of Digital Research, Inc.

FOR: 8080/8085/Z80/8086

DIGITAL RESEARCH

P.O Box 579
160 Central Ave.
Pacific Grove, CA. 93950
Phone No. 408/649-3896
TWX 910-360-5001

*All prices and specifictions subject to change without notice.

Circle 147 on inquiry card.

Incidentally, I have noticed a possible problem with the macros defined in part 2 of the article. When an error condition is recognized in a macro, a long branch to the EXBUG monitor is inserted into the code. Since this can occur in code that is entirely relocatable, the relative offset of this error jump will be wrong any time the program is relocated. If this happens, the results will be entirely unpredictable and possibly very hard to debug.

Derek Gitelson
Sansaska Systems
3311 Concord Blvd.
Concord, CA 94516

A Recipe for Standards

I have been involved with the microprocessor standards work of the IEEE (Institute of Electrical and Electronics Engineers) Computer Society from its beginning (August 1977), so Chris Morgan's editorial in the November 1981 BYTE caught my eye. The question is "Can we agree on standards?" The correct answer is a qualified "Yes," and the "heated debate" usually occurs only when that qualification is violated.

What is this qualification? The standard must be done *right*. The right way to establish a standard, once the need for a standard is apparent, requires three steps:

- First define the objectives of the standard that the potential users can agree on.
- Examine the marketplace to see if there exist any widely accepted products that are designed to specifications that meet or are near the objectives. This examination can go four ways: (1) if there are no products, establish a design team of competent technical people to design specifications; (2) if there is one product fully meeting the objectives, adopt its specifications; (3) if there are one or more products close to the objectives but in some way inadequate; establish a design team to adopt one (impartially, if possible) and to produce from it adequate specifications; (4) if there are several incompatible products whose specifications fully meet the objectives, establish an impartial selection board to choose one set. (In this case it is usually too late to define a standard, but sometimes the need for it will reshape the marketplace.)
- Write the specifications into a draft standard and take it out for public review. This is a necessary safeguard against per-

sonal bias and technical incompetence in the designers. All responses to this review step must be dealt with before the standard can be established. The draft standard need not be modified for every response, since some of them will themselves be biased or incompetent, but all responses must be considered.

The American National Standards Institute (ANSI) and the IEEE, as a member of ANSI, are set up to develop standards by these procedures, and the standards so developed do receive wide public acceptance. Although it is still being reviewed and revised, the proposed standard for the S-100 bus is an example of such success.

What about the wrong way? Usually it is some variety of "Let's standardize on *my* way of doing it." A lot of standards are proposed this way, and some actually succeed. If they succeed, it is in spite of the attitude, not because of it, and then only because the proposer has done the technical homework and controls the marketplace (for example, IBM, which is known for this attitude).

How does DIF fit in? [**Editor's Note:** *DIF, for Data Interchange Format, is a method for representing data in a program so that it can be transported directly to other programs. See "DIF: A Format Between Applications Programs" by Candace E. Kalish and Malinda F. Mayer, November 1981 BYTE, page 174.*] Software Arts is promoting DIF as a standard, using the "let's do it my way" approach. It may succeed at this, because Visicalc happens to dominate the market. It may even be that DIF is a good technical proposal, but we cannot know this without the proper review procedures, which Software Arts has bypassed.

I think it is unfortunate that monopoly industries like IBM and Software Arts can wield such Machiavellian powers as to impose on the rest of the world standards like EBCDIC (extended-binary-coded-decimal interchange code) and (possibly) DIF without the benefit of good technical review.

Tom Pittman
Itty Bitty Computers
POB 23189
San Jose, CA 95153

I concur with Mr. Pittman's rational approach to the establishment of a standard. However, our industry does not always behave rationally. I take issue with the implication that IBM and Software Arts are necessarily Machiavellian or even monopolistic. To be monopolistic, by definition a company must have exclusive control of the means of producing a product or service. Visicalc may be the best-selling microcomputer program of all time, but that hardly excludes competitors from offering their own types of spreadsheet programs. In the case of IBM, whatever its past record has been in the mainframe market, its behavior in the personal computing market has been remarkably open and nonmonopolistic, if I may use that term . . . CM

Multicolored Players, or The Atari Tutorial Debated

I enjoyed reading Chris Crawford's "The Atari Tutorial, Part 3: Player-Missile Graphics" in the November 1981

BYTE (page 312). I believe, however, he has made an error. On page 319 he stated that multicolored players are not possible unless you use display-list interrupts. On the contrary, there *is* a way to produce multicolored players in BASIC very easily. If you look on page III.7 of the Atari Hardware Manual, you will see that setting the fifth bit of GPRIOR ($26F) at location 623 decimal will cause a logical OR function of the colors of player 0 with player 1 and player 2 with player 3. The result is a choice of three colors in the overlapped region. The following program demonstrates this effect:

```
10 A= PEEK(106) – 8:POKE 54279,A:REM
   SET UP PLAYER – MISSILE GRAPHICS
20 POKE 559,46:POKE 53277,3:REM
   DOUBLE – WIDTH RESOLUTION
30 POKE 704,26:POKE 705,102:REM
   PLAYER 0 & 1 COLORS
40 PMBASE = 256*A + 512
50 FOR I = 0 TO 256:POKE
   PMBASE + I,0:NEXT I
60 FOR I = 0 TO 7:READ A:POKE
   PMBASE + 48 + I,A:NEXT I
70 DATA 255,255,195,195,195,195,255,255
80 FOR I = 0 TO 7:READ A:POKE
   PMBASE + 176 + I,A:NEXT I
90 DATA 60,60,60,60,60,60,60,60
100 L = 100:R = 148:POKE 53248,L:POKE
    53249,R
110 FOR T = 0 TO 1000:NEXT T
120 FOR I = 1 TO 24:L = L + 1:R = R – 1
130 POKE 53248,L:POKE 53249,R:NEXT I
140 FOR T = 0 TO 300:NEXT T
150 POKE 623,32:REM SET BIT 5 OF
    GPRIOR
160 GOTO 160
```

Lines 50-100 POKE the player images into the player graphics buffer and set their horizontal positions. Lines 110-160 let you see the player images coming together and then the three colors being produced as one player. Remember that to move this three-colored player requires you to POKE the same horizontal position into the horizontal-position registers of both player 0 and player 1.

Peter Hecke
767 Bergen Blvd.
Ridgefield, NJ 07657

Chris Crawford replies:

Thank you for your program; it demonstrates the OR function of GPRIOR bit 5 very well. This technique, however, does not *create a multicolored player. Instead, it creates a three-colored object using two* players*—certainly a useful technique for "getting more for your money" with two players. If you are not otherwise using all your players, you can create a multicolored object by overlapping several players of different colors. With the technique you describe, you can get seven colors (the normal five plus two "overlap" colors), although you do not have full control over the overlap colors; without this technique, the most you can get is five colors (if you use all four players and the missiles as a fifth player).*

The method I referred to in my article modifies the display list to execute an assembly-language display-list interrupt routine to change the color register of a given player while the video image is being drawn. This technique can produce one *player that has multiple colors, but it has two disadvantages: first, it can only produce images striped horizontally with different colors; and second, unless you change the display list on the fly, the multicolored player cannot move vertically (display-list interrupts are tied to a certain horizontal line of the video display).*

Thanks for sharing your letter and program with other BYTE readers and me.

Wanted: Education in Computerized Business Systems

Students interested in obtaining a university education in the development of business-oriented computer systems should investigate the programs offered by the business schools. Paul Brady in his article on "Bridging the 10-percent Gap" (see the October 1981 BYTE, page 264) identifies the need for this type of training, which combines courses on computers with courses on business organizations and management skills. However, his comments do not indicate that such programs already exist. Rigorous computer science programs provide excellent technical and theoretical training but are not typically designed to produce business-systems analysts and application programmers. For further information on the educational issues involved and a survey of programs offered, see the article by Jay F. Nunamaker Jr., "Educational Programs in Information Systems," *Communications of the ACM*, March 1981, and the in-depth report on "the DPMA Model" in *Computerworld*, September 21, 1981.

Hugh Howson
Professor Invite
Université du Québec à Montréal
Case postale 8888, Succursale "A"
Montréal P.Q. H3C 3P8 ■

The Generic Word Processor

A word-processing system for all your needs.

You'll be amazed by this product's versatility.

Philip Schrodt
Department of Political Science
Northwestern University
Evanston, IL 60201

Congratulations on your purchase of the GWP Inc. Generic Word-Processor System. We are sure that you will find this word processor to be one of the most flexible and convenient on the market, as it combines high unit reliability with low operating costs and ease of maintenance.

Before implementing the system, carefully study figure 1 to familiarize yourself with the main features of the GWP word-processing unit.

Initialization

The word-processing units supplied with your GWP are factory-fresh and uninitialized. Before they can be used, they must be initialized using the GWP initialization unit (see figure 2). Because of the importance of this unit, we designed it with a distinctive shape so that it will not be misplaced among the voluminous vital papers on your desk.

To initialize a word-processing unit, carefully place the character insertion subunit into the left side of the initialization unit and rotate the word-processing unit approximately 2000 degrees clockwise while exerting moderate pressure on the word-processing unit in the direction of the initializer. Check for successful initialization by attempting a character insertion. If the insertion fails, repeat the initialization procedure. The word-processing unit will have to be reinitialized periodically; do this whenever necessary. (*Warning:* do not attempt to initialize the word-processing unit past its character deletion subunit. Doing so may damage both the word processor and the initializer.)

Editor's Note: *Once in a while we come across a product that's so useful we feel compelled to bring it to our readers' attention. The Generic Word Processor System (GWP) is such a product, incorporating the essentials of a word processor in a sublimely simple form.*

With the manufacturer's permission, we are reprinting the documentation for this product. After working with the GWP for several weeks, we're delighted by the feeling of total control that the system gives us and are certain you will be too. No more accidentally erased files, no damaged disks, no hardware problems . . . **SJW.**

Operating the Word Processor

The GWP can perform all the basic functions featured in word processors that cost thousands of dollars more. Furthermore, because the GWP does not require electricity, it can operate during power blackouts, electrical storms, and nuclear attacks. By conserving precious energy resources, it helps free our beloved country from the maniacal clutches of OPEC.

Basic functions of the word processor are listed below:

Inserting text: Use the character-insertion subunit to write in the words you wish to insert, applying moderate downward pressure to the unit. Be sure to write clearly so that the typist can follow what you have written.

Deleting text: With moderate downward pressure, rub the character-deletion subunit across the text to be deleted. Repeat this procedure several times. The text will gradually disappear, whereupon you will be able to insert new text.

Underlining: Using the character-insertion subunit, place the unit slightly below and to the left of the first character you wish to underline. Move the unit to the right until you reach the last character to be underlined.

Bold face: Repeat the text-insertion procedure twice, pressing downward with greater pressure than you would normally apply.

Move to beginning of text: With the text you are working on in hand,




Figure 1: *The GWP System word-processing unit is composed of the character-insertion subunit (at right) and the character-deletion subunit (at left).*




Figure 2: *The word-processing initialization unit, which should be operated over a wastebasket.*



Figure 3: *The block text extraction and replacement units, commonly run in unison.*

SANSKRIT

AMHARIC

HIEROGLYPHICS

Figure 4: *Sample type fonts illustrating the wide variety available with the GWP System. The manufacturer claims that if a language can be written, the GWP System can be adapted to it.*

move the unit to the beginning of the text.

Move to end of text: Take the text you are working on and move the unit to the end of the text.

Moving blocks of text: Block moves require use of the block text extraction unit and the block text replacement unit pictured in figure 3. By means of the block text extractor unit, sever the paper immediately above and below the text you wish to move. Instructions for operating the extractor unit are etched on the side of the unit in Korean. If you still have difficulty operating the unit, call our service department for consulting help at our introductory fee of $50 per hour, or ask any 5-year-old child.

After separating the text to be moved, open the lid of the block text replacement unit and, grasping the block text replacement medium application unit, spread the block text replacement medium on the back of the text. Move the text to the new location and affix it to another sheet of paper with gentle but firm pressure. In a few minutes, your text will be permanently affixed in the new location.

Other Features

Page numbering: After writing your entire text, inscribe a 1 on the first page, a 2 on the second page, etc. When you finish, all of the pages will be numbered.

Centering: Determine where the center of the page is by looking at it. The center is usually near the middle of the page. Place the text to be centered evenly on each side of the center. It is now centered.

Special fonts: The GWP System is extremely versatile and easily adaptable to specialized type fonts such as Sanskrit, Amharic, and hieroglyphics (see figure 4). You will find these fonts valuable in business correspondence, particularly if you are in frequent contact with Vedic gurus, Egyptologists, or Ethiopian Airlines.

Saving files: Put the work you have finished in a safe place, one where nobody will find it or spill coffee on it. If it is not disturbed, it will be there when you return.

INTELLIGENT PRINTER INTERFACE

Free Your Computer from the Mundane Task of Printing

Imagine being able to use your computer seconds after beginning an extensive printout.

Visualize your printout with page breaks, page numbering and titles, margins of your choice, indented carryover lines, on any size paper!

Appreciate the time and money you will save by not waiting on your printer.

SooperSpooler, a buffered printer interface, maintains control over your printer while you go on using your computer for more productive activities. Eliminate waiting while your printer pecks through a long document. SooperSpooler accepts information from your computer at up to 2500 characters per second and feeds it to your printer as fast as it can handle it—without using any of your computers memory or time! As soon as SooperSpooler has stored your document in its buffer, control of your computer is returned to you.

SooperSpooler features include:

- 16K Memory—Will handle most of your printing jobs (expandable, see options)
- Buffer Status Readout—Lets you know just how much data is stored
- Space Compression—Makes the best use of memory on columnar documents
- Pagination—Eliminates printout on page perforations
- Page Stops—For single sheet printouts
- Headers and Page Numbering—Give your listing a professional look
- Indentation on Carryover Lines—Easy to find the beginning of a line
- Self Test Routine—You instantly know that all is well
- All Features Software Controllable—Your program can take over
- Plugs into Most Computer Systems—Standard cables available
- **$349.00!**—16K parallel I/O unit

Options:

- Serial Board—$95.00—Gives you the option of any combination of serial or parallel input or output. Can also be used for modem transmission.
- Memory Expansion—$159.00—Additional 46K for a total of 62K
- Cables—Available per your application.

SooperSpooler™ by Compulink —The missing link that gives your microcomputer mainframe printing.

COMPULINK CORPORATION

1840 Industrial Circle, Dept. A
Longmont, CO 80501
(303) 651-2014
Order line: 800-525-6705

Dealer inquiries welcome

Circle 96 on inquiry card.



We accept
- VISA
- MasterCard
- Checks
- Money Orders
- COD

Add $3.00 per order for postage and handling
COD add $3.00
Colorado residents add sales tax

Prices and Specifications Subject to Change Without Notice

Deleting files: Take any files you no longer need and deposit them in the wastebasket. They probably will be gone in the morning. In most offices, this can also be accomplished by leaving the files in the open, forgetting to remove them from the copying machine, or writing CONFIDENTIAL on the file in bold letters.

Appending files: Place the first file on top of the second file. Treat the two files as though they were one file.

Justification: Most word processors have little justification. This word processor has no justification at all, as it does not even lend prestige to the office where it is used, which is the justification for most word processors.


Printing Files

A printer for the GWP must be purchased separately. For convenience of operation, we recommend an ordinary typewriter and a typist. Give the text to the typist and tell him or her to type it. Printing speed can be improved by increasing the wages of the typist, threatening to withhold the wages of the typist, kidnapping pets, plants, or children of the typist, instigating intimidating tactics, and other conventional office-personnel management techniques. Printing speed can be decreased by asking to see the text, making continual changes in the text, asking the typist to answer the phone, decreasing the typist's wages, and installing a conventional electronic word processor. You will soon learn to adjust the printing speed to the optimal level for your particular needs.

Copyright © 1981, Generic Word Processing Inc., Skokie, IL 60076

*(WARNING: This system and accompanying documentation are fully protected under the provisions of the Galactic Copyright Convention, ser. B, Rigal system, Code 56-*ADF6 45932030: f. Duplication is strictly prohibited without the permission of copyright owner. Violators will be prosecuted to the fullest extent of the law or devoured at the discretion of the copyright owner or such agents as the copyright owner may choose to designate.)* ■

Software An Industry Standard for CP/M & 8086



Uniquely User Oriented

VEDIT is user oriented to make your editing for program development and word processing as fast and easy as possible. The customization (installation) process makes VEDIT the only editing package that allows you to determine your own keyboard layout and use any available cursor and function keys. Just think of the difference it makes in your ease of learning and usage to type cursor and function keys instead of memorizing obscure control characters. This customization is menu driven, extends to much more and takes only a few minutes.

Unequaled Hardware Support

The CRT version directly supports over 35 terminals (including ANSI standard) in its installation menu and utilizes 'smart' terminal features such as line insert/delete, reverse scroll, status line and reverse video. Function keys on terminals like the Televideo 920/950, Heath H19, and IBM 3101 are all supported. The memory mapped version is extremely flexible, supports bank select such as on the SSM VB3 and screen sizes up to 70 X 200.

Sophisticated Full Screen Editing

VEDIT gives you true 'what you see is what you get' full screen editing with an extensive set of features for creating and editing standard text files of up to one diskette in length. Very large files are effortlessly handled by VEDIT's ability to edit up to 47K of a file entirely in memory without performing any slow and annoying disk accessing. And you can handle multiple files, insert a specified line range of another file anywhere in the text and even change diskettes.

User Oriented Features

You get the features you expect, like searching, a scratchpad buffer for moving and rearranging sections of text, complete file handling on multiple drives and flexible macros. For ease of use VEDIT has features you won't find elsewhere, like automatic indenting for use with structured languages such as Pascal and PL/I. You are less likely to make a mistake with VEDIT, but if you do, one key will 'Undo' the changes you just made to a screen line. And if you run out of disk space with VEDIT, you can easily recover by deleting old files or even inserting another diskette. It is therefore no surprise that VEDIT is the industry standard for program development editing.

Word Processing

VEDIT is suitable for simple stand-alone word processing, or it may be used in conjunction with a text processor. Its features include word wrap, adjustable left margin, reformatting of paragraphs, word oriented cursor movement and deleting, and imbedding of printer control characters. VEDIT can print any portion of your file and display the cursor's line and column positions.

Now for
IBM
Personal Computer
XEROX 820

Ordering

Please specify your microcomputer, video board or the CRT terminal version, the 8080, Z80 or 8086 code version and disk format.

VEDIT - Disk and manual
For 8080 or Z80 . . . . $145
For CP/M-86 or IBM MDOS . $195
Manual only $15

VISA and MASTER CARD Welcome.

Apple II Softcard • TRS-80 II and I
SuperBrain • Heath H8/H89 • Altos
NorthStar • Vector • MP/M • IBM

1955 Pauline Blvd., Suite 200
Ann Arbor, Michigan 48103
(313) 996-1299



CP/M and MP/M are registered trademarks of Digital Research, Inc. Apple II is a registered trademark of Apple Computer, Inc. Softcard is a trademark of Microsoft. TRS-80 is a trademark of Tandy Corporation.

Circle 450 on inquiry card.

Here's just a taste of our great prices.

To really feast your eyes, send for our new catalog.

Great prices are only one feature of our new catalog. More importantly, we think you'll find it to be a well-written, well-organized reference tool.

When you receive our catalog, you get with it our committment to help you keep it up to date.

Unlike most catalogs that are obsolete the moment they're printed, ours is designed to accommodate all the rapid-fire changes in micro-computer hardware and software. Its loose-leaf-binder format makes it a snap to add the new pages we'll send out on a regular basis.

Our new catalog was developed on exactly the same principles as our business — to offer you the lowest possible prices combined with the highest quality of service.

16K RAM KITS . . . 13.95

Set of 8 NEC 4116 200 ns. Guaranteed one full year.

DISKETTES

ALPHA DISKS 21.95

Single sided, certified Double Density 40 Tracks, with Hub-ring. Box of 10. Guaranteed one full year.

VERBATIM DATALIFE

MD 525-01. 10. 16	26 50
MD 550-01 10. 16	44 50
MD 557-01. 10 16	54 95
MD 577-01. 10. 16	34 80
FD 32 or 34-9000	36 00
FD 32 or 34-8000	44 95
FD 34-4001	48 60

DISKETTE STORAGE

5¼" PLASTIC LIBRARY CASE	2 50
8" PLASTIC LIBRARY CASE	3 50
PLASTIC STORAGE BINDER w/ Inserts	9 95
PROTECTOR 5¼" (50 Disk Capacity)	23 95
PROTECTOR 8" (50 Disk Capacity)	29 95
DISK BANK 5¼"	5 95
DISK BANK 8"	6 95

NEC PERSONAL COMPUTERS

PC-8001A CPU	899 00
PC-8012A I/O	559 00
PC-8033A DISK I/O	125 00
PC-8031A DUAL DISK	899 00

ALTOS COMPUTER SYSTEMS

Call Alpha Byte for our low Altos prices.

ATARI COMPUTERS

ATARI 800	699 00
ATARI 400 (16K)	339 00
ATARI 810 DISK DRIVE	449 00
ATARI 850 INTERFACE	449 00
ATARI 410 PROGRAM RECORDER	79 00
EPSON CABLE	35 00
MEMORY MODULE (16K)	89 95
JOYSTICK CONTROLLERS	10 00
PADDLE CONTROLLERS	19 95
STAR RAIDERS	35 00
MISSILE COMMAND	35 00
ASTEROIDS	35 00

INTEC PERIPHERALS RAM MODULES

48K FOR ATARI 400	279 00
32K FOR ATARI 800	135 00

ACTIVISION ATARI CARTRIDGES

LAZAR BLAST	21.95
SKIING	21.95
DRAGSTER	21.95
BOXING	21.95
CHECKERS	21.95
BRIDGE	21 95
KABOOM	21 95

HEWLETT PACKARD

HP CALCULATORS

HP-11C LCD SCIENTIFIC	115.95
HP-12C LCD BUSINESS	128.95
HP-37E BUSINESS	64 95
HP-32E SCIENTIFIC w / STATS	46.95
HP-33C Programmable Scientific	76 95
HP-41C Advanced Programmable	211 95
HP-41CV Advanced Prog 2K mem	274 95

HP-41 PERIPHERALS

HP-82106A MEMORY MODULE	27.95
HP-82170A Quad Memory Module	89 00
HP-82143A PRINTER/PLOTTER	324 95
HP-82160A IL INTERFACE	119 00
HP-82161A DIGITAL CASSETTE	419.00
HP MATH PAC	29.00
HP STATISTICS PAC	29.00
HP REAL ESTATE PAC	39.00
HP SURVEYING PAC	29.00
HP STRUCTURAL ANALYSIS PAC	39.00

HP COMPUTERS

HP-85A PERSONAL COMPUTER	21 95
HP SINGLE 5¼" DISK DRIVE	12.95
HP DUAL DISK DRIVE	19 95
HP-85A 16K MEMORY MODULE	239.00
HP-7225B GRAPHICS PLOTTER	21.95
HP PLOTER MODULE	605.00
HP HP-IB INTERFACE	329.00
H P STO APPLICATIONS PAC	83.00
HP GENERAL STATISTICS PAC	83.00
HP GRAPHIC PRESENTATIONS	159.00
HP VISICALL PLUS	159 00
HP ROM DRAWER	39 00
HP PRINTER/PLOTTER ROM	116.00
HP MASS STORAGE ROM	116 00
HP RS-232 INTERFACE	329 00

PRINTERS

ANADEX DP 9500	1295.00
ANADEX DP 9501	1295.00
C-ITOH 25 CPS PARALLEL	1440.00
C-ITOH 25 CPS SERIAL	1495.00
C-ITOH 45 CPS PARALLEL	1770.00
C-ITOH 40 CPS SERIAL	1870.00
C-ITOH PROWRITER PARALLEL	549.00
C-ITOH PROWRITER SERIAL	695.00
C-ITOH COMET I	289.00
EPSON MX-80	$CALL
EPSON MX-80 F/T	$CALL
EPSON MX-100 GRAPHIC	$CALL
EPSON GRAFTRAX	90.00
IDS-445G PAPER TIGER	779.00
IDS-460G PAPER TIGER	945.00
IDS-560G PAPER TIGER	1195.00
NEC SPINWRITER 3510 S. RO	2095.00
NEC SPINWRITER 3530 P. RO	2095.00
NEC SPINWRITER 7710 S. RO	2545.00
NEC SPINWRITER 7730 P. RO	2545.00
NEC SPINWRITER 7700 D SELLUM	2795.00
NEC SPINWRITER 3500 SELLUM	2295.00
OKIDATA MICROLINE 80	389.00
DKIDATA MICROLINE 82A	549.00
OKIDATA MICROLINE 83A	799.00
OKIDATA MICROLINE 84	1199.00
OUME 9/45	2149.00
MALIBU 200 DUAL MODE	2695.00

CORVUS

FOR S-100, APPLE OR TRS-80 MOD I, III

Controller. Case/P.S., Operating System, A & T.

5 MEGABYTES	3245.00
10 MEGABYTES	4645.00
20 MEGABYTES	5545.00
MIRROR BACK-UP	725.00

APPLE HARDWARE

VERSA WRITER DIGITIZER	259.00
ABT APPLE KEYPAD	119.00
MICROSOFT Z-80 SOFTCARD	299.00
MICROSOFT RAMCARD	159.00
VIDEX 80 x 24 VIDEO CARD	299.00
VIDEX KEYBOARD ENHANCER II	129.00
VIDEX ENHANCER REV 0-6	99.00
VIDEX SOFT SWITCH	29 00
M & R SUPERTERM 80 x 24 VIDEO BD.	315.00
SSM AID BOARD (INTERFACE) A & T	165.00
SSM AID BOARD (INTERFACE) KIT	135.00
APPLE FAN	44.95
T/G JOYSTICK	54.95
T/G PADDLE	34.95
VERSA E-Z PORT	21.95
MICRO SCI A40 W/CONTROLLER	479.00
MICRO SCI A40 W/O CONTROLLER	409.00
MICRO SCI A70 W/CONTROLLER	629.00
MICRO SCI A70 W/O CONTROLLER	549.00
THE MILL-PASCAL SPEED UP	329.00
PROMETHEUS VERSACARD	229.00
SUPERCLOCK II	129.00
LAZAR LOWER CASE +	59.00
MICROBUFFER II 16K	259.00
MICROBUFFER II 32K	299.00
WIZARD 80 COL VIDEO	279.00

MONITORS

NEC 12" GREEN MONITOR	199.00
NEC 13" COLOR MONITOR	399.00
SANYO 12" MONITOR (B & W)	249.00
SANYO 12" MONITOR (GREEN)	269.00
SANYO 13" COLOR MONITOR	469.00
ZENITH 13" HI RES GREEN MDN	139.00
AMDEK COLOR I	389.00
AMDEK RGB COLOR	859.00
AMDEK RGB INTERFACE	169.00

Circle 17 on inquiry card.

MOUNTAIN HARDWARE

CPS MULTIFUNCTION BOARD	199.00
SUPERTALKER SD200	259.00
ROMPLUS W/ KEYBOARD FILTER	179.00
ROMPLUS W/O KEYBOARD FILTER	130.00
KEYBOARD FILTER ROM	49.00
COPYROM	49.00
MUSIC SYSTEM	369.00
ROMWRITER	149.00
APPLE CLOCK	252.00
A/D + D/A	299.00
EXPANSION CHASSIS	625.00

CALIF. COMPUTER SYSTEMS

S-100 BOARDS

2200A MAINFRAME	459.00
2065C 64K DYNAMIC RAM	539.00
2422 FLOPPY DISK CONT. & CP/M*	359.00
2710 FOUR SERIAL I/O	279.00
2718 TWO SERIAL/TWO PARALLEL I/O	269.00
2720 FOUR PARALLEL I/O	199.00
2810 Z-80 CPU	259.00

APPLE BOARDS

7710A ASYNCHRONOUS S. INTERFACE	149.00
7712A SYNCHRONOUS S. INTERFACE	159.00
7424A CALENDAR CLOCK	99.00
7728A CENTRONICS INTERFACE	105.00

VISTA COMPUTER CO.

APPLE VISION 80-80 COL CARD	329.00
APPLE 8" DISK DRIVE CONTROLLER	549.00

MODEMS

NOVATION CAT ACOUSTIC MODEM	145.00
NOVATION D-CAT DIRECT CONNECT	165.00
NOVATION AUTO-CAT AUTO ANS	219.00
NOVATION APPLE-CAT	349.00
UDS 103 LP DIRECT CONNECT	175.00
UDS 103 JLP AUTO ANS	209.00
HAYES MICROMODEM II (APPLE)	299.00
HAYES 100 MODEM (S-100)	325.00
HAYES SMART MODEM (RS-232)	249.00
HAYES CHRONOGRAPH	225.00
LEXICON LX-11 MODEM	109.00
RACAL VADIC 1200 BAUD/212A	795.00

TERMINALS

TELEVIDEO 910	639.00
TELEVIDEO 912C	745.00
TELEVIDEO 920C	830.00
TELEVIDEO 950C	995.00
ZENITH Z-19	799.00

TRS-80 MOD I HARDWARE

PERCOM DATA SEPARATOR	27.00
PERCOM DOUBLER II	159.00
TANDON 80 TRACK DISK DRIVE	429.00
TANDON 40 TRACK DISK DRIVE	289.00
LNW DOUBLER W/ DOSPLUS 3.4D	159.00
MOD III DRIVE KIT	649.00

MORROW DESIGNS

FLOPPY DISK SYSTEMS

Controller, P.S., Microsoft Basic, CP/M* A & T.

DISCUS 2D (Single Drive — 500K)	869.00
DISCUS 2D (Dual Drive — 1 MEG)	1499.00
DISCUS 2 + 2 (Single Drive — 1 MEG)	1099.00
DISCUS 2 + 2 (Dual Drive — 2 MEG)	1999.00

HARD DISK SYSTEMS

Controller, P.S., Microsoft Basic, CP/M® A & T.

DISCUS M10 (10 Megabytes)	3099.00
DISCUS M26 (26 Megabytes)	3749.00

ISOLATORS

ISO-1 3-SOCKET	53.95
ISO-2 6-SOCKET	53.95

BARE DRIVES

TANDON 5¼ INCH

100-1 SINGLE HEAD 40 TRK	219.00
100-2 DUAL HEAD 40 TRK	299.00
100-3 SINGLE HEAD 80 TRK	299.00
100-4 DUAL HEAD 80 TRK	429.00

TANDON THINLINE 8 INCH

848-1 SINGLE SIDE	459.00
848-2 DUAL SIDE	549.00

MICRO PRO

APPLE CP/M*

WORDSTAR*	249.00
SUPERSORT*	145.00
MAILMERGE*	90.00
DATASTAR*	215.00
SPELLSTAR*	169.00
CALCSTAR*	169.00

CP/M®

WORDSTAR	310.00
SUPERSORT	195.00
MAILMERGE	110.00
DATASTAR	245.00
SPELLSTAR	195.00
CALCSTAR	239.00

MICROSOFT

APPLE

FORTRAN*	165.00
BASIC COMPILER*	315.00
COBOL*	595.00
Z-80 SOFTCARD	299.00
RAMCARD	159.00
TYPING TUTOR	17.95
OLYMPIC DECATHLON	24.95
TASC APPLESOFT COMPILER	159.00

CP/M®

BASIC 80	299.00
BASIC COMPILER	319.00
FORTRAN 80	369.00
COBOL 80	595.00
MACRO 80	189.00
mu MATH/mu SIMP	219.00
mu LISP/mu STAR	175.00

APPLE SOFTWARE

MAGIC WINDOW	79.00
MAGIC SPELL	59.00
BASIC MAILER	59.00
APPLE PIE	99.00
DB MASTER	179.00
PFS: PERSONAL FILING SYSTEM	79.00
PFS: REPORT	79.00
Z-TERM*	89.95
Z-TERM PRO*	129.95
ASCII EXPRESS	63.95
HAYDEN APPLESOFT COMPILER	149.00
EASY WRITER-PRO	199.00
EASY MAILER-PRO	79.00
EXPEDITER II APPLESOFT COMPILER	73.95
A-STAT COMP. STATISTICS PKG.	129.00
SUPER TEXT II	129.00
FINANCIAL PARTNER	199.00
LISA 2.5	59.95
SUPERSCRIBE II	99.95

CONTINENTAL SOFTWARE

G/L	199.00
A/R	199.00
A/P	199.00
PAYROLL	199.00
PROPERTY MGMT	399.00
THE HOME ACCOUNTANT	59.95

PERSONAL SOFTWARE

DESKTOP PLAN II	199.00
VISIPLOT	179.00
VISITREND/VISIPLOT	239.00
VISIDEX	199.00
VISITERM	79.00
VISICALC	199.00
VISIFILES	209.00

CP/M® SOFTWARE

THE WORD-SPELL CHECK	75.00
d BASE II	599.00
SUPER CALC	229.00
SPELLGUARD	239.00
P & T CP/M® MOD II TRS-80	175.00
COMMX TERMINAL PROG.	82.50
C BASIC 2	115.00
PASCAL Z	349.00
PASCAL MT +	439.00
PASCAL/M	205.00
SYSTEMS PLUS — G/L, A/R, A/P, P/R	1799.00

CONDOR I	579.00
CONDOR II	849.00

DIGITAL RESEARCH

MAC	89.00
SID	69.00
ZSID	97.00
PL/ 1-80	439.00

SUPERSOFT

DIAGNOSTIC I	69.00
DIAGNOSTIC II	89.00
'C' COMPILER	179.00
UTILITIES I	59.00
UTILITIES II	59.00
RATFOR	89.00
FORTRAN	239.00

TRS-80 GAMES

TEMPLE OF APSHAI	34.95
HELLFIRE WARRIOR	34.95
STAR WARRIOR	34.95
RESCUE AT RIGEL	24.95
CRUSH, CRUMBLE AND CHOMP	24.95
INVADERS FROM SPACE	17.95
PINBALL	17.95
STAR TREK 3.5	17.95
MISSILE ATTACK	18.95
STAR FIGHTER	24.95

TRS-80 SOFTWARE

NEWDOS/80 2.0 MOD I, II	139.00
LAZY WRITER MOD I, II	165.00
PROSOFT NEWSCRIPT MOD I, III	99.00
SPECIAL DELIVERY MOD I, III	119.00
X-TRA SPECIAL DELIVERY MOD I, III	199.00
TRACKCESS MOD I	24.95
OMNITERM SMART TERM. MOD I, III	89.95
MICROSOFT BASIC COMP. FOR MOD I	165.00
LDOS 5.1 MOD I, II	159.00

APPLE GAMES

PERSONAL SOFTWARE

CHECKER KING	21.95
GAMMON GAMBLER	21.95
BRIDGE PARTNER	21.95
MONTY PLAYS MONOPOLY	29.95
ZORK I	32.95
ZORK II	32.95
MONTY PLAYS SCRABBLE	34.95

BRODERBUND

GALAXY WARS	20.95
ALIEN RAIN (AKA GALAXIAN)	20.95
ALIEN TYPHOON	20.95
APPLE PANIC	24.95
MIDNIGHT MAGIC	29.95
SPACE QUARKS	24.95

AUTOMATED SIMULATIONS

INVASION ORION	20.95
STAR WARRIOR	32.95
TUES. MORNING QUARTERBACK	25.95
CRUSH, CRUMBLE AND CHOMP	24.95
THE DRAGON'S EYE	20.95

MUSE SOFTWARE

ROBOT WARS	32.95
THREE MILE ISLAND	32.95
A.B.M.	20.95
GLOBAL WAR	20.95
CASTLE WOLFENSTEIN	24.95

ON-LINE SYSTEMS

WIZARD AND PRINCES	29.95
MISSILE DEFENSE	25.95
SABOTAGE	20.95
SOFT PORN ADVENTURE	24.95
THRESHOLD	31.95
JAW BREAKER	24.95
CROSSFIRE	16.45
TIME ZONE	69.95
H/R FOOTBALL	32.95
H/R CRIBBAGE	20.95
PEGASUS II	25.95

SIRIUS SOFTWARE

SPACE EGGS	24.95
GORGON	32.95
SNEAKERS	24.95
EPOCK	29.95
BEER RUN	24.95
HADRON	29.95
PULSAR II	24.95
EPOCK	29.95

EDU-WARE

PERCEPTION PKG.	19.95
COMPU-READ	24.95
STORY TELLER	18.95
COMPU-MATH: ARITHMETIC	39.95
COMPU-MATH: FRACTIONS	34.95
COMPU-MATH: DECIMALS	34.95
COMPU-SPELL (REQ. DATA DISK)	24.95
COMPU SPELL DATA DISKS 1-4, ea.	17.95

MORE GREAT APPLE GAMES

COMPUTER QUARTERBACK	32.95
TORPEDO FIRE	49.95
THE SHATTERED ALLIANCE	49.95
POOL 1.5	29.95
ULTIMA	33.95
RASTER BLASTER	24.95
FLIGHT SIMULATOR	27.95
INTERNATIONAL GRAND PRIX	25.95
SARGON II	28.95
SHUFFLE BOARD	29.95
FIREBIRD	24.95
SNACK ATTACK	24.95
THIEF	24.95
ROACH HOTEL	29.95
JABBERTALKY	24.95
THE WARP FACTOR	32.95
COSMO MISSION	24.95

SUPPLIES


AVERY TABULABLES

1,000 3½ x 15/16	8.49
3,000 3½ x 15/16	14.95
5,000 3½ x 15/16	19.95

FAN FOLD PAPER

(Prices F.O.B. S.P.)

9½ x 11 18lb WHITE 3,000 ct.	29.00
14 7/8 x 11 18lb WHITE 3,000 ct.	39.00



To order, or for information, call:

(213) 706-0333

To use our 24-hour modem order line, call: (213) 883-8976.

We guarantee everything for 30 days. If anything is wrong, return the item and we'll make it right. And, of course, we'll pay the shipping charges.

We accept Visa and Master Card on all orders; COD up to $300.00.

Add $2.00 for standard UPS shipping and handling on orders under 50 lbs. delivered in continental U.S. Call for shipping charges over 50 lbs. Foreign, FPO and APO orders, add 15% for shipping. Californians add 6% sales tax.

Prices quoted are for stock on hand and subject to change without notice.

31245 LA BAYA DRIVE, WESTLAKE VILLAGE, CALIFORNIA 91362

Circle 17 on inquiry card.

CP/M is a reg. trademark of Digital Research.

*Requires Z-80 Softcard.

Use Infrared Communication for Remote Control

The Texas Instruments SN76832AN Infrared Remote-Control Receiver simplifies the tough job of receiving modulated infrared light.

Steve Ciarcia
POB 582
Glastonbury, CT 06033

Two dozen images of Howard Cosell danced before my eyes. Suddenly there were two dozen images of acid indigestion, and then, just as suddenly, Howard Cosell was back.

Undaunted, I stood my ground, which happened to be in the television department of a large store a few miles from home. I was wielding a small box covered with push-button switches, trying out a display of remote-controlled TV sets.

There has been a silent revolution going on in the TV remote-control business. Silent indeed. No longer do the control boxes emit ultrasonic impulses that drive all the dogs in the household into hysterics. Today's remote-controlled TV sets receive viewers' instructions on beams of infrared light.

Detecting an information-bearing infrared beam in an infrared-saturated environment is a signal-to-noise horror show.

The silent revolution has also made controlling the sets easier. Ultrasonic remote-control units, because of their complexity and cost, usually have had only two or three control channels, making channel changing a tedious, repetitive task and limiting the set functions that could be remotely commanded.

Infrared-light units are not only practical; they have become much more sophisticated, often making available thirty or more control channels for less than the cost of a pair of ultrasonic transducers.

To supply the demand for support circuitry to build remote-control systems, several semiconductor manufacturers (such as General Instrument, Hitachi, Signetics, and Texas Instruments) are producing integrated circuits that encode and decode the command information used in these TV remote controls. Most encoder chips are designed to accept a keyboard input and directly modulate an infrared light source. At the receiving end, the encoded data stream is decoded by a decoder chip and a few discrete components.

I decided to buy a pair of infrared encoder/decoder chips and build a

About the Author

Fifteen years ago, Steve Ciarcia (pronounced "see-AR-see-uh") gave up a promising career as a security guard for the Famous Writers' School to become an electrical engineer and computer consultant. He has experience in nuclear instrumentation, process control, digital design, product development, and marketing. In addition to writing for BYTE magazine, he has published several books, including Build Your Own Z80 Computer *(BYTE Books, 1981).*

When he's not working in his Circuit Cellar, he enjoys cooking such foods as Eggplant Siciliana and Shrimp Provençale and driving his DeTamaso Pantera sports car.




Figure 1: *Relative spectral characteristics of infrared light-emitting diodes and photodiodes.*

quick and dirty remote-control unit. It was going to be so easy.

Not so fast! There was a missing link: detecting the beam of infrared light so it could be decoded.

To Find a Missing Link

Was I going to let a little thing like a beam of light stop me? Of course not. I started investigating how to sense a beam of infrared light.

Once again I found myself working on a topic about which I could find very little published information of use in practical experimentation. I suspect there have been few magazine articles dealing with infrared-light communication because of the difficulty in detecting an information-bearing beam of infrared light in an infrared-saturated environment. It's a signal-to-noise horror show! The sensitivities and dynamic ranges required are beyond simple amplifier-design techniques. My goal of building an inexpensive remote-control scheme using TV-set encoder/decoder chips therefore had to wait until I first designed a reliable infrared communication receiver.

This article contains both a discussion of optical communication and a construction project of a useful infrared-light transmitter/receiver interface for use with a personal computer. Along the way I attempt to answer some basic questions including the following: In what kind of applications can light transmission be useful? Why use infrared rather than visible light? What is the best choice of optoelectronic components for each application?

Why Use Light?

Light is used in communication for two major reasons: the medium's immunity to certain forms of interference and the relative ease of providing security for the communications link. Electrically noisy motors and other equipment generate electromagnetic interference (EMI) that can play havoc with radio-wave transmissions, and ambient noise can disrupt ultrasonic communication. These problems do not bother light beams, and a protected line-of-sight beam path or waveguide provides fair security against unauthorized interception.

Light can also be used in providing physical security for premises; a prowler might step over a tripwire, but he wouldn't know to avoid an invisible shaft of infrared light aimed at a detector in an alarm system.

What Is Infrared Light?

The segment of the electromagnetic spectrum that we perceive optically as visible light is narrow. On both sides of this band of visible light are regions of radiation that we can't see but which otherwise exhibit similar optical properties. Radiation of wavelengths shorter than we can see is called ultraviolet (UV) light, while wavelengths longer than we can see form infrared (IR) light. Any warm object radiates some amount of infrared radiation.

(Some may quibble with my use of the term "light" to discuss radiation that cannot be seen. I feel that any radiation that can be manipulated optically [by lenses and the like] should be called light, and that's how I am using the term in this article.)

The spectral graph of figure 1 shows that the visible band has wavelengths between about 400 and 700 nm (nanometers). Within the range of 400 to 700 nm, the different frequencies are perceived as different colors. For example, a light beam of 550-nm wavelength is perceived as green. What we perceive as white light contains all the visible frequencies.

Transmitting information on a beam of light is done much the same way as on a radio wave. The light must be amplitude-modulated at some carrier frequency, say 40 kHz. This allows the receiver to differentiate between the light coming from the transmitter and unmodulated ambient light. The data to be transmitted can be modulated onto the carrier in a number of ways, including amplitude and frequency modulation, pulse-width modulation (PWM), and pulse-code modulation (PCM).

For my application of a simple optical remote-control system, the less complicated PCM technique seemed best. This merely consists of turning the 40-kHz-modulated light on and off. At the receiving end, the presence of light is interpreted as a logic 1 and the absence of light as a logic 0.

Why use so high a carrier frequency? We have to use a frequency high enough that the communication is not susceptible to interference. The operating environment of our infrared system may contain such sources of interference as fluorescent lights, which flash at 120 Hz, or television sets, whose screens emit light with interference patterns at over 15 kHz. For open-air optical communication, frequencies at or above 40 kHz are preferred.

Any electrically excited light source can be amplitude modulated, but not




Figure 2: *Cross section of the structure of a standard visible red light-emitting diode.*

all of them at 40 kHz. Modulating a 100-watt incandescent light bulb at such a high frequency is out of the question: the thermal time constant of the filament is much too long. The only light sources capable of switching at such a frequency are electroluminescent devices, of which the light-emitting diode (LED) is the least expensive and most familiar.

In a light-emitting diode, shown in figure 2 on page 42, light is generated when a forward-bias current is applied. This causes electrons to be injected into the n-type (negative-doped, electron-rich) semiconductor material and holes (shortages of electrons) to be injected into the p-type (positive-doped, electron-poor) material.

When the injected electrons and holes recombine with the majority carriers at the p/n junction, energy is released in the form of photons. The pattern of radiation emission can be controlled somewhat by reflective surfaces within the mounting structure and by plastic lenses. Generally, a spherical dome lens with a narrow beam width is best for communication.

The color of the light emitted depends upon what semiconductor materials are used in the p/n junction and how they are doped (seeded with selected impurities): the amounts of energy released in the electron/hole recombinations of different materials vary, and the wavelength (and therefore the color) of light varies in a direct relation to the amount of energy contained in its photons.

Most of the semiconductor materials used in LEDs are compounds of gallium: gallium arsenide phosphide (GaAsP, which emits red, orange, or yellow light), gallium phosphide (GaP, green emitting), gallium aluminum arsenide (GaAlAs, red emitting), and gallium arsenide (GaAs, which emits infrared photons at about 900 to 1000 nm). The efficiency of an LED depends upon wavelength. The longer the wavelength, the higher the efficiency (see the text box "Blue LEDs at Last").

Operating at longer wavelengths, infrared LEDs are more efficient than visible-light red or green LEDs; *IR* LEDs are therefore preferred for line-of-sight beam breaking or communication. For a given power input, an IR LED produces a brighter light than a green LED. Many IR LEDs have radiant-power outputs of more than 10 mW (milliwatts)—for instance, the TIL39 component I have been experimenting with has an 11-mW output at 940 nm.

Efficiency is important, because an LED is almost a point source of light. The illumination it casts on a surface is proportional to its brightness and inversely proportional to the square of the distance to the surface. If we want our open-air communication link to operate over distances as great as 10 meters, our LED light source must be very bright to produce an acceptable signal-to-noise (S/N) ratio using an ordinary-sized receiving photosensor measuring perhaps 0.1 cm^2 (square centimeter).

Other incentives for using IR light are reduced sensitivity to ambient visible light, greater ability to pierce through fog or smoke, and better reflection off most surfaces for a greater chance that the receiver will be able to see the light source.

Choosing the Light Detector

Choosing the proper light detector is as important as selecting the light emitter. Selectivity, response, and inherent noise are important considerations.

There are many materials which function as photoconductors. The simplest are bulk materials such as cadmium selenide (CdSe), lead sulfide (PbS), and cadmium sulfide (CdS).

Blue LEDs at Last

Longtime readers of BYTE may recall Steve's article from several years ago on a self-refreshing LED graphics display (see reference 2). In it, he described how single-color graphic images can be formed on display panels containing arrays of many red light-emitting diodes and suggested that multicolor images could be displayed on a panel that contained arrays of triads of different-color LEDs. But his suggestion was ahead of technology. At that time, no practical method was known for making an LED that could emit blue light.

Now the blue-light barrier has been broken, and in a way eminently suitable to flat-panel graphics displays. In October 1981, the Sanyo Electric Company of Japan unveiled an LED lamp component that contains two separate LED chips, one of which emits blue light at a wavelength of 480 nanometers (see reference 3). The blue-emitting chip is formed from two liquid-phase-epitaxial layers of silicon carbide grown on a silicon-carbide wafer. The other chip, made of gallium phosphide with four epitaxial layers, can emit both red light at 700 nanometers and green light at 565 nanometers. A single component that can produce all three additive primary colors makes possible a full-color, flat-panel LED graphics display.

The voltage potential dropped by the blue LED chip is about 3.5 V, producing 2 mcd (millicandelas) of light, while the two-color chip drops 2 V for 3 mcd of green light and 1.9 V for 3 mcd of red light. Thus we see that real components reflect the theoretical predictions of greater efficiency at longer wavelengths. . . . RSS

Generally these materials exhibit poor temperature stability and are sensitive over a very broad range of wavelengths.

The familiar semiconductors germanium (Ge) and silicon (Si), on the other hand, are sensitive chiefly to the near-infrared (wavelengths close to the visible range) light radiated by IR LEDs.

Two types of devices that use silicon and germanium are photodiodes and phototransistors. Phototransistors are constructed in much the same manner as commonplace planar-diffused transistors. The base area is usually made large to provide an area into which incident light can penetrate and generate electron/hole pairs. Phototransistors are subject to the variation in performance typical of all transistors.

Many of the bad traits of phototransistors are eliminated in *PIN photodiodes*. The term PIN is an acronym meaning that the components are made from three layers of different types of semiconductor material: p-type, "intrinsic," and n-type. A PIN photodiode is one in which two heavily doped p and n regions are separated by a lightly doped region (which exhibits mostly properties intrinsic to the substance). Its large depletion region (interface region between the p-type and intrinsic layers) provides the PIN photodiode with much faster speed, lower noise, and greater efficiency at longer wavelengths.

Photo 1 shows a TIL413 infrared-sensitive PIN photodiode (right) and a TIL39 infrared light-emitting diode (left).




Photo 1: *The TIL413 infrared-sensitive PIN photodiode (right) and the TIL39 infrared light-emitting diode (left).*




Photo 2: *Prototype of the infrared-light remote-control or communication receiver of figure 4.*

Ready-Made IR Detector

Designing a reliable infrared-light detector/receiver is no simple task; it has been the major obstacle in designing any infrared communication system. The engineer must coax his receiver into extracting the transmitted data from a dismaying amount of background noise, and he must take care that his design will withstand the impairments to theoretical performance caused by deviations from ideal component values and manufacturing techniques. But there is nothing conceptually complicated in the receiver, just a photodiode and a series of amplifiers and filters.

I haven't presented an infrared communication system before now because I couldn't design one that I felt readers could successfully duplicate. But recently I discovered that an integrated circuit has been developed to do all the hard work. Texas Instruments recognized the need and designed a chip which eliminates all the frustrations in building the IR receiver.

The new component is the SN76832AN Infrared Remote-Control Receiver. This chip replaces a combination of several integrated cir-

+V
R2
VCO TIMING
C5
2
1
16
VCC
C4
C10
R3
LOOP FILTER
5
VCO
÷2
10
C9
D1 TIL413 PHOTO-DIODE
SUPPLY DECOUPLING
11
L1
R1
C1
TUNED INPUT STAGE
3 OUTPUT ENABLE
4 DATA OUTPUT
GND GND
13 12 7 8 6 14 9 15
C2
C3
C7
C8
C6
DECOUPLING CAPACITOR
COUPLING CAPACITOR
DIFFERENTIAL AMPLIFIER DECOUPLING CAPACITORS
OUTPUT FILTER CAPACITOR




Figure 3: *Block diagram of the internal structure of the Texas Instruments SN76832AN Infrared Remote-Control Receiver.*

cuits and discrete components. It connects directly to a PIN photodiode and is designed to receive and detect digitally encoded information modulated on a carrier (typically 40 kHz). It has an open-collector gated output suitable for direct operation with a microprocessor. For the benefit of readers of BYTE, the Micromint will be distributing a kit that includes the SN76832AN (see page 49).

A block diagram of the SN76832AN receiver chip is shown in figure 3 . Inside the receiver chip, the signal from the photodiode is connected to an amplifier with an input impedance of 220 kilohms and a typical gain of 1.6 million volts/amp at 40 kHz. The output of this first amplifier stage is fed to a differential amplifier coupled to the demodulator section.

The receiver chip demodulates the signal by comparing its amplitude and phase with that of reference signals produced by a voltage-controlled oscillator (VCO) and a frequency divider. The bandwidth and capture frequency are controlled by external passive components. The demodulated output signal is filtered and gated by the output-enable control signal. (A high level on the output-enable line causes the demodulated signal to appear on the output line. If the demodulated signal is to be constantly present, the output-enable line should be tied high.)

Figure 4 on page 45 is a schematic diagram of the completed circuit for a very sensitive IR receiver which operates at a carrier frequency of 40 kHz. A prototype is shown in photo 2.

In the receiver circuit of figure 4, potentiometer R1 sets the frequency of the VCO, which is twice that of the capture frequency (the center frequency of the incoming modulated carrier signal). With the external oscillator-control components shown, this circuit can detect carrier frequencies from 20 kHz to 70 kHz. The rest of the components, however, are optimized for 40-kHz operation. The photodiode I suggest is a type TIL413, because it has a spherical lens that allows it to "see" over a wider angle,

Figure 4: *Schematic diagram of a remote-control or communication circuit based on the SN76832AN. This circuit is set up for use at 40 kHz, although the voltage-controlled oscillator can be adjusted from 20 kHz to 70 kHz. Any voltage from +8 V to +18 V may power the circuit.*

thus enhancing the effective sensitivity. In a pinch other photodiodes such as the TIL100 may be used.

The data output is permanently enabled in my design unless the external-output-enable line is brought to ground potential by external means. The output signal is buffered and level-shifted through transistors Q1 and Q2 to provide a TTL- (transistor-transistor logic) compatible output. The circuit runs at any voltage between +8 V (volts) and +18 V. I run it at +12 V.

When the circuit "sees" a 40-kHz-modulated infrared light beam, the output goes to a normally high state, and the indicator light (LED1) comes on. The output then changes state in accordance with the demodulated data, exactly duplicating the sequence of the logic levels of the input signal that was fed into the infrared transmitter.




Photo 3: *Prototype of the infrared transmitter assembly, internal view.*



Photo 4: *The assembled infrared remote-control/communication system. On the left is the infrared receiver; the transmitter is to the right. The TIL413 photodiode is the small projection to the right of center of the receiver's front panel; the small projection on the left is a visible red LED that lights when the infrared carrier is detected.*

Number	Type	+9V	GND
IC1	CD4011	14	7
IC2	NE555	8	1

Figure 5: *Schematic diagram of a handheld infrared remote-control transmitter. Four pushbutton switches actuate a NAND gate wired as an oscillator; different frequencies may be selected for testing or in communicating simple command functions. Two high-power infrared and one visible indicator light-emitting diodes are modulated at a carrier frequency of 40 kHz; control signals are sent as a simple on/off modulation of the 40-kHz-modulated light beam.*




Figure 6: *A simple circuit that provides only a 40-kHz carrier modulation for an infrared beam. This may be used for simple beam-breaking intrusion-detection schemes.*

A Matching Transmitter

After building and testing the receiver section, I argued with myself about an appropriate transmitter. The "hardware" side of me wanted to follow up on the inspiration that got me started on the project by using one of those complex encoder/decoder chip sets previously mentioned. The encoder chip would be built into the transmitter, and the decoder would be connected to the infrared-receiver circuit, providing parallel decoded outputs.

The "software" side of me (I do have one!) argued that anything these chips could do in encoding and decoding could be done by any fairly competent programmer in a few lines of code. The real challenge of the project was creating the infrared-light communication link, not encoding and decoding the signal.

In the end, I decided that my inspiring vision was not worth the trouble, and I designed a relatively simple transmitter essentially consisting of a gated 40-kHz oscillator driving a pair of high-power infrared LEDs. As you can see in the schematic diagram of figure 5, jumper connections on the oscillator can be changed to allow modulation from an external signal source or to allow the communication link to be tested by your pushing one of the four pushbutton switches connected to the CD4011 NAND-gate component (IC1). The prototype transmitter circuitry is shown in photo 3 on page 45. The assembled transmitter and receiver are shown in photo 4 on the same page.

In the transmitter circuit, IC1 is configured as a low-frequency oscillator. The four switches control the frequency of the oscillator. With the "1" button pressed, an 8-Hz, 50-percent-duty-cycle waveform is directed to the IR LEDs. Pressing "2" produces a 16-Hz waveform, pressing "4" produces a 32-Hz waveform, and pressing "8" produces a 64-Hz waveform (the exact frequencies may vary somewhat). By pressing two or more of the buttons together, a total of 16 distinct frequencies can be created.




Photo 5: *The familiar BSR X-10 hand-held control unit. This was built to work using ultrasonic pulses, but it can be modified to use infrared light. The added infrared LED can be seen on top of the housing.*




Figure 7: *Modification of the hand-held ultrasonic transmitter of the BSR X-10 Home Control System that converts it to infrared-light operation.*

System Testing and Use

To test the transmitter and receiver, aim the transmitter's IR LEDs in the general direction of the receiver unit and press the buttons. The output signal from the receiver should be the frequency corresponding to the switch operated on the transmitter.

The single-bit output of the receiver can be connected to any convenient input line on your computer (such as a game-paddle input), and a simple program can be written to count and determine the frequency of the input signal. While much higher frequencies can be transmitted by this system, I chose these low, pulsed frequencies so that even a BASIC program could count the frequency. Nevertheless, if the frequencies are still too fast, simply substitute a higher capacitance for C1 in the transmitter circuit of figure 5 on page 46.

The external modulation input of the transmitter is quite suitable for use in a wireless data link. Attach a serial output from your computer to the external data-input line, and connect the output of the receiver to another computer or to a remotely located printer.

In fulfillment of my original plan, I decided to configure the transmitter in my infrared remote-control system as a hand-held actuator.

If you simply want an infrared beam source for use as an intrusion detector in a security system, you don't have to build the entire data-transmission circuit; the simple 40-kHz oscillator in figure 6 on page 46 will work nicely.

TV-Set Controllers, Too

After building the IR receiver and transmitter circuits described, I discovered that signals from any of the commercial TV-set remote-control transmitters could be received just as easily as those from the transmitting device I had designed. Most set controls operate with carriers in the 38-kHz to 41-kHz range. Of course, the data output that you get is a coded bit stream, generally 5 to 12 bits repeating every half second, but this should be no obstacle.

While I haven't analyzed the coded TV-set-control data, they should be susceptible to differentiation by the same methods that worked for my simple frequency input. Perhaps you'd have to use a machine-language program to catch the fast data (about 25 milliseconds per word), but the results would be a professional-quality, very versatile remote interface to your computer.

BSR Goes Infrared

The remote-control transmitters for television sets are not the only means to an elegant remote-control system for your computer.

Perhaps you have on hand the hand-held transmitter from the BSR X-10 Home Control System. (Some of you may remember when I wrote about the BSR X-10; see reference 1.) This unit was made to work using ultrasonic sound, but it can be easily adapted for IR transmission to work with the receiver circuit in this article. Photo 5 shows the adapted BSR X-10 transmitter.

The modification is outlined in figure 7 and shown in photo 6 on page 48. Note that the ground connection should be the black lead directly connecting to the battery. The other two circuit connections are to pins 7 and 14 on the integrated circuit as illustrated. The BSR transmitter already operates using a carrier frequency of 40 kHz. The modification is simply to add an emitter-follower IR LED driver to the output section. The existing ultrasonic transducer can be cut out or used concurrently with the optical transmitter.

The message transmitted by the X-10 hand-held unit is approximately 100 milliseconds (ms) long and is composed of 13 eight-millisecond segments, each of which consists of a burst of 40-kHz signal. The reception




Photo 6: *Interior view of the modified BSR X-10 hand-held transmitter, modified according to figure 7.*

of the 40-kHz carrier will be marked by a high logic level coming out of the infrared receiver board for the duration of the 40-kHz signal. The coded data is sent as a series of 1.2-ms and 4-ms bursts, representing logic 0 and 1 respectively. The complete 13-bit message consists of a start bit (logic 1), 5 data bits corresponding to the key being pressed, 5 bits representing the logical inversion of the first 5 data bits, and 2 stop bits (logic 1). The binary codes and the transmission sequence are shown graphically in figure 8 on page 49.


I'm sorry I was halfway through writing this article before I thought to use the BSR X-10 controller. After the idea struck home, I took a pizza break. Then I came back to the Circuit Cellar, added the modification of figure 7, and verified correct data reception using an oscilloscope. I haven't actually written the code to interpret the BSR controller's signals yet. But considering the well-documented transmission protocol used in the BSR, it may be easier to use this unit rather than figure out the unknown coding of a TV remote-control unit.

The longer the wavelength of its light, the higher the efficiency of an LED.

In Conclusion

Building a reliable infrared receiver has been a goal of mine for a long time. Many of my first designs did eventually work, but they couldn't be easily duplicated. Since I believe that many other experimenters are equally interested in IR communication and have experienced similar frustrations, I have arranged with Micromint to make available a complete kit of the infrared-communication circuits shown in figures 4 and 5. Included with these kits is a complete data sheet on the SN76832AN should you care to configure it for another frequency range.

If you try infrared communication and are successful, you might develop applications for it that have previously been ignored. Certainly experimenters like myself have been looking for better types of man/machine interaction than presently exist. Until computer speech recognition becomes



CHANNEL NUMBER OR FUNCTION	BINARY CODE D8	D4	D2	D1	F
1	0	1	1	0	0
2	1	1	1	0	0
3	0	0	1	0	0
4	1	0	1	0	0
5	0	0	0	1	0
6	1	0	0	1	0
7	0	1	0	1	0
8	1	1	0	1	0
9	0	1	1	1	0
10	1	1	1	1	0
11	0	0	1	1	0
12	1	0	1	1	0
13	0	0	0	0	0
14	1	0	0	0	0
15	0	1	0	0	0
16	1	1	0	0	0
ALL OFF	0	0	0	0	1
ALL LIGHTS ON	0	0	0	1	1
ON	0	0	1	0	1
OFF	0	0	1	1	1
DIM	0	1	0	0	1
BRIGHT	0	1	0	1	1

Figure 8: *Timing diagram and binary command-code table used by the BSR X-10 Home Control System.*

practical, we shall have to be satisfied with pushing buttons to communicate with computers. But perhaps the infrared transmitter and receiver in this article can make the connection a little more convenient.

Next Month:

It's been a long time since I wrote about time, time as measured by a computer's real-time clock. Next month, we'll look at plans for connecting a versatile clock to a personal computer. ■

Editor's Note: *Steve often refers to previous Circuit Cellar articles as reference material for each month's current article. Most of these past articles are available in reprint books from BYTE Books, 70 Main St., Peterborough, NH 03458.* Ciarcia's Circuit Cellar, Volume I *covers articles that appeared in BYTE from September 1977 through November 1978.* Ciarcia's Circuit Cellar, Volume II *contains articles from December 1978 through June 1980.* Ciarcia's Circuit Cellar, Volume III *contains the articles that were published from July 1980 through December 1981.*

Parts Source

The following is available from:
The Micromint Inc.
917 Midway
Woodmere, NY 11598
telephone (516) 374-6793
(for technical data)
(800) 645-3479
(orders only)

Infrared Transmitter/Receiver Kit $42

Includes two printed-circuit boards (one for the transmitter and one for the receiver) and all components shown in figures 4 and 5. Does not include the cases and power supplies shown in the prototype photos. Assembly manual and specification sheets provided.

Please include $2 for delivery within the United States or $6 for foreign delivery. Residents of New York state please add 7% sales tax.

References

1. Ciarcia, Steve. "Computerize a Home," BYTE, January 1980, page 28.
2. Ciarcia, Steve. "Self-Refreshing LED Graphics Display," BYTE, October 1979, page 58. Reprinted in *Ciarcia's Circuit Cellar, Volume II*. Peterborough, NH: BYTE Books, 1981, page 109.
3. Cohen, Charles. "Blue-light LED joins red and green chip in package," *Electronics*, October 6, 1981, page 6E.
4. Hewlett-Packard Optoelectronics Division—Applications Engineering Staff. *Optoelectronics Applications Manual*. New York: McGraw-Hill Book Company, 1977.
5. Seippel, Robert G. *Optoelectronics*. Englewood Cliffs, NJ: Prentice-Hall, 1981.

How to Use Color Displays Effectively

A look at the elements of color vision and their implications for programmers

Color is becoming an affordable option for personal computers, but like any new tool, it has special limitations and requirements.

John Durrett and Judi Trezona
Center for Automated Systems in Education (CASE)
Southwest Texas State University
San Marcos, Texas 78666

Walk into a computer store these days and you'll be blitzed by color: games with vividly colored objects moving amid colored textual instructions; graphs representing many relationships at once, using a different color for each; and screens full of color-highlighted text. If you're a veteran of the black-and-white days of personal computing, you'll probably feel like celebrating.

After spending some time with one of those colorful systems, however, your eyes may give you quite a different message. Where did those shadows on the screen come from? Why is the red fading in and out? Is that a purple enemy ship or a blue friendly ship?

Your eyes will be telling you that something is wrong with the color; it actually seems to *interfere* with the presentation of information. Misuse of color is all too common in software designed to take advantage of this new small-computer capability. Like all new tools, color has its own special limitations and requirements, many of which are based on human physiology and psychology.

Color vision is a complex process of three interacting variables: hue, brightness and saturation.

Physiology of Color Vision

The eye receives light in an area known as the *retina*. An extension of the brain, the retina is the most complex component of the eye. The light-sensitive cells within the retina are called *rods* and *cones*. Rods respond to low levels of illumination, producing visual sensations of shades of gray but no color. They respond most to blue light and require about 30 minutes to totally adapt to changes in illumination brightness.

Cones respond to high illumination, producing visual sensations of color and detail. They require about 7 minutes to totally adapt to changes in illumination. Each cone is sensitive to red, green, or blue light; blue receptors are significantly less sensitive than are green and red.

Near the retina's center is a slight depression called the *fovea*. Here, light has unobstructed access to the

About the Authors
John Durrett is a psychologist and the director of CASE, a research center for human factors in automation. Judi Trezona is a freelance writer based in New Braunfels, Texas.




Photo 1: *Green and yellow against a dark background can cause confusion by producing the sensation of shadows and afterimages with color reversal. For a demonstration, stare at the center of the flag for 30 seconds, then look at a blank white surface.*

cones, which cover this area and are responsible for sharply detailed vision. The number of cones gradually decreases from maximum concentration at the fovea toward the edge of the retina, where the concentration of rods is greatest. Because a high concentration of cones produces detailed visual experiences, the sharpness of an image decreases as the distance from the fovea increases.

Besides determining sharpness, the retinal area receiving light affects color perception as well. In the fovea, the eye is sensitive to all colors. Moving away from the fovea toward the edge of the retina, red and green become difficult to perceive. Even farther from the center, yellow and blue become difficult to perceive. At the extreme periphery of the retina, only black, white, and shades of gray are perceived.

Current Theory

The current theory of color perception is based on an opponent-process mechanism. Three opponent receptions—blue/yellow, green/red, and white/black—produce color sensation by increasing and decreasing neural firing rates. The theory emphasizes adaption, contrast, color appearances, and afterimages to explain color vision. For example, since it's impossible to see a mixture of red and green in the same patch of light, these sensations are explained as results of opposite and incompatible activity in the same system.

The opponent-process theory has several implications for programmers setting up color displays. If the goal is to convey text or graphic information, opponent-color combinations should always be avoided. Yellow on a blue field and red on a green field produce the sensation of "shadows" on the display and afterimages with color reversal. This phenomenon is illustrated in photo 1. Certain other color combinations are undesirable because the colors tend to "vibrate" (imagine red on blue as an example).

These characteristics and limitations of the visual system lead to the following recommendations about color display organization:

- Since red and green areas of the color spectrum are reduced at the edge of the eye's visual field, don't use red and green outside the normal line of sight or place codes in these colors where they're likely to be overlooked. If they must be used at the periphery of the visual field, first get the user's attention by making the codes blink before beginning continuous display .
- For best viewing on a black background, always code alphanumerics in red, white, or yellow.
- Limit blue to large nonfoveal areas (i.e., nonfocal); blue characters are more difficult to read than other characters.

Psychophysical Factors

Psychophysical factors also affect how we perceive color. Color vision is a complex process of three interacting variables: hue, brightness and saturation. *Hue* is what we normally think of as color (e.g., red and green are different hues). *Brightness* is related to the intensity of light reaching the retina. Generally, higher-intensity light sources appear brightly

Guidelines for Using Color Effectively

Select compatible color combinations. Avoid red/green, blue/yellow, green/blue, and red/blue pairs.

Use high color contrast for character/background pairs.

Highly saturated colors are generally limited on inexpensive color displays, so stay within the primary hues of red, blue and green.

For casual users, limit the number of colors in one display to four. For experienced, long-term users, up to seven colors may be used.

Always code alphanumeric information in red, white, or yellow and confine light blue to large background areas.

Since red and green are not easily visible at the periphery of the eye's visual field, code signals to be perceived in this area in white.

Assign colors in ways that agree with the usual denotations. For example, use red for "stop" or "danger" and green for "go" or "all-clear."

Incorporate shape as well as color when possible. This redundant coding improves communication and makes the system usable by color-blind individuals.

When fast responses are needed, use highly saturated red or blue prompts rather than yellow.

If color coding has been used to teach relationships, use the same color coding when the individual is tested or expected to apply the learned relationships.

As the number of colors increases, increase the size of the color-coded objects.




Photo 2: *Reduction in contrast lowers our ability to determine details, as illustrated in the various foreground and background color combinations.*




Photo 3a: *Common denotations used incorrectly: green shouldn't be used to show deficit.*




Photo 3b: *Common denotations used correctly to portray the same information.*

colored while lower-intensity light sources appear more dull. The retina, however, is also sensitive to differences among various wavelengths in the color spectrum. For instance, yellow is perceived as the brightest spectral color, while red and blue are perceived as the least bright.

Saturation, which is produced by the interaction of hue and brightness, is diminished by adding white light. For example, a fully saturated spectral red becomes pink when you add white light. In terms of hue, it's still red, but a red of decreased saturation. Highly saturated colors are easiest to read. (Unfortunately, displays capable of producing saturated colors are among the most expensive.)

Contrast is another variable that interacts with the physiological components of the human eye. While brightness is essentially a measure of the intensity of a light stimulus, contrast is the relative brightness of signal over background. The greater the contrast, the better the readability of a display. In other words, darker colors (red or blue) are not as visible as light colors (white or yellow) when both are viewed on a dark background. By using higher contrast, you produce more readable graphics. This phenomenon arises from characteristics of the human visual system. Lower contrast reduces our ability to determine details, as illustrated in the various foreground/background combinations presented in photo 2.

Research has indicated that visual acuity depends on the size and color of a symbol as well as the type of background. In fact, symbol size must be increased as the number of colors increases.

Another factor affecting display visibility is the *environment* in which a task is performed. Artificial or natural lighting in the work environment can reduce foreground-to-background contrast. Too, sensitivity to color increases as the eye adapts to darkness. Improper lighting can result in reduced performance, discomfort, and fatigue in addition to limiting the effectiveness of color changes. Illumination surrounding a color-display task can have a significant effect on the time required to re-




Photo 4: *The words are easy to read, but try naming the colors!*

spond to the displayed information. Response times range from fastest for red and blue to slower for yellow and yellow-orange. When programming games and other interactive tasks, consider the user's environment.

Remember that not all individuals have a perfect visual system. About 6 to 10 percent of the male population is color-blind, meaning that their eyes have defective color receptors and are unable to perceive certain colors. This factor affects less than .05 percent of the female population. Out of consideration for color-blind individuals, programmers can code redundantly, i.e., use both color and shape for coding.

For *memory's* sake, a limited number of color codes should be employed in most contexts. Users have recognized more than 50 colors with training, but the average user shouldn't be expected to remember more than 5 to 7 colors. This is the "magic number" usually associated with short-term memory (the memory you use to keep a telephone number in mind from the page to the dial). Novel displays should have no more than 4 colors, since this number is well below the average limit of short-term memory. This provides your brain with some memory space for other decision-making activities while the meaning of colors is being processed.

Color also influences *attention* (where you are looking and what you are thinking about). By carefully using color to manipulate attention, you can partition material at key points, organize it, and code or give meaning to it. Again, the number of colors used is important; having too many can interfere with the attention-gaining potential of color. You pay attention to the first flash of red, but by the tenth, it's routine.

Our *understanding* of information can also be significantly affected by color. Material presented in color is generally processed faster than the same material presented in black-and-white. Apparently, color helps the computer operator organize work by directing his or her attention to what's important. No differences in the interpretation of information presented in either color or black-and-white are observed *if* adequate study time is allowed.

Color can assist learning if used as a redundant cue or to highlight key concepts. However, the color coding of the concepts and responses must be matched for optimum performance.

Common denotations of color should be considered when you plan color displays. For example, most people assume that red denotes "stop," "danger," or "down." Usually, green indicates "go," "up," or "OK," and yellow means "caution," "slow," or "test."

Any application of color to a specific task should employ these color denotations to achieve maximum performance. Graphics using red and green in ways contrary to accepted meanings interferes with information processing and can result in incorrect conclusions. Conversely, applying these two colors in agreement with their usual denotations actually assists information processing. For a clearer idea of this, compare photos 3a and 3b. Photo 4 illustrates the confusion that can result from improper color coding. Guidelines for the effective use of color in displays are summarized in the text box.

Conclusions

Color motivates. It gets attention. If applied with its limitations and requirements in mind, color can be a powerful manipulator of our attention, memory, and understanding. ■

References

1. Borges, Marilyn A., Stepnowsky, Mary A., Holt, Leland H. Recall and recognition words and pictures by adults and children. *Bulletin of the Psychonomic Society.* February 1977, vol 9(2), 133-144.
2. Cahill, Mary Carol and Carter, Robert C. Color code size for searching displays of different density. *Human Factors.* June 1976, vol 18(3), 273-280.
3. Christ, Richard E. Review and analysis of color coding research for visual displays. *Human Factors.* December 1975, vol 17(6), 542-570.
4. Durrett, H. J. Color display systems: State of the art. *Behavior Research Methods and Instrumentation.* April 1979, 11.
5. Dwyer, Francis M. Color as an instructional variable. *AV Communication Review.* Winter 1971, vol 19(4), 399-416.
6. Elio, Renee E. And Reutener, Donald B. Color context as a factor in encoding and as an organization device for retrieval of word lists. *Journal of General Psychology.* Ocotober 1978, vol 99(2), 223-232.
7. Farley, Frank H. and Grant, Alfred P. Arousal and cognition: Memory for color versus black-and-white multimedia presentation. *Journal of Psychology.* September 1976, vol 94(1), 147-150.
8. Katzman, Nathan and Nyenhuis, James. Color vs. black-and-white effects on learning, opinion, and attention. *AV Communication Review.* Spring 1972, vol 20(1), 16-28.
9. Knoll, Neal E. Effects of irrelevant color changes on speed of name decisions. *Quarterly Journal of Experimental Psychology.* May 1977, vol 29(2), 277-281.
10. Schontz, William D., Trumm, Gerald A., Williams, Leon G. Color coding for information location. *Human Factors.* June 1971, vol 13(3), 237-246.

PTED WHERE.

having to wrestle with multiprocessing software.

Most importantly, iRMX 86 is the only operating system taking full advantage of VLSI—already putting its advanced architectural virtues into silicon.

A prime example being our iAPX 80130 operating system processor. It squeezes timing tasks, interrupt processing and key functions of the iRMX 86 nucleus all onto a chip. Marking the first major chapter in our commitment to bring operating software into silicon—so performance goes up as the cost goes down..

And when it's time to tie into a communications network, you won't have to get tangled up writing complicated software: built-in software drivers are already in place. In fact, iRMX 86 is the only microcomputer operating system to support Ethernet,* the de facto standard for local area networks.

The leading software vendors have added the most popular languages to iRMX 86.

Company	Language Available
Microsoft	BASIC Interpreter BASIC Compiler COBOL
Microfocus	CIS COBOL
Digital Research	CBASIC
Intel	FORTRAN Pascal PL/M Macroassembler

Incidentally, all these features are available for $130/unit in OEM quantities. Plus all are backed by extensive documentation, development tools, workshops, field support, software maintenance, and a company name that's liable to turn up anywhere.

Who knows, maybe everywhere.

For a free copy of our article "Choosing a Microcomputer Operating System," contact your local distributor. Or write our Literature Department, 3065 Bowers Avenue, Santa Clara, CA 95051, (408) 987-8080.



Europe: Intel International, Brussels, Belgium. Japan: Intel Japan, Tokyo. United States and Canadian distributors: Alliance, Almac/Stroum, Arrow Electronics, Avnet Electronics, Component Specialties, Hamilton/Avnet, Hamilton/Electro Sales, Harvey, Industrial Components, Pioneer, L.A. Varah, Wyle Distribution Group, Zentronics.

Circle 211 on inquiry card.

*Ethernet is a trademark of Xerox Corporation.

A Human-Factors Case Study Based on the IBM Personal Computer

Members of a human-factors evaluation team put the Personal Computer to the test.

Robert G. Cooper Jr.
Paul Thain Marston
John Durrett
Theron Stimmel
Center for Automated Systems in Education (CASE)
Southwest Texas State University
San Marcos, TX 78666

How user-friendly is the new IBM Personal Computer? How hard is it to learn to use? Will I get eyestrain from using it eight hours a day? Are the manuals complete, understandable, and easy to use? Does it operate efficiently for an experienced user? Are the error messages informative? These are some of the questions that a human-factors specialist would pose in evaluating any computer system. In this article we will use the IBM Personal Computer as an example in evaluating human-factors issues in microcomputers.

Microcomputers present a special challenge to the human-factors specialist because the group of operators is diverse and the machine is used for many different tasks. Thus, it's impossible to specify any single set of criteria by which to measure the computer's human-factors performance.

We will examine here some of the features of the IBM Personal Computer that involve consideration of human factors to illustrate that the set of criteria fluctuates. A complete human-factors evaluation of the Personal Computer would be far too extensive to present here. Our discussion should not be interpreted as either a complete or a representative assessment of the Personal Computer's overall quality from a human-factors perspective.

We chose the IBM Personal Computer as an appropriate model for illustrating the process of human-factors evaluation for two reasons. First, it is a new model and marks the entry into the microcomputer market by the largest computer manufacturer. Thus, it has generated substantial interest. Second, because it is a new model, it will almost inevitably exhibit some human-factors flaws despite the best efforts of the designers and engineers.

Expert users often uncover new human-factors problems.

Evaluation Procedures

Two kinds of information go into any human-factors evaluation: judgments made by human-factors specialists based on their knowledge of previous research and their experience with similar systems and observations of users operating the system.


The data collected often include:

- types of errors made
- frequency of different types of errors
- frequency of consulting instruction manuals or seeking other kinds of aid
- user comments about strengths and weaknesses of the system
- user suggestions about needed additions or changes to the system

Most human-factors specialists prefer to draw conclusions based on empirical data collected from users of the specific system. However, because this way of evaluating a system is very time-consuming and expensive, most human-factors analyses, including those done at CASE, are based on a combination of the two methods.

For the evaluation of the Personal Computer, we asked several types of users to operate the system. Some had experience on other systems, including substantial programming ex-

About the Authors
The authors are psychologists at the Center for Automated Systems in Education (CASE) in San Marcos, Texas.



Alspa + Hard Disk
CP/M*
ACI-1
CORVUS SYSTEMS
FAULT BUSY READY
ACI-2
STOP
SHOCKLEY
MORE COMPUTER POWER
MINIMUM REAL ESTATE
NOW! All ALSPA computers come standard with a CORVUS** hard disk interface. In less than 5 minutes you'll be up and running. In the space of a standard 8 inch drive, ALSPA computers have three RS-232, one parallel, and one hard disk port; 8 inch drives; and run CP/M software. Optional clock/calendar. ALSPA performance starts at $1995, list.
DEALER/DISTRIBUTOR INQUIRIES INVITED
Alspa Computer, Inc.
Circle 22 on inquiry card.
300 HARVEY WEST BLVD., SANTA CRUZ, CA 95060 • (408) 429-6000
*CP/M is a trademark of DIGITAL RESEARCH, INC.
**CORVUS is a trademark of CORVUS SYSTEMS, Inc.

perience. Some were adults—like many in the target market for the Personal Computer—with little or no previous experience with computers. And some were children from age 10 to 14 with at least some experience programming microcomputers at home or in school.

An important group missing from this set of users was individuals who have had extensive experience on the Personal Computer. People with experience on a particular system often have the most informative comments. They often demonstrate that apparent problems can be minimized simply by changing the operating procedures. Because they are competent enough to use the full set of features a system offers, they often uncover new human-factors problems. However, because the Personal Computer is so new, we couldn't find such a group of users, and we didn't have the Personal Computer long enough at CASE to develop such a group. Also, because of limited time and resources we couldn't test using standard scientific methodology. Rather than following a carefully planned procedure, we made new procedures as we went along, responding to insights from the test group. This type of evolutionary process normally occurs before an actual human-factors experiment is conducted. Then a consistent procedure is established so that all participants are asked to do the same set of tasks.

Hardware Characteristics

We will begin our examination of the Personal Computer by looking at some of the human-factors characteristics of the overall packaging. In its simplest form it consists of three units: the computer, the keyboard, and the display. For many applications, it is irrelevant whether these three components are integrated or separate. For others, separate-component packaging is a decided advantage because it offers flexibility in choosing a display or the option of locating the main unit with the disk drive away from potentially destructive young hands (see also the discussion of the keyboard below). However, for a user who must move the system from place to place, the benefits of one-piece packaging may bias him or her toward an integrated system like the Superbrain or TRS-80 Model III. For a school system, the separate units are at least a complication: three units rather than one must be anchored permanently to avoid accidental damage or pilfering.

A second characteristic, which has been the focus of substantial human-

CASE

Researchers at the Center for Automated Systems in Education (CASE) at Southwest Texas State University conducted the human-factors research on the IBM Personal Computer discussed in this article. The staff of CASE is engaged in teaching, research, and development in the area of the human-factors considerations associated with computer-based systems. Although much of the early work by CASE emphasized human-factors issues in the use of computers in educational settings, recent projects, including work for Control Data Corporation (CDC), Comshare, and Polaroid, encompass a much broader range of human-factors issues in computer systems.

The procedure at CASE is first to define the scope for a particular human-factors analysis. Once the issues are clarified, researchers collect data from previously published human-factors studies as well as more general psychological studies in the areas of perception, cognition, and learning. Occasionally, previous research is adequate, but more frequently it is used to further clarify issues and design the appropriate research study to answer the specific human-factors issue being studied.

In some ways the analysis of the IBM Personal Computer presented here is not characteristic of our usual research because no single task or user group is anticipated for the Personal Computer. As a result, researchers simulated a range of human-factors experiments that represent the kind of research which would be done in a full-scale human-factors analysis of a microcomputer. Thus, the general approach and analysis presented here typify work conducted by groups like CASE on human-factors issues and problems in computer systems.

factors research, is the quality of the display. This of course depends largely on the monitor used. The IBM monochrome monitor, the only monitor supplied by IBM for the Personal Computer, meets or exceeds all the standard criteria with respect to character size and clarity, screen brightness, freedom from flicker, etc. All the users we questioned were impressed by the display, even those who did not in general like green-phosphor screens. When evaluating a display for a large group of potential users (for example, for a school system), the criteria based on the results of published experiments are particularly useful because they were developed from data on a representative sample of users. When an individual evaluates a display for personal use, experience with the display may be more useful than reading published results because the published criteria are more stringent than many people require.

A third feature of the Personal Computer, on which a substantial amount of human-factors research exists, is the keyboard. Despite some of the advantages of alternate keyboard designs, it appears that American National Standards Institute (ANSI) standard and related keyboards (sometimes called QWERTY keyboards because of the first row of letters) will continue to dominate the field because of conversion and retraining expense. Therefore, we will examine the IBM keyboard from within these standard constraints.

The keyboard "feel," the tactile sensation of typing on it, was highly praised by all who used it, particularly those who were familiar with other microcomputer keyboards. Frequently mentioned virtues included the ability to move and change the angle of the keyboard, the sculpturing of the keys, and the keyboard's curved-plane surface. However, every user complained about the Enter and the left Shift keys (see photos 1a-1f). The Enter key is about ½ inch farther to the right than most users expected, and the left Shift key is about ½ inch farther to the right with the backslash key inserted between the Z and the Shift key. These unconventional locations caused errors initially, but extended practice usually eliminated such errors after about a week.

Again, the importance of the keyboard layout depends on the context in which the computer will be used. For occasional use by individuals who frequently type on other keyboards (e.g., by a secretary in an office or by someone at home who does a substantial amount of typing at work), the keyboard layout may be a major annoyance. For the individual who types mostly on the IBM keyboard, it should be no problem. Also, if the use of the computer involves nontext materials, as in financial planning or playing games, the layout may be less important than if the computer is needed for word processing.

The inclusion of an extra key between the Z and the left Shift key may become standard in the future. In Europe, many keyboards have this extra key to facilitate typing extra characters required in some languages. Some word processors in the U.S. are using this style keyboard to accommodate extra functions required in word processing. So what is a potential human-factors problem today may be an asset in the future. However, on several Japanese keyboards, it is the right Shift key that is moved to allow the addition of an extra key, illustrating that no standard exists for these additions.

The keyboard of the NEC PC-8001 suggests one near-term solution. On this computer the user can select, with a single button, either an almost-ANSI-standard keyboard (with the right Shift key out of place) or a keyboard with the letters in alphabetical order (which is helpful for young children). This flexibility could be expanded to let users program the arrangement of their own keyboards.

Documentation

Human-factors considerations are especially significant in the area of documentation. Minimally, documentation needs to fulfill three func-

FREE CATALOG OF COMPUTERS AND SOFTWARE

- Easy-to-build Heathkit® Computers for hobbyists
- Typewriter-quality printers, smart video terminals
- Reliable service, friendly advice
- Fully assembled Zenith Data Systems Computers for business
- Heath User's Group library of 500 programs for home, work or play
- Wordprocessing – accounting – Super-Calc™ – small business applications
- Self-study courses for writing your own programs

HEATH/ZENITH

Your strong partner

☐ Yes, send me my free Heathkit Catalog. I am not currently receiving one.

name ____________________

address ____________________

city ____________________

state __________ **zip** __________

Byte 334-889 PC-143




PLACE
STAMP HERE
Post Office
will not
deliver mail
without postage

HEATH COMPANY

Benton Harbor, MI 49022

And The Winner Is . . . IBC By Four Users!



When you are racing toward that finish line, beating the competition is everything. IBC is the choice of OEM's, system integrators and dealers throughout the world, because in benchmark after benchmark our small business computer systems finish first.

We finish first because we are faster, offer higher quality peripherals and can expand our system significantly beyond our nearest competitors. In fact, looking at the chart below, you can quickly see why knowledgeable resellers are choosing IBC.

	IBC	onyx	ALTOS
Oasis Operating System (Max. Users)	9	5	4
CPU Speed (MHz)	6	4	4
Disk Speed I/O (MB/Sec.)	.81	.65	.54
Seek (Milli Sec.)	35	50	65
Cache Disk Memory	Yes	No	No

Circle 199 on inquiry card.

Join us in the winners circle with high performance equipment and the best dealer plan in the industry. Call or write:

OUTSIDE THE USA
IBC/Integrated Business Computers
21592 Marilla Street
Chatsworth, CA 91311
(213) 882-9007 TELEX NO. 215349

WITHIN THE USA
IBC/ DISTRIBUTION
4185 Harrison Blvd., Suite 301
Ogden, UTAH 84403
(801) 621-2294




1a



1b




1c



1d



1e



1f

Photos 1a-1f: *Comparisons of keyboards. All have letters in the same position, but note the variation in the placement of the Shift, Return, and other special symbols. Note also the various solutions to the problem of where to put all the keys not needed on ordinary typewriters.*


tions: initial training in using the system, quick reference for momentarily forgotten information, and complete documentation of capabilities and how to access them. Ideally, many other functions will be served, including guidance on uses for system features, information to aid in debugging (including common errors and their symptoms), etc.

The manuals for the Personal Computer have received very high praise. Gregg Williams in "A Closer Look at the IBM Personal Computer" (January 1982 BYTE, page 36) wrote,

Your computer.

Your printer.

Compute.
Compute.
Compute.
Compute.
Compute.
Dump...
Compute.
Compute.
Compute.
Compute.
Compute.



...Print.
Print.
Print.
Print.
Print.
Print.

New Microbuffer II lets you use your printer without tying up your computer.

Time. As an important resource it shouldn't be wasted. One such waste is in printing, where your computer must wait for your printer. Now there's a way to eliminate this waste.

Introducing the Microbuffer][™, a buffered parallel printer interface for the Apple][® computer with 16K characters of memory (user expandable to 32K). It accepts data as fast as your computer can send it, allowing you to use your computer while the Microbuffer][is in control of your printing.

The Microbuffer][, compatible with Applesoft, CP/M® and Pascal, comes with complete print formatting features as well as advanced graphics dump routines for most popular graphics printers.

The Snapshot™ option permits you to dump the text screen or graphics picture to the printer while any program is running — without interuption.

The 16K Microbuffer][is available for $259. And the 32K version, for $299. The Snapshot option is $69.

So why waste time while your computer waits for your printer? Ask your computer dealer for the Microbuffer][or call us for the name of a dealer near you.

MICROBUFFER][

M][

Microbuffer][and Snapshot are trademarks of Practical Peripherals, Inc.
CP/M is a registered trademark of Digital Research, Inc.
Apple][is a registered trademark of Apple Computer, Inc.

PRACTICAL PERIPHERALS, Inc.
31245 La Baya Drive
Westlake Village, California 91362
(213) 991-8200

Circle 18 on inquiry card.

"They will set the standard for all microcomputer documentation in the future." Our analysis of the manuals is less enthusiastic, although in many ways the documentation is excellent.

We will take a look at the BASIC manual first to illustrate some of the strengths and weaknesses of the documentation. The manual is for reference and does not claim to be a programming tutorial. For its stated purpose the manual is quite good. All users who had prior knowledge of BASIC had no difficulty programming on the Personal Computer, including using some of the special features of IBM's version of BASIC. The features of the manual that are most useful are the index and the brief and extended descriptions of every command, statement, and function. The extended descriptions are most complete for those features that are unique to IBM's BASIC and include informative examples.

There are five parts to each keyword description: format, version, purpose, remarks, and example. The only drawback is that some information is omitted, apparently because it does not fall neatly into any of the categories. For example, restrictions and probable error messages from mistakes are only included in some of the descriptions. For the FOR and NEXT statements, information about errors is given in the body of the remarks section, and no information is given at all about restrictions on the amount of nesting or about overflow in nesting, which will lead to an "out of memory" error. Despite these problems, the manual can be used effectively.

IBM has left the market for tutorial manuals to outside publishers.

As adequate as this manual is for the experienced user, it does not fill the need of the novice for an instruction manual. General instruction manuals do exist (e.g., *Basic BASIC* and *Advanced BASIC*), but the idiosyncrasies of different BASICs have led to a demand for instruction manuals for individual machines. According to our observations, novice IBM users had much greater difficulty with IBM's reference manual than do novices starting out on an Apple II Plus with Apple's instruction manual. IBM apparently made a conscious decision to leave the novice market to the independent producers of computer manuals and books. An IBM spokesperson assured us that such independent sources are already hard at work and their manuals should be out shortly, but until such manuals are written, a hole remains in the documentation from the perspective of the computer novice.

In the interim, IBM could make two simple additions to the current manual that would be helpful. One is a quick-reference card that could be removed from the manual; it would decrease the need to flip back and

SYSTEM BUILDERS: THINK SOLID. THINK PRICE. THINK CCS.

Each month, CCS produces, tests, and ships over 3,000 board-level building blocks. About ten come back for repair. And we're working on that.

Built like a commodity. Priced like a commodity.

Volume means we keep our prices down. Low prices and reliability mean our customers keep coming back for more.

High performance that *works.*

You get all the performance that most systems want. Benchmarks prove it. You get the reliability and low price that all systems *need.*

S-100 in quantity.

Whether you want to add capability to an existing S-100 system, or build a system from scratch, chances are you'll find a solution in the CCS product line.

Call or write for the CCS S-100 product catalogue.

- 16K STATIC RAM
- 32K STATIC RAM
- 64K DYNAMIC RAM
- SERIAL I/O
- PARALLEL I/O
- FLOPPY DISK CONTROLLER
- HARD DISK CONTROLLER
- Z80® CPU
- PROTOTYPING BOARDS
- MOTHER BOARDS
- MAINFRAME / POWER SUPPLY

Z80 is a registered trademark of Zilog Corporation.



California Computer Systems, Inc.

250 Caribbean Drive Sunnyvale, CA 94086
408 734 5811 Telex 171959 CCS SUVL

Circle 76 on inquiry card.

forth from the brief- to extended-description sections of the manual. Second, a comment could be added to the preface about the existence of Appendix D, which discusses the differences between IBM Personal Computer BASIC and other BASICs. None of our novice users discovered this appendix within the first hour of trying to learn to program in BASIC (we showed it to them after an hour), and such information would have been very useful in trying to use the general manuals for BASIC. Of course, these changes would be useful for more experienced users also.

IBM's *Guide to Operations* presents a similar problem. It appears to be written for novices and contains excellent illustrations and very clearly written instructions. However, crucial pieces of information are either left out or have odd locations in the manual. For example, we had several novices set up the computer from scratch. Perhaps because we were watching with notepad in hand, all followed the written instructions scrupulously. As instructed on page 2—6, they turned on the system for the first self-test after connecting the keyboard and power cord. Four out of five continued on to page 2—7 and began to connect the cables for the display and printer without first turning off the system, and would have done so had we not stopped them. Next, the manual calls for the use of the diagnostic disk on page 2—16 without any cautions about the handling of disks. This information is contained several pages later. None of our novices mishandled the disk. But if they had mishandled it and were looking in the problems section because the disk would not load, the warning there would obviously be too late.

IBM's monochrome monitor meets or exceeds all the standard human-factors criteria for video displays.

Because the Personal Computer we used for our evaluations had a defect

```
]AN APPLE II WITH A LOWER-CASE ADAPTER
PRODUCED THIS DISPLAY ON A HEATH/ZENITH
COLOR MONITOR. THE APPLE'S
40-CHARACTER LINE WAS DESIGNED TO ALLOW
THE USE OF TVS AND INEXPENSIVE COLOR
MONITORS WITH THEIR LOWER RESOLUTION.
THE LARGER LETTERS ARE EASIER TO READ
ON LOWER RESOLUTION DISPLAYS.
]ALSO, WITHOUT THE LOWER-CASE ADAPTER
THE ALL CAPITAL FORMAT IMPROVES
LEGIBILITY TOO. OF COURSE, AN APPLE II
CAN BE EQUIPED WITH AN 80-COLUMN
ADAPTER AND USED WITH A HIGH RESOLUTION
MONITOR._
```

2a


```
The IBM Personal Computer Basic
Version A1.00 Copyright IBM Corp. 1981
34049 Bytes free
Ok
10 print "This is the IBM Personal Computer monochrome monitor"
20print "All the screens from the other computers were photographed"
30 print "at the same distance from the screen."
run
This is the IBM Personal Computer monochrome monitor
All the screens from the other computers were photographed
at the same distance from the screen.
Ok
_
```

2b


```
          B:ABC    PAGE 1 LINE 8 COL 01                       INSERT ON
L----!----!----!----!----!----!----!----!----!----!----!-------
This is the monitor from a Xerox 820 Information Processor
The screen size is almost identical to that of the IBM
Personal Coomputer.  As is apparent in the photograph the
color of the phosphor is different.  Some people prefer
one type over the other, but there is no clear consensus.
```

2c

Photos 2a-2e: *A representative sampling of computer video displays.*



2d



2e

in the power supply and disk system when first received, we noticed another documentation problem. We had decided to have a novice unpack and set up the system. He progressed through the setup procedures to the point of loading the diagnostic disk, which wouldn't load. In response to this failure he repeated all the previous steps, looping through the procedures twice. He then turned to the section "Problem Determination Procedures." This proved fruitless because, by the time he reached page 4—7, he was reassured that the system was working because it met the criteria of correct information on the screen and correct auditory response (one short beep). At this point our novice gave up. It took another eight minutes for the "experts," who had been observing, to discover on page 4—8 the statement "Error messages may or may not remain on screen. So look quickly." An error message had flashed on and off shortly after the power was turned on.

Two documentation requirements illustrated here are that warnings, cautions, and other crucial information should appear very early in the manual before the relevant error can be made and that error conditions ought to lead to a permanent message that is terminated only by user action.

We discussed the problems described in the last two paragraphs with people from IBM and the local Computerland store. Both commented that the Personal Computer is not being sold by mail order and that a purchaser would be given substantial training before taking the computer home. Although this may lessen the necessity of the above requirements in some ways, we do not believe it eliminates them. It is poor practice to leave the task of conveying such important information to a group over which IBM has little if any control. In addition, people other than the original purchaser may need to learn to use the computer. Instruction manuals should be complete and sufficient to allow one to learn and use the system in isolation, even if this is not the ideal context for learning.

All the IBM manuals fit in 8½- by 5½-inch, hardcover, three-ring binders. The advantages of this format include easy updating. Sections are added to the *Guide to Operations* each time a new option (e.g., communications interface or printer) is added to the system. However, there are some negative human-factors consequences of this format. Three times during our testing, a manual was dropped in such a way that the binder came open and pages fell out. For a home or business user, this would probably be only an occasional annoyance. However, in a school setting these manuals would not be acceptable. Something more durable is required. The specific use for which the system is intended will determine whether this is a significant human-factors failing.

IBM does have some human-factors problems with its manuals for the Personal Computer. However, compared to documentation that other new computers have had when they were first introduced, the IBM manuals are outstanding. And they compare favorably even with the updated offerings from other manufacturers.

Operational Characteristics

A human-factors evaluation of the functional operation of the Personal Computer is the most difficult to do without a specific task in mind and

without a long period of time in which to observe users trying to accomplish this task. Also, an examination of the individual features of the Personal Computer reveals that many of the best features from microcomputers of other manufacturers have been incorporated. A separate examination of each feature in terms of how it helps facilitate people's ability to use the system would start to sound like an IBM press release. However, the Personal Computer's versatility (in itself a human-factors asset) does entail human-factors costs. For example, many individuals have happily used their microcomputer for years without being bothered by lack of precision or by rounding errors. On the other hand, the use of some computers for business bookkeeping is problematic because of limited precision. The IBM

The error message appeared on the screen so briefly the operator never noticed.

Personal Computer (and several others) offers the choice of single or double precision. This is an advantage to business users but requires a decision by other users ("Is 6-digit precision enough, or do I need 17?"). Some users may find that they prefer the old situation in which they obtain 9-digit precision (sufficient for home bookkeeping) automatically and do not have to make the determination.


The system reset procedure on the Personal Computer provides a different perspective on the problem of assessing human factors without a specific context. For purposes of comparison, it is important to be aware of the human-factors problem with the system reset on the Apple II. On the Apple II, an operator would push the key labeled Reset, an extremely simple procedure. Unfortunately it was too simple, and because the Reset key was directly above the Return key, it often occurred accidentally. Apple corrected this problem on the more recently produced versions by giving the user the option of choosing to re-

How to chart your company's fortune without spending one

It's a fact. A single chart or graph can tell you instantly what it takes hours to interpret from printouts or other raw data.

Now, with the Strobe 100 Graphics Plotter and Software package, you can create superb hardcopy graphics directly from your computer. And you can do it for an investment of only $995.

The Strobe System transforms complex data into dynamic, colorful visuals with a few simple commands from your computer. Charts and transparencies that once took hours to produce are plotted within minutes. Information can be presented as bar charts, pie charts, curves or isometrics in a variety of colors. And with a resolution of 500 points per inch, the Strobe 100 matches or surpasses the quality of plotters costing thousands of dollars more.



You can also save and modify your graphics through Strobe's menu-driven programs. A broad selection of software—including a VisiCalc*-compatible program—is now available.

When the Strobe Graphics System is interfaced to your computer, an 8-1/2 x 11 inch sheet of paper can speak anyone's language—visually. Visit your local dealer and learn how to start charting your fortunes today. Because a perspective on the present can also be your window on the future.



Strobe Inc.
897-5A Independence Avenue
Mountain View, CA 94043
Telephone 415/969-5130

The Strobe Graphics System

Seeing is believing

Circle 389 on inquiry card.

*VisiCalc is a trademark of VisiCorp.

quire a control key plus Reset for a reset to occur.


On the Personal Computer, the operator initiates a system reset by holding down the Control and Alternate keys and then pressing the Delete key. This procedure is certainly cumbersome enough that it is unlikely to occur by chance. Is it too cumbersome? Because the operator uses three keys, none of which is labeled Reset, will the procedure be forgotten by those who need to use it? Without considering a specific context we can't answer these questions, but we can consider the kind of criteria a human-factors specialist would use in answering them for some particular context. First, how frequently is a system reset executed? If it occurs extremely rarely (as might be the case for someone using already developed software), it probably is all right if the command is forgotten and the user has to look it up. If it is used quite frequently (perhaps in debugging complex programs), it will be remembered because of the constant use. If it is used occasionally, it may be hard to remember and yet be frustrating to have to look up each time. Second, what are the consequences of making a mistake when trying to execute a system reset? If delay in a reset or if some combination of related keys might lead to dire consequences in some application, then for that application the Personal Computer would have a major human-factors failing. Third, what alternatives are available and how do they interact with other human-factors characteristics of the system? For example, a separate key could be used as on the Apple II, but that either adds another key to the keyboard or takes up a key that might have been used for some other function. Too many keys produce an added memory load on the human operator, just as multi-keystroke commands do. The human factors trade-offs here must be evaluated in terms of the way the system will be used.

The Personal Computer has ten special-function keys called "soft keys," which have a set of default functions but can be changed by the user. The "soft keys" are a very popular characteristic among the experienced users we questioned. However, because the keys can be redefined, they are labeled F1 through F10—not very effective labels for remembering their functions. The Personal Computer solves this problem by displaying partial labels at the bottom of the screen (for all 10 keys on an 80-column display and for the first 5 on a 40-column display). We expect that those operators using a television display (40 columns) and others not wanting the labels at the bottom of the screen will tape a list of the ten functions somewhere near the computer. In some ways it would have been nice if space had been left on the keyboard for labeling these keys. However, that would have had the undesirable effect of enlarging the keyboard. Again, there are always trade-offs.

The relation of the line-editor pro-

SANYO MONITORS

When you're ready to stop playing around.



Maybe your home TV was OK as a display when all you were concerned with was blasting Klingons.

But if you spend more than a couple of hours in front of your TV screen, you'll start to pay the price in eyestrain. Maybe even headaches.


It's not worth it. Not when you can get a Sanyo data monitor that's specifically designed for long-term, day-in, day-out use.



Compare display quality of a typical home TV (left) with a Sanyo professional monitor (right).

Sanyo monitors have been the industry standard for as long as there's *been* a personal computer industry—in fact they're recommended by computer dealers and manufacturers alike. That's because when you buy a Sanyo, you're not just getting a stripped-down TV set. You're getting a truly professional display system.

Sanyo offers a complete selection of monitors for any application. You can choose from 9" models with either white or easy-on-the-eyes green phosphors. Or a sleek new 12" model with a special anti-reflective screen (green or white), and an optional desk stand with adjustable tilt. If color graphics are your thing, check our 13" full-color models—one with TV-compatible video input, and a new ultra-high resolution RGB model for computers like the IBM, NEC and Apple III.



Visit your computer dealer and find out how much better things look on a real, professional monitor from Sanyo.

Anything less is just playing around.



Communications Products Division

Sanyo Electric Inc., 1200 W. Artesia Blvd., Compton, CA 90220 (213) 537-5830

Circle 360 on inquiry card.

gram that is part of the disk operating system (DOS) to some of the characteristics of BASIC is another human-factors issue. Using the line editor, for example, the Personal Computer lists lines 100 to 200 with a command of the form "100, 200 L" and deletes with a command of the form "100, 200 D". In BASIC, lines are listed with a command of the form "LIST 100-200" and deleted with a command of the form "DELETE 100-200". The difference in syntax adds a memory burden for no intrinsic reason to anyone who uses both capabilities of the Personal Computer. An experienced user who was asked to use the line editor had trouble with the syntax. On the second day he used it he made errors and had to go to the manual to check the syntax of the commands. This syntax problem is a relatively minor issue when considering the line-editor program and BASIC but is representative of the more general class of differences in syntax that can lead to disastrous mistakes (not necessarily on the IBM machine). Perhaps the best example of syntax-function problems is that of commands for copying: on some systems the source is first and the destination second, whereas on others the reverse is true. Errors that were the product of moving from one system to the other can and have resulted in the loss of crucial files.

Conclusions

We have illustrated the process of human-factors evaluation of microcomputers and its importance. Understanding that the user is part of the system is crucial to understanding the human-factors approach. Just as no single language is best for all programming, no single system design is best for all users. We have presented some general principles that apply to all systems but, for the most part, evaluations must take into account requirements of the specific, potential user. Groups like CASE, which perform human-factors evaluation, start by determining the requirements of the user, then they evaluate the human-factors characteristics of the hardware, software, and documentation in terms of those requirements.

Because user needs vary so, it was almost certain that the IBM Personal Computer would have some human-factors failings; it could not be all things to all people. Although we did not attempt to perform a complete evaluation, our overall impression of the human-factors design of the Personal Computer is very positive. IBM has begun to put substantial emphasis on human-factors design, and the IBM Personal Computer exhibits many positive results of the efforts of human-factors specialists. However, some of the simple and easily changed human-factors failings that we uncovered could have been detected from relatively simple observations of users.

If you are considering purchasing a microcomputer, these comments have two major implications. First, be clear about the use or uses to which the system will be put, and then concentrate on human-factors characteristics that are relevant to those uses. Do not buy a computer that will be used primarily for word processing on the basis of the enthusiastic recommendation from someone who uses his for home finance and playing games. Second, get as much information on the actual use of the system as possible. Use it yourself in the way you intend to use it; do not just go through a set of demonstration programs, even if they are designed to illustrate the features of the programs you will be using. Try to find someone who is already using the system in an application similar to the one you anticipate. As mentioned previously, we find experienced users to be one of the best sources of human-factors insights. If you make use of the insights of others, you may avoid being the source of negative human-factors insights about your own system. ■

Acknowledgment

BYTE would like to thank Computerland product manager Richard Mandel and the Austin, Texas, Computerland store for equipment and assistance provided during the preparation of this article.



In an age when new standards are constantly emerging, one disk consistently meets or exceeds them all.

Maxell. The Gold Standard.

Not all disks are created equal. Some are better than others. To find out what's best for you, look for Maxell disks. They now carry the Gold Standard symbol of quality. It's your assurance Maxell disks meet or exceed every definition of quality. No matter who establishes it. We've earned this universal superiority by never relaxing our uniquely demanding quality control. Every aspect of manufacturing is checked, then checked again.

Your benefits are many. Take the perpetual problem of drop-outs. A drop-out is a tiny defect that wastes time and degrades computer accuracy and performance. Now that you understand what a drop-out is, forget it. Maxell disks don't have any. Each disk comes to you certified drop-out free at the time of manufacture. You can depend on this quality protecting your valuable programs and programming time, indefinitely. We've run disks over ten million passes under conditions designed to find weak points and wear. We couldn't. And you won't.

There is a Maxell disk for the floppy system you use, or plan to use. Check your computer's instructions. Or write for our complete, highly informative brochure.

When you set the Gold Standard as your level of quality, you'll benefit from improved disk performance, immediately. Bank on it.

maxell®

Maxell Computer Products Division, 60 Oxford Drive, Moonachie, N.J. 07074, 201-440-8020

WE'RE STILL



STANDARD

● 64K internal memory. ● Up to 1.5 Megabytes of dual disk storage – easily expandable to 10 Megabytes. ● Twin RS-232 serial ports. ● A CP/M† disk operating system. ● Two 4 MHZ Z80A Processors for faster response. ● A Full 80 x 24 line display on a 12-inch non-glare screen. ● Optional graphics capability.

SUPERBRAIN™

It used to be that buying a microcomputer was a simple task. There were only two or three manufacturers offering them and comparing prices and specifications was easy to do. Today, Intertec is no longer one of a handful of microcomputer vendors trying to attract your attention, but. . . we think we're still the best. And for a good reason.

Consider pricing. Our customers tell us we're still the price/performance leader in single-user *and* multi-user microcomputer systems. Ask around. Most folks (and even some manufacturers) will concede that point. What a lot of people do not know is that Intertec may very well offer the best customer protection programs in the industry. What is customer protection? It's a totally new, comprehensive product and customer support program which virtually guarantees your long term satisfaction with every new Intertec product you buy. It means that if you are not satisfied with your Intertec purchase, you can get your money back at any time during the original factory warranty.* Or, in the unlikely event your equipment should become inoperative during the first few weeks of the warranty period, we will

*At participating dealers only. Refunds are prorated.

THE BEST!

FEATURES

● True multi-user capability—network up to 255 users. ● Up to 1.5 Million bytes of local, off-line user storage. ● Four models of user workstations available. ● 64K Internal memory in each workstation. ● A CP/M† operating system. ● 10 – 384 Megabytes of auxiliary disk storage.

COMPUSTAR™

replace it for you! And we'll even provide a reimbursement allowance to cover your cost of returning the system to us.

Go ahead. Review the pricing and performance specifications of *all* the microcomputers available today. We think you'll agree with us. . . ours are *still* the best! If you want uncompromised performance, competitive pricing, sophisticated expandable products and just plain peace-of-mind, you'll want Intertec.

Ask your dealer about Intertec's SuperBrain and CompuStar microcomputer systems. Or, call or write us at the address below and get more information on today's best values in single and multi-user microcomputer systems.



2300 Broad River Rd./Columbia, SC 29210
(803) 798-9100/TWX: 810-666-2115

Circle 214 on inquiry card.

†CP/M is a registered trademark of Digital Research, Inc.

The Hewlett-Packard Interface Loop—HPIL

Unique Two-Wire System Allows Low-Cost Data Collection

Robert Katz
248 East 90 St. #3B
New York, NY 10028

The most intriguing feature of the Hewlett-Packard HP-41C has been the multiple plug-in port on the unit's back (see Steve Leibson's *"The Input/Output Primer, Part 3,"* page 186). Until now, four ports have been available for plug-in RAMs, ROMs, a card reader, a thermal printer, and a bar-code reader. Yet users have been begging for the chance to let the HP-41C talk to the outside world. Hewlett-Packard is very protective of its products and does not publish specifications of the connections to these ports. Justifiably, because the calculator's delicate CMOS (complementary metal-oxide semiconductor) circuitry can be damaged easily by improper connections.

The public demands and Hewlett-Packard responds. By announcing the Hewlett-Packard Interface Loop (HP-IL), Hewlett-Packard has provided users with much more than they've been requesting. The HP-41C was a quantum leap beyond conventional calculators, and, remarkably, the HPIL is a quantum leap for the HP-41C.

The Loop Hardware

HPIL operation is powerful and sophisticated, but the hardware is simple, small, and easy to interconnect. A board called the HPIL Module (HP82160A) plugs into any of the four ports on the back of the HP-41C. The module receives its power from the HHC's internal batteries. Two 71-cm (28-inch), 2-wire cables extend from the module; at their ends are 2-pin male and female con-

At a Glance

Name
Hewlett-Packard Interface Loop (HPIL)

Manufacturer
Hewlett-Packard
1000 Northeast Circle Blvd.
Corvallis, OR 97330

Price
HP82160A HPIL Module: $125, available now; HP82183 Extended I/O ROM: price to be announced, available summer 1982; HP82180A Extended Functions/Memory Module: $75, available now; HP82181A Extended Memory Module: $75, available now; HP82166 HPIL Converter: $395 for a prototyping kit including 2 converters, test board, HPIL cables and manual, or $1250 in quantities of 10 with no accessories, available spring 1982; HP82182A Time Module: $75, available mid-1982; HP82161A Digital Cassette Drive: $550, available now; HP82162A Thermal Printer/Plotter: $495, available now; HP3468A Programmable Digital Multimeter: $695 plus $125 for battery option, available now; HP82938A HPIL Interface Card for HP Series 80 Personal Computers: $295, available now;

Description
HPIL is a complete software and hardware system that turns the HP-41C handheld computer/calculator into a general-purpose, data collection, measurement, and analysis tool as well as an equipment controller.

Other features
Simple 2-wire connectors, "transparent" operating system

Hardware options
Digital Data Cassette, Thermal Printer/Plotter, Programmable Multimeter, GPIO Interface, Computer Interface, among others

Audience
Original equipment manufacturers (computer-aided manufacturing), instrumentation manufacturers, hobbyists, others

About the Author
Robert Katz, who prefers to be called "Bob," is a recording engineer for records, TV, and radio. He also dabbles in computers.

enjoy the problem-solving power of APL language on your Apple computer

Solve engineering, scientific, or business problems easily--write finished applications software in a fraction of the time you'd take to write similar programs in BASIC, FORTRAN, or COBOL. . . and do it all with your Apple® right at your desk.

Test your language against APL/V80™

To compare APL/V80's clear concise code with the language you're now using to solve problems, take this short programming test. Here are three common problems, showing the APL/V80 solution for each. Program your best effort for each problem in the language you use now. Now compare the number of lines and keystrokes needed to achieve a solution in your language to the APL solution. Keep in mind the APL/V80 solution shown contains not only the computation commands, but also every instruction needed to input required data, as well as all the commands to print out the results.

Problem 1:

Write a program to input a list of values (List "A"), sort the list from lowest to highest values, then print all the values in list A in ascending order.

APL/V80 solution:

```
A[⍋A←⎕]
```

Solution in your present language:

(Hint: Usually this takes two loops and 15 to 20 statements.)

Problem 2:

Write a program to input a list of values (List "X") and compute the standard deviation for the list values.

APL/V80 solution:

```
((+/(X-(+/X)÷N)*2)÷¯1+N←⍴X←⎕)*.5
```

Solution in your present language:

(Hint: This takes at least one loop and about 16 statements.)

Problem 3:

Write a program which will compress adjacent spaces to a single space, with possible multiple occurences, in a string of characters called TEXT.

APL/V80 solution:

```
(1,(¯1↓T)⍲1↓T←' '=TEXT)/TEXT←⍞
```

Solution in your present language:

?

Whether you're an engineer, scientist, educator, or businessman, now you can solve problems faster than ever using your Apple®. With APL/V80™ from Vanguard Systems Corporation, search for solutions in a fraction the time you thought possible. Get the added benefit of creating programs which are not only easier to write, but also are easier to understand, modify, and explain.

Solve your problems faster

APL/V80™ is the most concise powerful programming language available for computer solutions to scientific and business problems on Apples (or CP/M®based computers). When you have APL/V80, you can focus your attention more on problem-solving, and concern yourself less with the details of program coding. APL/V80 lets you develop functional software, and debug it, in about one-fifth the time you need to program a solution in other languages.

If you're an APL user already, you'll appreciate knowing we developed APL/V80 for the Apple with the ISO-ANSI proposed APL standard in mind. All future enhancements will be guided by developments in this standard, so APL/V80 programs maximize compatibility with other APL systems.

More than a language: a new world of convenience

APL/V80 is more than a language. . .it's a whole new world of convenience for you and your Apple. A variety of special features and auxiliary processors give you problem-solving power unmatched by any other language available for the Apple.

Powerful auxiliary processors included

The Graphics Processor gives you full access to Apple's high resolution graphics from APL. You can print to any ASCII device, including plotters, through arbitrary input and output modes. Our system variable quad-AV gives you all the characters any APL/ASCII device can print, plus all 32 ASCII control characters, APL overstrikes, underlines, lower-case letters, and special control characters for full-screen applications. The Utility Processor gives you memory access and processor calls to both the 6502 and the Z80, so APL/V80 can access virtually any Apple system ROM or peripheral card. Our CP/M Input File Processor lets APL/V80 read and work with any CP/M file.

An Input Stack Processor lets you spool input commands for later execution. Our APL File Processor gives you an indexed file system. The WSFNS workspace makes APL/V80 compatible with common functions from standard mainframe APL versions, plus some non-standard functions such as string-searching and extended formatting. Workspace FILEFNS gives you the most commonly used facilities of file systems found on large timesharing services such as I.P. Sharp and STSC.

Make your Apple a wizard of a terminal

Appropriate settings of APL/V80's system variable quad-TT, combined with your modem, let your Apple communicate with other computers. The APLTERM workspace goes even further, transforming your Apple into a wizard of an APL terminal. WSIS uses the workspace Interchange Standard format to transfer application workspaces in from or out to other APL systems. This gives you the power to move APL programs developed in one version of APL into another.

Amazing APL power for your Apple

If you already use some version of APL on a mainframe, a time-sharing service, or a minicomputer, you may wonder how useful APL/V80 can be in an Apple-size workspace. Our answer: you'll be amazed! To give you utmost memory availability, APL/V80's auxiliary processors occupy memory only when loaded. By using our)CSAVE and)CCOPY commands to move functions and variables into and out of a workspace, you can run applications far larger than your workspace. Also, APL/V80 makes auxiliary processors you develop more powerful. By offering a variety of supervisory services, APL/V80 lets your AP's write error messages, read input, convert data, do string search and compare, or even halt processing upon error discovery.

Minimum hardware required

APL/V80 for the Apple requires a 48k Apple II with autostart ROM, or Apple II+, one disk drive, a Z-80 SoftCard, and either the Language Card, RamCard, or some other compatible 16k memory extension card.

To learn more, act now

No matter what problems you're resolving, APL/V80™ can help you solve them faster, more easily. If you'd like to know more, send us the coupon below. APL/V80 does so many things, in a single page we can hardly begin to tell all the ways it can help you. Write today for the full story of APL/V80 for your Apple.

NOTE: Specifications subject to change without notice. Apple design, Apple II, Apple II+, and Language Card are trademarks of Apple Computer, Inc. CP/M is a trademark of Digital Research. SoftCard and RamCard are trademarks of Microsoft.

Contact your local Apple dealer for a demonstration of APL/V80 and get your copy today. If you don't have a local dealer, use this coupon to order direct from us now: Please rush the items ordered below. I understand all items are normally in stock and available for immediate shipment:

- ☐ **More information about APL/V80 for Apple**
- ☐ **APL/V80™ User's Manual** - Enclosed is $30.
- ☐ **Complete APL/V80 - Apple Software Package** Enclosed is $500. Please send me an end-user license, object code disk, documentation manual, and special APL character generator.
- ☐ **Software PLUS RamCard** - Enclosed is $675.
- ☐ **Software PLUS Z-80 SoftCard** - Enclosed is $850
- ☐ **Software PLUS Z-80 SoftCard PLUS RamCard** Enclosed is $995
- ☐ **Complete Hardware - Software system** - APL/V80 - Apple Software PLUS Apple II+ 48k computer with APL character generation card already installed PLUS Apple Disk Drive, PLUS NEC 12" video screen PLUS SoftCard PLUS RamCard. Enclosed is $3195.
- ☐ **As above with second Disk Drive** - Enclosed is $3695.

Enclosed is my check for $ ________ Card # ________ exp. date ____

OR Charge to: ☐ MasterCharge ☐ Visa Signature ________

Ship to: Name ________

Address ________ Phone ________

City ________ State ________ Zip ________

VANGUARD SYSTEMS CORP.
6901 Blanco Road
San Antonio, TX 78216
(512) 340-1978

Circle 423 on inquiry card.

A Day in the Life of an HP-41C

I prefer to call my HP-41C an HHC. That way I don't have to call it a "calculator" or a "computer." Hewlett-Packard calls it both a "calculator" and a "system." Actually, the versatile HP-41C can be treated any way the user desires. Its power and flexibility are illustrated by the following tour of the HP-41C world.

It's morning and I find no cash in my pockets. No, the HP-41C cannot mint money, but its continuous memory can tell me how much I have in my checking account. Upon pushing RCL *(recall), the legend* RCL *appears in the alphanumeric liquid-crystal display. To the right, two* prompts *(cursors) can be seen; these prompts are the HHC's signal to supply a two-digit number in response. Since data register 9 contains the amount of my checking account balance, I punch* 0 *and* 9. *The HP-41C answers with $127.59000.*

I only need to display two digits after the decimal, so I push SHIFT *for secondary key functions, then* FIX *and* 2. *Each key gives a satisfying "thunk" when pressed; tactile feedback has always been a Hewlett-Packard feature. The display is even more helpful by naming each button's function as it is pushed. It's also easy to cancel or correct a function if a mistake is made. By using the back arrow key ←, the screen unambiguously shows each correction, and HP-41C error messages appear in English.*

I see that I have exactly $127.59 in my checking account. Before deciding to deplete the account, I run downstairs to check the just-delivered mail and happily discover the arrival of a check for $300. Pushing 3 0 0 STO + 0 9 *adds the $300 to my checking account (at least within the calculator). In addition, I push* Σ+ *and see the number 12, marking the twelfth deposit I have made since I began to count deposits in the Sigma registers. The Sigma registers can compute the mean (average) of all my deposits, the standard deviation, and other statistical functions. To find the mean, I push* XEQ *(for* execute *or* run*) and then spell out* M-E-A-N. *This ability to call a function by spelling out its name is very much a computer-like action.*

After stopping at the bank, I head for the recording studio where I work as an acoustical consultant and maintenance man. Arriving at the studio, I discover a volume unit (VU) meter that reads too low. I apply a sine wave to the recording console's input; 2.0 volts (V) are measured across the output terminals, yet the meter reads 0 VU. Thanks to a program I've written, my HP-41C can talk to me in English and clue me in to the decibel error of the meter (see listings 1 and 2). I can call this program in two ways. One way is by name as above: XEQ d-B-V, and the program begins running. Since I use the dBV program a lot, I reduced the keystrokes to a single one via the USER mode.

In USER mode, the HP-41C is customized for individual use; programs or functions can be reassigned to any keys. The entire keyboard can even be reconfigured if desired, then returned to normal by a second push of the USER *key. An added attraction is a keyboard overlay which allows you to identify reassigned keys with stick-on labels. Thus, a small, uncluttered keyboard can call literally hundreds of functions.*

Throughout the course of the morning, I will use several HP-41C functions and two other programs. When the job is done, I attach the HP-41C to one of many available accessories, a battery-powered thermal printer. With the aid of still another program, it prints out an invoice of parts and labor performed on this job.

On the way to the next job, a friend and I play a game of Hangman on the HP-41C. This game is included in the Games Pac, which is designed to help while away those between-business hours. More serious Standard Module Pacs are available to help perform engineering and scientific tasks, among others. The average application module price is $35. The COPY function permits copying any program from ROM (read-only memory) to RAM (random-access read/write memory) to allow customizing. For example, I have added personalized prompts to the game of Hangman.

Listing 1: A single key depression in USER mode executes the author's program dBV. The calculator first prompts for a voltage entry; response is 2.0 V, and the RUN key is pressed. The calculator asks for reference voltage; 0.775 V is assumed if RUN is pressed. The answer is 8.2 dB over 0.775-V reference. Next, the program is run with a different reference voltage (1.23 V, which is 4 dB above a one-milliwatt reference across 600 ohms). The answer is 4.2 dB over 1.23 V. Another key depression in USER mode executes the author's program VOLTS. The calculator indicates that 1.55 V is 6 dB over 0.775 V. The display is formatted to two decimal places but can easily be changed.


```
      XEQ  "dBV"
VOLTS?
  2.0      RUN
REF?R/S=STND
           RUN
8.2 dB/0.8 V
      XEQ  "dBV"
VOLTS?
  2.0      RUN
REF?R/S=STND
 1.23      RUN
4.2 dB/1.2 V
 XEQ  "VOLTS"
dB?
 6.00      RUN
REF?R/S=STND
           RUN
1.55 V/0.77
```

Don't gamble with your business!

Invest in an M System

"Okay, which entry-level, single-user microcomputer should I own?"
The BOS M System.
"Which multi-user system should I own?"
The BOS M System.
"If I want a larger system with the ultimate in performance and capacity, what should I own?"
The BOS M System Multiprocessor.
"How much more does it cost to own a single-user set-up and upgrade it, than to start with a larger system?"
Not a penny more.
"Can I have diskette, tape, and large rigid disk storage?"
Yes.
"How about really good accounting software?"
The MBSI* package (GL, AR, AP, PR, OE/INV, Sales Analysis — all in Cobol) is probably the best available on any system...this is one you have to see to believe.
"How about Word Processing?"
WordStar, and others.**
"Can I run all the other software I've seen?"
Yes, if it's CP/M* compatible, almost certainly!**
"Will I have to change the operating system when I expand?"
No, with BOS/TURBODOS**, just upgrade it.**
"Well, this is important...will service be available when I need it?"
Yes, with a large dealer network, strategically placed maintenance depots, and fast factory repair turn-around.
"Sounds great! But isn't it too good to be true?"
No...and it's not even expensive! So, why take a chance with somebody else?
"Okay, how can I get one?"
Contact your dealer, systems house, or consultant — or call us toll-free!

Dealer and OEM Inquiries Welcome



Business Operating Systems, Inc.
2835 East Platte Avenue
Colorado Springs, Colorado 80909
In Colorado Call: (303) 634-1541
Toll Free Number: 1-800-525-3898

Circle 63 on inquiry card.

APPLICABLE INDUSTRY STANDARDS: S-100 IEEE 696 • RS 232, HDLC, SDLC, Async, Sync • CP/M*** TURBODOS**** • 8" soft sectored diskettes • ANSI X3/B5/15 Tape Ca tridge

*Micro Business Software, Inc. • **Trademark of Micropro Int. Corp., San Rafael, CA • ***Registered Trademark of Digital Research • ****Software 2000, Inc.

The powerful programming ability of the HP-41C is enabled by an extended version of the RPN language that Hewlett-Packard introduced to the public in 1971 with the world's first handheld scientific calculator, the HP-35. Over 130 scientific functions and 56 programmable flags are available, some of which keep track of the status of peripheral devices as well as control the peripheral's status. While all previously made calculators were hardware-intensive *devices, the HP-41C is a* software-intensive *device. As such, each plug-in module adds completely new functions, giving the HHC a new personality.*

Hewlett-Packard has taken a lot of care in naming functions so one can remember them easily, but if I forget the name of a function and don't have the instruction manual handy, I'm not helpless. I can call up a CATALOG, a directory of the many functions available. Three such catalogs exist in the HP-41C (see listing 3). Usually this list is enough to jog my memory.

The future of the HP-41C is virtually unlimited. If there were enough demand, a higher-level language such as FORTH or even BASIC could be implemented in a plug-in ROM. However, I find that the versatility of RPN eliminates the need of a higher-level language in most applications. A BASIC interpreter would run markedly slower than RPN. FORTH might be faster than BASIC, but the experienced user soon discovers that new functions can be added in a remarkably FORTH-like manner.

Listing 2: A single key depression in USER mode executes the author's program PTOF (pitch to frequency). The calculator asks for the note, and the operator responds with "B Flat," one octave below middle C. The answer is 223 Hz; the note and its octave are also given. Next comes a printout of the first 22 steps of the PTOF program. Note the compact nature of the RPN code. Each line's interpretation follows: 01—ALPHA Label; 02 and 03—store loop control number in register 00; 04 and 05—store ALPHA string in register 01; 06—display format with no digits following the decimal; 07 through 09—these steps display the PROMPT shown above; 10—the operator's note is stored in the X register; 11—clear flag 22, the digit entry flag; 12 through 14—these steps display the second PROMPT shown in the running program; 15 through 17—if flag 22 is clear, store 0 in register Z. Otherwise, store the octave number there; 18 through 22—some of the alphanumeric manipulations available to the HP-41C user. A complete listing of this program is available from Hewlett-Packard's Users' Library. Write to Hewlett-Packard, Corvallis Division, 1000 Northeast Circle Blvd., Corvallis, OR 97330 for information on how to join the Library.

```
   XEQ  "PTOF"
NOTE?
BF
            RUN
OCTAVE?R/S=0
   -1       RUN
233 HZ, BF/-
1
         PRP  ""

 01♦LBL  "PTO
            F"
 02 .005
 03 STO 00
 04 "CDEFGA"
 05 ASTO 01
 06 FIX 0
 07 "NOTE?"
 08 AON
 09 PROMPT
 10 ASTO X
 11 CF 22
 12 "OCTAVE?
        R/S=0"
 13 AOFF
 14 PROMPT
 15 FC?C 22
 16 0
 17 STO Z
 18 XEQ 05
 19 ARCL Y
 20 ASTO Y
 21 ASHF
 22 ASTO T
```

Listing 3: A printout of the HP-41C's CATALOG 1 function, which lists all user programs in RAM, including the number of bytes required. Total room used here is 1148 bytes. Approximately 1064 bytes are free in the HP-41CV for more user programs, an astounding amount of storage ability for an HHC.

```
             CAT 1
LBL'HEX
END        268 BYTES
LBL'PTOF
END        203 BYTES
LBL'dBV
LBL'VOLTS
LBL'dBM
LBL'WATTS
END        292 BYTES
LBL'Z
END        62 BYTES
LBL'FREQ
END        19 BYTES
LBL'PAR
LBL'RPAR
END        37 BYTES
LBL'HANG
END        262 BYTES
.END.      33 BYTES
```

Text continued from page 76

nectors. The cables are simple stranded wire; gauge is of little importance. Cable lengths can be up to 10 meters between devices when using simple stranded wire. Distances of up to 100 meters are possible with twisted, shielded, pair wire. Each HPIL peripheral (e.g., printer or data cassette) is equipped with two corresponding mating connectors. Extension cables are available from Hewlett-Packard.

Plug the two loose cables into the side of the peripheral and you're ready to go. If there is more than one peripheral, connect the devices in a sort of daisy chain. In this loop, information passes from a sending device

Look What Apparat has for your IBM Personal Computer.



The following add-ons are available immediately:

- 2 Dual Headed 40 Track Drives — (appears as four) 640K of storage, software patch, easy internal mount. $630.00
- Combo Card — Parallel printer, ASYNC communication (RS-232), and clock calendar functions, uses only one slot. $279.00
- 2 Single Headed 40 Track Drives — 320K of disk storage, easy internal mount. $450.00
- 48K additional RAM — 27 chips plug into master PC board $75.00
- Add-on Memory Card — (uses 64K dynamic RAM chips), 64K — $425.00, 128K — $525.00, 192K — $625.00, 256K — $725.00
- Prom Blaster — Programs most 1K to 4K EPROMS of 25XX and 27XX single or multivoltage, personality modules, read/write software. $149.00
- Apparat Game Diskette — $24.95
- Clock Calendar — Features seconds, minutes, hours, day of week, date, month and year, backup battery, leap year and crystal time base. $129.00
- Prototype Card — 3.5 by 8 inch wirewrap holds 150-14 pin dips. $29.95
- RGB Color Monitors — Includes cable, 16 color modifications, NEC — $1,095.00, AMDEK — $899.00, TECO — $699.00.
- 3rd and 4th Add-on Drives — Expansion cabinet and IBM compatible drives, cabinet and 1 drive — $499.00, two drives — $749.00
- 64K Hardware Print-Spooler — Parallel printer adapter, buffers 13 minutes of output at 80 characters/second. $399.00.
- EPSON MX Printers — MX-80 (with dot addressable graphics) — $499.00, MX-80 F/T — $575.00, MX-100 — $775.00
- Verbatim Datalife Diskettes — (5-1/4″ 40 track, box of 10) $24.95
- 16K Memory Kits (9 chips) — $25.00
- 5-1/4″ Flip-Sort — $21.95
- 5-1/4″ Plastic Library Case — $1.95

Apparat will continue to develop add-on products for your IBM Personal Computer. Call today for more information. Dealer inquiries welcome.

(303) 741-1778

IBM Personal Computer is a trademark of IBM.





4401 So. Tamarac Parkway, Denver, CO 80237 (303) 741-1778

"ON GOING SUPPORT FOR MICROCOMPUTERS"

Circle 33 on inquiry card.






Photo 1: *The HPIL Module.*




Photo 2: *HP-41C connected to an HPIL Module, Digital Cassette Drive, and Thermal Printer/Plotter in the loop.*




Figure 1: *The HPIL is a continuous loop, with data and instructions traveling from an originating device back to that device for a complete, bit-for-bit error check.*

through all the other devices. When data return to the source, they are completely checked for errors (see photos 1 and 2 as well as figure 1). Since each succeeding battery-operable device uses its own power to retransmit the data it receives, total power in the loop is shared equally, minimizing battery drain. All communication between devices is supervised by the HPIL Module, which is now available for $125.

Circle 431 on inquiry card.

HPIL Specifications: The New Firmware

As mentioned earlier, plugging a ROM into the HP-41C gives it a new personality. The HPIL Module is no exception. Within it are the routines essential for turning this portable, programmable calculator into a versatile "outside world" controller. Three types of HPIL routines are supported: printer-type operations (also suitable for video display and for controlling external devices); mass storage operations (for digital cassette or disk drive); and interface control operations (largely used for controlling external devices).

The HP-41C as controller can address each device in the loop by a unique number. The HPIL Module is capable of addressing up to 30 devices in the loop, certainly a quantity large enough to satisfy most users. If that's not enough, the addition of a module called the Extended I/O (Input/Output) ROM will allow the HP-41C to extend its address capability to a total of 961 devices on the loop. If still more devices are needed, loops can be connected through an HPIL Converter. (Each loop, however, must have its own controller.) The Extended I/O ROM has additional capabilities which I'll discuss later.

The calculator/controller designates which peripheral is to be a sending device (called a *talker*) because there can be only one talker at a time. The other devices on the loop become *listeners*. When so instructed, listeners can also act upon data passing through. For example, a printer can print information, a video display can display it, etc.

Hewlett-Packard does not intend to publish the actual voltage levels or the digital nature of the commands used within the two-wire HPIL loop. It has revealed that the HPIL communicates with the outside world through the HPIL Converter, a general-purpose interface board designed to be attached to the user's GPIO (general-purpose input/output device) equipment. For example, an original equipment manufacturer (OEM) may wish to install an HPIL Converter within its electronic voltmeter, enabling the voltmeter to be programmed by an HP-41C or other computer. Hewlett-Packard intends to aid other manufacturers by providing all the details necessary for them to successfully communicate with the HPIL Converter. An overview of converter hardware connections will be presented in a later section.

An Asynchronous Communication Loop

Quite a few more essential details are known about the loop's *protocol*. The HPIL is an asynchronous communication loop whose speed self-adjusts to that of the slowest *active* device in the loop. For example, if a slow printer is connected within the loop but is not to be used, the controller can instruct the printer to ignore data/instructions and pass them on to the next loop device. That way the loop can operate at its fastest possible speed. The Extended I/O ROM will even allow a means for the Digital Cassette Drive to pass data to the printer through an essentially inert HP-41C. In this mode, the HP-41C

will become a relay device rather than a controller and will not retard loop operation.

HPIL Speed

Just how fast is the HPIL loop? Depending on circumstances, it can approach speeds of 40,000 bps (bits per second). While this is many times faster than most RS-232C serial links, the HPIL can be slower than the parallel-based IEEE-STD-488 bus. (Originally known as GPIB or HPIB for Hewlett-Packard Interface Bus, the present IEEE-STD-488 was developed by Hewlett-Packard.) The HPIL is intended to be a low-cost, noncompetitive alternative to IEEE-STD-488. The HPIL *is* competition, however, for the more antiquated RS-232C. Just the fact that the HPIL uses only two wires gives it a definite advantage; then there is the availability of an HHC as a controller.

Let's look at the speed of this asynchronous loop in more detail. Since instructions as well as data are sent around the loop, the instruction cycle of the controller may become a significant factor. In almost all cases, the loop controller will be the HP-41C portable calculator. While microcode (machine language) runs through the HP-41C at a speed of about 350 kHz, the practicalities of the Macro Instruction Interpreter effectively make an instruction cycle much slower. An instruction such as ENTER↑, originally keyed into program memory by the operator, takes about 40 ms to execute. This includes the overhead of the Instruction Interpreter and the HP-41C Operating System. Therefore, practical data throughput speed will probably average about 150 bytes per second (1200 bps). The 40,000-bps HPIL maximum could only be managed by, for example, an HP-80 series computer running a machine-language controller program or by controllers Hewlett-Packard is now developing.

Using the Loop

Operation of the loop can be completely transparent to the user. When a printer is in the loop, the operator (or a running program) simply executes a PRINT function; the HPIL searches for the first available printer to perform the function using a unique feature called an *accessory poll*. Optionally, the operator (or a program) may specify a particular printer by means of the SELECT function. In this case, the operator becomes only a little more involved with HPIL operation.

Manufacturing plants may wish to have the HPIL control a set of relays and read a number of indicators. The HP-41C is ideally suited to that task. Its alphanumeric capabilities and versatile keyboard allow programs to be written so that they can talk to the plant operators in plain English while performing complex underlying operations.

Efficient firmware in the HPIL Module is available, allowing a user to perform READ/WRITE functions onto a mass storage device (such as the Hewlett-Packard Digital Cassette Drive) or PRINT functions. Firmware supports either the Hewlett-Packard printer or any ASCII-compatible standard printer having a parallel port. Using less efficient instruction methods, the present firmware also allows the HP-41C to query and change the status of relays, monitors, voltmeters, or hundreds of other devices.

More Efficient I/O Operation

The Extended Input/Output ROM plugs into the back of the calculator and will add the following functions to the firmware:

- Extended addressing of up to 961 devices on the loop
- User access to all additional functions involved with

Listing 4: *The DIRECTORY that leads every HP digital cassette. Owners of the Card Reader will be interested to know that file ALL is a WRITEALL file containing the complete status of an HP-41CV. This file loads in about 25 seconds as opposed to the several minutes and inconvenience of using over 10 magnetic cards. More than 50 files of this size can be stored on one cassette!*

```
                    DIR
NAME     TYPE      REGS
HEX      PR          39
STATUS   KE           1
TEST     ST          10
ALL      WA         336
PTO      PR          29
dBY      PR          42
Z        PR           9
```

control and query of external devices attached to the loop

- A routine to enable bar-code generation on the new HP82162A Thermal Printer/Plotter
- A routine to allow one or more cassette copies to be generated; especially valuable when distributing software or data for OEM use
- An external device will be able to "call" the controller for service requests

The HP82183 Extended I/O ROM will be available by the summer of 1982, with price to be announced.

Extended Functions/Solid-State Mass Memory

The HP82180A Extended Functions/Memory Module adds firmware as well as additional read/write memory to the HP-41C. While this new product is not directly involved with HPIL operations, it is being introduced now in an effort to make the HP-41C a more "friendly," versatile controller and, of course, an even more powerful HHC. HP-41C owners not interested in controlling external devices can still make use of the Extended Functions/Memory Module. First, this device adds 47 new functions not included in the HP-41C mainframe. Second, the HP82180A and two companion Extended Memory Modules can increase the solid-state memory space of the calculator by 4.2K bytes to a whopping, handheld total of 6.2K bytes.

Many users will look forward to a programmable ASSIGN function, which will enable special-purpose keys to be automatically assigned and later cancelled within specific programs. Previously, key assignments had to be executed manually. Note that the *software-intensive* design of the original HP-41C is what makes these post-production enhancements possible.

Another extended function allows alphanumeric manipulations previously manageable but relatively cumbersome in the standard HP-41C. For example, the leftmost character of an alphabetic string can be identified by a program and then acted upon. The 104-step program PTOF (partially described in listing 2) could be reduced to approximately 80 steps and would run faster with the new extended functions.

Additional memory of 889 bytes is contained in the HP82180A; its companion, the HP82181A Extended Memory Module adds 1666 bytes. Two HP82181A units can be used at any one time. With all three modules plugged in, 4221 bytes of extended memory are available to the user. The additional 4.2K-byte memory is called *extended* memory to distinguish it from the *resident* memory of the HP-41C. Extended memory is not online in the sense that programs can be executed directly or that data can be used directly. Instead, the new read/write memory is organized in a *file and register format,* just as on a disk drive and with equivalent access speed.

For example, two completely different specialized calculators could be kept in solid-state storage and downloaded into the main RAM on demand. ASCII data of up to 4221 characters could be collected and stored in the field to be acted later on by the HHC, by a computer, or transferred to the new Digital Cassette Drive. It will not be necessary to "wipe" information in main RAM in order to move data from the extended memory to the Digital Cassette Drive. Data within the extended memory can also be sorted, alphabetized, or otherwise organized at disk-access speeds. The HP82180A Extended Functions/Memory Module is now available for $75, as is the HP82181A Extended Memory Module.

Industry Reaction to the HPIL

The HPIL is certainly a versatile system, but what's the catch? For now, there *is* one little catch: other manufacturers may design peripherals to attach to the HPIL, but the only loop controller presently available is a Hewlett-Packard product. Therefore, a turnkey system would contain at least two Hewlett-Packard products—the HPIL Converter and an HPIL controller. The company says that the converter hardware will support controller operation. Unfortunately, the software to run a controller is very complex, causing concern over possible improper HPIL operation. Nevertheless, manufacturers who wish to develop a controller for the HPIL may contact Hewlett-Packard for details. Despite the Hewlett-Packard monopoly on the controller, the HPIL will probably become popular with other manufacturers simply because the versatility of Hewlett-Packard's most powerful calculator makes it the ultimate controller.

HPIL Peripherals: The Digital Cassette Drive

To me, the most intriguing new peripheral is the Digital Cassette Drive. Using digitally certified magnetic tape, it is truly a *mass* storage device (see photo 2). Up to 131,072 bytes of online mass storage will fit into a small cassette similar in size to an audio microcassette. The drive itself is compact, and its flip-top cover contains a convenient storage space for two cassettes. The magnetic storage is 50 times the size of the HP-41CV RAM and, according to Hewlett-Packard, contains enough mass memory to accommodate all the programs from the 26 HP-41 Solutions Books onto one tape. If this is not enough online capacity, HPIL firmware even allows "chaining" of multiple drives. The user or a running pro-




Photo 3: *With the HP-41, HP82160A, HPIL Interface Module, HP-85, and HP82938A HPIL Interface Card, portable data collection, direct data transfer, and sophisticated data analysis are made easy.*

gram simply calls a file by its name. The HPIL firmware searches the directory at the head of each cassette until it finds the selected file, then loads the file from that drive into RAM.

The cassette drive is of digital quality. It records data with parity, and a VERIFY function is available to check for errors. Being HPIL compatible, it can be addressed by controllers yet to be developed for the loop. Powered by rechargeable batteries, the drive has a standby power mode feature, especially valuable where operation on batteries and without human intervention is expected for long periods. The controller *automatically* calls a POWER UP function when it wishes to access the cassette drive. As a result, this unit is truly field operable.

Using a two-track format, the cassette drive is bidirectional (one track per direction) with two speeds: 23 centimeters (9 inches) per second read/write speed and 76 centimeters (30 inches) per second search/rewind speed. For those concerned about potential head wear at these speeds, the company asserts that the tape-to-head pressure is so light that head wear is insignificant. Data density is 335 bits per centimeter. Format is 256 bytes per record, with 512 records available per cassette.

When a file is called, the machine first reads the directory at the head of the cassette for the location of the named file (see listing 4 for an example of a tape directory). Then the cassette rapidly (76 cm/s) winds to the file and reads it back to the HPIL. Before writing a file, the machine looks through the directory to see if the name already exists. If so, it will rewrite (record over) that file. If not, and if space is available on the medium, it will add the new file name to the directory, speedily jump to the free spot on the tape, then record the new file, all under HPIL control.

Seven different types of files may be recorded: Program, Data, Key Assignments, Status (condition of the HHC—useful for reestablishing conditions after a running program has been interrupted), Writeall (entire contents of the calculator), ASCII, and Unknown.

To check the effective speed of the cassette drive, I recorded and then read back a Writeall file (2352 bytes). I timed the machine from the moment I pressed the last key of the READALL command to the time the read was completed. It took 27.5 seconds; therefore, effective average speed of data transfer using cassette is 85.5 bytes per second (684 bps). The read/write speed on the medium is a respectable 963 bytes per second, but, as you can see, tape-cuing time must lower the real speed considerably. The same amount of information could be loaded from a typical disk drive in a couple of seconds.

New Thermal Printer

Probably the most important feature of the new thermal printer is its HPIL capability, which allows it to be addressed by future controllers and computers. The HP82162A Printer/Plotter includes all the features of the earlier HP82143 as well as the ability to print bar code. Since it too runs on rechargeable batteries, a standby power mode is included.

For those who are unfamiliar with the earlier printer, its features include: ASCII standard upper and lowercase characters and special characters, double-wide printing option, a 24-character line, user-definable characters, and plotting capabilities. HP-41C users should immediately see the potential of the HPIL interface plus printer plotting—an input signal can now be plotted in real time.

More HPIL Peripherals

The HP3468A Digital Multimeter (DMM) is programmable through the HPIL. Its 12-character alphanumeric display can output messages generated by the controller or by the DMM. Resolution is adjustable from 3 to 5 digits, with increased resolution resulting in a proportional trade-off in speed.

The HP82938A HPIL Interface Card shown in photo 3 plugs into the Hewlett-Packard Series 80 personal computer. The computer will then be able to take control of the loop. It can also be programmed to store and analyze data collected on the calculator. ROMs for the Series 80 machines are compatible with the HPIL Interface Card, allowing the computer to use the printer, cassette drive, and all future HPIL peripherals.

The HP82182A Time Module plugs directly into the HP-41C. This will allow the unit to be turned off and then "awakened" automatically by the timer's programmable ALARM function. The program will start running the line at which the HP-41C was positioned when it was turned off (or when it turned itself off). Since OFF is a programmable function, the process can be repeated indefinitely. The timer becomes especially useful in a controller situation, allowing measurements to be taken at regular intervals, devices to be turned off, pressures regulated, etc. This module can also display time and date and provide calendar data over a 2738-year span.

The HPIL Converter

The key to the HPIL's success will be the availability of

TAKE A TEST DRIVE.



Our drives feature excellent engineering, and all of the advanced performance features you've come to expect from the nation's leading disk drive manufacturers. All systems are completely burned-in and tested. And, you'll see at least five quality assurance stamps on each and every drive, which is how we make sure our drives will run and will continue to run past our optional two year extended warranty.

Our drive packages start at $250.00 and include a comprehensive operations manual and an attractive static free, dust free cover.

Systems available for Altos, [1]Apple™, Atari, Heath™, North Star™, S-100, [2]TRS-80™ (Model I, II, III, Color), Zenith™.

If one of our drives fails to meet your highest expectations of how trouble free and reliable a disk drive can be, then return it to us for a complete refund.*

So, before you buy another drive, take a test drive with one of ours. We're sure that you'll find TRAXX to be the finest.

IT'S GUARANTEED!

Circle 419 on inquiry card.

TRAXX
COMPUTER CORPORATION

Call our toll-free TRAXX LINE: 1-800-621-3102. In Illinois, call: (312) 987-1024. 10AM-6PM CST, Monday thru Friday. *For full refund drives must be returned within 10 days of purchase.

[1] Apple is a registered trademark of Apple Computer Inc.
[2] TRS-80 is a registered trademark of Radio Shack, a Tandy Company.




Photo 4: *The HPIL Converter (4.5 by 11 by 2 cm) connects the HPIL loop with the outside world.*

the HPIL Converter. This component (see photo 4) is designed to interface the HPIL with the outside world. OEMs may wish to build HPIL capability into components such as measurement instruments, enabling programmable control by an inexpensive HHC rather than a much more costly computer.

BYTE readers who have connected hardware to computer input/output ports are probably familiar with a VIA (versatile interface adapter) or a PIA (peripheral interface adapter). Applying a similar philosophy, the HPIL Converter is a much smarter device. The converter contains the necessary firmware to recognize HPIL instructions and to convert specific instructions and data from the serial HPIL format to a dual 8-bit parallel format. As a matter of fact, one of the sample schematics presented in the converter manual is an interface with a Centronics-style parallel printer connector.


Hewlett-Packard supplies a 34-pin printed-circuit-type mating connector; a standard ribbon connector will also work. Power for the HPIL Converter (+5 V DC at 90 mA) is derived from the host device. All input/output lines are TTL-compatible and include two bidirectional 8-bit ports, three input handshake lines, three output handshake lines, and several special-purpose lines. The latter are used for triggering external devices and for communicating special conditions such as power down, power up, or service request. Complete hookup details for programming negative or positive logic strobes, full or half duplex operation, and more are furnished in the HPIL Converter documentation.

Some Revisionist Thoughts

The addition of all this hardware to the Hewlett-Packard arsenal poses a couple of logistical problems. The first problem concerns battery charging; there are too many plugs and not enough sockets. The HP-41C, printer, and cassette drive each come with identical-style power connectors. A power transformer and a charging cable are also furnished with each unit. It is certainly inconvenient to have to find wall sockets for all these devices. I hope that Hewlett-Packard relieves the conges-

galaxy of features

A GALAXY of features makes the **LNW80** a remarkable computer. As you explore the **LNW80,** you will find the most complete, powerful, ready to run, feature-packed personal and business computer ever made into one compact solid unit.



MODEL I COMPATIBILITY – The **LNW80** is fully hardware and software compatible with the Model I. Select from a universe of hardware accessories and software – from VisiCalc® to space games, your **LNW80** will launch you into a new world of computing.

FULLY LOADED – A full payload includes an on-board single and double density disk controller for 5 ¼" and 8" single or double sided disk drives. RS232C communications port, cassette and parallel printer interfaces are standard features and ready to go. All memory is fully installed – 48K RAM, 16K graphics RAM and 12K ROM complete with Microsoft **BASIC.**

QUALITY CONSTRUCTION – Instrumentation quality construction sets **LNW80** computers apart from all the rest. Integrated into the sleek solid steel case of the **LNW80** is a professional 74-key expanded keyboard that includes a twelve key numeric keypad.

HIGH RESOLUTION GRAPHICS & COLOR – The stunning 480 X 192 resolution gives you total display control – in color or black and white. The choice of display formats is yours; 80, 64, 40 and 32 columns by 24 or 16 lines in any combination of eight colors.

PERFORMANCE – Lift-off with a 4MHz Z80A CPU for twice the performance. The **LNW80** outperforms all computers in its class.



Our down to earth price won't send you into orbit

LNW Research Corp.
2620 WALNUT Tustin, CA. 92680
(714) 641-8850 (714) 544-5744

Monitor and Disk drives not included
TM Personal Software, Inc.




Photo 5: *Hewlett-Packard's HP82163A Video Interface connects a monitor or TV to HP's interface loop. This permits handheld computers like the HP-41C—previously limited by a single-line display—to display information in a 16-line by 32-character video format. Aided by the new interface (available by the end of 1982), HP-41C owners can review up to 16 program steps at a time.*

tion by introducing a charger capable of powering several peripherals at once.

The second logistical problem is more serious. Hewlett-Packard has supplied a "horn of plenty" in modules, but there are only four sockets to receive them. A user may very well need to operate several of these modules simultaneously. Hopefully, the company will soon supply a "piggyback module adapter" of some sort to relieve the problem. Outside of the above, very few complaints can be made about Hewlett-Packard's well-supported products.

The Future

With the introduction of the HPIL Loop, Hewlett-Packard has made a commitment to issue a series of new HPIL controllers, peripherals, and instruments. Expect to see in the near future a video/TV monitor interface (shown in photo 5), an 80-character/line impact printer, an HPIL/RS-232C converter, and a self-powered version of the GPIO board designed for the home hobbyist. No official corporate announcement has been made at this writing, but Hewlett-Packard probably will introduce these items before the end of the year.

I'm sure someone will ask about word processing with the HP-41C and the HPIL. It's conceivable but not without an external keyboard since the HP-41C is only good for "hunt and peck" typing. Its alphanumeric capabilities and portability will lend themselves to many other unique jobs in the very near future.


Conclusions


As usual, Hewlett-Packard's documentation is excellent. Prototypes of the new products must have been in use within the Corvallis, Oregon, plant for a considerable length of time because the style of the instruction manuals reflects much experience with the products.

With any new and complicated product, there are bound to be bugs. The ones I have found so far have been minor. My experience is that Hewlett-Packard's Corvallis Division will respond to consumer complaints quickly and efficiently.


The potentials of the HPIL loop are literally awe-inspiring. As such, it is difficult for me to make an overall evaluation other than that the future looks bright. I suggest you read on to page 94 and delight in what's just over the HPIL horizon. ■

S-100 STATIC MEMORY BREAKTHROUGH









64K STATIC RAM $795

32K PARTIALLY POPULATED $479 48K PARTIALLY POPULATED $659

Finally, you can buy state-of-the-art S-100 static memory for your computer at unprecedented savings.

Memory Merchant's memory boards provide the advanced features, quality and reliability you need for the kind of operational performance demanded by new high-speed processors.

COMPLETELY ASSEMBLED

These memory boards are not kits, nor skeletons—but top quality, high performance memories that are shipped to you completely assembled, burned-in, socketed, tested and insured with one of the industry's best warranties.

SUPERIOR DESIGN & QUALITY

Memory Merchant's boards are created by a designer, well-known for his proven ability in advanced, cost-efficient memory design. Innovative circuitry provides you with highly desired features and incredible versatility.

Only first quality components are used throughout, and each board is rigorously tested to assure perfect and dependable performance.

SHIPPED DIRECT FROM STOCK

All Memory Merchant's boards are shipped direct from stock, normally within 48 hours of receipt of your order.

NO RISK TRIAL

We are so convinced that you will be absolutely delighted with our boards that we extend a no risk trial offer. After purchasing one of our boards, you may return it (intact) for any reason within 15 days after shipment and we will refund the purchase price.

NEW 18 MONTH LIMITED WARRANTY!

The reliability of our boards, through quality controlled production and proven performance, has enabled us to extend our warranty to a full 18 months. This includes a 6 month exchange program for defective units.

HOW TO ORDER

Please send check, money order, VISA or MASTERCHARGE (add ICA#) with your order. Sorry, no C.O.D.'s. Specify model number, and quantity desired. Shipping and handling charge is $5.00 per board. California residents add 6% Sales Tax. Credit card purchases may be telephoned to (415) 483-1008.

OEM and DEALER inquiries invited.



14666 Doolittle Drive
San Leandro, CA 94577
(415) 483-1008

64K RAM, Model MM65K16S

Cool running operation to 10 MHz

Ultra low-power consumption
- Fully loaded 64K board draws: Typ. 350 Ma. (Max. current 550 Ma.)

Bank Select Capability

Extended Addressing Capability

One 16K submodule equipped with a 2K window which may be located in any of the 2K segments

2716 (5V) EPROM Compatibility: Programmed 2716 EPROM's may replace any or all of the RAM

Four independently addressable 16K submodules on one board organized as two pair of independent 32K banks or as one 64K Extended Address Page. Each 32K bank responds independently to phantom. Bank Select logic is compatible with either Cromemco Cromix* or standard Bank Select software.

*Cromix is a trademark of Cromemco.

New 16K (2K X 8) 150ns Static RAM

Runs on any S-100, 8-bit system

MPM Conversion Option: Write for details.

16K RAM, Model MM16K14

Bank Select Capability

Extended Addressing Capability

One 4K segment equipped with 1K windows

Four independent 4K X 8 byte segments

Uses field proven 2114 (1K X 4)

Low-power consumption (Typ. 1.3 Amps)

Runs on any S-100 8080, 4 MHz Z-80 or 5 MHz 8085 system.

Prices, terms, specifications subject to change without notice.

Circle 252 on inquiry card.

A Future Day in the Life of an HP-41C

It's morning (February 1, 1983), and I find no cash in my pockets. No, the HP-41C cannot mint money, but it can call the bank for me and engage in a friendly conversation with the bank's computer. I plug the Modem Management Pack into a blank slot and connect the HP-41C to an HPIL converter which in turn has been hooked up to a telephone coupler. I quickly learn that the check from Detroit finally cleared, and my checking account is good for $1000.

Later, I arrive at the recording studio and discover a faulty VU meter (things haven't changed much). I am now carrying a powerful tool consisting of my trusty HP-41C attached to an HPIL Converter, an A/D (analog-to-digital) converter, and a long cable terminating in alligator clips. These components make up not just a programmable multimeter, but a complete measurement and analysis system customized by the user—me!

The HHC tells me that there is 2.0 V across the console's output terminals, which represents 4.2 dBs above the reference of 1.23 V. I suspect an intermittent connection, so I've programmed the HP-41C to beep whenever a change in level occurs (a high-frequency beep if the level goes up, low-frequency if it goes down) and to display the new voltage and dB level. When I wiggle a loose resistor on the circuit board, the HP-41C cheerfully beeps to signal the cause of the problem. Even in 1983, cold solder joints and bad connections cause the majority of service problems.

My next job is rather distantly located, but this time the HP-41C is not available to play Hangman. It has a much more important job to do—it's helping to fly my Beechcraft. You see, back in 1981, the Hewlett-Packard company produced a custom ROM for the Beech Aircraft Corporation, turning the HP-41C into a revolutionary flight-planning system capable of saving thousands of gallons of fuel a year. Well, today (1984?) this system has been updated so that the plane is equipped with an HPIL Converter. Since instrument data is now transmitted directly to the HP-41C, the pilot does not need to key in information about fuel flow, speed of descent, wind velocity, or air speed.

Of course, as soon as I get the money, the next step will be to purchase the HP-41C Auto Pilot. By 1985, I will be able to plan my flight at home on the portable HP-41C, carry it with me to the airport, and plug it into the control panel of my airplane. Thus, it will help me in the air and continue to serve me on the ground.

The preceding "science fiction" story is based entirely on components that are available today and on technology that is completely within reach. We have only begun to dream.

SUPERCOLOR RGB BOARD

Designed especially for the Apple II, the Supercolor RGB Board comes complete with connecting cable for Electrohome ECM-1302 RGB Monitors—for outstanding overall video quality. You select any 16-color combination from 256 available colors, for pure white text plus color in a 'Hi-Res' mode. Efficiency was never so colorful.



ELECTROHOME
ELECTRONICS

ELECTROHOME LIMITED, 809 WELLINGTON STREET NORTH, KITCHENER, ONTARIO N2G 4J6

Electrohome Distributors

Consumer Computer Mktg. Inc., Sudbury, Mass (617) 443-5128
Components Unlimited Inc., Lynchburg, VA (804) 237-6286
EMES Systems Ltd., New York, NY (800) 223-1799
Anthem Systems Company, Burlingame, CA (415) 342-9182
Mycrosystems Distributors Inc., Dallas, Texas (214) 669-9370
Computerland, San Leandro, CA (800) 772-3545 (Ext. 118)
Outside California (800) 227-1617 (Ext. 118)

Circle 164 on inquiry card.

Hardware Review

Strawberry Tree's Dual Thermometer Card for the Apple

Dr. William Murray
RD #3, Box 363
Montrose, PA 18801

If you've ever needed to monitor temperatures over an extended period of time, then Strawberry Tree's Dual Thermometer Card is for your Apple. Actually, the card is part of a complete package that also contains a disk, two thermometer probes, and a user's manual.

The thermometer card has an internal clock that can be set when the system is loaded, or, if a clock/calendar card is present in the system, the clock can be set automatically. This feature enables your Apple to record the time at which temperature data is taken. Data-sampling intervals can also be set to occur at any preset time by means of the internal timer. The current temperature, along with the maximum and minimum, can be recorded for each probe and stored on disk or sent to a printer as output.

Everything in the package (see photo 1) is first class, which helps justify the retail price of $260. The card has fully socketed integrated circuits (ICs) and gold-plated edge connectors. The 83-page manual covers virtually every topic from installation to software modification. The software is a refreshing departure from many Apple peripherals on the market today. It is usable, understandable, and can be modified if necessary.




Photo 1: *Strawberry Tree's complete package of temperature-monitoring equipment for the Apple.*

THE $595* SMART TERMINAL


The Heath 19 Smart Video Terminal gives you all the important professional features you want in a terminal, all for under $600.* You get the flexibility you need for high-speed data entry, editing, inquiry and transaction processing. It's designed to be the backbone of your system with heavy-duty features that withstand the rigors of daily use.

Standard RS-232C interfacing makes the 19 compatible with DEC VT-52 and most computer systems. And with the 19, you get the friendly advice and expert service that makes Heath/Zenith a strong partner for you.

Sold through Heathkit Electronic Centers† nationwide (see your white pages for locations). Stop in today for a demonstration of the Heath 19 Smart Video Terminal. If you can't get to a store, send for the latest Heathkit® Catalog. Write Heath Co., Dept. 052-894, Benton Harbor, MI 49022.

HEATH/ZENITH

Your strong partner



*In kit form, F.O.B. Benton Harbor, MI. Also available the completely assembled Zenith Z-19 at $895. Prices and specifications are subject to change without notice.

†Heath Company and Veritechnology Electronics Corporation are wholly-owned subsidiaries of Zenith Radio Corporation. The Heathkit Electronic Centers are operated by Veritechnology Electronics Corporation.

CP-202C

At A Glance

Name
Dual Thermometer Card for the Apple II

Use
Long- and short-term temperature measurements

Manufacturer
Strawberry Tree Computers
949 Cascade Drive
Sunnyvale, CA 94087

Price
$260

Features
Two temperature-sensing probes, Apple hardware board, software contained on a 5¼-inch disk, user's manual

Capabilities
Reads present temperature of each probe, keeps track of maximum and minimum of each probe, and records temperature difference between probes. Also records date and time when samples are taken and sends data to printer or to disk for storage.

Hardware required
Apple II Plus with 48K bytes of memory or Apple II having 48K bytes of memory with Applesoft; disk drive with DOS 3.2, 3.21, or 3.3 (will load on 13- or 16-sector machines).

Additional options
Will output with no modifications to almost all printers that have been correctly interfaced; will set the date and time directly from a Mountain Hardware card; otherwise, the internal clock can be set from the keyboard.

Hardware

The thermometer card contains 12 ICs that draw 70 mA (milliamperes) from the +5-volt supply and 30 mA from the +12-volt supply. If the need arises, up to 7 cards can be installed in an Apple II, permitting you to monitor 14 different temperatures. The probes come with 10 feet of wire but can be extended to 500 feet without loss of accuracy. The probes are electrically isolated from their 0.19-inch by 0.65-inch case but cannot be immersed in water or other conductive fluids. (Special probes are available upon request.) For noncritical applications, the probes could be enclosed in a boilable freezer bag. The accompanying loss in sensitivity wouldn't affect results where slow temperature changes are expected. The accuracy of the unit is 0.4° from −20° to 50°C and within 1° from −50° to −20° and 50° to 100°C.

The thermometer card contains two major sections—a timer and an analog-to-digital converter. Its data-acquisition is similar to that used by the Apple's game paddles: resistance changes from the probes are used to alter the timing of a latch. The precision of the timing circuit is much more accurate, however, than the Apple's simple circuit and is fully described in the user's manual.

Because the system is set up to be slot independent, the card can be located anywhere (yes, even slot 0) without major modifications. External devices such as fans or heaters can be controlled using the data obtained from the dual thermometer board with the addition of the necessary interface hardware. This makes the device helpful not only for monitoring temperatures but also for controlling them.

Software


The software will load on 16- or 13-sector machines (DOS 3.3 or 3.2) without modification. When the disk is loaded, the time must be set from the keyboard if a clock/calendar is not available. This shouldn't be much of an inconvenience once the equipment is up and running. The internal clock of the dual thermometer is triggered by the Apple's crystal-controlled clock, so accuracy shouldn't be a problem.

The second thing that must be done upon starting the system is to set up the data-measuring parameters. The program gives you the ability to:

- choose one or two probes for temperature measurement
- monitor maximum and minimum temperatures of both probes
- set alarms for temperatures above and below the preset maximum and minimums
- record the difference between the two thermometers
- specify output in Fahrenheit, Celsius, or absolute (Kelvin)
- record data at predefined intervals on a printer or disk

If the same setup is used frequently, it too can be recorded on disk, eliminating the necessity of entering the same information each time.





SEATTLE COMPUTER'S NEW RAM+ GIVES YOU THE MEMORY YOU NEED AT A PRICE YOU CAN'T FORGET.

A great new machine, the IBM personal computer, just got better. With RAM+, the new expansion memory from Seattle Computer.™

RAM+ can change your personal IBM from a pony to a workhorse by adding up to 256 K of memory. RAM+ is expandable, reliable and is made by Seattle Computer, the people who created the operating system for the IBM personal computer.

To make your IBM work even better, each RAM+ card has a RS-232 serial port which uses IBM supplied software. And RAM+ comes fully assembled, tested and with a 90 day guarantee.* The RAM+ is available in 64 K, 128 K, 192 K or 256 K, with affordable prices ranging from $475. to $1,075. Expansion kits are also available.

How to order: Call Anna Ford at **(206) 575-1830** for the location of the nearest RAM+ dealer.

The RAM+ —a great addition to your IBM personal computer. At a great price.

Dealer inquiries welcome.



1114 Industry Drive, Seattle, Washington 98188

Circle 366 on inquiry card.

*Extended warranty available.




Figure 1: *Tracking Strawberry Tree's thermometer probe versus a laboratory mercury thermometer. Figure 1a shows responses to an 8.89°C/minute rate of change; figure 1b shows responses to a 4.57°C/minute rate of change.*

One missing feature, however, is a method for obtaining an average temperature for the collected data. If desired, the software can be modified to accumulate the sum of all temperature samples taken and divide that sum by the total number of samples. This should be an easy modification since the disk is not "copy protected," and the software is fully described in the user's manual.

Limitations

One of the major limitations of the Strawberry Tree Dual Thermometer card is the stabilizing time necessary for accurate measurements. The manual states that the probe requires 4 minutes to stabilize to within 0.1° for a 100° change. For comparison, a laboratory-grade mercury bulb thermometer will stabilize over the same temperature change in approximately 10 seconds. This would limit application of the device where large temperature variations can occur in relatively short time intervals.

Appendix E of the user's manual addresses this issue and offers several suggestions for obtaining greater accuracy. Figure 1 shows two experimental plots. Each plot contains two curves, one of the probe and one of a mercury bulb thermometer. In figure 1a, the average rate of change is 8.89°C per minute, while that of figure 1b is 4.57°C per minute. The rapid change in temperature with respect to time in figure 1a produces as much as a 4° error between probe and mercury thermometer. When the rate of change is slowed by a factor of 2, the two devices give about the same reading. This drawback won't be a problem where temperature variations change slowly. Indeed, given the required stabilization time, I found the probes to be well within their rated accuracy.

Applications

The possible applications of this dual thermometer board are many because of the careful attention given to writing the software. With the ability to record data on a printer or disk, many long-term temperature studies can be undertaken.

An engineer could use the dual-thermometer board in a solar heating experiment. One thermometer probe would monitor the internal temperature of the solar collector while the other would record the surrounding temperature. The data collected would help determine the best angle for the collector, the best collector coating for maximum heat gain, etc. With the card, readings for an entire day could be gathered automatically.

A homeowner might want to do a long-term energy study by monitoring the temperature difference between the inside and outside of the house. After keeping track of temperature differences and the amount of oil, gas, or electricity used per month, the most efficient temperature setting for the house could be determined by plotting a curve of temperature difference versus fuel consumption.

A scientist desiring to monitor the temperature of a microscopic culture might wish to record the information on a printer as it is gathered. A further possibility would be to have the computer sound an alarm if the culture got too hot or cold (this could be done by setting the alarms for the probe at the maximum and minimum limits).

Conclusions

The hardware and software of the Strawberry Tree Dual Thermometer board are excellent, with all operations fully supported and documented. Any modifications to the BASIC program should be straightforward and require only fundamental programming skills.

The temperature probes can be located at distances up to 500 feet, offering great flexibility in probe placement. Special probes can be ordered for immersion in liquids. Two probes can be used at the same time, each recording its present temperature, maximum, minimum, and the temperature difference between the two.

The software permits readings to be calibrated in Fahrenheit, Celsius, or Kelvin. Data can be recorded on a printer or disk at preset intervals. An alarm can be set for each probe to indicate when a preset maximum or minimum temperature has been passed. ■

Circle 182 on inquiry card.

Software Psychology: Human Factors In Computer and Information Systems

Ben Shneiderman
Winthrop Publishers Inc.
Cambridge, MA, 1980
320 pages, hardcover
$24.95

Reviewed by
Bruce Robert Evans
16 Marwin Road
Pickering Ontario
Canada L1V 2N7

Until recently, computers have been the domain of professionals. With the advent of personal computers, information networks, and dedicated controllers in equipment, programmers and designers must be aware of the impact of software on end users and vice versa. Much has been written about human engineering, but nothing has appeared about humanizing software. *Software Psychology* will help the systems engineer and programmer remedy this deficiency.

The layout of the book reflects the author's background in the psychology of learning. At the beginning of each chapter, there is a list of the section headings, followed by an explanation of what is to come. Two summaries, one of practical points for the programmer and one of possible leads for the psychology researcher, follow the body of the book. The repetition distressed me, but with time it became obvious that it was achieving the desired purpose—I was retaining the material.

Shneiderman starts by analyzing what programmers do. Using one of the key tenets of management analysis, he delineates tasks and their performance. Without generalizing, the author dissects some of the well-entrenched "truths." Do comments clarify a program? Do symbolic variable names help? Expect your prejudices to be challenged. The author insists on measuring as he attempts to assess a programmer's output. Many commonly held beliefs topple. For example, while the number of lines produced may be acceptable criterion for one program, the efficiency of style may be better in another.


Chapters seven and eight, in which Shneiderman discusses database systems, should be read by all programmers. In them, the author explores possible sources of friction between programmers and nonprofessional users. Ways of dealing with irate nonprofessional users (Why is my credit card bill different from what I think it should be?) are discussed.

In chapter nine, Shneiderman discusses programming languages, emphasizing the attempts to create new languages that will correct some of the faults of existing ones. (Does a month go by when someone doesn't come up with the "perfect language"?) The author stresses that because no one language covers all situations, programmers should consider the advantages and disadvantages of each when writing for a nonprofessional.

Chapter ten, "Interactive Interface Issues," justifies the entire book. In it, Shneiderman indicates the need for more study of the psychologic impact of computer programming on the end user. He discusses computer systems from the user's point of view and points out user demands of which the programmer may be completely unaware.

In summary, Ben Shneiderman guides the systems engineer in deciding what a customer wants and needs, suggests how the software should be written, and assists in its evaluation. At the same time, the author shows the programmer what the software user wants and how the end user looks at a computer system. Often the user is very different psychologically and intellectually from the programmer; the successful programmer must be aware of this. ■

Start talking business



with your Apple

COBOL is the most effective business language. Apple II is the most friendly business computer. CIS COBOL with FORMS-2 brings together the best features of COBOL and Apple to enable you to deliver the most effective, user-friendly applications.

Business Programmers: Take the COBOL expertise you have acquired on big business mainframes, and use it on Apple II to create friendly applications that will talk directly to your users – where it suits them best, on their own desks.

CIS COBOL's dynamic module loading gives you big application capability and the FORMS-2 source generator lets you build and modify conversational programs from visual screen formats, creating much of the code automatically.

Application vendors: CIS COBOL with FORMS-2 steps up the pace for your development of the high quality professional application packages needed today. And creating them in COBOL makes them more maintainable.

Over half the Apple II's now being sold are going to business or professional users so demand for quality applications is growing fast, creating big business opportunities for you.

Stability proven by the US Government. CIS COBOL has been tested and approved for two consecutive years by the US General Services Administration as conforming to the ANSI '74 COBOL Standard. Apple II under CP/M is included in CIS COBOL's 1981 GSA Certificate of Validation (at Low-Intermediate Federal Standard plus Indexed I-O and Level 2 Inter-Program Communication).

Get your hands on CIS COBOL at your Apple dealer.

Talk business with him now!

Micro Focus Inc., 1601 Civic Center Drive
Santa Clara, CA 95050. Phone: (408) 248-3982.



CIS COBOL with FORMS-2 for use on the Apple II with CP/M is an Apple Distributed Product. CIS COBOL and FORMS-2 are trademarks of Micro Focus. CP/M is a trademark of Digital Research. Apple II is a trademark of Apple Computer.

Circle 264 on inquiry card.

Product Description

The Epson HX-20

The First BYTE-sized Computer

Gregg Williams
Senior Editor

Unfortunately, no monthly magazine can be completely up to date on a given subject—some new product or idea always appears between the time we send the magazine to the printer and the day you see that same issue. However, we did get a chance to preview a product so exciting that we "stopped the presses" to get it into this issue.

The Epson HX-20 microcomputer (see photo 1) is a remarkable unit that might be dubbed the first "notebook computer"—larger than a pocket computer and smaller than a briefcase computer, it is about the size of a notebook. It weighs in at 1.73 kilograms (3 pounds, 13 ounces) and measures 28.9 by 21.6 by 4.44 centimeters (11.375 by 8.5 by 1.75 inches)—somewhat lighter than but almost the same size as two issues of BYTE. The HX-20 has a full version of Microsoft BASIC, 16K bytes of memory, a standard-size and standard-configuration keyboard, a 24-character-per-line printer, a built-in cassette interface, and a 20-character by 4-line liquid-crystal display. The product will be officially announced at the National Computer Conference in June. Epson plans to have its distributors fully stocked with HX-20s by the time it is officially introduced.

The unit was lent to us for a few days by Chris Rutkowski of Epson America Inc. Since this was a sneak preview of the HX-20, Chris told us some but not much about it. Most of the details below are a result of our physical inspection of the unit. For example, executing the BASIC statement "PRINT FRE(X)" produces the answer 12,832. This leads me to believe that the unit has 16K bytes of RAM (random-access read/write memory),




Photo 1: *A prototype of the HX-20 microcomputer. The final unit will have a different keyboard layout.*




Photo 2: *The HX-20 printer and a printout of its character set. The Japanese katakana characters will be replaced in the U.S. version of the unit by geometric symbols that can be combined to make larger graphic images.*



Photo 3: *The liquid-crystal display of the HX-20, which gives four rows of 20 characters each.*

12,832 of which are free for BASIC programs and data.

The unit we saw is a prototype of the final unit, which may be packaged somewhat differently and which will have a typewriter-style keyboard layout. Aside from the layout, the present keyboard is very good—it is standard-sized (a very important feature if the computer is used for programming, word processing, data entry, or similar applications) and the keys have a good feel. The printer can display 24 characters per line, each in a 5 by 7 dot matrix (see photo 2). The LCD (liquid-crystal display) provides four rows of 20 characters, each displayed within a 6 by 8 dot matrix (see photo 3). Both the printer and the LCD can show graphics, numbers, punctuation, and uppercase and lowercase letters. The LCD is ultimately 120 dots by 32 dots, each of which can be controlled by BASIC. Because Epson is a subsidiary of Seiko (the watchmakers), you might suspect the HX-20 to contain a clock; it does. The clock is accessed from BASIC by reading the variable TIME$. Setting the clock is just as easy.

The cassette interface is said to transfer information at about 2400 bits per second (about 300 bytes per second) onto a standard dictating machine microcassette. This area of the unit appears to be detachable, which may indicate other storage options and/or telecommunication potential.

The unit has several interesting sockets. The rear of the unit contains a socket for a power supply (the unit is estimated to run 50 to 100 hours on the internal nicad batteries), as well as two DIN sockets marked SERIAL (with holes for five pins) and RS-232C (with holes for seven pins). The left side contains a long, narrow, recessed plug containing two rows of 20 pins each (perhaps a system bus of some kind), and the right side contains plugs for an external cassette recorder, as well as a small phono jack marked BARCODE (which means that the unit is capable of reading bar codes). In addition, the right side of the unit contains a recessed Reset key and an on-off switch. (The unit, however, is never really "off"; this switch turns off the LCD display, but retains the program currently in memory.)

Few details on the internal organization of the machine are yet available. It contains CMOS (complementary metal-oxide semiconductor) memory to keep the power consumption low. The HX-20 also uses the 6301 microprocessor, a CMOS version of the Motorola 6801 microprocessor.

The price? Epson hadn't decided at the time this was written, but I was led to believe that it would be under $1000.

I hope you are as tantalized by this information as I am. More information will be available after the unit is introduced at the NCC in June. Until then, it is enough to know that microcomputers are becoming more portable, more powerful, *and* cheaper at the same time, a trend that will probably not stop with the HX-20.■



5-10-20 Megabytes in an add-on hard disk for:

IBM Personal Computer • Xerox 820
Apple • SuperBrain • Heath-Zenith
TRS-80 Models II & III

Targa, a truly high performance design, whether by Porsche or by CMC. Targa hard disk system, a significant extension to the storage capacity of your microcomputer, at an unheard of price/performance ratio. Suggested list for 5 mb:

only $2895.

Targa 5 6.38 Mbytes unformatted, 5 MB formatted. Upgradeable to 10 MB

Targa 10 12.8 Mbytes unformatted, 10 MB formatted. Upgradeable to 20 MB formatted

Targa 20 20 Mbytes formatted, 25.6 MB unformatted

Our Targa Winchester-type, hard disk drives are offered in desk-top dimensions of 15″ × 5¼″ × 13½″. It comes complete with cables, software and interface. Call or write for complete specifications and/or the dealer nearest you. Dealer inquiries invited.

Circle 86 on inquiry card.

CMC INTERNATIONAL

A Division of Computer Marketing Corporation

11058 Main • Suite 220 • Bellevue, WA 98004 • Phone (206) 453-9777 • Telex: 152556 SEATAC

Call Toll-Free 1-800-426-2963

A Human-Factors Style Guide for Program Design

Taking the user into account in the design of software.

Henry Simpson
Anacapa Sciences Inc.
P.O. Drawer Q
Santa Barbara, CA 93102

Human factors is a small but growing discipline which seeks to provide a method for taking into account human strengths and limitations during the design of computer hardware and software. In this article, I'll present a brief introduction to human factors and discuss its application to program design. I'll define six human-factors design principles and show how they can be applied to three areas of program design: data entry, display-screen design, and sequence control.

Human factors can be applied to any area in which a human being interacts with a machine. The discipline applies, or at least can and should be applied, to many aspects of man's interaction with computers. The most obvious area, and the one most people think of when considering human factors, is hardware design. Human-factors specialists often design video displays and controls.

More recently, human factors has been applied to software design. Research has led to the development of human-factors guidelines that programmers can use to make their programs easier to use and less prone to error. Human factors is also important to the design of computer operating systems, programming languages, and documentation, although the discipline has received less attention in those areas.

Human factors matter because people must operate machines. If you fail to take people into account during design, then your machine (or system or program) may be difficult or impossible for people to operate. As obvious as it seems, this point is often overlooked. Consider some recent examples. No brand names are mentioned in what follows, but you may recognize some of the players:

- The microcomputer whose nonstandard keyboard made it awkward for touch-typists—all keys were there, but they were the wrong kind of keys and in the wrong locations. (The keyboard has since been redesigned.)
- The minicomputer whose operating system identifies program errors with numeric codes that are contained in three separate manuals. (This machine was recently discontinued.)
- The computer program whose screen displays are cluttered and confusing, whose data-entry sequences permit input errors that cause the program to interrupt, whose menus can lead the operator down blind alleys and into stable program states from which he or she cannot escape. The documentation for this program consists of three smudged photocopies of an original that displays creative spelling and grammar and omits many important details.

The more serious the error consequences, the more designers should consider human factors.

We often blame human error for disasters and near disasters, from nuclear near-meltdowns to bank errors in checking account balances. Equally often, we blame "the computer" for some ill fate that befalls us. Seldom do we recognize that neither man nor machine alone is completely responsible. In today's complex world, man and machine work together interactively. The "system" is the combination of both.

When we design things, it is usually fairly easy for us technically oriented people to take into account the limitations of our hardware. However, we are likely to forget that the operator or maintainer of our system has limitations. We can design much better systems—more workable and more maintainable—if we accurately take human limitations into account.

What are human limitations? First and most obvious, no two human be-

MORE BANG

Qantex Impact Printers
150 Characters Per Second
136 Columns Per Line

The microprocessor controlled **Series 6000** is packed with standard features. True lower case descenders and underlining. Bidirectional logic seeking. Built-in test capability. Rugged 400 million character print head. Beautiful 96 character set in a 9 x 9 matrix. Parallel, or up to 19,200 baud serial interfaces supporting RS-232, X-ON, X-OFF or Current Loop. Full operator controls. Quietized, sleek enclosure to enhance your system. Delivery from stock.

Qantex* Division of North Atlantic Industries
60 Plant Avenue, Hauppauge, N.Y. 11788
(516) 582-6060 TWX 510-227-9660
(800) 645-5292



For more information call your local distributor:

ARKANSAS
Hemco Electronics (501) 663-0375
ARIZONA
The Phoenix Group Inc. (602) 967-1421
CALIFORNIA
Basic Systems Corp. (213) 673-4300
Basic Systems Corp. (714) 268-8000
Basic Systems Corp. (408) 727-1800
ILLINOIS
Electro-Tech Marketing Assoc. (312) 588-4535
Engineered Sales (312) 832-8425
INDIANA
Audio Specialists (219) 234-5001
LOUISIANA
Micro Computer of New Orleans (504) 885-5883
MARYLAND
Systems International Inc. (301) 977-0100
MASSACHUSETTS
S & S Electronics, Inc. (617) 458-4100

MINNESOTA
Integrated Peripherals (612) 831-0349
Vikeland Sales (612) 645-4647
MISSOURI
ESC Sales & Leasing (314) 997-1515
NEW YORK
Washington Electric Co.(212) 226-2121 / (800) 221-5416
Daily Business Products, Inc. (516) 543-6100
(800) 645-5556 / (212) 594-8065
Synchro Sound Enterprises (516) 484-1852
PENNSYLVANIA
QED Electronics (215) 674-9600
TENNESSEE
Southland Video Distributors (800) 238-3274
TEXAS
Datanet, Inc. (214) 669-1758
VIRGINIA
Nine Associates, Inc. (703) 273-1803

AUSTRALIA
Mitsui Computer Systems 02-9299921
CANADA
Computer Markets 416-445-1978
DENMARK
T.M.S. Dataudstyr (45) 2-911122
ENGLAND
Northamber Limited (44) 372-67646
FRANCE
Gepsi (33) 1-554-9742
GERMANY
Technitron 49 (89) 692-4141
HONG KONG
Computerworld Ltd. 5-44033
Hong Kong Equipment 5-453870
ITALY
Eltron s.r.l. (030) 55026-41554-44414
NETHERLANDS
Compudata Benelux B.V. 31-73-215700
SPAIN
2i Ingenieria Informatica 204-2099

Distributor inquiries welcome!

*Registered Trademark of North Atlantic Industries, Inc.

Circle 342 on inquiry card.

ings are alike. They vary in size, strength, acuity, intelligence, education, and level of motivation. The general requirement for considering human factors in the design of your system, whether hardware or software, is to *recognize the needs of the users*. The type of user varies with the application. If you are designing an arcade game with a coin slot and two push buttons, you are aiming at a different sector of the population than if you are developing a computer-based econometric model to predict the gross national product in 1985. Either of those programs can be written for specific, definable, homogeneous groups of users.

More often than not, however, the hardware or software we design will be used by a varied group that ranges widely in sophistication. Knowing your system users and recognizing their needs are the first two steps in taking human factors into consideration during system design.

In general, the rules for designing a system with the user in mind parallel those for good writing: define your system users, know their limitations, and find the simplest way to get your message across.

That which separates good programs from bad cannot always be described in terms of simple, obvious things such as bad keyboard designs or cumbersome error-handling procedures. I can name some general qualities to look for, however. First, programs that consider human factors are generally easier to learn and use than those that do not. They usually have simpler displays, are less likely to "bomb," and are supported by good user documentation; they appear to be written for less specialized users and not for computer experts. These programs also refrain from trying to make the machine behave as if it were a human being. Poorly designed programs lack some or all of these features.

To illustrate when human factors matter I'll limit my discussion to software design and, more specifically, to microcomputer software in which the operator controls the computer and interacts continuously with it. This scope includes such applications as games, business and scientific programs, computer graphics, and computer music but excludes most control, robotics, and other minimally interactive applications.

A human-factors purist might say that serious consideration of human factors *always* matters, but this simply isn't true. You can decide in each case how important human factors are by looking at four different aspects of your program: (1) number of people who will operate the program, (2) diversity of the operators' backgrounds, (3) complexity of the program, and (4) consequences of operator error.

Obviously, the more people who will operate your program, the more time and energy you will invest in its development. If you are running a business, you want to assure that your A/R (accounts receivable) program works efficiently and effectively because it will cost you money and



At Hayes, we don't believe in second best. Or planned obsolescence. We believe in taking the state of the art to the limit. Our new Smartmodem, for example, is the most sophisticated 300-baud originate/answer modem you can buy. And yet, it is perhaps the easiest-to-use modem ever.

RS-232C Compatible. Smartmodem lets any RS-232C compatible computer or terminal communicate by phone with other computers and time-sharing systems located *anywhere in North America*. You get full and half-duplex operation with both Touch-Tone* *and* pulse dialing.

Auto-Answer/Dial/Repeat. Smartmodem can answer the phone, dial a number, receive and transmit data, and then hang up the phone—automatically! If desired, Smartmodem will even repeat the last command. You can depend on Smartmodem for completely unattended operation.

Completely Programmable. Smartmodem can be controlled using *any* programming language. Over 30 different commands can be written into your programs or entered directly from your keyboard.

Smartmodem also includes several switch-selectable features that let you tailor performance to your exact needs. You can "set it and forget it" for the ultimate in convenience.

Built-in Audio Monitor. Thanks to an internal speaker, you can actually listen to your connection being made. You'll know immediately if the line is busy or if you reached a wrong number—*and you don't even need a phone!*

Status at a Glance. Seven LED's indicate Smartmodem's current operating mode: auto-answer, carrier detect, off hook, receive data, send data, terminal ready and modem ready. You're never left in the dark!

Direct-Connect Design. Smartmodem is FCC registered for direct connection to any modular phone jack—there's no acoustic coupler to cause signal loss and distortion.

Smartmodem, Smart Buy. Professional quality features. Versatile performance. A full two-year limited warranty. A suggested retail price of only $279.

What more could you want? Perhaps the matching Hayes Stack Chronograph, an RS-232C compatible calendar/clock system.

Check out the Smartmodem wherever fine computer products are sold. And don't settle for anything less than Hayes.

Hayes

Smartmodem. The ultimate concept in modems is now a reality.

Smartmodem
Hayes
AA CD OH RD SD TR MR
FRI SAT

Hayes Microcomputer Products Inc. 5835 Peachtree Corners East, Norcross, Georgia 30092 (404) 449-8791

Circle 194 on inquiry card.

perhaps your credit rating if it doesn't.

If that same program must serve a wide group—ranging, say, from clerk to company president—then you must assure that the program serves all levels well. This takes special effort during program design.

The more complex the program, the greater the chance of error, and the more you must strive to reduce the likelihood of error by carefully considering human factors.

Last, and probably most important, are error consequences. The more serious these are, the more important the human element becomes. If the reactor core will melt down, the navigator will get lost, or the names and addresses of all the people who owe you money will disappear, then the consequences of error are very serious indeed. If the worst that can happen is that the bouncing ball in your game program may disappear from the screen, then the consequences are not quite so serious (unless you depend upon the program for your livelihood).

In sum, if you are writing programs purely for your own use and are not tracking important data, then you have probably spent too much time on this article already. On the other hand, if you are writing programs for a wide and varied group of users to track things that matter to them, then human-factors considerations *are* important.

Design Principles

If you decide to apply human factors to your program design, where do you begin? Probably the best way is to familiarize yourself with some general human-factors design principles. Six such principles are presented below. These principles grow out of behavioral research conducted over the last several decades, although their application to program design is recent. Later in this article I'll give specific examples of how these principles may be applied.


Provide Feedback: People need to know that an action they have taken has had an effect. When you turn the wheel of your automobile, you receive feedback in the form of resistance from the wheel, centrifugal force on your body, and movement of your visual field. In turn, you adjust the rate at which you turn the wheel to conform to the feedback you are receiving. Without this feedback, you would find it much more difficult to control your automobile.

The user of your program also needs feedback. If he makes a keyboard entry and nothing appears on the screen, then he has no way of knowing that his action has had an effect. In consequence, he may repeat his action or try another, possibly causing something unintended to happen.

Feedback should be immediate and obvious. Show it on the screen in a place where it is expected.

Be Consistent: Mention "consistency" in a group and someone will probably quote Emerson to the effect that it is the "hobgoblin of little minds." Emerson may have been able to get along without it in certain trivial matters, but computer programmers cannot. The tools and programming languages with which they work are based on rigid adherence to rules of syntax, the order of programming operations, and the laws of mathematics. Rigid adherence to these "laws of the machine," which are internally consistent, reduces uncertainties and makes it possible to program the machine exactly. Human beings can tolerate more ambiguity than machines, but ambiguity reduces people's effectiveness. If we paid half as much attention to consistency in our programs' interactions with human beings as we do in the interactions between programs and machines, most of our programs would be improved.

What, exactly, do we mean by "consistency"? One way of defining it is as a set of rules that you, the programmer, establish for yourself and follow compulsively. These rules per-


64K at 8MHz
Static RAM
. . .PLUS HIGH STANDARDS
The bus standards are theirs (the IEEE's 696/S-100). The quality standards are ours. The combination of price, performance, and versatility sets NEW standards unmatched by any other EPROM-compatible memory on the market. Compare these features:
Fully static 150ns 2K x 8 RAM's for performance to 8MHz
Extended 24-bit addressing (page address switch-selectable)
Bank select (port address switch-selectable) for compatibility with Cromemco (including CROMIX*), MP/M**, North Star, others
Two separate banks configurable as 64/0, 48/16, or 32/32K
Base address of 16K segments within a bank may be set to any 16K boundary
Automatic bank select/deselect on Reset (for each bank)
Up to eight 2K segments may be disabled to create windows for memory-mapped I/O — makes optimum use of available RAM
Phantom capability
Solderless field configuration
Any number of RAM's may be replaced with 2716 EPROM's
Low power consumption (3.0 watts)
All these features PLUS the reliability you expect from first quality components, the confidence of a 12-MONTH WARRANTY, AND an absolutely fascinating price. All boards are sold assembled, burned in (48 hrs.), and rigorously tested. Available partially populated to 48K or 32K.
*CROMIX is a trademark of Cromemco.
**MP/M is a trademark of Digital Research.
NO RISK TRIAL
All Indigo Tech products are sold on a no-risk basis. If not completely satisfied return board within 15 days and the full purchase price will be promptly refunded.
M12/64 64K $725.00
M12/48 48K $645.00
M12/32 32K $595.00
Shipping and handling $5.00 per board.
Visa or Mastercard accepted. California residents add 6% sales tax.
indigo tech
670 NUTTMAN AVENUE, SUITE 110
SANTA CLARA, CA 95050 • (408) 727-4710
Circle 204 on inquiry card.

mit the operator to learn one part of your program's operation and then to apply the new knowledge to other parts of the program. For example, you might make a rule that all of your error messages will appear on the bottom line of the display screen. When the operator sees one error message displayed on the bottom line, he expects all others to be displayed there, too. If they are, then the rule is adhered to, and the operator will not have to learn a new rule for each new display. If not, then the operator's learning task is that much more difficult.

Minimize Human Memory Demands: Psychologists have determined that human beings possess two types of memory—short-term and long-term. A vast amount of research has been conducted on the subject, most of which will interest only the specialist. About human memory, the computer programmer needs to recognize two things. The first of these is obvious, the second less so.

First, computers have better memories than people. (We said it was obvious.) Data stored on magnetic media are never forgotten.

Second, computers always remember things exactly as they were stored. People usually do, but sometimes they get things mixed up.

What follows from these two points is that, when designing programs, you should rely on computer memory as much as possible. Suppose, for example, that your program has many subprograms. How should the operator select a subprogram—from a displayed menu or by entering a memorized mnemonic? Although selection with memorized mnemonics (used in "program-like languages") has advantages in some situations, the displayed menu depends much less on operator memory and is generally preferable. (Some players of Star Trek games may recall the frustration with which they attempted to master the game in the absence of displayed menu options.)

Keep the Program Simple: Simplicity in programming, as in writing, does not come easily or painlessly. You must work to achieve even the appearance of simplicity. Simplicity usually results from paring down or editing. In programming, as in writing, simplicity is an ideal that one strives to achieve by conscious design, by trial and modification, by cutting away the unnecessary, and by reorganizing and rearranging.


Match the Program to the Operator's Skill Level: You must determine the operator's skill level before you write your program. Determine also if operators of differing skill levels will use the same program. Human-factors specialists do these two things systematically by conducting a task analysis. There are several ways to do this, but usually it involves defining what *mission* a system must perform, what *functions* are involved in this mission, and what *tasks* are required to accomplish the functions. Conducting task analyses is time-consuming, technical, expensive, and probably beyond your needs or interests. Still, you do need to think about operator tasks as you write your program and ask questions like the following:

- What will operators be expected to do?
- What decisions must they make?
- What must they know to make the decisions?
- What skill levels will be required?

Consider these questions before you write your program. Then design your program so that it matches the skill level of your system users.

Sustain Operator Orientation: If you have ever been lost then you know what *not* being oriented is. Anyone who has ever used a computer has had the experience of getting into some new program and not being able to find the way out. This often happens when you try the program without first reading the manual (as all of us are prone to do).

You have an obligation as a pro-






Figure 1: *A data-collection form and the data-entry screen that goes with it. The data-entry screen resembles the form. Prompts shown in parentheses on the screen make clear the expected data formats and give range limits. The brackets serve as field delimiters, showing the maximum length allowed for each entry.*

grammer to minimize the possibility of disorientation. Provide your operator with signposts that tell him where he is and how to get back to where he came from. Menu-driven programs often do this by providing a main menu which serves as a home base. The program begins with this menu from which the operator can select various subprograms, perform them, and then return.

Some game programs are intentional mazes, consciously designed to disorient the operator. If that's your intention, all well and good. But if it's not, remember that an unwanted maze is about as much fun as an inaccurate road map on a dark and rainy night.

The six principles described above reduce to one idea: know the needs of your system users. Recognize that they need feedback to avoid confusion, consistency to ease the learning process, minimal strain on memory capacity, simplicity rather than complexity, demands gauged to their skill levels, and constant, clear orientation.

The remainder of this article will focus on three areas of computer programming: data entry, display-screen design, and sequence control. Data entry concerns how you get data into a database; display-screen design concerns layout of video-terminal-display screens; and sequence control concerns how you interact with your program to get it to do something.

I'll show how the six human-factors principles apply in each of these areas. In most cases, recommendations made are based on research that has shown that the suggested feature permits more effective man-machine interaction. In a few cases, recommendations are based on prevailing practice. None of these guidelines should be applied blindly, and all of us will find it necessary to ignore them from time to time. But most of these are simple things to do, and if you follow them, you will write a better program.

Data Entry

The following guidelines apply mainly to programs in which data are entered through the keyboard to build a database which the program accesses later. Typically, the data entry process consists of the following sequence of steps:

- presentation of a prompt
- data entry by the operator
- display of entered data on the screen
- error test
- presentation of an error message if entered data fail error test
- editing of data
- acceptance of data into database

Prompting: If data are to be entered into the computer from a standardized data-entry form, then the data-entry screen should resemble that form as closely as possible. The cursor should move from field to field as the operator fills in the form. It is easier to write a program consisting of a series of INPUT statements that cause the screen to scroll. However, the operator can more readily orient himself to a screen that looks like a data-entry form. Figure 1 shows a data-collection form and a data-entry screen designed to elicit the necessary data. The screen presents prompts, states acceptable ranges, and delimits fields.

The program should provide a prompt for every data input. The prompt should be brief and specific, and show the range limits and entry

Quality Computer Services presents..

Hard Disk Systems





For TRS®, Apple®, Heath®, S-100, IBM......
6,12,20,40 and 80 Megabyte systems

Completely assembled and tested subsystem including:

- Switching power supply
- Winchester drive
- Host adapter card
- Sealed case
- Expansion
  The encloser, controller and power supply have been designed to allow for future backup hardware or increased storage
- Software
- Auto attach CP/M*
- Hard disk utilities
- Real time clock

- Formatting program
  Assigns alternate sectors for any weak sectors detected during formatting assuring the lowest possible error rate

- Warranty: The system has a full one year warranty on all parts and workmanship
- Also available: attach for TRSDOS, OASIS*, Apple DOS
- Optional 5¼" floppy (shown)

See local dealer
or call:
Quality Computer
Services
178 Main Street
Metuchen, New Jersey
201-548-2135

QuCeS inc

- Quantity discounts available. Distributor, Dealer and OEM inquries invited.

*OASIS is a trademark of Phase One Systems, CP/M is trademark of Digital Research

Toll free number: 800 631 5944

```
[ 2/31/1979 ]   Date (Month/Day/Year)

DATA ENTRY ERROR: Date contains invalid DAY -- re-enter date
```

Figure 2: *A sample error message. The message is specific and helps the operator correct the error identified.*

format of data to be entered. Range limits or entry format can be shown parenthetically after the prompt. For example, a date entered in the form of month-day-year could be prompted as follows: "Enter Date (Month/Day/Year)." If there is a length limit, then this length should be shown on the screen using an underline, pair of brackets, or other visual cue. If certain data entries have *default* values (i.e., values that the computer will assign unless the operator enters others), then display the default values—do not rely on operator memory. If there are similar or identical data-entry requirements in different parts of the program, prompt consistently. One way to do this is to put data-entry statements into subroutines that can be called from various parts of the program.

Entering Data: You do not always control the length of the data to be entered, but when you do, keep length to a minimum. This saves keystrokes and time and reduces errors. Provide feedback by displaying entered data on the screen. If data being entered consist of logically related groups, then permit the user to enter several fields together, rather than requiring him to enter each item separately.

Error Check: Check all entered data for errors. The types of checks you must make depend upon the data and what will be done with them. Anticipate possible errors, check for them, and protect against them. For example, if the entry is supposed to be a number, anticipate what will happen when (not if) the operator enters a letter. Many programmers protect against this by taking all inputs as character strings and then converting them to equivalent numeric values.

Analyze the situation and be ready for errors. Are there range or length limits to what is acceptable? Is it possible for the operator to enter something that will cause an illegal program action to take place—for example, dividing by zero or attempting to take a substring of illegal length?

When an entry error is detected, alert the operator, identify the error, and tell him how to recover. In other words: *alert, identify, direct.* Alerting signals must differ from the customary background. An audio tone—a beep—is alerting but meaningless if the program is already emitting a continuous stream of beeps. Similarly, a flashing message can effectively alert, provided that the screen is not filled with other flashing messages. Many programmers reserve the use of both sound and flashing messages for those conditions that truly require an alert.

The error message itself should be placed consistently from screen to screen. Ideally, it should appear near the erroneous entry. The content of the message must tell what is wrong—for example, that the entered value is too long. If error identification will permit the operator to figure out what to do next, then that is *all* the message needs to contain. However, if many possible actions may be taken, then the message must also tell the operator which to take. If prompts to the user are adequate, then it should be possible in most cases for the operator to figure out what corrective action to take based solely on definition of the error. Figure 2 shows a helpful error message.

Editing: Editing is an important part of the data-entry process, and no data-entry program is complete without editing capability. Being human, operators will make data-entry errors that they may not recognize until later. You should therefore permit them to edit entries before the program accepts data into a database. Many programs permit data to be edited at three stages: during initial data entry (while being typed in), after a block of related entries has been made, and after the data have become part of the database.

The first editing capability is routine and in fact most people probably do not think of this as editing. If you make a typing error, you can usually back up the cursor before data are stored. The last capability, editing the actual database, varies in importance, but in many programs with large databases it is considered as necessary as utility programs for copying files, purging files, or the main menu itself.

Less routine, often ignored, yet very important is the block editing capability mentioned above. Often the program user will not recognize an error until after he has made several data entries. If he cannot go back and correct the error at that point, it may be uncorrectable, or he may have to use a separate database editing program to make the correction. The way block editing typically works is that after the operator has made a set of related entries, the screen presents a prompt asking if he wants to edit any earlier entries. If he

"My computer helped me write The Final Encyclopedia. I wouldn't trust anything less than Scotch® Brand Diskettes to make a long story short."

Cover art by Michael Whealen, courtesy of Ace Publishing Co.

Gordon R. Dickson,
Science Fiction Author,
Minneapolis, Minnesota

Gordon Dickson: a small businessman whose product is his own imagination. He's written more than 40 novels and 150 short stories; his newest work is *The Final Encyclopedia.* He uses his personal computer and word processing software to maximize his production. All his words—his product—are stored on diskettes. He calls up sentences and paragraphs on demand, and gets more rewrite out of the time available. So he depends on Scotch diskettes to save himself production time.

Dependable Scotch media can work just as hard for you. Each Scotch diskette is tested before it leaves our factory, and certified error-free. So you can expect it to perform exactly right.

Scotch 8" and 5¼" diskettes are compatible with computer/diskette systems like TRS-80, Apple, PET, Wang and many others. Get them from your local 3M distributor. For the one nearest you, call toll-free: 800/328-1300. (In Minnesota, call collect: 612/736-9625.) Ask for the Data Recording Products Division. In Canada, contact 3M Canada, Inc., Ontario.

If it's worth remembering, it's worth Scotch Data Recording Products.



3M Hears You...



Circle 414 on inquiry card.



ORANGE MICRO JUST TURNED A PAGE IN PRINTER HISTORY.

OUR PRICES, SELECTION & SAME-DAY SHIPPING MAKE US COMPETITIVE...

NEC 8023
Outstanding Graphics, Print Quality & Performance



144 x 160 dots/inch • Proportional Spacing • Lower case descenders • Nx9 dot matrix • 8 character sizes • 5 unique alphabets • Greek character set • Graphic symbols • 100 CPS print speed • Bi-directional logic seeking • Adjustable tractors • Single-sheet friction feed • Vertical & horizontal tabbing

NEC 8023
Dot Matrix . . . . List $795 **$Call**

IDS Paper Tiger 560/Prism 80/132
Affordable Color, Speed



Dot Resolution Graphics • 9-wire staggered printhead • Lowercase decenders • Over 150 CPS • Bi-directional, logic-seeking • 8 character sizes • 80-132 columns • Hi-res dot graphics • Proportional spacing • Text justifications

Prism 80 . . . . List $899 $700
IDS Paper Tiger 560G . . . List $1395 $1100
Prism 132 (Color) . . . . List $1995 $1895

NEC Spinwriter 7700 & 3500
Daisy Wheel Quality Leader



High speed, letter quality • 55/33 CPS • Typewriter quality • Bi-directional plotting & proportional spacing • Quiet • OCR quality print • Hi-res plotting/graphing • Quick change ribbon • Optional cut-sheet feeder, horizontal or bidirectional tractors • Prints up to 8 copies.


NEC Spinwriter RO
Serial Parallel 77xx . . . . . . List $3055 $2575
35xx . . . . . . List $2290 $1975

The Epson Series. High-Quality Printers at a Low Price.




Epson MX70
Super low priced dot resolution graphics • 5 x 7 dot matrix • User replacable printhead • Top of form • 80 CPS optional friction feed • 10" paper width

Epson MX70 . . . . List $450 **$390**




Epson MX80/MX80FT
9 x 9 dot matrix • Lower case decenders • 80 CPS • Bi-directional • Logic seeking • 40, 66, 132, columns per line • 64 special graphic characters: TRS-80 Compatible • Forms handling • Multipage printing • Adjustable tractors



Epson MX80 . . . . List $645 **$Call**

Epson MX80FT . . . . List $745 **$Call**



Epson MX100
Same basic features as the MX80 • Plus friction feed for single sheets • Plus 15" wide carriage • Dot Resolution Graphics

MX100 . . . . List $995 **$Call**

Full Line of Epson Accessories

Anadex 9501
High Speed, Commerical Duty Plus Graphics



Dot graphics • Wide carriage • 11 x 9 dot matrix • Lower case descender • Dot resolution graphics • Bi-direcitonal, logic seeking • Up to 200 CPS • RS 232 Serial & Parallel • Forms control • X-On/X-Off • Up to 6 part copy

Anadex 9501 . . . . List $1650 **$1350**

INTERFACE EQUIPMENT
Complete stock of options, cables and accessories.

GRAPPLER APPLE INTERFACE $175
CCS APPLE SERIAL Interface & Cable $150
ORANGE INTERFACE for Apple II
Parallel Interface Board and Cable $110
NOVATION D-CAT direct connect modem $180
COMPLETE STOCK OF EPSON ACCESSORIES . . . . $Call
CUSTOM PRINTER CABLES FOR Apple, Atari, IBM,
TRS-80 (all models) . . . . $Call
HAYES MICROMODEM $300
PRINTER STANDS: Large $99
Small $25
PRINTER RIBBONS—Most Types . . . . $Call



OUR PEOPLE MAKE US EXPERTS.

Malibu 200
Dot Matrix & Letter Quality in One Printer



200 CPS standard • Letter quality font • 12 optional fonts • Bi-directional logic seeking • 19 x 18 dot matrix • Expanded characters (2x, 4x) Optional • Dot resolution graphics of 144 x 120 • Underlining

Malibu 200 . . . . List $2995 **$2600**

Okidata 82A
Hi-Res & TRS-80 Block Graphics



120 CPS • Bi-directional printing • Logic seeking • Double width & condensed printing • Friction & tractor feed standard • Font selection, character pitch & line spacing are program controllable

Okidata 82A . . . . List $799 **$Call**

Centronics 739
Crisp Dot-Matrix Characters



Graphics & word processing print quality • N x 9 dot matrix • suitable for word processing • Underlining • Proportional spacing • Right margin justificaiton • Serif typeface • 80/100 CPS • 9½" pin feed/friction • Optional 2 Color Kit

Centronics 739-1 . . . . . . List $695 **$Call**

Centronics 739-3 . . . . . . List $795 **$725**

Our People, Our Product: Both Are Specialized.




Because our salespeople are printer specialists, they know the capabilities of each printer—and how to match one to your exact need. Red Baron's volume stocking assures a low, low price on a wide array of major brands. We're sure you'll like the product and services you get from Red Baron, and we know you'll love our Customer Benefit Package; an exclusive at Red Baron.

Customer Benefit Package

1. Free Expert Consultation. Before you buy, after you buy. **2. Toll-Free Ordering.** There's never a toll charge when you place your order at Red Baron. **3. Free Catalog.** Get your informative catalog with printer comparison chart and character samples today! **4. Warranty.** The manufacturer's warranty applies where applicable. **5. Same-Day Shipping.** Your order is sent the same day when you call before 11:00 a.m. **6. Free/MasterCard & Visa.** Call us toll-free and charge your printer to your credit card. **7. We Stock What We Sell.** No bait and switch, no hassle. We make every effort to keep a large stock of our advertised products.

Televideo CRT's
Price, Performance & Reliability



910C	List $699	$600
920C	List $995	$770
925C	List $995	$750
950	List $1195	$970

Here's how to order.

Phone orders are welcome; same-day shipment on orders placed before 11:00 a.m. Free use of Master-Card and Visa. CODs accepted. Personal checks require 2 weeks clearance. Manufacturer's warranty included on all equipment. Prices subject to revision.

Orange Micro Retail Stores
Sherman Oaks: 13604 Ventura Blvd. (213) 501-3486
Anaheim: 3150 La Palma, # I (714) 630-3622
Santa Clara: 3216 Scott Blvd. (408) 980-1213

Circle 309 on inquiry card.







CALL FOR FREE CATALOG



1100 N. TUSTIN
ANAHEIM, CA 92806

TOLL FREE
1-800-854-8275

CA, AK, HI
(714) 630-3322

```
* * WARNING * *

You have selected the 'PURGE FILES' program.
If you use it, your data files will be purged.

Do you want to continue with the PURGE program?
( Y/N )_
```

Figure 3: *A message that protects the operator against a serious error. The operator must confirm the decision to purge the data files before the program will proceed.*

indicates that he does, the program asks him to define the entry he wants to correct, usually by line number. Then the cursor moves to the appropriate data-input field to permit reentry of data, and the edit prompt reappears to permit corrections. When the operator indicates that he has no more changes to make, the program moves on to the next step.

Certain data entries have far-reaching effects. A "profound, irreversible data entry" is one that will significantly affect the database or a phase of program operation. How profound the data entry is depends, of course, on the situation. Consequences of data-entry errors in these cases vary from inconvenience (you are delayed because you must print a report) to disaster (you just purged six months' worth of data).

Clearly, it is important to protect the operator from such traps by providing "fail-safe" devices. The general idea is to make the operator action more complex than for usual data entry. One way is to make data entry require two stages. For example, when the operator selects the "FIRE ICBM" program from the menu, firing does not occur immediately but causes a message to appear on the screen that tells what will happen next. This is accompanied by a prompt that permits the operator either to continue or to back out.

Protect your operator against himself. The programmer who writes a program that will purge all files at the stroke of a single key deserves no mercy and will receive none from program users. Figure 3 shows a message that provides sufficient warning to the operator before beginning to purge data.

Display Screen Design

Screen layout design is partly art and partly science but all programmers can profit by observing the guidelines in this section.

Designing a good screen requires planning. Many experienced programmers find that a screen design aid, consisting of a paper matrix that identifies all possible character locations on the screen, is useful. This permits design of the screen with paper and pencil. The design can be perfected before it is committed to code. (It is much faster to make pencil erasures than to change a series of tab settings.)

As a general rule, access screens by paging, not by scrolling. Keep in mind that people find it easier to read stationary pages than moving pages. The only people who like to read scrolling information are those at the end of hot news wires. Unless your program has that sort of application, clear the screen before you put up a new display.

Most displays need a title to tell the operator what he is looking at. The title should be centered at the top of the screen.

Display screen designers center displayed information primarily for aesthetic considerations, although centering assumes more practical importance with large screen displays. With large screens, if information is not centered, the operator will spend his time turned to the left side of the screen instead of along a more natural line of sight—straight ahead.

Your screens will probably contain a variety of different types of information: title block, numerical information, prompt line, error-message line, operating-mode indicator, etc. Analyze your needs and determine how many different categories apply. Then allocate a screen area for each information category.

Assure that information on screens does not stray from its assigned area. This is an application of the consistency principle discussed earlier. The more complex your screen displays, the more important it is to allocate areas. If you have complex screens and do not design them consistently, you will confuse the operator.

If possible, separate each area of the screen from the next by at least three rows or columns of blank spaces. Different blocks can also be separated by lines, which will make the separation more distinct. More effective still is to color-code different screen areas.

"Keep it simple" has become a cliché but is valuable and important advice. Unfortunately, keeping it simple is, to use another cliché, easier said than done. What, after all, is "simple"? And when is something "not simple enough?"

Finding the answers to these questions requires you to take a close look at the information needs of your program users at each point in your program. Present no more information than necessary.

Some programmers use the "one logically connected thought or step per screen" rule. Where much information must be conveyed, these programmers break it up into logical thoughts or steps and present each one on a separate screen. This is like the rule of presenting one idea in each paragraph of prose.

Programmers in the "densely packed display" school of thought hold the view that if they can get




Figure 4: *The same list presented in random order and in alphabetical order. Recognizable orderings—e.g., alphabetical, numerical, and chronological—make data easier for the operator to comprehend.*


everything onto one screen they are saving something. What, exactly, they are saving is unclear, although they must gain a certain satisfaction by rising to the challenge of making everything fit. This satisfaction resembles the exultation of the first guy who engraved the Declaration of Independence on the head of a pin. Judge for yourself how useful that was.

In designing screen displays, it is important to follow prevailing conventions. Because of experience with written language, people have certain built-in expectations for the way information will be presented to them. If you don't follow convention in displaying information, you make things more difficult for the operator.

Think of your display screen as the page of a book. In a book, information is normally presented in lines that are read from left to right and from top to bottom. Numeric information is usually presented in tabular format, i.e., beneath column headings and from top to bottom. Certain obvious things you should avoid are printing numeric information from left to right or presenting very wide columns of text. If in doubt, recall how you have seen such information portrayed in books.

You should display information in a recognizable order. Some screens present directories or lists through which the operator must search. A menu is one such list, although it is usually short, with the most frequently called options listed at the top and the least frequently at the bottom (more on this later). Long directories or lists should be presented in an order that the operator will recognize, for example, alphabetic, numeric, or chronological order. This simplifies the search and saves time. Figure 4 shows the same information presented in random order and again in alphabetical order. Judge for yourself which ordering makes it easier to find the name "Grogono."

Long strings should be broken up. A "long" string is one that has more than about five independent characters. By "independent" we mean characters that do not unite to form a recognizable whole such as a person's name. A telephone number without the separating hyphen would be such a string. People have difficulty recognizing and separating the individual characters of long strings. If you have



I learned that I could get *specific advantages* when purchasing from A.E.I.

A.E.I. has valuable knowledge gained from selling millions of dollars of computer equipment, and will take the time to discuss which equipment is right for me.

Based on its vast experience, A.E.I. sells only reliable equipment.

A.E.I. can test and configure equipment to match my system.

A.E.I. will initalize my software to match my system, saving me valuable time.

A.E.I. stocks repair parts and can answer my technical questions, and expedite repairs to my equipment when necessary.


A.E.I. is price competitive even when compared to No-Service sales companies.

I learned that 40% of all A.E.I. sales are to public and semi-public institutions,* such as the Universities of Nebraska, Virginia, Kentucky, California, M.I.T., the U.S. Air Force, Princeton; as well as scores of major corporations.

Calling A.E.I. is the *smart* thing to do.

*A.E.I. does not wish to imply that any of these fine organizations endorse A.E.I., merely that A.E.I. is proud to have them as customers.

A PARTIAL LIST OF PRODUCTS AVAILABLE AT A.E.I.



TELEVIDEO COMPUTER


	List	Sell
TS-800 User Station	1795	1450
TS-801 Computer	3295	2650
TS-802 Comput/Terminal	3495	CALL
TS-802H Comput/Termin.	6995	CALL
TS-806 Multi User Proc.	7195	5749

TELEVIDEO TERMINALS

	List	Sell
910 Terminal	699	575
912 Terminal	925	659
920 Terminal	995	725
925 Terminal	995	729
950 Terminal	1195	925

NEC PRINTERS

	List	Sell
3510-1 30CPS Serial	2450	1895
7710-1 55CPS Serial	CALL	CALL
7720-1 KSR Serial	CALL	CALL
Forms Tractors	CALL	CALL



NORTHSTAR HORIZON PRODUCTS

	List	Sell
HRZ-2Q-64K	3599	CALL
HRZ-1Q-64K-HD5	6695	4999
HRZ-1Q-64K-HD18	9270	6749


NorthStar is discontinuing many of their horizon products. Call for availability and price of any product not listed.

NORTHSTAR SOFTWARE

	List	Sell
Northword D/Q	399	295
Mailmanager D/Q	299	235
Infomanager D/Q	499	365
General Ledger D/Q	599	475
A/R D/Q	599	475
A/P D/Q	599	475

TEXAS INSTRUMENTS PRINTERS

	List	Sell
TI-810 BASIC	1645	1398
TI-810 Full ASCII	1745	1479
TI-810 Package	1945	1649
TI-820 R/O BASIC	1995	1625
TI-820 KSR Package	2395	1950



NORTHSTAR ADVANTAGE COMPUTER

	List	Sell
ADV-2Q-64K	3995	CALL
SIO Board	175	CALL
PIO Board	200	CALL
FPB Board	399	CALL
Graphics Option	299	CALL


MODEMS

	List	Sell
Cat Modem	189	140
D-Cat	199	150
Auto-Cat	249	190
Apple-Cat	389	310
DC Hayes Micro-100	379	330
DC Hayes Smart Modem	279	240

EPSON PRINTERS

	List	Sell
MX-80	645	CALL
MX-80 FT	745	CALL
MX-100	995	CALL

Call for pricing on interfaces and cables
We will beat any advertised price.



MORROW DECISION COMPUTER

	List	Sell
Decision 1 BASIC	1725	1350
65 K Static Ram	1000	780
Switchboard I/O	259	210

Select drives from Morrow disc systems for desired configuration.


MORROW DISC SYSTEMS

	List	Sell
Discus 2D 1 Drive	1095	849
Discus 2D 2 Drive	1875	1389
Discus 2 + 2 1 Drive	1395	1075
Discus 2 + 2 2 Drive	2495	1859
M26 Hard Disc	4495	3395

CP/M & Microsoft Basic Included

LINE PRINTERS

	List	Sell
Okidata 82A	719	550
Okidata 83A	1195	799
Anadex 9500	1650	1285
Anadex 9501	1650	1285



SYSTEMS GROUP

	List	Sell
2800 Computer	5035	3595
DM-6400 Memory	760	585
DMB-6400 Memory	995	735
CPC-2813 CPU + I/O	460	365
FDC-2801 Controller	465	370

MICROPRO SOFTWARE

	List	Sell
Wordstar	495	330
Apple Wordstar	375	275
Spellstar	250	190
Mailmerge	150	100
Datastar	350	250
Supersort	250	190

DISC-CABLES

	List	Sell
Memorex 5" 1D	47	27
Verbatim 5" 2D	40	30
Verbatim 5" 2D	55	45
Dysan 5" 2D	70	60
RS-235 5' Cable	30	20
RS-232 10' Cable	40	25

—SEE THESE PRODUCTS AND MORE IN OUR SHOWROOM—
PRICES CHANGE DAILY—CALL OR VISIT FOR CURRENT PRICING



AUTOMATED EQUIPMENT, INC.
18430 WARD STREET, FOUNTAIN VALLEY, CALIFORNIA 92708

Calif. and International:
(714) 963-1414
Toll Free:
(800) 854-7635

Circle 44 on inquiry card.

```
                    ACCOUNT REPORT
DESCRIPTION

            Account #: 3281
                name : Budget
-----------------------------------------------
STATUS

This account is not currently up to date.
Last payment was made 12 months ago.
-----------------------------------------------
ACCOUNT INFORMATION

              Balance : $ 31,000.00
              Payment :      292.89
          Amt Last Pmt :       3.69
```

Figure 5: *Standard methods of presenting text and numbers on the screen. Text is easier to read if left-justified. Numbers are easier to read if right-justified and aligned on the decimal point (if any).*

ever tried to count over to, say, the 15th character of a 40-character string, you know the problem.

Elements of the string can be more readily located if you display the string as several short strings, (i.e., consisting of five or fewer characters) separated by spaces. (Better yet, find an explicit, uncoded method to present your information.)

According to standard practice, text is normally justified to the left side of the screen or to a defined tab value. Numerical information is normally justified to the right. Where the number of decimal places may vary on successive lines, decimal points on all lines should align at a particular tab value. These conventions are carry-overs from mainframe practice, where the availability of sophisticated formatting statements makes alignment easy. Justifying numbers to the right and aligning decimal points are more difficult with most microcomputer BASICs, although subroutines for performing these functions have appeared in publications, and most moderately skilled programmers can write their own. Figure 5 illustrates conventional alignment of information on the display screen.

Sequence Control


Sequence control is the manner in which the operator controls the sequence of program operations. In menu-driven programs, the operator exercises sequence control through menu choices. These let the operator select the subprograms he needs to do his job.

An operator can exercise sequence control in many other ways. Control simply requires an interaction or "dialogue" with the program. The menu-driven program permits a particular type of dialogue. Other common dialogue types are question and answer, query, program-like language, and action code.

In *question-and-answer* dialogue the program displays a question and the operator responds with an answer. The expected answer is one of a limited set of alternatives, such as "yes" or "no." Example: Program asks whether output should be displayed on video terminal or printer.

Query dialogue is an extension of question and answer: a question is posed but the number of alternatives is large. Example: Program requests the number of the file it should display.

Program-like language dialogue uses a defined set of commands to control the program. Valid commands are usually brief mnemonic abbreviations of action words. Example: Command words used to control the Star Wars game.



As inevitable as evolution.
Mainframe solutions at micro prices.
A new era has begun. With computer prices down and computer power up, micro's are already more powerful than five-year old mainframes.
Professional demand was inevitable. Software unavailable.
The solution: ISE.
The new kind of computer company...offering mainframe-quality software at micro-software prices.
For more information on this significant breakthrough, phone (317) 463-2581.
ise TM
Professionals know the difference.
P.O. Box 248 Lafayette, IN 47902
Circle 261 on inquiry card.

How to stay hot with the leading programming languages.



When you're hot, you're hot. And SuperSoft's language series keeps you that way. Out front with the most advanced capabilities for microcomputer programming.

SuperSoft's Language Series

Ada* Required by the Department of Defense for all its programming, Ada is the language of the 80's. SuperSoft Ada is a native code, fully recursive two pass compiler which generates ".COM" files. It currently supports most features of the standard Ada language. (requires 48k CP/M) Ada: $250.00. Manual only: $25.00.

C Version 1.1 of SuperSoft's widely used C compiler has now been released. With this release SuperSoft's C, a two pass compiler which produces assembly code, now includes all the most widely used features of the C language. (requires 48k CP/M) C: $200.00. Manual only: $15.00. C for 8086: $500.00.

LISP SuperSoft LISP is a complete implementation of an EV-LISP type interpreter. It is fully recursive and also supports the much needed PROG functions. LISP for TRS-80 cassette: $75.00. (requires 16k level II) LISP for TRS-80 disk: $100.00. (requires 16k disk) LISP for CP/M: $150.00. (requires 32k CP/M) Manual only: $15.00.

BASIC SuperSoft BASIC Compiler is a superset of Standard BASIC which accepts the most popular syntax and also supports many extensions to the language. (requires 48k CP/M) BASIC: $200.00. Manual only: $25.00. BASIC for Z8000: $500.00.

FORTRAN IV and RATFOR The SSS FORTRAN Compiler is fast, efficient, and complete (full 1966 ANSI standard with extensions). (requires 32k CP/M, Z 80 only) FORTRAN: $275.00. RATFOR: $100.00. FORTRAN and RATFOR: $350.00. FORTRAN manual: $25.00

FORTH The production code of Stackwork's FORTH (1977 FORTH Standard) is capable of compactness approaching and frequently smaller than the size of equivalent assembly code. (requires 48k CP/M) FORTH: $200.00. Manual only: $25.00.

Also Available From SuperSoft:

System Maintenance Series
Diagnostics II, Disk Doctor, System Checker

Financial Planning Series
ScratchPad, Data-view, Stats-graph, The Optimizer

System Utilities
Term II, Utilities Packs I & II, Elink, Disk Edit, Encode/Decode II, BCD

Entertainment Series
Nemesis, Dungeon Master, Analiza II

Word Processing
Star-Edit, TFS

Available from fine dealers everywhere, or directly from SuperSoft. U.K. and European Distribution: Digital Devices, 134 London Road, Southborough Kent, Tunbridge Wells, TN4 OPL, England. Tel. Tunbridge Wells (892) 37977/9 Telex. 95582.

Japanese Distribution: ASR Corporation International, 3-23-8, Nishi-Shimbashi, Minato-Ku, Tokyo 105, Japan, Tel. (03)-437-5371, Telex. 0242-2723.

Required by the Department of Defense for Ada copyright protection: "This compiler is presently an incomplete implementation of the Ada programming language. It is intended that this compiler will be further developed to enable implementation of the complete Ada programming language, and then to be submitted to the Ada Joint Program Office for validation."

*Ada is a trademark of the Department of Defense (Ada Joint Program Office)

CP/M registered trademark Digital Research
SSS FORTRAN copyright Small Systems Services
Unix registered trademark Bell Laboratories

Circle 392 on inquiry card.

SuperSoft software available for virtually all CP/M systems. Please specify your system.



FIRST IN SOFTWARE TECHNOLOGY P.O.Box 1628 Champaign, IL 61820 (217) 359-2112 Telex 270365

```
PROMPTING LEVEL SELECTION MENU

Please select desired level of prompting:

1. Full
2. Partial
3. None

Enter Choice #_
```

Figure 6: *Menu which allows the operator to choose the prompting level. Features like this accommodate operators who differ in skill.*

Action code dialogue usually involves the use of specially defined and labeled function keys for calling up displays or programs. User-defined function keys are not widely available on microcomputers, but we will see more of them in the future. The new IBM Personal Computer has 15 or more user-defined function keys.

Beside these methods, sequence control can be exercised in a number of other ways—in fact, via any channels that permit the operator to enter data into the computer and receive feedback. Possibilities include trackball, joystick, optical device, human voice, and whatever else creative minds can invent and implement.

The Old Standby—the Menu-Driven Program

In this article I cannot cover sequence-control design principles that apply to all dialogue types. For one thing, there isn't room. But more important, the research with many of these methods is limited, and I can offer few definitive recommendations. For these reasons, I will focus on that old standby, the menu-driven program. Though its origin is traceable to the earliest days of computing machinery, the menu-driven program remains the principal means by which people carry on dialogues with computers. Until people perfect ways of talking with computers, the menu-driven program will probably remain the mainstay.

There are good reasons for its popularity and success. First, it makes no demands on human memory. Menu options are displayed on the screen and the operator picks the one he wants. This makes a menu-driven program easy to learn. Second, menus help the operator orient himself because they explicitly display the available "roads" (subprograms) from each "crossroad" (menu).

Menu-driven programs have certain drawbacks as well. Storing and generating menus cost memory and time overhead. Once familiar with a program, operators may find that layers of menus impede progress more than they help.

For all that, the menu-driven program is a good vehicle for our discussion of sequence control because most people are familiar with it. Many of the design principles I will discuss in relation to it can be extended to other types of dialogues as well.

Your menu-driven program should be self-explanatory. The operator should not have to refer constantly to a manual to figure out how to make something happen. Obviously, you cannot explain everything within the program, but you should provide screens that describe special sequence-control features. For example, suppose that your program has several subprograms, each containing sub-subprograms, and so on, and that different program levels are accessed through layers of menus. Suppose further that you have designed certain sequence-control features to shortcut some menus so that the experienced operator can move quickly around to different parts of the program. Special features such as these should be explained within the program, either on separate screens which precede menus or, if the explanation is brief enough, on menus themselves.

Your program will function, of course, without built-in screen documentation. However, the operator will learn the intricacies of your program much more quickly if you do your explaining when and where he needs it—within the program itself.

If the operators using your program will vary in skill level, attempt to build in features that will accommodate skill growth. For example, let the operator select the level of prompting—full, partial, or none. This will help the inexperienced operator gain skill and confidence and save the experienced operator a lot of time. Make the choice of the prompting-level convenient, as shown in figure 6.

Your program may have one menu or several, depending on complexity. If it is a complex program with many options, analyze how each subprogram will be used. Determine which subprograms are functionally related. Estimate how often each menu choice will be made. You may be able to make a very long menu into a number of short ones.

Functional relationships and *frequency of use* of the subprograms are the two most important criteria to consider in designing a menu. List functionally related subprograms on the same menu. If possible, list frequently called subprograms on the same menu. If these requirements conflict, let functional relationships rule menu design. Avoid designing very long menus that contain a grab bag of unrelated options. This only makes sense if all programs are equally likely to be called under all conditions. That is seldom the case.

Make menu choices brief, explicit, and distinct from one another. To make up the label, consider exactly what each subprogram does and then label it accordingly.

Use terminology consistently. For example, don't call subprograms that do essentially the same thing by different names in the same program—don't call a program "edit" in one place and "modify/delete" in another.

The menu itself has three essential parts: (1) title, (2) list of menu choices, and (3) prompt line. Some menus also contain a statement that directs the operator to "select one of the menu choices." This feature is useful to operators unfamiliar with computers and can be considered optional.

```
MAIN MENU

Select one of the following programs by
entering its number

        1. ENTER DATA
        2. GENERATE REPORTS
        3. EDIT DATA BASE
        4. START NEW FILE
        5. PURGE FILE
        6. QUIT

        Enter Choice #_
```

Figure 7: *Menu showing the three essential menu parts: title, list of choices, and prompt line. Some menus also have a directive to prompt operators unfamiliar with the system.*

Center the menu title at top of the display and put the word "menu" at the end of the title. If you are providing the (optional) directive line, print this next, offset to the left, so that it is recognized as an instruction and not a title. Center the prompt and the data input field at the bottom of the screen. The prompt should be brief and explicit, for example, "ENTER CHOICE #," as shown in figure 7.

Menu selection can be done in several different ways: by entering the number of a menu option, by entering a letter, by typing in the menu choice, and by moving a cursor to the choice. Typing in the menu choice label usually requires several keystrokes and should be avoided. Most microcomputer software is not set up to permit cursor selection of menu choices.

The most common selection method is to type in a number or letter. In general, short menus should permit selection by letter—preferably the first letter of the choice label. (This can present problems if different menu choices start with the same letter.) On longer menus, numbered menu choices are more convenient.

If you do use numbers, then any list of numbered items appearing on one of your display screens will resemble a menu. This may cause confusion. Minimize confusion by titling menus as menus and titling other displays appropriately. Avoid numbered items on nonmenu displays, if possible. If you are presenting a list of instructions, for example, precede each instruction by a bullet instead of a number.

Conclusion

This brief excursion into the world of human factors covered areas of interest to the average microcomputer programmer. Much more is written on the subject, and those interested should consult the references listed at the end of this article.

Note that application of human-factors considerations to software design is immature as a technology and that much research still needs to be done. At present there is no single source to which the reader can refer to find all the important answers. (Martin's book is comprehensive but aimed primarily at the mainframe user.) Much of what is now available comes as technical reports that present recommendations cautiously labeled as "preliminary" or "tentative" findings.

In this article, I have attempted to congeal this somewhat indefinite material into a form that is useful to the average reader. Much has been left out because of inapplicability to microcomputers or because the material was of a specialized nature and would probably not be of interest. In general, what was presented is based on the references, although at some points I have condensed and simplified things. I hope that I have not distorted any author's intentions in the process. ■


References

1. Anacapa Sciences Inc. "Fundamentals of Human Factors for Engineering and Design—Session 22: Human-Computer Interface Design" (classroom notes from seminar). Santa Barbara, CA: 1981.
2. Engel, S. E., & Granda, R. E. *Guidelines for Man/Display Interfaces*, Technical Report TR 00.2720. Poughkeepsie, NY: IBM, December 19, 1975.
3. Martin, J. *Design of Man-Computer Dialogues.* Englewood Cliffs, NJ: Prentice-Hall, 1976.
4. Smith S. L. *Man-Machine Interface: Requirements Definition and Design Guidelines—a Progress Report,* Project No. 572R. Bedford, MA: Mitre Corporation, February 1981.

Best prices anywhere. We beat 'em all!

COMPUTERS

INTERSYSTEMS



DPS1, DPS1A, DPS2A CALL FOR PRICES


DYNABYTE List........Less 30%

ALTOS List..............Less 20%

NORTHSTAR
Horizons & Advantages ....CALL

TELEVIDEO COMPUTER SYSTEMS..................CALL

SUPERBRAIN



64K DD	$2639
64K QD	$2949
DSS-10MEG Hard Disk	$3195

CROMEMCO

CS-1 List $3495	OUR PRICE	$3195
CS-2 List $4695	OUR PRICE	$3549
CS-3 List $7995	OUR PRICE	$6349
Z2H List $9995	OUR PRICE	$7995






Z-89 List $2895
OUR PRICE
$2099

TERMINALS

TeleVideo



Televideo 910C	CALL
912C	CALL
920C	CALL
925C	CALL
950C	CALL

INTERTUBE	$725
Emulator	$725

OKIDATA

Microline 80	$359
Microline 82A	$469
Microline 83A	$749

C.ITOH................CALL FOR PRICES

SOROC

Soroc IQ120	$679
IQ130	$585
IQ135	$719
IQ135 w graphics	$789
IQ140	$995

HAZELTINE

1420	CALL
1500	SAVE
1510	CALL

ZENITH Z19..............**$639**

Prices quoted are for prepaid orders only, and reflect a cash discount. C.O.D.'s and chatge cards slightly higher.

Most items in stock for immediate delivery. factory sealed cartons w full factory warranty. NYS residents add appropriate sales tax. Prices do not include shipping. C.O.D. orders require 25% deposit. Prices subject to change without notice.

PRINTERS

CENTRONICS



749-1 PAR	$699
739-3 SER	$619
704-11 parallel	$1569
704-9 (RS232)	$1519

TI 810

810 Basic	$1289
810 Full Option	$1599
820 RO Basic	$1545
820 KSR Basic	$1739

NEC 7710 (RS232) SERIAL	$2395
7730 PARALLEL	$2395

Qume..................CALL FOR PRICE

Diablo 630 RO	$2049
1640 KSR	$3495
1640 RO	$3095

Paper Tiger 445G	$739
560G	$1099

Epson

MX-80	$465
MX-80FT	$548
MX 100	$745

DISK SYSTEMS



MORROW

Discus 2D	$835
Dual Discuss 2D	$1385
Discuss 2 + 2	$1089
M 5 5meg Hard Disk	$3750
M 10 10 meg Hard Disk	$2999
M26 26 meg Hard Disk	$3349

CORVUS 5 meg Hard Disk	$3109
CORVUS 10 meg Hard Disk	$4439
CORVUS 20 meg Hard Disk	$5349

COMPUTERS WHOLESALE

P.O. Box 144 Camillus, N.Y. 13031

315-472-2582

Prices subject to change without notice

Circle 119 on inquiry card.

The Atari Tutorial

Part 8: Generating Sound with Software

The sound capabilities of the Atari 400 and 800 computers are influenced by the software technique used.

Bob Fraser
1639 Martin Ave.
Sunnyvale, CA 94087

The sound system in the Atari 400 and 800 microcomputers can be used in two basic ways: static and dynamic. Static sound generation is the simpler of the two. The program sets a few sound generators, turns to other activities for a while, and then turns them off. Dynamic sound generation is more difficult. The computer must continuously update the sound generators during program execution. For example:

```
SOUND 0,120,8,8
```

generates a static sound, while:

```
FOR X=0 TO 255
  SOUND 0,X,8,8
NEXT X
```

generates a dynamic sound.

This article appears in slightly different form in De Re Atari, *published by Atari Inc., and is reproduced with its express permission.*

Static Sound

Although static sound is normally limited to beeps, clicks, and buzzes, there are exceptions. Two examples are the programs given last month as special effects in the sections on high-pass filters and 16-bit sound. Another way to obtain interesting effects is to use interference, as in this example:

```
SOUND 0,255,10,8
SOUND 1,254,10,8
```

The strange effect is a result of closely phased peaks and valleys. Figure 1 shows two channels independently running sine waves at slightly different frequencies and their sum. The sum curve shows the strange interference pattern created when these two channels are added.


Figure 1 also shows that, at some points in time, the waves are assisting each other; at other points, they oppose each other. Adding the volumes of two waves whose peaks coincide will yield a wave with twice the strength or volume. Similarly, adding the volumes of two waves while one is at maximum and the other is at minimum will result in a cancellation of both of them. On the graph of the sum curve, we can see this effect. An interesting project would be writing a program to plot interaction patterns of two, three, and four channels; the program would display graphs like that of figure 1. You might discover some unique sounds.

The slighter the difference in frequency between the two channels, the longer the pattern of repetition. To understand this, draw some graphs similar to figure 1 and study the interaction. As an example, try the following BASIC statements:


```
SOUND 0,255,10,8
SOUND 1,254,10,8
SOUND 1,253,10,8
SOUND 1,252,10,8
```

As the difference in frequency grows, the period of repetition decreases.

From CMC International, world's largest Intertec distributor...



SUPERBRAIN and COMPUSTAR - YOUR CUSTOMERS WILL NEVER NEED ANOTHER SYSTEM!



CMC International is the largest distributor in the world of Intertec Data Systems products -the SuperBrain and CompuStar - Intertec's incredibly expandable microcomputers. No matter how small or large your customers are or become, we doubt that they'll ever outgrow these computers. Both SuperBrain and CompuStar offer the industry-standard CP/M disk operating system and 64K of dynamic RAM. Both are expandable to 10 megabytes of storage with the CompuStar disk storage system. CompuStars can be linked together to form a 255-user network.

Dealers benefit from the service and support offered through CMC. Like advertising co-op, software and hardware support, module replacement. And a toll-free line so you can call from anywhere in the continental United States.


The bottom line is profitability. Our dealers benefit with a combination of quality Intertec products and CMC International's pricing.

Contact us today. We deliver.




For Information Call (206)453-9777
To Order, Call Toll-free 1-800-426-2963

CMC INTERNATIONAL



A Division of Computer Marketing Corporation

11058 Main Street, Suite 220
Bellevue, Washington 98004
TELEX 152556 SEATAC



SuperBrain and CompuStar are registered trademarks of Intertec Data Systems Corporation
CP/M is a registered trademark of Digital Research



Minicomputer performance in

Multi-user. Multi Tasking. Decision I™ memory management hardware includes a memory map that is similar to the IBM 360,® and IBM 370.® It supports up to 16 tasks or 15 users and a supervisor without swapping. And, more with swapping. Each task or user enjoys complete memory protection and dynamic memory allocation. One task may be delegated as a supervisor to privileged system functions forbidden to ordinary tasks or users. Such functions (I/O calls, unauthorized memory access, etc.), will trap to the supervisor. If supervisory functions are not required the system can be configured for turnkey multi-user operation.

Multi-purpose IEEE696/S-100. Decision I utilizes the Morrow Designs IEEE Standard S-100 Wunderbuss.® That means you can configure it to your specific applications. Add a floating point processor, add memory (to a full megabyte), add I/O, add controllers...add boards from dozens of manufacturers. And S-100 has a major advantage over single-board computers: If a board goes down, you simply replace it. And keep running. If you want to expand your system. Add boards and terminals.

An unmatched software base. Decision I runs on the M/OS™ operating system. M/OS supports all system calls source compatibly with UNIX.® Thus, UNIX programs will compile directly and UNIX documentation is almost totally applicable. Morrow CP/M• has been configured to run under M/OS and communicate with both CP/M and UNIX standard media for maximum portability. Languages available include BASIC, COBOL, FORTRAN, RATFOR, Pascal and C. That means Decision I offers you a software base unmatched in its price/performance arena.

The OEM machine. A basic multi-user system at $5,225 includes the Decision I, 4 Mhz Z80A-based CPU, sophisticated memory

IBM 360 and 370 are trademarks of IBM Corp.
Wunderbuss is a registered trademark of Morrow Designs
Decision I and M/OS are trademarks of Morrow Designs
UNIX is a trademark of Bell Laboratories, Inc.
CP/M is a trademark of Digital Research Corp.



a multi-user Microcomputer.

management hardware, CP/M 2.2, M/BASIC 5.2, 3 serial and 2 parallel I/O ports, 14 I/O slots with S-100 connectors, supervisor control in both hardware and software, 128K of RAM and two quad-density disk drives (800K) with DMA controller. Plus, cabinet (either desk-top or rack-mount), and power supply. The same system with 8″ floppies and a full Megabyte of formatted storage costs $5,659. And, we offer OEM pricing.

A better microcomputer. Whether you're building a single or multi-user system, the Decision I offers you a hardware/software combination unmatched in the field. Decision I is not simply an improved 8-bit microcomputer. It's a breakthrough. In both computing power and price.

Systems your way. Morrow Designs' full range of hard and floppy disk memory, add-in memory boards, I/O boards, controllers and software allow you to configure your system your way...through a single supplier.

The decision is yours. Compare the Decision I, feature-for-feature with mini or microcomputers on the market today. Compare capabilities. Compare flexibility. Compare utility. Then, compare price. We think Decision I will change the way you think about microcomputer systems.

Complete information? See your computer dealer. Or, write Morrow Designs.

LOOK TO MORROW FOR ANSWERS.

MORROW DESIGNS

5221 Central Avenue, Richmond, CA 94804
(415) 524-2101

Circle 284 on inquiry card.




Figure 1: *Complex waveform generation from the addition of waveforms.*

Listing 1: *Using machine language to assist BASIC in generating multiple-note chords on the Atari 400/800. This demonstration program uses a short machine-language program placed in the BASIC string SIMUL$ (see lines 25 and 9999) to specify the frequency- and control-register values of up to four of the Atari sound generators. It is done quickly enough to make all the generators seem to start simultaneously (BASIC is too slow to do this). Note the use of the string SIMUL$ to store the machine-language program and the USR call in line 50 to execute it.*

```
10     SOUND 0,0,0,0:DIM SIMUL$(16)
15     REM read in machine lang. program
20     RESTORE 9999:X=1
25     READ Q: IF Q<>-1 THEN SIMUL$(X)=CHR$(Q):X=X+1:GOTO 25
26     REM read and then play sound data
27     RESTORE 100
30     READ F1,C1,F2,C2,F3,C3,F4,C4
40     IF F1=-1 THEN END
50     X=USR(ADR(SIMUL$),F1,C1,F2,C2,F3,C3,F4,C4)
55     FOR X=0 TO 150:NEXT X
60     GOTO 30
90     REM sound data
100    DATA 182,168,0,0,0,0,0,0
110    DATA 162,168,182,166,0,0,0,0
120    DATA 144,168,162,166,35,166,0,0
130    DATA 128,168,144,166,40,166,35,166
140    DATA 121,168,128,166,45,166,40,166
150    DATA 108,168,121,166,47,166,45,166
160    DATA 96,168,108,166,53,166,47,166
170    DATA 91,168,96,166,60,166,53,166
999    DATA -1,0,0,0,0,0,0,0
9000   REM
9010   REM
9020   REM this data contains the machine lang. program,
9030   REM and is read into SIMUL$
9999   DATA 104,133,203,162,0,104,104,157,0,210,232,228,203,208,246,96,-1
```

Dynamic Sound

More complex sound effects normally require the use of dynamic sound techniques. Three levels of dynamic sound generation are available to the Atari 400/800 programmer: sound in BASIC, 60-hertz (Hz) interrupt sound, and sound in machine code.

BASIC Sound

BASIC is somewhat limited in its handling of sound generation. As you may have noticed, the SOUND statement negates any special AUDCTL setting. [*The audio-control register AUDCTL was discussed in last month's installment of "The Atari Tutorial." . . .* **GW**] This problem can be avoided by poking values directly into the sound registers, rather than using the SOUND statement.

In addition, the use of BASIC to control sound generation is somewhat limited because of its slowness. If the program is not completely dedicated to sound generation, there is seldom enough processor time to do more than static sound or choppy dynamic sound. The only alternative is to temporarily halt all other processing while generating sound.

Another problem can occur when using the computer to play music on more than one channel. If all four channels are used, the time separation between the first SOUND statement and the fourth can be substantial enough to make a noticeable delay between the different channels.

The program in listing 1 solves this problem. SIMUL$ is a tiny machine-language program that pokes all four sound channels very quickly. A BASIC program using SIMUL$ can rapidly manipulate all four channels. Any program can call SIMUL$ by putting the sound-register values inside the USR function as in line 50 of the demonstration program. The parameters should be ordered as shown, with the control-register value following the frequency-register value for each channel; this ordering is followed one to four times, once for each sound channel to

8086 Super-micro

8 Mhz. - 16-bit - S-100 bus - 128K 70 nsec. RAM

Computer Benchmarks – All systems running the same BASIC program.

Manufacture – Model	Class	Operating System	Language (Type*)	Run Time (Seconds)
IBM 3033	Mainframe	VS2-10RVYL	Stanford BASIC	10
Seattle Computer System 2	Micro	MS-DOS	Microsoft BASIC (C)	33
Digital Equipment PDP 11/70	Mini	n/a	BASIC (I)	45
Prime 550	Mainframe	PRIMOS	BASIC V16.4 (I)	63
Digital Equipment PDP-10	Mainframe	TOPS-10	BASIC (I)	65
IBM System 34	Mainframe	Release 05	BASIC (I)	129
TEI System 48	Micro	MAGIC 1.0	Microsoft BASIC (C)	178
Hewlett-Packard HP3000	Mini	Time Share	BASIC (I)	250
Seattle Computer System 2	Micro	MS-DOS	Microsoft BASIC (I)	310
Alpha Micro AM-100/T	Micro	AMOS 4.3a	Alpha BASIC (SC)	317
Digital Equipment PDP 11/45	Mini	n/a	BASIC (I)	330
Data General NOVA 3	Mini	Time Share	BASIC 5.32	517
Ohio Scientific C4-P	Micro	OS65D 3.2	Level 1 BASIC (I)	680
North Star Floating Point	Micro	NSDOS	NorthStar BASIC (I)	685
Radio Shack TRS-80 II	Micro	TRSDOS 1.2	BASIC (I)	792
Apple II +	Micro	DOS 3.2	Applesoft II (I)	960
Cromemco System 3	Micro	CDOS	32K BASIC (I)	1074
Commodore Pet 2001	Micro	n/a	Microsoft BASIC (I)	1374
IBM 5100	Micro	n/a	BASIC (I)	1951
Vector MZ	Micro	n/a	Micropolis BASIC (I)	2251

* C = Compiler; I = Interpreter. Times (except for Seattle Computer) taken from August 1981 issue of Interface Age.

Seattle Computer System 2 consists of 8 Mhz. 8086 CPU set, 128K of 70 nsec. static RAM, double-density disk controller, 22-slot TEI constant voltage mainframe, a cable for two 8' drives, and MS-DOS operating system (also called 86-DOS, IBM PC-DOS, Lifeboat SB-86). The system is fully assembled and tested and ready to run with the addition of disk drives (we can supply) and terminal. Price: $4185. 8087 Adapter also available.

Call for location of our nearest dealer

Software

We have the following Microsoft high-level languages running under MS-DOS.

- BASIC-86 Interpreter $400
- BASIC-86 Compiler $400
- Fortran-86 .... $600
- Pascal-86 .... $600
- Cobol-86 .... $900
- Macro-86 Assembler $300

Check for new additions



1114 Industry Dr. Seattle WA 98188

Information Hotline

206/575-1830

Circle 367 on inquiry card.

be set. As a speed consideration, as well as a convenience, SIMUL$ allows you to specify sound for less than four channels (i.e., channels 1 through 3, channels 1 and 2, or just channel 1). Simply omit the unused parameters from the USR function.

SIMUL$ offers another distinct advantage to the BASIC programmer. The AUDCTL register is reset upon execution of any SOUND statement in BASIC. However, using SIMUL$, no SOUND statements are executed; thus, the AUDCTL setting is retained.

Another method of sound generation in BASIC is impractical. This method uses the volume-only bit of any of the four audio-control registers. Type in and run the following program:

```
SOUND 0,0,0,0
10 POKE 53761,16:
   POKE 53761,31:
   GOTO 10
```

This program sets the volume-only bit in channel 1 and modulates the volume from 0 to 15 as fast as BASIC can. Although it uses all the processing time available to BASIC, it produces only a low buzz.

60-Hz Interrupt

This technique is probably the most versatile and practical of all methods available to the Atari computer programmer.

Precisely every 1/60 second the computer hardware automatically generates an interrupt. When this happens, the computer temporarily leaves the main program (the program running on the system—BASIC, Star Raiders, etc.). It then executes an interrupt service routine, a small machine-language routine designed specifically for servicing these interrupts. When the interrupt service routine finishes, it executes a special machine-language instruction that restores the computer to the interrupted program. This all occurs in such a way (if done properly) that the program execution is not affected. In fact, it has no idea that it ever stopped!

The interrupt service routine currently resident on the Atari 400/800

Announcing the Printing Breakthrough of the Century: Smith-Corona® TP-1™ Text Printer

- **Low Cost Daisy Wheel Printer**


$845.00

- Microprocessor Electronics
- Serial or Parallel Interface
- Simple, Reliable Mechanism

ACT NOW: Limited Supply, Low, Low Cost

Smith Corona, one of the largest manufacturers of small printers in the world, gives a whole new perspective to printing with their electronic text printer—**TP-1.** The **TP-1** is a microprocessor controlled, high quality **daisy wheel printer.** It produces perfectly formed, executive quality printouts at the speed of 120 words per minute. Typewriter quality printing at dot matrix prices.

Simple, durable and dependable, **TP-1** may be used with word processing systems, microcomputers and most small business systems. Compact and attractively styled, the **TP-1** blends well with any setting.



Additional daisy print wheels $4.95



Additional ribbons $2.95

Now, all your letters, documents forms and reports can have the crisp, professional look you demand—for business or personal use—at an affordable price. **TP-1,** the electronic text printer.

Don't delay. Order your **TP-1** TODAY at the low price of **$845.**

Micro Printer Marketing offers same day shipping, nationwide service and invites dealer inquiries. Catalogues available. No shipping charges on pre-paid orders.



Call Micro-Printer Marketing

CALL TOLL FREE **1-800-523-9859**

In PA Call Collect **215/433-3366**

MasterCard and Visa Accepted





Circle 267 on inquiry card.

computers maintains timers, translates controller information, and performs other chores requiring regular attention.

Before the interrupt service routine returns to the main program, it can be made to execute any user routine—for example, your sound-generation routine. This is an ideal situation for sound generation since the timing is precisely controlled, and especially since another program can be executing without paying heed to the sound generator. Even more impressive is its versatility. Because it is a machine-language program, the interrupt sound program will lend itself equally well to a main program written in any language—BASIC, assembly language, FORTH, Pascal. In fact, the sound generator will require few, if any, modifications to work with another program or even another language.

A *table-driven* routine offers maximum flexibility and simplicity for such a purpose. Table-driven refers to a type of program that accesses data tables in memory for its information. In the case of the sound generator, the data tables would contain the frequency values and possibly the audio-control-register values. The interrupt service routine would simply read the next entries in the data table and put them into their respective audio registers. Using this method, notes could change as often as 60 times per second, fast enough for most applications.

Once such a program has been written and placed in memory (for example, at location 600 hexadecimal, the beginning of the page of memory reserved for the user), you need to install it as a part of the 60-Hz interrupt service routine. This is accomplished by a method known as *vector stealing*.

Direct control of sound registers with a dedicated machine-language routine opens new doors in sound generation.

Memory locations 224 and 225 hexadecimal contain the address of a small routine called XITVBL (eXIT Vertical BLank interrupt service routine), which is designed to be executed after all 60-Hz interrupt processing is complete, restoring the computer to the main program as previously discussed.

The following procedure shows how vector stealing can be used to install your sound routine:

1. Place your program in memory (e.g., 600 hexadecimal).
2. Verify that the last instruction executed is a JMP $E462 (since location E462 hexadecimal is the XITVBL routine, this will make the main program continue).
3. Load the X register with the high byte of your routine's address (a 6 in this case).
4. Load the Y register with the low byte of your routine's address (a 0 in this case).
5. Load the accumulator with a 7.
6. Do a JSR $E45C (to set locations 224 and 225 hexadecimal).

Steps 3 through 6 are required to change the value of the pointer at locations 224 and 225 hexadecimal without error. The routine called is SETVBV (SET Vertical Blank Vectors), which simply puts the address of your routine into locations 224 and 225 hexadecimal. Once installed, the system works as follows when an interrupt occurs:

1. The computer's interrupt routine is executed.
2. The computer jumps to the program whose address is in locations 224 and 225 hexadecimal, which is now your routine.
3. Your routine executes.
4. Your routine then jumps to XITVBL.
5. XITVBL restores the computer's state previous to the interrupt and makes it resume normal operation.

[An elusive and infuriating "bug" may occur when a 60-Hz interrupt routine involving arithmetic operations (ADC and SBC op codes) is used as part of a BASIC program. The Atari BASIC floating-point routines set the 6502 decimal flag and cause add and subtract operations to be done in binary-coded decimal (BCD) instead of binary. If the 60-Hz interrupt occurs during a BASIC floating-point operation, the interrupt routine will be in decimal—not binary—mode unless you execute a CLD instruction at the beginning of the routine. My thanks to Chris Crawford of Atari for pointing out this bug. . . . GW*]*

If you do not wish to implement such a program yourself, one is available from the Atari Program Exchange. The package is called INSOMNIA (Interrupt Sound Initializer/Alterer). It allows creation and modification of sound data while you listen and is accompanied by an interrupt sound generator that is table-driven and compatible with any language. For more information, contact the Atari Program Exchange, 155 Moffett Park Dr., POB 427, Sunnyvale, CA 94086.


Machine-Code Sound Generation


Direct control of sound registers with a dedicated machine-language routine opens new doors in sound generation. The technique is as follows: write a program similar to the 60-Hz interrupt routine in that it is table-driven. However, the only routine now being executed by the Atari is dedicated to sound generation. By expending much more processor time on sound generation, you can produce higher-quality sounds. Consider, for example, the output of a typical 60-Hz interrupt music routine; its output will look something like figure 2a.

The volume-only bit offers a tremendous capacity for accurate sound reproduction.

Since much more processing time is available with a dedicated machine-language routine, you can change the frequency at very high speed *during* the note's playing time. For example, suppose you discover that whenever any piano key is struck it produces the characteristic sequence of frequencies shown in figure 2b.

The graph in figure 2b is called the *piano envelope*. To simulate a piano, the idea is to apply the piano envelope very quickly to the "plain-vanilla" square-wave beep. The note is thus slightly modified during its playing time. For example, a piano simulation of the three notes in figure 2a would be modified to look like figure 2c. This is essentially the same sound produced by the standard music routine of figure 2a, only the









Figure 2: *Complex waveform generation under computer control. Figure 2a shows a frequency-versus-time plot of three simple notes generated by one of the Atari sound generators. If the complete resources of the computer are used to modulate the frequency (or other parameters) of the notes while they are being played, the computer can produce highly complex sounds. For example, if we find that a frequency envelope such as figure 2b simulates the sound of a piano, the envelope can be superimposed on the generated notes of figure 2a to give a modified set of notes that has a graph like that of figure 2c.*




THE ATARI® STAR

Win $25,000 in cash, plus prizes and an ATARI STAR by entering your software in the ATARI® ASAP competition.

ATARI is looking for some of the greatest software from the brightest stars in the software field. And naturally, we're willing to reward you for it.

Every three months, ATARI will be presenting ATARI STARS to the writers of software programs judged first, second and third place in the following categories: consumer (including entertainment, personal interest and development); education; home business (personal finance and record keeping); and system software. The decision of the ATARI judges is final.

Quarterly prizes will be from $750 to $3,000 worth* of selected



ATARI products and an ATARI STAR. The annual Grand Prize will be the coveted Super Star trophy and $25,000 in cash.**

To be eligible, your software idea must be submitted to and published in the ATARI Program Exchange catalog. Submit your program on the official entry form which we'll rush to you if you send in the attached coupon.

The ATARI STAR Awards are in addition to the percentage of revenues you will automatically be entitled to as a result of sales of your software programs in the ATARI Program Exchange.

If you're a star, ATARI wants to reward you. Send in the coupon today, or call toll-free 800-538-1862, in California 800-672-1850, and you could be the proud winner of an ATARI ASAP STAR Trophy, and some great ATARI prizes.

*Based on manufacturer's suggested retail price.

**Taxes are the sole responsibility of the winner. Void where prohibited by law. Winners will be notified by mail. ATARI employees and their families are not eligible. For more contest details, call the toll-free numbers.

Circle 42 on inquiry card.

For more contest details, call 800-538-1862, in California 800-672-1850.

Send to: ATARI Software Acquisition Program, Dept. C1E, P.O. Box 427, Sunnyvale, CA 94086

Yes, I want to enter the ATARI ASAP competition. Please rush me my entry form.

Name________________

Address________________

City________________

State/Zip________________



A Warner Communications Company

We've Brought The Computer Age Home.™

Listing 2: *A machine-language program that uses the waveform mode of the Atari 400/800 to generate tones with a sine wave amplitude envelope (tones normally produced by the Atari have a square-wave amplitude).*

```
0100 ;
0110 ; VONLY          Bob Fraser 7-23-81
0120 ;
0130 ;
0140 ; volume-only AUDC1-4 bit test routine
0150 ;
0160 ;
0170 ;
0180 ;
0190 AUDCTL = $D208
0200 AUDF1 = $D200
0210 AUDC1 = $D201
0220 SKCTL = $D20F
0230 ;
0240 ;
0250                  * = $B0
0260 TEMPO            .BYTE 1
0270 MSC              .BYTE 0
0280 ;
0290 ;
0300 ;
0310                  * = $4000
0320                  LDA #0
0330                  STA AUDCTL
0340                  LDA #3
0350                  STA SKCTL
0360                  LDX #0
0370 ;
0380                  LDA #0
0390                  STA $D40E ; disable vertical blank interrupt
0400                  STA $D20E ; disable nonmaskable interrupts
0410                  STA $D400 ; disable screen DMA
0420 ;
0430 ;
0440 ;
0450 LOO              LDA DTAB,X
0460                  STA MSC
0470 ;
0480                  LDA VTAB,X
0490 L0               LDY TEMPO
0500                  STA AUDC1
0510 L1               DEY
0520                  BNE L1
0530 ;
0540 ;                dec most significant counter
0550                  DEC MSC
0560                  BNE L0
0570 ;
0580 ;
0590 ;                new note
0600 ;
0610                  INX
0620                  CPX NC
0630                  BNE LOO
0640 ;
0650 ;                wrap note pointer
0660                  LDX #0
0670                  BEQ LOO
0680 ;
0690 ;
0700 NC               .BYTE 28 ; note count
0710 ;
0720 ;                table of volumes to be played in succession
0730 VTAB
0740                  .BYTE 24,25,26,27,28,29,30,31
0750                  .BYTE 30,29,28,27,26,25,24
0760                  .BYTE 23,22,21,20,19,18,17
0770                  .BYTE 18,19,20,21,22,23
0780 ;
0790 ;                this table contains the duration of each entry
                      above
0800 DTAB
0810                  .BYTE 1,1,1,2,2,2,3,6
0820                  .BYTE 3,2,2,2,1,1,1
0830                  .BYTE 1,1,2,2,2,3,6
0840                  .BYTE 3,2,2,2,1,1
```

notes now have a piano tone and they sound much prettier than just unmodulated beeps. Unfortunately, all other processing had to be sacrificed to get that piano tone. The sound channel is no longer updated only once every note; it is now done perhaps 100 times within the note's duration.

Volume-Only Sound

As indicated earlier, the AUDC*n* volume-only bits aren't of much use in BASIC. This is due entirely to the fact that BASIC is too slow to effectively use them. However, this is not the case with machine language.

As mentioned last month, the volume-only bit of the AUDC*n* registers offers a tremendous capacity for accurate sound reproduction. True waveform generation (within the time and volume resolution limits of the computer) is made possible with this bit. Instead of just putting a piano flavor into the music, you can now make it closely replicate a piano sound. Unfortunately, it can never precisely duplicate an instrument. Four bits (16 values) is not enough volume resolution for true high-quality work. Nevertheless, the technique does generate surprisingly good sounds. The program in listing 2 demonstrates the use of one of the volume-only bits. If you have an assembler, type it in and try it. Surprisingly, speed is not really a problem here. The wave has almost sixty steps, and the program can still be made to play the wave at up to 10 kilohertz.

Remove lines 390 through 410 and try the program once more. It will sound quite broken up. The cause is the 60-Hz interrupt discussed in the previous section. You can actually hear the interrupts taking place since all sound stops during that time.

Line 410 disables screen DMA (direct memory access). By disabling screen DMA, the ANTIC chip within the Atari 400/800 no longer "steals" time from the 6502 processor to get data from screen memory in time to display it on the video display. This is why the screen goes to a solid background color when the program is executed. Disabling screen DMA serves two purposes: to speed up the 6502 processor and to make the timing consistent, since screen DMA steals cycles at odd intervals.

GET ON trak™

Get trak™ 5¼" & 8" Floppy Drives

TRAK Drive Systems are ready to plug in and use—complete with power supply and cable.

TRAK—the way to go in floppy disk drives. Whether you are just buying your computer system, adding to it, or up-dating it—make it TRAK.

TRAK features the finest industry-standard 5¼" and 8" drives, custom compact packaging, custom power supplies, ventilating fans with multi-drives and unique control facilities for your convenience and protection.

Complete control is yours with deluxe TRAK Systems. System control panels feature lighted "Sentinal" power switch so you always know when your TRAK drive is powered up. And individual "Protector" (write-protect) switches guard your stored information.

TRAK offers you the widest choice—singles or multi-drives—5¼" or 8"—double sided—single/double densities—3 to 8 ms access—from 125 K-Bytes to 4.8 Megabytes storage—choice of colors (office brown, silver gray or oyster)—optional door locks, front bezels, write-protect switch, extender card, optional 220V/50 Hz power supply for international use—and more.

System compatibility. TRAK drive systems are compatible with more than just one or two popular computer systems. TRAK drives are compatible with Apple II®, TRS-80®, IBM, Xerox, Heath/Zenith and other micros and minis. And more compatible systems are added continuously.

Circle 451 on inquiry card.

TRAK is committed to making a significant contribution to the world-wide computer industry by providing the latest products at the best prices. We invite you to join us in this common goal and get on TRAK.

For price, order information and the name of your nearest dealer call TRAK toll-free.

1-800-323-4853
(in Illinois call collect 1-312-968-1716).



trak™ Microcomputer Corp.
1511 Ogden Ave.
Downers Grove, IL 60515 TWX 910-222-1848

Distributorships, dealerships available. International and OEM inquiries invited for TRAK drives, cabinets, power supplies and computer systems.

New TRAK products coming soon. 5¼" & 8" Slimline floppy drives, 5¼" & 8" Winchester systems, multi-user networking, special Controller and host system adaptor boards.

$25 **INTRODUCTORY FACTORY REBATE** $25

Buy from your TRAK dealer, then mail copy of sales receipt with TRAK serial number and this coupon to TRAK. We will rebate $25 direct to you as our way of welcoming you to the TRAK drive family.

Name____________________

Address____________________

City__________ State______ Zip______

Offer expires May 30, 1982. Limit one rebate per customer. Offer void where prohibited.

® TRS-80 is a registered trademark of Radio Shack, a Tandy Company
® Apple II is a registered trademark of the Apple Computer Company


FREE SHIPPING*

*On all prepaid cash orders - Continental US Only

MAIL ORDER DISCOUNTS

PRINTERS


Epson MX-80 or MX-80 FT CALL



Anadex 9501 w/2K Buffer	1349
C. Itoh Starwriter 25 CPS daisywheel	1449
C. Itoh Starwriter 45 CPS daisywheel	1649
Epson MX-70	CALL
Epson MX-80 & MX-80 FT	CALL
Epson MX-100	CALL
NEC 8023 Impact Dot Matrix	629
NEC Spinwriters (Latest models)	CALL
Paper Tiger IDS-460G w/graphics	899
Paper Tiger IDS-560G w/graphics	1099
Qume Spring Daisywheels (Latest models)	CALL
Diable 630 Daisywheel 40 CPS	1795

VIDEO MONITORS

Amdek/Leedex Video 100 12" B&W	129
Amdek/Leedex Video 100G 12" Green Phospher	149
Amdek (Hitachi) 13" Color w/audio output	389
NEC 12" Green Phospher Display JB-1201M	CALL
NEC 12" Lo-Res Color Display	CALL
NEC 12" Hi-Res RGB Color Display	CALL
Sanyo 9" B&W Display	185
Sanyo 9" Green Display	CALL
Sanyo 12" B&W Display	269
Sanyo 12" Green Phospher Display	285
Sanyo 13" Color Display	449
Zenith 12" Green Phospher Display	139



ZENITH 12" GREEN $139



IBM ACCESSORIES BY TECMAR

256 Dynamic Ram Card
Hi-Speed Parallel I/O Card
Hi-Speed Serial I/O Card
Real-Time System Clock
Card Expansion Chassis

CALL FOR BEST PRICES

Ordering Information: Phone orders using VISA, MASTERCARD, AMERICAN EXPRESS, DINER'S CLUB, CARTE BLANCHE, bank wire transfer, cashier's or certified check, money order, or personal check (allow ten days to clear). Unless prepaid with cash, please add 5% for shipping, handling and insurance (minimum 5.00). California residents add 6% sales tax. Foreign customers please call or write for shipping information and charges. OEM's, Institutions and corporations please send for a written quotation. All equipment is subjecct to price change and availability without notice. All equipment is new and complete with manufacturer's warranty (usally 90 days). Showroom prices may differ from mail order prices.

Send Orders to:

consumer computers Mail Order
8338 Center Drive
La Mesa, California 92041

VIC=20 $249




VIC ACCESSORIES

8K Ram Cartridge for VIC-20	$50
3K Ram Cartridge for VIC-20	$34
Superslot	$24
Super Alien	$24
Jupiter Lander	$24
Draw Poker	$24
VIC Software 6 pack 'A'	$49
VIC Software 6 pack 'B'	$49
Datasette Cassette I/O Unit	$69
VIC IEEE-488 Interface	$79
Vicmon Machine Lang Monitor	$47
VIC Super Expander	$54
VIC RS232C Terminal Interface	$39
Voice Synthesizer CBM/PET	$319
Pgrm Char Set/Game Graphics ED	$13
3D Invaders	$31
Spiders of Mars	$39
Outworld	$32
Satellites and Meteorites	$39
Alien Blitz	$32
RS-232 Communicator Interface	$40
18 In. Communicator Cable M/M	$13
36 In. Communicator Cable M/M	$15
3K RAM Expander for VIC-20	$65
8K RAM Expansion for VIC-20	$99
VIC-20 Reference Card	$4
VICTerm A	$16
Vicalc for VIC-20	$11
VIC Portfolio Mgmt. (VPM)	$19
VICHECK	$19
PAC It In	$15
Amok	$15
Don't Fall	$11
Simon	$7
Blastoids	$16
Superadditon	$7
Supersubtraction	$7
Skymath	$12
Space Division	$12
Long Division	$12
Super Hangman	$17
BK ROM/RAM	.25
Alien Blitz	$19
Globber	$19
The Alien (Req. 6K memory)	$19
Invader Fall (Req. 6K memory)	$17
Star Wars	$13
3D Maze	$11
Breakout	$11
Carom	$11
Raceway	$11
Lazer War	$14
Dragon Maze	$13
Shape Matcher	$9
Doggy Maze	$9


16K RAMBOARD by ConComp for Apple II Computers

FOR ONLY  $99



AVAILABLE NOW

APPLE II ACCESSORIES



16K Ram Board by ConComp Industries	99
Hayes Micromodem II	299
Hayes Smartmodem	369
Hayes Chronograph	199
NovationApple-Cat	339
Novation Cat Modem	169
Novation Expansion Mod	39
Novation Handset	29
Novation BSR	19
Videx Videoterm 80 column card	249
Videx Keyboard Enhancer (Rev. 6)	115
Videx Keyboard Enhancer (Rev. 7)	99
Videx Keyboard Enhancer II (Rev. 7 & up)	129
Videx Switchplate	15
Videx Soft Video Switch	29
Z-80 Softcard by Microsoft	299
Applesoft Complier	149
Typing Tutor II	20
Microsoft Adventure	25
Olympic Decathaion	24
16K RamCard by Microsoft	159
Thunderclock clock/calender card	129
Thunderclock X-10 Inter/Scheduler	49
Smarterm 80 col card	299
Corvus Winchester Disk Drives	CALL
ALF 3 Voice Music Card	199
ALF 9 Voice Music Card	149
Alphasyntauri keyboard system	CALL
Lazer Lower Case +	55
Lazer Keyboard Plus +	99
23 Key Numeric Keypad by Keyboard Co.	120
Joystick by Keyboard Co.	45
6809 CPU Card (The Mill) by Stellation	319
AIO Serial & Parallel Interface by SSM A&T	189
DB Master by Stoneware	189
Music System (16 voices)	299
A/D + D/A Interface	279
Expansion Chassis (8 slots)	569
Introl/X-10 Controller card	169
Clock/Calendar Card	225
CPS Multi-function Card	175
Supertalker SD-200	159
Romplus + card	135
Romwriter card	149
Symtec Hi-Res Light Pen	210
Sup-R-Fan	45
Sup-R-Terminal	329
SVA ZVX4 Megabyter 8" Disk Controller	649
SVA 2+2 Single Den. 8" Disk Controller	345
Speechlink 2000 by Heuristics	249
Versawriter Digitizer Tablet	229
Asynchronous Serial Interface card by CCS	139
Centronics Parallel Interface card by CCS	119
VisiCalc version 3.3	169
VisiFile (NEW data base manager)	199
VisiTrend/VisiPlot	219
VisiDex	169
VisiTerm	99
Desktop Plan II	169
Wordstar (Apple 80 col version)	299
VisiPak (Calc, Trend, Plot, File)	550
Easywriter Word Processor	199
Tax Preparer '81 version	89
Real Estate Analyzer	129
Creative Financing	139
Personal Filing System (PFS)	79
PFS...Report	79
Datastar (Apple II - 80 col)	249
Spell Star (Apple II - 80 col)	219
Super-sort (Apple II - 80 col)	179
Peachtree Accounting Software	CALL
BPI Accounting Software	CALL
Systems Plus Accounting Software	CALL

CALL OR WRITE FOR FREE CATALOG

NO RISK* MAIL ORDER DISCOUNTS

*Call for Details

***ORDER TOLL FREE* 800-854-6654**

In California and outside continental U.S. (714) 698-8088

Telex 695-000 Beta CCMO

Please refer to ordering instructions on preceding page.

Circle 127 on inquiry card.




Figure 3: *An amplitude-versus-time graph of the sine wave sound produced by listing 2.*

In this demonstration program, the sound created is a close approximation to a sine wave. A graph of the waveform is given in figure 3.

The Role of Sound in Programs

This article and last month's installment of "The Atari Tutorial" have discussed the technical aspects of sound generation with the Atari 400 and 800 computers. However, the programmer must also understand the broader role of sound in the complete software package.

Moviemakers have long understood the importance of mood-setting background music. The recent *Star Wars* movies by George Lucas are excellent examples. When Darth Vader enters the room, you immediately fear and hate him because of the menacing background rhythms accompanying his entry. You know to gleefully applaud when Luke Skywalker saves Princess Leia because gallant music plays in the background. Likewise, horror films can frighten you merely by playing eerie music, even though the action may be completely ordinary.

Tatio America's Space Invaders program for the Atari 400/800 issues a personal threat to the player with its echoing stomp. As the tempo increases, knuckles whiten and teeth grind. When you fire a photon torpedo in Atari's Star Raiders game, the computer gives you a "launch" sound that decreases in frequency as the torpedo speeds away from you. The effective use of sound can increase your involvement with a game or other program.

Impressionistic sounds affect our subconscious and our state of mind. This may be due to the fact that sounds, if present, are continuously entering our mind whether or not we are actively listening. Visual inputs, on the other hand, require the user's attention. If we are distracted from the TV set, we cease to concentrate on the picture and the image leaves our mind. Sound therefore offers the programmer a direct path to the users' minds—bypassing their thought processes and zeroing in on their emotions. ■

In this age of runaway inflation...

Look what $825* will buy

The HIPAD™ digitizer

Inexpensive input to your computer

The HIPAD™ digitizer can be used for both converting graphic information into digital values and as a menu. Utilizing either the stylus or the optional cursor, the operator can input graphic data into the computer by locating individual points on the digitizers 11" x 11" (28cm x 28cm) active area. In the "stream mode" a continuance of placements of coordinate pairs may be input.

Not a kit, the HIPAD™ comes complete with both RS-232-C and parallel interfaces and has its own built-in power source. The origin is completely relocatable so coordinates may be positive or minus for a true reference value and oversized material may by input by simply resetting the origin.


Accurate positional information, free form sketches, even keyboard simulation

All can be entered using the multi-faceted HIPAD™ digitizer. Its capabilities and low price make the UL listed HIPAD™ a natural selection over keyboard entry, inaccurate joysticks, or expensive approximating light pens. It's perfect for inputting isometric drawings, schematics, X-rays, architectural drawings, business graphs, and many other forms of graphic information, as well as creating your own graphics.

Use it with Apple II™, TRS-80 Level II™, PET™ or other popular computers

The HIPAD's™ built-in RS-232C and parallel 8 bit interfaces make it all possible. (For Apple II order DT-11A, for TRS-80 or PET order DT-11). Furthermore, you get English or metric scaling, data format (Binary/BCD/ASCII), selectable baud rates, and resolution of either .005" or .01".

The ideal input device for the small system user.



Available with stylus or optional cursor.



Available with optional display.

For complete information, contact Houston, Instrument, P.O. Box 15720, Austin, Texas 78761. (512) 835-0900. For rush literature requests, outside Texas call **toll free 1-800-531-5205.** *For technical information ask for operator #5. In Europe contact Houston Instrument, Rochesterlaan 6, 8240 Gistel, Belgium. Phone 059/27-74-45. Telex Bausch 81399.*

INSTRUMENTS & SYSTEMS DIVISION

Together...we'll create tomorrow.



TM HIPAD is a trademark of Houston Instrument
TRS-80 is a trademark of Tandy Corporation
APPLE is a trademark of Apple Computer Inc.
PET is a trademark of Commodore Business Machines, Inc.

Circle 195 for literature.

Circle 196 to have representative call.

*U.S. Suggested retail price

The $149.95 personal computer.

Introducing the Sinclair ZX81

If you're ever going to buy a personal computer, now is the time to do it.

The new Sinclair ZX81 is the most powerful, yet easy-to-use computer ever offered for anywhere near the price: only $149.95* completely assembled.

Don't let the price fool you. The ZX81 has just about everything you could ask for in a personal computer.

A breakthrough in personal computers

The ZX81 is a major advance over the original Sinclair ZX80—the world's largest selling personal computer and the first for under $200.

In fact, the ZX81's new 8K Extended BASIC offers features found only on computers costing two or three times as much.

Just look at what you get:

- Continuous display, including moving graphics
- Multi-dimensional string and numerical arrays
- Mathematical and scientific functions accurate to 8 decimal places
- Unique one-touch entry of key words like PRINT, RUN and LIST
- Automatic syntax error detection and easy editing
- Randomize function useful for both games and serious applications
- Built-in interface for ZX Printer
- 1K of memory expandable to 16K

The ZX81 is also very convenient to use. It hooks up to any television set to produce a clear 32-column by 24-line display. And you can use a regular cassette recorder to store and recall programs by name.

*Plus shipping and handling. Price includes connectors for TV and cassette, AC adaptor, and FREE manual.

If you already own a ZX80

The 8K Extended BASIC chip used in the ZX81 is available as a plug-in replacement for your ZX80 for only $39.95, plus shipping and handling—complete with new keyboard overlay and the ZX81 manual.

So in just a few minutes, with no special skills or tools required, you can upgrade your ZX80 to have all the powerful features of the ZX81. (You'll have everything except continuous display, but you can still use the PAUSE and SCROLL commands to get moving graphics.)


With the 8K BASIC chip, your ZX80 will also be equipped to use the ZX Printer and Sinclair software.

Order at no risk**

We'll give you 10 days to try out the ZX81. If you're not completely satisfied, just return it to Sinclair Research and we'll give you a full refund.

And if you have a problem with your ZX81, send it to Sinclair Research within 90 days and we'll repair or replace it at no charge.

**Does not apply to ZX81 kits.




NEW SOFTWARE: Sinclair has published pre-recorded programs on cassettes for your ZX81, or ZX80 with 8K BASIC. We're constantly coming out with new programs, so we'll send you our latest software catalog with your computer.



ZX PRINTER: The Sinclair ZX Printer will work with your ZX81, or ZX80 with 8K BASIC. It will be available in the near future and will cost less than $100.



16K MEMORY MODULE: Like any powerful, full fledged computer, the ZX81 is expandable. Sinclair's 16K memory module plugs right onto the back of your ZX81 (or ZX80, with or without 8K BASIC). Cost is $99.95, plus shipping and handling.



ZX81 MANUAL: The ZX81 comes with a comprehensive 164-page programming guide and operating manual designed for both beginners and experienced computer users. A $10.95 value, it's yours free with the ZX81.

The $99.95 personal computer.

Introducing the ZX81 kit

If you really want to save money, and you enjoy building electronic kits, you can order the ZX81 in kit form for the incredible price of just $99.95.* It's the same, full-featured computer, only you put it together yourself. We'll send complete, easy-to-follow instructions on how you can assemble your ZX81 in just a few hours. All you have to supply is the soldering iron.

How to order

Sinclair Research is the world's largest manufacturer of personal computers.

The ZX81 represents the latest technology in microelectronics, and it picks up right where the ZX80 left off. Thousands are selling every week.

We urge you to place your order for the new ZX81 today. The sooner you order, the sooner you can start enjoying your own computer.

To order, simply call our toll free number, and use your MasterCard or VISA.

To order by mail, please use the coupon. And send your check or money order. We regret that we cannot accept purchase orders or C.O.D.'s.

CALL 800-543-3000. Ask for operator #509. In Ohio call 800-582-1364. In Canada call 513-729-4300. Ask for operator #509. Phones open 24 hours a day, 7 days a week. Have your MasterCard or VISA ready.

These numbers are for orders only. For information, you must write to Sinclair Research Ltd., 2 Sinclair Plaza, Nashua, NH 03061.

sinclair

AD CODE Ø 4BY	PRICE†	QTY.	AMOUNT
ZX81	$149.95		
ZX81 Kit	99.95		
8K BASIC chip (for ZX80)	39.95		
16K Memory Module (for ZX81 or ZX80)	99.95		
Shipping and Handling	4.95		$4.95
		TOTAL	

MAIL TO: Sinclair Research Ltd., One Sinclair Plaza, Nashua, NH 03061.

NAME ____________________

ADDRESS ____________________

CITY/STATE/ZIP ____________________

† U.S. Dollars

GRRRR

Bison Takes the Bite Out of High Prices

Epson Eradication

Espon MX 80	$405
Epson MX 80 FT	$515
Epson MX 100	$695
Epson Graftrax Roms	$ 74
Epson Replacement Cart	$ 11
Interface to Apple	$ 84

Monitor Munch

Amdek 13" Color Monitor	$346
Amdek Color II RGB Monitor	$895
NEC 12" Green Screen	$166
NEC RGB Color Monitor	$945
Zenith Green Screen	$134

Peripheral Portion

D.C. Hayes Micromodem II	$295
D.C. Hayes Smartmodem	$239
Microsoft RAM Card	$149
Microsoft Z-80 Card	$295
Paddle Adapple	$ 24
Smarterm 80 Column Card	$286
Thunderclock X-10 Interface	$ 42
Thunderclock Card	$116
Tandon Drive TM 848-2	$475
Visidex Videoterm 80 Col	$277

FORTH 79 Fit

Starting FORTH	$ 14
FORTH Programming Aids	$135
Nautilus System Cross-Compiler	$179
System Guide to Fig-FORTH	$ 22
Micromotion FORTH 79 for Apple	$116
Micromotion FORTH 79 for 280 CPM	$116

Software Scrunch

dBase II 8"	$595
dBase II 5"	$540
DB Master	$179
Wordstar 8"	$310
Wordstar 5"	$227
Spellstar 8"	$189
Spellstar 5"	$164
Visicalc	$146
Visiplot	$145
Visiterm	$123
Visitred/Visiplot	$214
Personal Filing System	$ 71
Personal Report System	$ 71
Data Capture 4.0	$ 52
Data Capture 4.0/80	$ 77

Game Gnaw

David's Midnight Magic	$ 28
Red Alert	$ 24
Space Eggs	$ 18
High Res Soccer	$ 23
Gamma Gobblins	$ 22
Robot Wars	$ 31
Sargon II	$ 26
Alien Typhoon	$ 19
Bug Attack	$ 24
Castle Wolfenstein	$ 25
Computer Baseball	$ 31
Computer Bismark	$ 48
Cops and Robbers	$ 28
Epoch	$ 26
Phantom Five	$ 23
President-Elect	$ 31

ORDER FORM

Address ______________________
City ______________________
State ________ Zip ____________
Visa/MC # ______________________
Expiration Date ______________________
Signature ______________________

Item	Price

California res. include
6% state sales tax ______________
Total ______________

Send cashier check, money order or charge order on Visa or Master Card. Please allow 4-6 weeks for delivery. Shipping C.O.D. based on weight. Free shipping on all orders over $500. No C.O.D. orders. Prices and availability subject to change without notice. Phone orders welcome.

Mail to: **Bison Products**
P.O. Box 9078-184
Van Nuys, CA 91409





FOR FAST SERVICE CALL
(213) 891-5702



16709 Roscoe Boulevard, Sepulveda, CA 91343

Circle 53 on inquiry card.

The Mind's I

Douglas R. Hofstadter
and Daniel C. Dennett,
Basic Books Inc.,
New York, 1981.
501 pages, hardcover
$15.50

Reviewed by Lloyd Milligan
8604 Maywood Dr.
Columbia, SC 29209

This book is designed to provoke, disturb, and befuddle its readers, to make the obvious strange and, perhaps, to make the strange obvious.

(from the Preface)

Most people take considerable pleasure in being astonished. Witness the popular television show *That's Incredible.* For those who are less easily astonished, but who enjoy a special kind of challenge, Douglas R. Hofstadter and Daniel C. Dennett have "composed and arranged" *The Mind's I,* a splendid collection of essays on mind and consciousness, "self and soul." Each essay concludes with a "Reflection" based on the editors' own thoughts and reactions.

Of all the pursuits of man, science has been the most productive. In the present century, the so-called neurosciences (neurobiology, neurochemistry, neuropsychology, etc.) have contributed significantly to our understanding of how the human brain works. Paradoxically, however, deep issues of both historical and enduring interest have been on the whole ignored by these new sciences. The denial of mind and consciousness as valid topics of scientific inquiry may be traced to the influence of logical positivism, operationalism, and behaviorism. *The Mind's I* could be said to be about those things that behaviorism denies.

A recurring theme or device in many of these essays is the "thought experiment." In a thought experiment, one imagines all the procedures and conditions of an experiment and attempts to imagine or deduce what the outcome would be. The power of a thought experiment—and also its weakness—comes from imagining procedures which cannot be carried out in reality. The key to distinguishing whether a thought experiment could be realizable is to decide if the conditions of the experiment are possible "in principle." In reading these essays I was sometimes reminded of Mark Twain's satire on facts and miracles: ". . . if it is a Miracle, any sort of evidence will answer, but if it is a Fact, proof is necessary." It is often difficult to know whether a suggested condition is merely technically infeasible or impossible in principle. Fortunately, Hofstadter and Dennett provide some assistance in this regard, but there is still a danger—thought experiments that support your point of view will seem more likely to be realizable than those that oppose it.

Thus far it may not be obvious why *The Mind's I* has special interest to computer enthusiasts. That it does is partly due to a new breed of cognitive psychologists—called computer scientists—whose major research interest is artificial intelligence (AI). If your concept of AI is based on the Eliza program, then you probably need to be brought up to date. Current AI research involves topics such as simulating human ability to understand stories (Roger Schank et al.; discussed by John R. Searle in "Minds, Brains, and Programs," page 353). Such projects shed new light on the meaning of "understanding," and at the same time expose the awesome complexity of human knowledge database design. In one sense, the ultimate goal of AI research is to give objective meaning to concepts that have heretofore been understood only in the subjective sense.

The brain's hardware, which at the very least "supports" thought, cannot be ignored. Several thought experiments in this book focus on the neural-circuit description of brain functioning. It is easy to slip from this focus to the assumption that the brain is purely a digital machine. This assumption is unwarranted even at the cellular level. For example, synapses (connections between nerve cells) are *not* strictly analogous to logic gates. Thousands of axon terminals may impinge upon the dendrites of a single cell. The events that transpire there (at the synapse) are more analog than digital in nature. One may even speculate that it is *not* possible "in principle" to model these processes sequentially in real time.

While reading these essays I found myself formulating point-by-point replies. More often than not, Hofstadter or Dennett expressed my approval or misgivings more clearly than I could have done. Their comments not only reflect on the essays themselves, but go on to present new variations on related themes. The reader is compelled to reflect on the reflection, and so on, until intellectual fatigue sets in.


A common thread runs through this collection, but it is not easy to discern. Various conceptions of mind, self, and soul are set up, exposed, scrutinized; the idea is to inquire which, if any, of these are *possible* models of mind, self, or soul. The mind as a program of immense intricacy, involving deep "level-crossing" structures (e.g., how can a thought influence a synapse?) and Gödelian loops, is one idea that emerges.

The Mind's I does not explain the mind's I. Perhaps it aims to describe what such an explanation would be like. In one reflection, Hofstadter is careful to distinguish emulation of the mind from simulation. Explanation is at least one step further removed. And while this book does not pretend to "explain" self or soul, the impression emerges that, with thoughtful consideration, these problems of the ages may be tractable, after all.

At another level, *The Mind's I* expresses a tone of personal warmth and enthusiasm. The authors inquire of one of Stanislaw Lem's essays, "Is this poetry, philosophy, or science?" I asked myself the same question about the book as a whole and concluded that it is a combination of all three. One thing that the book is not is *hocus pocus.* Hofstadter and Dennett eschew pseudoscience. Their views are completely compatible with the scientific world view. It's just that science has not yet made deep inroads into the problems that make up the main focus of this book. Perhaps this deficiency will yield in part to the union of computer science, neuroscience, cognitive science, philosophy, and linguistics. ■

LOWEST PRICE·BEST QUALITY

NORTH STAR Horizon 2



2-5¼" Disk Drives
64K Double Density
Factory assem. & tested
Factory guaranteed

A few left
Low Price only
$2499

Powerful North Star BASIC Free
Superb for Business & Science

HORIZON STANDARD IS NOW HRZ-2-64K QUAD

Factory Assembled & Tested	List	Only
Horizon-2-32K-Double Density		$2349
Horizon-2-32K-Quad Density		$2549
Horizon-2-64K-Quad	$3599	$2699
Horizon-2-64K-QHD 5	$5999	$4499
Horizon Ram ASM	32K=$374	64K=$524
Big Sale on Multi-User Time-Sharing		call
English to Basic Translator		$99
North Star Hard Disk 18 Mb	$5375	$3923
North Star Time Sharing Multi-User		call
Zbasic 2 to 5 times faster!	$350	call
Secretary Word Processor		$99
Wordstar Word Processor		$318
Floating Point Board	$399	$319
Oasis Multi-User Software	SAVE	call
CP/M for N* Extra features	$230	$220
Micro Mike Software	SAVE	call
Ecosoft Accounting $355 .. MICROSTAT		$265
Pascal-80	$600	$515
Extra Precision Basic		$50
Northword	$199	$179
Mailmanager	$299	$224
Infomanager	$399	$349
General Ledger	$499	$429
Accounts Receivable	$499	$429
Accounts Payable	$499	$429
Inventory	$499	$429
Order Entry	$499	$429
PROPAC	$1499	$1274
DOS + Basic 5.2		27

DECISION I



"The IBM-360 on the Z-80 & S-100 BUS!"

Sixteen Programs running simultaneously! Free CPM, Microsoft BASIC and WORDSTAR with Complete system!

	LIST	ONLY
DECISION 1 + 65K Static + 8" Disks	$4375	3500
DECISION 1 + 65K Static + 2 - 5" Disks	4195	3356
DECISION 1 + 65K Static + 5" Disk + 5 Mb Hard Disk	5990	4792
DECISION 1 3 user 195K Static + 5" Disk + 5Mb Hard Disk + MICRONIX	8035	6428
DECISION 1 — Z-80 + 1/0=Power	1725	1339

MORROW 8" Disk

Discus 2D + CP/M 600K only $849
Discus 2 + 2 + CP/M 1.2 MEGA B. $1149
Add Drives 2D = $599 2 + 2 = $795
Discus 2D-dual + CP/M Only $1388
Free Microsoft BASIC from MORROW with Discus system or hard disk



M-26 MORROW Hard Disk
26,000,000 Bytes!!
List $4495 .... Only $3395
Free CPM + BASIC
M-20 List $4795 .. Only $3835
M-10 List $3695 .. Only $2955
M-5 List $2495 .. Only $1995

InterSystems

Z-80A CPU 4 MHz
64K Dynamic RAM
Front Panel

VI/0-1 - with interrupts
FDCII Disk Controller
20 slot motherboard

List $3795 .... Only $2839


Without front panel as above only $2716
Front Paneless Recommended for Business

Save on Memory and Programs

Systems Memory 64K A&T $459	Corvus Hard Disk .... SAVE	Cat Novation Modem $169	Which Computers are Best?—FREE.
Systems Memory 64K Bank $555	SSM Video BRD VB3 kit $361	Memory Merchant 16K $159	Insured Shipping at Low Rates. Call
Microangelo $985	Spectrum Color ASM $326		For Latest Prices, Details. We Beat Advertised Prices.

Factory Guarantees ***Expert Advice***





COMPUTERS

919-889-4577 4167 Kivett Dr. Jamestown N.C. 27282 919-883-1105

®CP/M is a registered trademark of Digital Research, Inc.

Circle 27 on inquiry card.

A Po(r)tpourri of Ideas

Fifth in a Series

Three inexpensive hardware/software projects to let you use the cassette port for a tone generator, telephone dialer, and RS-232C output channel.

William Barden Jr.
28122 Orsola
Mission Viejo, CA 92692

There's always an advantage in using existing hardware to interface external devices—there's no need to perform address decoding, to hook up to a multiline bus, or to design and implement controller functions. The cassette port is the most rudimentary input/output port in the TRS-80 Models I and III. It was originally designed to interface to an audio cassette recorder so that BASIC and machine-language programs and data could be saved and loaded. The cassette port, however, can be used in a variety of other ways. In this article, I'll describe three projects that use *cassette-port output*.

These projects will work with a Model I system *without* the expansion interface and with any Model III. The projects are a tone generator with volume control, a telephone dialer, and an RS-232C driver. A fourth use, controlling a nuclear fast-breeder reactor, was to be included, but still needs a little polishing up. Perhaps in a later article . . .

Cassette Logic

The TRS-80 Models I and III use similar logic in the cassette output, as shown in figure 1. The REMote output to turn on the recorder is slightly different in address decoding between the Models I and III, but in both cases it simply closes a relay. Two normally open relay contacts go to pins 1 and 3 of the cassette jack, a 5-pin DIN connector. The relay output won't be used for these projects, since some of




Figure 1: *Model I/III cassette output is performed by a two-bit latch that generates three voltage levels. The three voltage levels can produce a square wave with a positive-going pulse, a negative-going pulse, and a zero level. A motor relay connects two normally open contacts.*

About the Author

William Barden Jr. has written many books on microcomputer programming and design. He is a member of the Association for Computing Machinery and the Institute of Electrical and Electronics Engineers.

Port 0FF Hexadecimal Bit 1	Bit 0	CASSOUT Voltage (V)
1	0	≅0
0	0	≅0.4
0	1	≅0.8
1	1	≅0.4

Table 1: *CASSOUT voltages. The two latch bits produce four voltage levels. The 11 configuration is redundant and is not used.*




Figure 2: *The recording technique for 500 bps uses a clock pulse spaced at 2-ms intervals. A data pulse at the midpoint between clock pulses represents a 1; the absence of a data pulse represents a 0.*




Figure 3: *In the TONOUT electronics, an LM386 audio-amplifier chip is driven by the CASSOUT signal. The output of the LM386 drives a small speaker.*

the earlier relays were prone to "sticking" (especially when used to control the AC supply for milling machines).

Instead, what will be used is the output that normally goes to the AUXiliary input of the cassette recorder to write data on the tape. This is a single line connected to pin 5 (CASSOUT) of the DIN connector. This line is driven by two bits at I/O address 0FF hexadecimal in both the Models I and III.

Three voltage levels can be output to the CASSOUT line, depending upon the configuration of the two least significant bits of port 0FF hexadecimal (see table 1). A bit configuration of 01 binary produces about 0 volts (V), 00 produces about 0.4 V, and 10 produces about 0.8 V. Bit configuration 11 is redundant as it generates 0.4 V again.

The three voltage levels are used to write data onto the cassette in the 500-bits-per-second (bps) mode, as shown in figure 2. A single square-wave cycle is first generated to produce a clock pulse. Then, either another cycle is output, representing a 1 data bit, or no cycle is output, representing a 0 data bit.

The Model III also has 1500-bps capability. In this mode, continuous *frequency-shift keying* is used, with 1320-hertz (Hz) and 2680-Hz tones representing the data. Only the 0- and 0.8-V levels are used for this scheme.

In both cases, the major part of the logic is in the ROM (read-only memory) firmware. The electronics really just consist of the two output latches and a few resistors.

In the following projects, I'll use the two bits of port 0FF hexadecimal to generate square waves for musical tones, telephone dialing, and RS-232C output. The greater part of the design effort, as in the TRS-80 cassette functions, is in the software. The hardware will consist of three simple circuits with a minimum of parts.


(**A note about connectors:** For connecting all three projects to your TRS-80 cassette port, use a standard, thin-walled, 5-pin DIN plug, such as Radio Shack's catalog item 274-003.)

A Musical Tone Generator

Our first project produces six octaves of notes representing the first six octaves on the piano keyboard. The notes are square waves, rich in odd-order harmonics. Two volume levels can be output, one using the 0- and 0.4-V levels, and a second using the 0- and 0.8-V levels.

The circuit shown in figure 3 uses the CASSOUT output as an input to an LM386 audio amplifier. The LM386 requires only a capacitor and 8-ohm (Ω) speaker to implement a complete audio amplifier. A miniature 10-kΩ potentiometer is used at the input for volume control. The power supply for the LM386 can be any convenient voltage from +4 to +12 V. A 6-V battery works fine for the power supply, or you can obtain a low-priced power-supply kit from Radio Shack.

TONOUT (listing 1) is an assem-



Listing 1: *TONOUT is a Z80 subroutine to output tones through the cassette port. The code is to be embedded in the BASIC program of listing 3.*

```
9000                      ORG     9000H
                   ;**************************************************************
                   ;* TONE OUTPUT. OUTPUTS TONE THROUGH CASSETTE PORT.            *
                   ;*     ENTRY: HL=> PARAMETER BLOCK                               *
                   ;*             PARAM+0=DURATION CNT IN 2 BYTES                   *
                   ;*                   +2=FREQ CNT*(18.04 MICROSECS MOD I          *
                   ;*                      15.79 MICROSECS MOD III), 2 BYTES        *
                   ;*                   +4=LEVEL: 2=LOW,3=HIGH, ONE BYTE            *
                   ;*     EXIT:  AFTER TONE HAS SOUNDED                              *
                   ;**************************************************************
                   ;
9000 CD7F0A        TONOUT  CALL    0A7FH          ;GET HL
9003 E5                    PUSH    HL             ;TRANSFER TO IX
9004 DDE1                  POP     IX
9006 DD4E04                LD      C,(IX+4)       ;PUT LEVEL IN C
9009 DD6603                LD      H,(IX+3)       ;MSB FREQUENCY
900C DD6E02                LD      L,(IX+2)       ;LSB FREQUENCY
900F 7C                    LD      A,H            ;GET MSB FREQ CNT
9010 B7                    OR      A              ;TEST FOR ZERO
9011 2022                  JR      NZ,LOWFRE      ;GO IF LOW FREQUENCY
                   ; HIGH FREQUENCY HERE
9013 45                    LD      B,L            ;GET FREQUENCY COUNT
9014 DD6601                LD      H,(IX+1)       ;MSB OF DURATION
9017 DD6E00                LD      L,(IX+0)       ;LSB OF DURATION
901A 2B                    DEC     HL             ;FOR JR NC'
901B 11FFFF                LD      DE,-1          ;FOR FREQ LOOP
901E 79            HI010   LD      A,C              ;LEVEL TO A (4)
901F EE02                  XOR     2                ;NOW 00 OR 01 (7)
9021 D3FF                  OUT     (0FFH),A         ;TURN ON (11)
9023 78                    LD      A,B              ;GET FREQ COUNT (4)
9024 3D            HI020   DEC     A                  ;ON LOOP (4)
9025 20FD                  JR      NZ,HI020           ;LOOP TIL 0 (12/7)
9027 79                    LD      A,C              ;DUMMY (4)
9028 3E02                  LD      A,2              ;NOW 10 (7)
902A D3FF                  OUT     (0FFH),A         ;TURN OFF (11)
902C 78                    LD      A,B              ;GET FREQ COUNT (4)
902D 3D            HI030   DEC     A                  ;OFF LOOP (4)
902E 20FD                  JR      NZ,HI030           ;LOOP TIL 0 (12/7)
9030 19                    ADD     HL,DE            ;DECREMENT DUR CNT (11)
9031 38EB                  JR      C,HI010          ;GO IF NOT 0 (12/7)
9033 1823                  JR      LOW090         ;RETURN TO BASIC
                   ; LOW FREQUENCY HERE
9035 E5            LOWFRE  PUSH    HL             ;FREQ COUNT TO DE
9036 D1                    POP     DE
9037 CB83                  RES     0,E            ;MAKE EVEN
9039 DD4600                LD      B,(IX+0)       ;DURATION CNT TO B
903C 79            LOW010  LD      A,C              ;GET LEVEL (4)
903D EE02                  XOR     2                ;NOW 00 OR 01 (7)
903F D3FF                  OUT     (0FFH),A         ;TURN ON (11)
9041 62                    LD      H,D              ;GET FREQ COUNT (4)
9042 6B                    LD      L,E              ;(4)
9043 2B            LOW020  DEC     HL                 ;DECR FREQ CNT (6)
9044 2B                    DEC     HL                 ;(6)
9045 7C                    LD      A,H                ;TEST HL (4)
9046 B5                    OR      L                  ;(4)
9047 20FA                  JR      NZ,LOW020          ;GO IF NOT 0 (12/7)
9049 79                    LD      A,C              ;DUMMY (4)
904A 3E02                  LD      A,2              ;NOW 10 (7)
904C D3FF                  OUT     (0FFH),A         ;TURN OFF (11)
904E 62                    LD      H,D              ;GET FREQ COUNT (4)
904F 6B                    LD      L,E              ;(4)
9050 2B            LOW030  DEC     HL                 ;DECR FREQ CNT (6)
9051 2B                    DEC     HL                 ;(6)
9052 7C                    LD      A,H                ;TEST HL (4)
9053 B5                    OR      L                  ;(4)
9054 20FA                  JR      NZ,LOW030          ;GO IF NOT 0 (12/7)
9056 10E4                  DJNZ    LOW010           ;GO IF D CNT NOT 0 (13/8)
9058 C9            LOW090  RET                    ;RETURN TO BASIC
0000                       END
```

bly-language program that drives the circuit to produce square waves from about 20 Hz to over 10,000 Hz. The extreme low and high frequencies won't come out very well (if at all) in the LM386, but for the middle range, tones sound fine. If you're a purist, you might consider using CASSOUT as an input to an amplifier with better fidelity.

TONOUT is designed to interface to a BASIC program. It is completely relocatable (more about that later) and requires three parameters from the BASIC code—a frequency count, a duration count, and a level.

The frequency count is a value from 1 to 65,535 that is used to control a timing loop. Each count causes a delay of 18.04 microseconds (μs) for




Figure 4: *A timing loop turns on the CASSOUT signal and then turns it off. The same frequency count is used for both the on and off delays; hence, the period of the tone is twice the delay time.*




Figure 5: *Three parameters are used to interface to TONOUT from BASIC. A duration count is held in two bytes, a frequency count in two bytes, and a level in one byte. The counts are in standard Z80 address format: least significant byte followed by most significant byte.*

the Model I (15.79 for the Model III) on the "on" and "off" portions of the square wave, as shown in figure 4. Therefore, the frequencies of the square waves produced are 1/(36.08E-6) and 1/(31.58E-6), respectively.

The duration count of 1 to 65,535 determines the length of time the tone is played. In fact, the duration count is the number of cycles of the tone. Thus, the length of time the tone plays is dependent upon the tone's frequency. To play a "quarter note," the duration count would be 25 for a 100-Hz tone, 50 for 200-Hz, and so forth. The duration count is 1/frequency times the fraction of a second the tone is to be played.

The third parameter is volume level. A value of 2 is low and 3 is high. The level parameter is in one byte.

The main problem in TONOUT is how to get the "tightest" possible loop to toggle port hexadecimal 0FF bits on and off and still allow for low-frequency notes with a longer duration. The approach used here is to split TONOUT into two segments of code, one for high-frequency notes, and one for low-frequency notes.

TONOUT is entered from BASIC by a DEFUSR call. The CALL 0A7FH gets the argument from BASIC and puts it into the HL register pair. The argument in this case is a pointer to a parameter block of the three arguments in 7 bytes (see figure 5). This pointer is transferred to the IX register.

The level parameter is put into the C register and the frequency count is put into HL. Next, the frequency count is tested for magnitude. If the H register is nonzero, the frequency count is greater than 255, and a low-frequency note is played.

If the frequency count is less than 256, the high-frequency segment is executed. The single byte of the frequency count is transferred to the B register. Also, the two bytes of the duration count are transferred to HL and decremented by one for the JR C loop. (C will decrement below 0 before the loop is terminated.) The DE register pair is loaded with −1 for a "tight" timing loop.

The output portion of the loop consists of two almost identical segments. Lines 350 through 400 are the "on" portion that turns on the "top" of the square wave. Lines 410 through 460 turn off the output. Both portions decrement the frequency count in a timing loop that determines the frequency. The voltage level for the "on" portion is determined by performing an XOR of binary 10 and the level parameter to produce either a 00 (low) or 01 (high).

After one complete cycle, the duration count in HL is decremented by an ADD HL,DE. If the result is not negative, another cycle is generated.

The code from line 510 through the end is a similar routine for low-frequency notes. In this case, the frequency count is held in HL and decremented twice. The frequency count is first made even by a RES 0 instruction for a test of decrementing down to zero. The duration count is assumed to be 254 or less and is held in B for a DJNZ instruction.

Using TONOUT with BASIC

TONOUT can be used to generate tones other than musical notes. The precise frequencies generated are:

$$1/((42.49 + 18.04 \times \text{count}) \times 10^{-6})$$

for high-frequency tones and:

$$1/((41.15 + 18.04 \times \text{count}) \times 10^{-6})$$

for low-frequency tones. These formulas are for the Model I. Use (37 + 15.79 × count) and (36 + 15.79 × count) for the Model III. The 18.04 (or 15.79) represents the on/off loop times; the other constants represent the "overhead" for the frequency and duration timing.

BASIC can easily be used to build up a table of values for matching frequency counts to musical notes.

NEW 256KB IBM PERSONAL COMPUTER MEMORY!

SINGLE BOARD 256KB IBM PERSONAL COMPUTER MEMORY

Designed Specifically for IBM's PERSONAL COMPUTER is Chrislin Industries newest CI-PCM Memory Module.

FEATURES INCLUDE:

- On-board parity generator checker
- Addressable as a contiguous block in 64K byte increments through 1 megabyte
- Access time of 225 NSEC
- Requires only one I/O expansion slot for 256K bytes memory
- Power requirements are +5V at 1.0A max.
- Cycle time of 400 NSEC

SEE YOUR LOCAL COMPUTER STORE FOR DETAILS OR CALL US.

DON'T ASK WHY WE CHARGE SO LITTLE, ASK WHY THEY CHARGE SO MUCH.



Chrislin Industries, Inc.

31352 Via Colinas • Westlake Village, CA 91362 • 213-991-2254
TWX 910-494-1253 (CHRISLIN WKVG)

Circle 84 on inquiry card.

Listing 2: *A BASIC program to generate frequency-delay values that, when input to the TONOUT routine, will reproduce tones in standard pitch. Results are shown in table 2.*

```
20 'PROGRAM TO FIND BEST FIT FOR 8 OCTAVES
40 DIM NT$(11)
60 A$="A A#B C C#D D#E F F#G G#"
80 FOR J=0 TO 11
100 NT$(J)=MID$(A$,J*2+1,2)
120 NEXT J
140 FOR I=0 TO 7
160 RESTORE
180 LPRINT "OCTAVE ";I+1
200 FOR J=0 TO 11
220 LPRINT NT$(J);"=";
240 N=(27.5*2↑I)*2↑((J)/12):LPRINTN;
260 CT=((1/N)-36.5E-6)/15.79E-6
280 LPRINT "F CNT=";CT
300 NEXT J
320 NEXT I
```

OCTAVE 1

A	= 27.5	F CNT = 2300.64
A#	= 29.1352	F CNT = 2171.39
B	= 30.8677	F CNT = 2049.39
C	= 32.7032	F CNT = 1934.23
C#	= 34.6478	F CNT = 1825.54
D	= 36.7081	F CNT = 1722.95
D#	= 38.8909	F CNT = 1626.12
E	= 41.2035	F CNT = 1534.73
F	= 43.6535	F CNT = 1448.46
F#	= 46.2493	F CNT = 1367.03
G	= 48.9994	F CNT = 1290.18
G#	= 51.9131	F CNT = 1217.64

Table 2: *Calculating counts for musical notes. A short BASIC program can match TONOUT frequency counts with standard pitch values. Here are the results.*

OCTAVE	MODEL I
1	2013,1900,1793,1692,1597,1508,1423,1343,1268,1196,1129,1065
2	1005,949,896,845,798,753,710,670,632,597,563,532
3	502,473,447,421,398,375,345,334,315,297,280,265
4	250,235,222,210,198,186,176,166,154,147,139,131
5	124,117,110,104,98,92,87,82,77,73,68,64
6	61,57,54,51,48,45,42,40,37,35,33,31

OCTAVE	MODEL III
1	2300,2171,2049,1934,1826,1723,1626,1535,1448,1367,1290,1218
2	1149,1085,1024,966,912,860,812,766,723,682,644,608
3	573,541,511,482,455,429,405,382,360,340,321,303
4	286,269,254,240,226,213,201,190,179,169,159,150
5	142,134,126,119,112,106,99,94,88,83,78,74
6	70,66,62,58,55,52,49,46,43,40,38,36

Table 3: *Frequency counts for standard pitch. Six octaves of note values are represented by the values in the table. Models I and III use slightly different values because of the difference in clock rates.*

If you don't know a baud from a floppy...

YOU NEED TO KNOW THE QDP-100 MICROCOMPUTER

It does more, does it easier, and costs a lot less.

Most people who need computers don't have the time, or desire, to become full-time computer "wizards."

With the budget-priced QDP-100 you get all the time-saving precision information you want from a computer, now and in the future, without all the unnecessary complexity associated with less considerate computers.

QDP-100 IS A FULL-SCALE 8-bit computer, readily upgradeable to 16 bits as your business or professional information-processing needs grow. It uses the IEEE S-100 bus, compatible with CP/M and MP/M disk operating systems.

QDP-100 HANDLES BOTH floppy disks and hard disks to give you total software versatility.

QDP-100 CONNECTS INSTANTLY to any standard terminal and printer. Both serial and parallel ports are available. Features most microcomputers can't match.

QDP-100 HAS SINGLE BOARD SIMPLICITY. Eliminates the hassle of complex multi-chip, multi-board computers.

QDP-100 IS EASY to learn and to operate. Most owners use their QDP-100 with professional skill and results in short order. Our instruction manual doesn't need an interpreter.

If you'd rather be a wizard with computer results, than with computers, choose the QDP-100. Call or write for literature and full details.

QDP NEEDS A FEW MORE GOOD DEALERS. Attractive, profitable, protected dealerships are still available in several high-potential computer market areas.

Quasar Data Products

10330 Brecksville Road
Cleveland, Ohio 44141
216/526-0838 Telex: 241596



CP/M and MP/M are registered trademarks of Digital Research Corp.

Circle 348 on inquiry card.

Listing 3: *The BASIC program to demonstrate tone generation with the Model I/III cassette port. The DATA statements contain the machine-language codes of the TONOUT subroutine.*

```
40 REM SAMPLE TONOUT DRIVER
50 DATA 205, 127, 10, 229, 221, 225, 221, 78, 4, 221
51 DATA 102, 3, 221, 110, 2, 124, 183, 32, 34, 69
52 DATA 221, 102, 1, 221, 110, 0, 43, 17, 255, 255
53 DATA 121, 238, 2, 211, 255, 120, 61, 32, 253, 121
54 DATA 62, 2, 211, 255, 120, 61, 32, 253, 25, 56
55 DATA 235, 24, 35, 229, 209, 203, 131, 221, 70, 0
56 DATA 121, 238, 2, 211, 255, 98, 107, 43, 43, 124
57 DATA 181, 32, 250, 121, 62, 2, 211, 255, 98, 107
58 DATA 43, 43, 124, 181, 32, 250, 16, 228, 201
60 FOR I=36864-65536 TO 36952-65536
62 READ A:POKE I,A
64 NEXT I
100 DEFUSR0=&H9000
110 INPUT D,F,L
120 POKE &HA001,INT(D/256):POKE &HA000,D-(INT(D/256))*256
130 POKE &HA003,INT(F/256):POKE &HA002,F-(INT(F/256))*256
140 POKE &HA004,L
150 A=USR0(&HA000)
160 GOTO 110
```




Figure 6: *Radio Shack's Experimenter Socket project board uses a matrix of holes into which component leads can be plugged. The holes are organized into 46 sets of five plus two buses.*

Listing 2 shows a Model III BASIC program for converting to standard pitch (A = 440 Hz). (The Model I version is identical except for the constants.) This scheme has 12 notes per octave: A, A# (A sharp), B, C, C#, D, D#, E, F, F#, G, and G#, each calculated by raising 2 to successive one-twelfth powers. The notes of each octave double in frequency over the preceding octave.

The first portion of output from the program of listing 2 is shown in table 2. Table 3 shows suggested integer counts for the notes for the Models I and III.

Listing 3 shows the TONOUT program incorporated into a BASIC program as DATA values. The DATA values are the machine-language bytes of TONOUT. TONOUT is relocatable and can be moved anywhere in RAM (random-access read/write memory). The program in listing 3 moves the bytes to 9000 hexadecimal by a series of POKEs. It then INPUTs a duration count, frequency count, and level value for experimentation.

Constructing the Electronics

All three projects in this article use a similar construction method. Radio Shack carries an Experimenter Socket project board, which is a matrix of 23 rows, each with two halves, as shown in figure 6. Each of the 46 row segments is connected electrically. Two buses run down the board on the extreme right and left.


Components can be plugged into the board with a minimum of fuss. The interconnections for the TONOUT electronics are shown in figure 7, along with the power supply, speaker, and cassette plug connections. Make the connections to the 5-pin DIN plug, as shown in figure 8.

To get precise frequencies for TONOUT, it's a good idea to disable the real-time clock interrupts in the Models I and III. If the real-time clock is running (and it may be, even without a display), the timing on tones may be off by 4 percent, and there may be some modulation on the tone. Add a disable interrupt (DI) instruction (243 decimal) at the beginning of TONOUT and an enable in-



MetaCard will turn your Apple II personal computer into tomorrow's high performance machine. It triples the memory of your Apple, and at the same time, greatly increases the processing speed with an Intel 8088 16-bit microprocessor. The future for your Apple is built into MetaCard.

Enough Memory to get the Job Done
MetaCard has up to 128K bytes of onboard memory with parity. Adding



MetaCard to your Apple's existing 64K bytes of memory gives you three times the capacity, and opens the door to applications never before possible on your system.


Faster Processing Speeds
Speed is just as important as memory. MetaCard is designed to handle all computing tasks at greatly increased speeds. The Intel 8088 operates at the full 5Mhz, running most applications at least 4 times faster than the Apple's 1Mhz 6502. And MetaCard gives you multiprocessing capabilities, allowing both the 8088 and 6502 to run simultaneously at full speed. Increased processing speeds, interprocessor interrupts and a real-time clock enable your Apple to perform like the machine you want.

Compatibility and Reliability
Compatibility has been designed into MetaCard. Metamorphic's processor card runs CP/M-86, which is included with the card at no extra cost. And Metamorphic offers UCSD Pascal 4.0 and the operating system for the IBM Personal Computer as options. Full parity checking, power-up diagnostics and a 48 hour burn-in will insure the reliable performance of your MetaCard.

Find Out More
Not everyone needs greater memory and speed. If you're one of those who does, MetaCard is for you. At an introductory price of $980 for the 64K configuration, it's not the least expensive addition you can make to your system, but high performance products never are. Call us today and find out what Metamorphic Systems has in mind for your Apple's future. Dealer inquiries welcome. Metamorphic Systems, Inc., P.O. Box 1541, Boulder, Colorado 80306, (303) 499-6502.

Intel 8088 is a product of Intel Corporation.
Apple II is a registered trademark of Apple Computer Inc.
CP/M-86 is a registered trademark of Digital Research Corp.
IBM Personal Computer is a registered trademark of IBM.
U.C.S.D. Pascal is a registered trade mark of the University of California.







$4/DAY
PER USER*
ALTOS
Built-In Dependability
ALTOS
PROVEN VALUE
QUALITY
RELIABILITY
DELIVERY
BRAND
COMPUTER · SYSTEMS
PRODUCED IN THE HEART OF SILICON VALLEY, CALIFORNIA U.S.A.

ANOTHER CRATE IDEA FROM ALTOS!


The complete multi-purpose, multi-terminal desktop business computer system with a built-in tutor.

Now you can get everything you need to computerize your business. An ALTOS® Series 5 computer (including 5 MByte Winchester hard disk that stores over 1,800 pages). Three of our new smart terminals and a quality printer. Plus the ALTOS COMPUTER TUTOR, the self-teaching business software package that provides simple, self-paced, step-by-step instructions and training.

All for less than $4/day per user. Virtually overnight, your operators will become faster and more accurate since an Altos system is like having three computers in one. For example, while your bookkeeper prepares payroll, other users can check inventory, compute cost estimates, or produce error-free reports. All at the same time.

An Altos system lets you communicate with other computers, mainframes and networks.

Need more? For less than another $1/day, each user can have Wordstar™ for word processing and Microplan™ for business analysis. Plus



you can choose from hundreds of other popular CP/M®, MP/M II™ and OASIS applications programs. There's also nationwide on-site service available from your dealer.

Join the thousands of businesses, professionals and institutions who already rely on Altos. Call our toll free number or write Altos Computer Systems, 2360 Bering Drive, San Jose, CA 95131 today. We'll put you in touch with your local Altos sales and service dealer who'll crate an Altos business computer system exclusively for you.

*Complete 3 user system for $4/day per user. Price approximate and may vary in your area. Daily lease based on $13,800 principal. 20% annual interest, five-year term. Packaged system includes Altos Series 5-5D computer with 5 MByte Winchester hard disk, draft quality printer, three Altos smart terminals, and the ALTOS COMPUTER TUTOR software package. Price does not include tax, installation, training and maintenance.

Packed with fresh ideas for business



800-538-7872
(In Calif. 800-662-6265)

Circle 23 on inquiry card.

Figure 7: *The TONOUT circuit is mounted on a project board. It uses three components. The 10-kΩ potentiometer can be adjusted for a comfortable volume.*

terrupt (EI) instruction (251 decimal) right before the 201 decimal for the RET; modify the POKE loop accordingly. The DI and EI were omitted from TONOUT to give the user some flexibility in using the project in different configurations.

A Telephone Dialer

Our second cassette-output project is a pulse-type telephone dialer (TELDIL). Most telephone lines, even those using tone dialing, will accept dialing by a series of break/make pulses, spaced at defined intervals—similar to those created by a rotary-dial telephone. See figure 9 for an illustration of pulse dialing.

The circuit for TELDIL is shown in figure 10. Put simply, the circuit opens and closes a relay to generate pulses, which are then transmitted to the telephone line through a special Data Access Arrangement (DAA) required by and available from the telephone company. The TELDIL






Figure 8: *Two wires are connected to the 5-pin DIN plug for the cassette port. Shielded wire is preferable, but any wire will suffice.*

IMAGINE IT..



CAPTURE IT




ACTUAL APPLE II PRINTOUT USING GRAPPLER™ AND EPSON MX100

The Grappler™ is the most intelligent Apple interface available. Simple commands from the keyboard or user program, are all you need to dump screen graphics to your printer. The Grappler's exclusive EPROM chip makes high resolution graphics that easy. There are Grappler versions to accommodate the Anadex, Epson Series,* IDS Paper Tigers, Centronics 739, NEC 8023, C. Itoh Pro-writer, Okidata 82A,* Malibu 200, and future graphic printers.

*Requires Graphics Upgrade.





The Grappler's features include:

- Graphics Screen Dump
- Inverse Graphics
- Emphasized Graphics
- Double Size Picture
- 90° Rotation
- Center Graphics
- Chart Recorder Mode
- Block Graphics
- Bell Control
- Skip-over-Perf
- Left and Right Margins
- Variable Line Length
- Text Screen Dump.

The Grappler™ works with Pascal and CPM.



3150 E. La Palma, Suite G, Anaheim, CA 92806
(800) 854 8275 TOLL FREE
(714) 630 3322 CA; AK; HI.




Figure 9: *Standard rotary dialing outputs a series of evenly spaced pulses to represent the digits 0 through 9.*




Figure 10: *The telephone-dialing circuit uses an operational amplifier to trigger a small relay. The relay opens and closes the telephone line through the Data Access Arrangement to simulate a rotary-dial pulse.*




Figure 11: *TELDIL breaks the circuit for 38.5 ms. Pulses are spaced at 100-ms intervals, representing 10 pulses per second. An interdigit delay of 830 ms separates the pulse trains for each digit.*




Figure 12: *BASIC passes a pointer to TELDIL. The pointer references a list of ASCII digits representing decimal values; the list is terminated by any non-ASCII value, e.g., binary 0.*

relay is driven by an LM3900 operational amplifier (op amp), which in turn is driven by the TRS-80's CASSOUT line.

Whenever the CASSOUT output level is greater than or less than 0 V, enough current flows through the 220-Ω resistor to turn on the LM3900, bringing the output on pin 5 to 0 V. This closes the relay and breaks the connection to the DAA. The diode (Radio Shack's 1N4000-series diode, catalog number 276-1102) across the relay coil is necessary to prevent high-voltage "spikes" from the inductive load of the relay coil from damaging the LM3900.

The software for TELDIL is also a relocatable assembly-language program that interfaces to BASIC (see listing 4). Although the version shown here uses a delay loop for the Model I, there is enough "leeway" in the constants to use the same code for the Model III as well. The "make/break" rate for digits is limited to 10 pulses per second for most telephone systems. The circuit is broken for about 38.5 milliseconds (ms) for each pulse, and then made for 61.5 ms, as shown in figure 11. Interdigit delay is about 830 ms. These delays can be adjusted for faster dialing on an experimental basis.

BASIC passes a pointer to TELDIL in the USR call. The pointer references a string of ASCII decimal digits, such as "17145551212." Any number of digits can be used. The last byte of the string is a non-ASCII digit, such as binary 0 (see figure 12).

TELDIL uses two loops. The outer loop from lines 250 through 480 picks up the ASCII digit from the string, tests it for valid ASCII decimal codes of 0 through 9, converts the digit into a stream of 1 through 10 pulses on the line, and increments the string pointer. It also delays 830 ms for the interdigit delay.

The inner loop at lines 330 through 430 pulses the line for each digit. The line is broken by outputting binary 01 to port 0FF hexadecimal and then delaying 38.5 ms. The line is then reconnected for 61.5 ms. The number of pulses is held in the B register, and the DJNZ repeats the loop for the number of pulses required.

BEAUTIFUL PROGRAMMING



WITH THE BRIDGE 3C™ COMPUTER.

Develop two programs for the time of one.

Sounds too good to be true? With the new BRIDGE 3C Compiler System you can easily do it! This new fully integrated BRIDGE system is designed for the professional who needs a powerful computer for software development. Our 3C System includes Pascal, C, and . . . a *completely structured* FORTRAN compiler package. What's more, you utilize the full 256 K of memory with *MEMDISK™* and overlay linker.

Check the capabilities it offers, and plan to make your work more pleasant and productive with the BRIDGE 3C.

UNIQUE SOFTWARE

- CPM 2.2 enhanced by Cache *BIOS™* performing disk buffering, and *MEMDISK,™* virtual disk, speeding operations 4 to 10 times.
- Operating utilities and diagnostics (all source code included).
- Interrupt driven console with type-ahead buffering.
- *BMATE™* screen oriented text editor/word processor.
- *R80™* RATFOR preprocessor, FORTRAN compiler, true overlay linker and symbolic debugger for fast structured application programming.
- Enhanced FORTRAN library, including. . .
  STRLIB™ string manipulations subroutines, system function calls, *EASYPAK™* math library including vector and matrix operations, and an extensive scientific library.
- *Pascal-Z™* generating efficient ROM-able and reentrant Z-code. Pascal package includes *SWAT™* symbolic debugger and overlay linker.
- C compiler generating assembly language source code.

INTEGRATED HARDWARE

InterSystems mainframe including . . .

- Powerful 1 Mbyte memory management system.
- 256 K of memory including parity check (expandable to 1 Mbyte).
- Two serial ports plus four parallel.
- Dual 8" double sided, double density floppy disc drives with DMA disk controller for fast data transfer.
- S-100 Bus follows IEEE 696 standards.
- Complete prioritized interrupt system.
- Choice of Zenith or Televideo terminal.

EXTENSIONS – OPTIONS

FPP – System calendar, 3 interval timers, one additional serial port, and a 9511 Floating point processor with complete software interface.

ROM – EPROM development package including programmer and dual port memory for emulating 2716's.

GRX – High resolution graphics package.


AD – Hardware and software drivers for 16 channels A-D converters (30kHz throughput) and 4 channels D-A converters.

MEM – Additional 256 K memory.


HD – Hard disk drive (30 Mbyte) with interface and all necessary software updates.

And what about support? BRIDGE offers monthly seminars (BRIDGE User Group) plus 90 day hardware warranty and software support, with optional 2-year extension.

If you need a truly professional computer, start thinking about the BRIDGE 3C Compiler System. For complete information and prices, call us at (617) 244-3203 or write today.



3C, MEMDISK, BMATE, R80, STRLIB and EASYPAK are trademarks of BRIDGE Computer Company, Division of Sea Data Corporation
Cache BIOS, SWAT and Pascal-Z are trademarks of Ithaca InterSystems, Inc.



ONE BRIDGE STREET NEWTON, MASS. 02158 U.S.A.

Circle 59 on Inquiry card.

Listing 4: *TELDIL is a Z80 subroutine to simulate a rotary telephone dialer.*

```
9000                           ORG     9000H
               ;********************************************************
               ;* TELEPHONE DIALER. DIALS ANY NUMBER OF DIGITS FOR     *
               ;* ROTARY-TYPE PHONE THROUGH CASSETTE PORT.             *
               ;*     ENTRY: HL=> STRING OF ASCII DECIMAL DIGITS, TERM- *
               ;*              INATED BY NON-ASCII                     *
               ;*     EXIT:   AFTER NUMBER HAS BEEN DIALED             *
               ;********************************************************
               ;
0604           PULSE   EQU     1540            ;38.5 MS PULSE
099C           WAIT1   EQU     2460            ;10 PULSES PER SECOND
7814           WAIT2   EQU     30740           ;830 MS INTERDIGIT
9000 CD7F0A    TELDIL  CALL    0A7FH           ;GET ARGUMENT IN HL
9003 E5                PUSH    HL              ;MOVE TO IX
9004 DDE1              POP     IX              ;IX POINTS TO STRING
9006 DD7E00    TEL005  LD      A,(IX)          ;GET NEXT DIGIT
9009 D630              SUB     30H             ;CONVERT TO BINARY
900B 2002              JR      NZ,TEL010       ;GO IF NOT 0
900D 3E0A              LD      A,10            ;0-USE 10 PULSES
900F 3828      TEL010  JR      C,TEL090        ;RTN IF LT 30H
9011 FE08              CP      11              ;TEST FOR GT 10
9013 3024              JR      NC,TEL090       ;RETURN IF GT 10
9015 47                LD      B,A             ;# OF PULSES IN B
9016 3E01      TEL020  LD      A,1             ;ON CODE
9018 D3FF              OUT     (0FFH),A        ;TURN ON RELAY
901A 210406            LD      HL,PULSE        ;DELAY CONSTANT
901D 0E00              LD      C,0             ;RETURN FLAG
901F 1819              JR      DELAY           ;DELAY
9021 3E02      TEL030  LD      A,2             ;OFF CODE
9023 D3FF              OUT     (0FFH),A        ;TURN OFF RELAY
9025 219C09            LD      HL,WAIT1        ;BETWEEN PULSE DELAY
9028 0E01              LD      C,1             ;RETURN FLAG
902A 180E              JR      DELAY           ;DELAY
902C 10E8      TEL040  DJNZ    TEL020          ;LOOP IF MORE PULSES
902E 211478            LD      HL,WAIT2        ;BETWEEN DIGITS DELAY
9031 0E02              LD      C,2             ;RETURN FLAG
9033 1805              JR      DELAY           ;DELAY
9035 DD23      TEL050  INC     IX              ;BUMP STRING POINTER
9037 18CD              JR      TEL005          ;LOOP FOR NEXT DIGIT
9039 C9        TEL090  RET                     ;RETURN TO BASIC
               ; DELAYS 24.81*CNT IN MICROSECS + OVERHEAD
903A 2B        DELAY   DEC     HL              ;DECREMENT DELAY COUNT
903B ED5F              LD      A,R             ;TIME WASTER
903D ED5F              LD      A,R             ;TIME WASTER
903F 7C                LD      A,H             ;TEST HL
9040 B5                OR      L
9041 20F7              JR      NZ,DELAY        ;LOOP IF NOT DONE
9043 CB49              BIT     1,C             ;TEST FOR RTN PNT 2
9045 20EE              JR      NZ,TEL050       ;GO IF RTN PNT 2
9047 CB41              BIT     0,C             ;TEST FOR RTN PNT 1
9049 20E1              JR      NZ,TEL040       ;GO IF RTN PNT 1
904B 18D4              JR      TEL030          ;RTN PNT 0
0000                   END
```

Listing 5: *A BASIC program to demonstrate telephone dialing via the TRS-80 cassette port. The DATA statements contain the machine-language codes of the TELDIL subroutine.*

```
40 REM SAMPLE TELDIL DRIVER
60 A=0:B=0:C=0:A$=""
80 DATA 205, 127, 10, 229, 221, 225, 221, 126, 0, 214
100 DATA 48, 32, 2, 62, 10, 56, 40, 254, 11, 48
120 DATA 36, 71, 62, 1, 211, 255, 33, 4, 6, 14
140 DATA 0, 24, 25, 62, 2, 211, 255, 33, 156, 9
160 DATA 14, 1, 24, 14, 16, 232, 33, 20, 120, 14
180 DATA 2, 24, 5, 221, 35, 24, 205, 201, 43, 237
200 DATA 95, 237, 95, 124, 181, 32, 247, 203, 73, 32
220 DATA 238, 203, 65, 32, 225, 24,212
240 CLEAR 500
260 DEFUSR0=&H9000
280 FOR I=36864-65536 TO 36940-65536
300 READ A:POKE I,A
320 NEXT I
340 INPUT A$: A$=A$+CHR$(0)
360 B=VARPTR(A$)
380 C=PEEK(B+1)+(PEEK(B+2))*256
400 A=USR0(C-65536)
420 GOTO 340
```

DELAY is a simple time-delay routine that delays 24.81 μs times the HL count. To keep the code relocatable, DELAY is not entered via an ordinary CALL, which would have a nonrelocatable address, but is called with a code for the three return points.

Listing 5 shows the machine-language code of TELDIL incorporated within a BASIC program. In this case, it is moved to 9000 hexadecimal, but it could be relocated to any convenient area in memory. The ASCII string is INPUT and a CHR$(0) is concatenated to the string for the terminating character.

VARPTR is used to find the string location. Make certain that VARPTR is used immediately before the USR call because string variables *move*. The "C-65536" adjusts for addresses in the upper 32K bytes of RAM; for a 32K- or 48K-byte system, this would normally be the area in which string variables would be located. String variables within a BASIC program line, however, have addresses that represent the location of the program line, and the argument in the USR call must be adjusted accordingly.

Constructing the TELDIL Circuit

TELDIL uses the project board discussed earlier (see TONOUT). The components are connected as shown in figure 13. Power-supply voltage should be more than 6 V; the relay shown will not work well with a 5-V supply. The cassette plug is connected as shown in figure 8.

A Serial Driver

Our third project using the cassette output is an RS-232C output port that can be used to drive a serial printer, modem, or other serial device. Standard rates of 300, 600, 1200, and 2400 bps can be selected with 10 bits per character.

RS-232C signals appear as shown in figure 14. A voltage level below −3 V represents a 1 bit; a voltage level above +3 V represents a 0 bit. Although the number of bits in a transmission varies, a common convention used with the TRS-80 is shown in figure 14.

As your business grows, grow with

NORTH STAR


Our new HORIZON computer lets you make beautiful music.

HORIZON® is our multi-user system that supports up to five simultaneous users at a cost per user that is the best in the industry.

With it, you can use up to five terminals performing word processing, accounting activities and information management—in perfect harmony.

Two packaged systems are available—the TSS/5, a 5Mb version and the TSS/18, an 18Mb version. Solo HORIZONs can expand to duets, trios, quartets or quintets with North Star's TSS/A Application System or North Star's TSS/C Multi-user CP/M®

When you purchase the HORIZON multi-user system, you receive worldwide service, support and the most widely used small business computer in the world. (There are some 30,000 HORIZONs conducting


business around the world.)

To find out how you can orchestrate your own kind of beautiful music, clip and mail this coupon, or call TOLL FREE 800-447-4700. (Illinois 800-322-4400.)

North Star Computers, Inc.
14440 Catalina St., San Leandro,
CA 94577 USA (415) 357-8500
TWX/Telex (910) 366-7001

Yes, I'd like more information on North Star's multi-user system performance.

NAME ____________________
COMPANY ____________________
ADDRESS ____________________
CITY ____________________
STATE ____________ ZIP ____________
PHONE ____________________



HEWLETT-PACKARD
HP-125
HP-85 CAPRICORN
HP-83 VIRGO

APPLE
APPLE III
APPLE II PLUS

XEROX
820

ATARI
800

NEW BEST WORD PROCESSING IN THE WORLD - WANGWRITER

Compumart is proud to announce the addition of Wangwriter to our product line. The finest word processor in the world. The Wangwriter is actually **four** products in one—a typewriter, a word processor, a CP/M personal computer, and an intelligent terminal. You'll find these outstanding features on the Wangwriter:

- Dual disk
- Up to 128K memory
- CP/M
- Advanced word processing
  —Math, merge, sort and auto pagination
- 75 pages of text on each 5¼" disk
- Supercalc
- Communications option
  —Connects to RS232 Interface
  —Or Wangnet.

It's no wonder that Wang, with 65% of the shared logic word processing market is the number one company in the field. When you think of word processing, think of the Wangwriter. You could free up to 20% of your secretary's time! And when you need a typewriter, CP/M computer, and an intelligent terminal, think of the Wangwriter too. Call Compumart today for configuration help.






Figure 13: *The TELDIL circuit is mounted on a project board. The relay leads can be trimmed, "built-up" with solder, and pushed into the project-board holes.*




Figure 14: *Logic is inverted in standard RS-232C signals. A 1 is represented by a negative voltage; a 0 by a positive voltage. Voltage levels from −3 to +3 V will not be recognized as legitimate values.*

WESTICO—The Software Express Service that really delivers:

SOFTWARE FOR PROFESSIONALS

The day is fast approaching when computers will be as commonplace as the office water cooler. The Westico software specialists offer a variety of programs to meet the needs of the professional looking for efficient solutions to a variety of tasks. In addition to quality software, you can count on the Westico experts for help and advice.

Here's just a sample of the more than 150 quality programs currently in stock:

MicroGANTT — Sophisticated project planning system which uses Critical Path Method analysis. Interactively defines tasks which comprise a project and displays a Gantt chart of the resulting plan. Budget costs and work hours are also calculated and displayed automatically. An entire project can be included in a more global project as a single task. All data is easy to modify and can be displayed or printed. **Available for IBM Personal Computer** and CP/M compatible computers. **$395/$25.**

PTA — Professional time accounting for billing based on time. Maintains client master files, work in progress files, employee history files and detailed job files. Produces detailed accounting reports for management. **$595/$40.**

MILESTONE™ — Critical Path Method project management. Displays and prints project plan in a summary cost/time table, by task or as Gantt charts. Project assumptions are easily revised to make "What if?" analyses. **$295/$30.**

STATPAK — Statistics software library in Microsoft BASIC. Performs probability calculations, one independent variable statistics, discrete distribution functions, continuous distribution functions, regression analysis, means testing, survey data/contingency tables, non-parametric statistics and analysis of variance. Includes plotting and file management modules. **$500/$40.**

LEGAL BILLING AND TIMEKEEPING — For law offices with up to 25 attorneys and a total of 35 timekeepers (including paralegals, secretaries, etc.). All time and expenses are distributed to client accounts or other designated overhead accounts. Produces monthly client review sheets and ready-to-mail itemized bills. **$895/$40.**

SUPERCALC™ — Makes it possible to manipulate numeric data quickly and easily. Spreadsheet simulator lets you examine and alter numbers and text within a grid that can cover up to 63 columns and 254 rows of data. Produces hardcopy reports. **$295/—.**

MINIMODEL™ — Financial planning tool. Does big financial planning jobs at micro prices for cash flow projections, financial forecasting, venture analysis, project planning and risk analysis. Models limited only by disk space. Report content and format totally under user control. **$495/$50.**

MICRO-TAX — Provides the tax practitioner or serious investor with an in-house computerized tax planning and preparation facility. Level 1 for individuals **$250,** level 2 includes state tax interface **$1000,** level 3 includes partnership forms **$750.**

TARGET™ Planner — Interactive modeling and planning program. Features include matrices up to 1000 elements and IF, THEN, ELSE, GREATER and LESSER conditionals. Commands for MINIMUM, MAXIMUM, AVERAGE and SUM. **$195/$25.**

TARGET Interchange — Enables TARGET Planner to read and write from and to other data bases. **$139/$15.**

TARGET Task — Integrates the procedures of Performance Evaluation and Review Technique (PERT) and Critical Path Method (CPM). Manipulates a project schedule to reach a desired completion date, or predetermined expense budget. **$329/$25.**

The Westico 24-Hour Computer Hotline (203) 853-0816 (300 baud) for detailed information and quick access ordering.



4 WAYS TO ORDER

- Write Westico, Inc., 25 Van Zant Street, Norwalk, CT 06855.
- Call (203) 853-6880.
- Telex 643-788.
- Dial-up our 24-hour computer (300 baud) (203) 853-0816.

For FREE catalog circle reader service number. More than 150 quality programs in stock.

- Westico has more than 150 programs for professionals and businesses that use a wide variety of microcomputers including: TRS-80 Model II, Apple, Vector Graphic, Cromemco, North Star, Micropolis, Ohio Scientific, Altos, Dynabyte, IBM, Intertec, Xerox, Zenith, Northern Telecom, AVL Eagle and more. We're working hard to be your software company.

COD, MasterCard and VISA accepted.

Prices do not include shipping and are subject to change. In CT add 7½% sales tax. All sales final.

Manual price may be credited toward purchase of software.

Dealer inquiries invited. **WES-45**



25 Van Zant Street • Norwalk, Connecticut 06855
(203) 853-6880 • Telex 643-788

Circle 480 on inquiry card.

Each byte to be transmitted occurs at *asynchronous*, or irregular, times. The line is normally at a 1 level. A start bit leads the output and signals the receiving device that data are coming in. Eight data bits follow, with the least significant bit first. A stop bit puts the line at the 1 level after transmission, in preparation for the next character.

The spacing for the 10 bits depends upon the transmission rate. Rates of 300, 600, 1200, and 2400 bps (bits per second) represent "bit times" of 3.333, 1.666, 0.833, and 0.416 ms, respectively.




Figure 15: *The SEROUT project uses an operational amplifier to generate a positive and negative voltage representing RS-232C data signals. Any convenient positive and negative voltage may be used.*

Listing 6: *SEROUT is a Z80 subroutine to perform RS-232C output through the Model I/III cassette port.*

```
9000            00100            ORG      9000H
                00110 ;*****************************************************
                00120 ;* SERIAL OUT THROUGH CASSETTE PORT.                 *
                00130 ;*     ENTRY:  H=BYTE TO BE TRANSMITTED              *
                00140 ;*             L=BAUD RATE: 300=201,600=100,1200=51, *
                00150 ;*                          2400=23 (MOD I)/ 230,115,*
                00160 ;*                          58,26 (MOD III)          *
                00170 ;*     EXIT:   AFTER OUTPUT                          *
                00180 ;*****************************************************
                00190 ;
9000 CD7F0A     00200 SEROUT  CALL     0A7FH           ;GET PARAMETERS
9003 54         00210         LD       D,H             ;MOVE DATA TO D
9004 2600       00220         LD       H,0             ;HL NOW HAS DELAY CNT
9006 E5         00230         PUSH     HL              ;TRANSFER CNT TO IY
9007 FDE1       00240         POP      IY
9009 3E02       00250         LD       A,2             ;START BIT
900B D3FF       00260         OUT      (0FFH),A        ;OUTPUT
900D FDE5       00270         PUSH     IY              ;DELAY CNT TO HL
900F E1         00280         POP      HL
9010 0E00       00290         LD       C,0             ;FLAG FOR RTN
9012 1820       00300         JR       DELAY           ;DELAY ONE BIT TIME
9014 0608       00310 SER040  LD       B,8             ;SETUP DATA BIT LOOP
9016 3E02       00320 SER050  LD       A,2               ;0 BIT TO A
9018 CB3A       00330         SRL      D                 ;SHIFT OUT DATA BIT
901A 3001       00340         JR       NC,SER055         ;GO IF DATA BIT=0
901C 3D         00350         DEC      A                 ;DATA BIT=1
901D D3FF       00360 SER055  OUT      (0FFH),A          ;OUTPUT
901F FDE5       00370         PUSH     IY                ;DELAY CNT TO HL
9021 E1         00380         POP      HL
9022 0E01       00390         LD       C,1               ;FLAG FOR RTN
9024 180E       00400         JR       DELAY             ;DELAY
9026 10EE       00410 SER060  DJNZ     SER050            ;LOOP IF MORE BITS
9028 3E01       00420         LD       A,1             ;STOP BIT
902A D3FF       00430         OUT      (0FFH),A        ;OUTPUT
902C FDE5       00440         PUSH     IY              ;DELAY CNT TO HL
902E E1         00450         POP      HL
902F 0E02       00460         LD       C,2             ;FLAG FOR RTN
9031 1801       00470         JR       DELAY           ;DELAY
9033 C9         00480 SER070  RET                      ;RETURN TO BASIC
                00490 ; DELAYS 14.6*CNT IN MICROSECS (MOD I)  + OVERHEAD
9034 2B         00500 DELAY   DEC      HL                ;DECREMENT DELAY COUNT
9035 7C         00510         LD       A,H               ;TEST HL
9036 B5         00520         OR       L
9037 20FB       00530         JR       NZ,DELAY          ;LOOP IF NOT DONE
9039 CB49       00540         BIT      1,C             ;TEST FOR RTN PNT 2
903B 20F6       00550         JR       NZ,SER070       ;GO IF RTN PNT 2
903D CB41       00560         BIT      0,C             ;TEST FOR RTN PNT 1
903F 20E5       00570         JR       NZ,SER060       ;GO IF RTN PNT 1
9041 18D1       00580         JR       SER040          ;RTN PNT 0
0000            00590         END
```

The chief problem now is to convert the low voltage levels of CASSOUT into the two RS-232C voltages. This is done with an LM741 comparator, as shown in figure 15. The supply voltages used with the comparator are +6 to +12 V and −6 to −12 V. Batteries will work fine, and the voltages are not critical.

The voltage-divider input to the plus ("+") input of the LM741 is biased at about (220/15000) × V+, where V+ is the positive supply voltage. This puts the plus input at about 1/10 V for a +6-V supply, or about 1/20 V for a +12-V. The output of the 741 will be −6 to −12 (1 level) whenever CASSOUT is greater than the plus input level, and +6 to +12 V (0 level) whenever CASSOUT is less than the plus input level.

BASIC initializes the port controlling CASSOUT to binary 00 (0.44 V), and so the TD (transmit data) line at reset is normally −6 to −12 V. By toggling the CASSOUT line at the appropriate rate, you can generate the RS-232C signals.

SEROUT (see listing 6) is a relocatable assembly-language program called from BASIC by a USR call. Two parameters are passed: the byte to be transmitted and the transmission rate to be used. The byte can be any value from 0 through 255. If seven data bits are to be transmitted (as in data-communications applications), make the eighth bit 0.

SEROUT first picks up the transmission-rate code and puts it into the HL register pair. The code is a delay count for the DELAY subroutine. The byte to be transmitted is moved to the D register.

Line 260 turns on CASSOUT to generate a start bit. A delay of one bit time is then done. The loop from lines 320 through 410 outputs the eight data bits, from least significant to most significant. A 1 bit is generated by sending a 01 to port 0FF hexadecimal, and a 0 bit is generated by sending a 10. A duration of one bit time is used for each bit.

A stop bit is generated in line 430 after the eight data bits. This leaves the TD line at the 1 level in prepara-

tion for the next start bit.

The DELAY subroutine is called by relative jumps with a return flag to keep the code relocatable.

Listing 7 shows a sample BASIC driver that contains the machine code for SEROUT as DATA statements. The code is relocated to start at 9000 hexadecimal. For demonstration, an ASCII 0 is continually output at a user-specified rate.

The actual BASIC code to be used depends a great deal upon the application. If you are using SEROUT

Listing 7: *A sample BASIC driver for the SEROUT subroutine. The DATA statements contain machine-language codes for the subroutine. This program outputs a continuous stream of ASCII zeros.*

```
100 REM SAMPLE SEROUT DRIVER
110 DATA 205, 127, 10, 84, 38, 0, 229, 253, 225, 62
120 DATA 2, 211, 255, 253, 229, 225, 14, 0, 24, 32
130 DATA 6, 8, 62, 2, 203, 58, 48, 1, 61, 211
140 DATA 255, 253, 229, 225, 14, 1, 24, 14, 16, 238
150 DATA 62, 1, 211, 255, 253, 229, 225, 14, 2, 24
160 DATA 1, 201, 43, 124, 181, 32, 251, 203, 73, 32
170 DATA 246, 203, 65, 32, 229, 24, 209
180 FOR I=36864 TO 36930
190 READ A:POKE I-65536,A
200 NEXT I
210 DEFUSR0=&H9000
220 INPUT "RATE?";RT
230 CH=48
240 B=USR0(CH*256+RT)
250 GOTO 240
```

Figure 16: *The SEROUT circuit is mounted on a project board. Two sets of power-supply connections are required.*




Figure 17: *I connected an NEC Spinwriter to the SEROUT circuit with two wires and some "jumper" interconnections on the Spinwriter side. Other RS-232C devices will require similar connections.*

as a printer driver, you'll have to make certain that the printer can accept characters at the rate you'll be transmitting. This is usually not a problem except on carriage return/line feeds where the print mechanism is busy for relatively long times as the carriage returns. If a character is output during this busy condition, it may be disregarded and lost.

The bit-delay times shown are values obtained by trial and error with the real-time clock active. You may have to adjust these on an experimental basis, depending upon your system. Output a line of characters continuously at different bit rates. Find the high and low values at which you start to lose characters and choose a midpoint value for your standard bit rate. For high bit rates, turn off the interrupts using DI and EI as described in TONOUT.

Constructing the Electronics

Figure 16 shows the project-board layout for SEROUT. Two sets of power-supply leads connect to the positive and negative supplies. The TD line and ground connect to the serial device.

The serial device may require other signals to be tied high to simulate a "ready" condition. Again, this depends upon the device and can't be detailed here. A typical connection to an NEC Spinwriter is shown in figure 17.

The projects presented here show what can be done with the cassette output port on a lowly 16K-byte TRS-80 Model I without an expansion interface. I'll cover transmission in the opposite direction—CASSIN—in another article. Perhaps by then the breeder reactor program will be working for CASSOUT. Hmmm . . . I keep getting these "Coolant Temperature Critical" indications. . . . ■



Green phosphor screen
High resolution (720h x 350v)
Combination monochrome adapter
and parallel printer interface
Upper/lower case
80 characters x 25 lines
16 colors
256 characters in text
2 graphics modes
Simultaneous graphics
and text capability
2¼″ integrated speaker
RS232C interface
Up to 9600 bits per second
6′ cord to system unit
Microprocessor-
controlled keyboard
Tactile feedback
10 function keys
10-key numeric pad
For the IBM Personal Computer dealer nearest you, call (800) 447-4700. In Illinois, (800) 322-4400. In Alaska or Hawaii, (800) 447-0890.


System expansion slots
2 optional internal diskette drives
8088 microprocessor
Parity checking
40KB in ROM
160KB per 5¼″ diskette
DOS
User memory expandable up to 256KB
Because we put what you want into it, you get what you want out of it.
We unwrapped our package for you, bit by bit.
It's all here. And you're looking at it.
From the 8088 microprocessor and the Macro Assembler that give you speed and capacity to the RS232C interface that gives you the world.
All told, no other personal computer offers as many advanced capabilities. Read all about them in the Technical Reference Manual available at your IBM Personal Computer dealer.
Software? IBM Personal Computer DOS. The UCSD p-System. Plus a documented set of our device driver routines. For high level languages, exactly what you want. Enhanced BASIC in ROM. Pascal. FORTRAN. But our software story is still being written.
Maybe by you.
If you're interested, start by writing to: IBM Personal Computer Software, Dept. 765, IBM Corporation, Armonk, New York 10504.
IBM®
The IBM Personal Computer
Circle 200 on inquiry card.

The Input/Output Primer

Part 3: The Parallel and HPIB (IEEE-488) Interfaces

An introduction to two common interfaces between computers and other devices.

Steve Leibson
Auto-Trol Technology Corporation
12500 North Washington St.
POB 33815
Denver, CO 80233

This article is the third in Steve Leibson's six-part series, The Input/Output Primer. *The series describes problems involved in communications between computers and the outside world and explains how some of these problems have been solved. The three remaining articles will discuss BCD and serial interfaces; character codes; and interrupts, buffers, grounds, and signal degradation. "An I/O Glossary," which defines many terms used in these articles, appeared with the series' first installment (February 1982* BYTE, *page 122).*

Last month, in addition to describing interrupts and DMA (direct memory access), I presented general information about interfaces. In this article, I'll examine two specific types of hardware interfaces: the parallel and the HPIB or GPIB (IEEE-488) interfaces (see Robert Katz's review of the Hewlett-Packard Interface Loop, page 76).

First, however, let's briefly review why these interfaces are necessary. As information-processing machines, computers require paths for raw data to enter and for processed information to exit. A common computer-design technique is to create one universal path leading both into and out of the processor. That path is the I/O (input/output) bus.

Data inversion occurs in software, not in the interface.

This concept simplifies computer design but introduces a complication: whatever the design of the I/O bus, the computer will be incompatible with many I/O devices. Some older devices use different signal levels; other devices have different data formats. Most devices will be slow enough to degrade the computer's performance seriously if it must wait on every data transaction.

The complication is solved through the use of interfaces, which act as transformers of voltage levels, data formats, and transaction speeds. Interfaces enable the computer to communicate with a vast array of peripheral devices.

The Parallel Interface

Simple peripherals often have interface requirements much like those of the computer's I/O bus. Data is transferred over a set of data lines (usually 8); a signal line indicates when the next chunk of information is ready. On a second signal line, the peripheral indicates its readiness to accept another piece of data.

This type of interface is a *parallel interface*, so named because the data lines are parallel, and multiple bits of data are simultaneously transferred in parallel. The HP 98032A is a parallel interface designed for Hewlett-Packard's 9800-series computers. The I/O bus described in earlier installments of this primer was taken from the 9800 computer. I'll use the 98032A 16-bit interface as an example of parallel interfacing.

Keep in mind that the I/O bus has 16 bidirectional data lines. Data is handled in 16-bit chunks and flows



THE FORMULA™ allows the computer professional to focus on the most important part of business: the needs of the client. Customized systems for any business application can be created in a fraction of the time required by conventional methods.

- Interactive data entry, file updating, and maintenance routines are automatically generated from a definition of the fields.
- Reports can be created through a unique full screen editor simply by typing a sample format.
- Menus and job streams are defined through a preprogrammed parameter-driven procedure.
- Fast response time is insured because each routine can be interpreted directly by the computer and data management is controlled by an efficient ISAM algorithm.

THE FORMULA™ is a complete system language which brings the process of developing applications closer to the user's description of his needs. That's **THE FORMULA™** for success.

Disk and manual, $595. Manual only, $60.

THE FORMULA™ will run on any 8080 or Z80 computer with CP/M,* 48K RAM, 300K total disk storage, and a CRT.

DMA • WE SPEAK YOUR LANGUAGE.

THE FORMULA™ For Success can help you build systems. Now, the General Accounting System, created with **THE FORMULA**,™ is available at no extra charge.



The General Accounting System includes:

- General Ledger: Journals, Trial Balance, Income Statement, Balance Sheet, etc.
- Accounts Payable: A/P Journals, Checks, Aged Payables, Vendor Report, etc.
- Accounts Receivable: A/R Journals, Aged Receivables, Customer Statements, Customer Activity Report, etc.

In addition, two new optional packages have been developed for use with **THE FORMULA™**:

Professional Time Management **$80**

Manager's Billing Report, Employee Production Report, Client Invoices, etc.

Label Option Pak **$80**


Name Inversion, Multiple Up Labels, Customized Label Size and Format, etc.

Circle 150 on inquiry card.

DYNAMIC MICROPROCESSOR ASSOCIATES • 545 Fifth Avenue, New York, New York 10017 • (212) 687-7115

We ship prepaid and COD orders. Shipping & handling charges extra: $5 UPS areas; $7 non-UPS areas, Mexico, Canada; $10+ elsewhere. MasterCharge and VISA accepted.

New York State residents add appropriate sales tax. *CP/M is a trademark of Digital Research.






Figure 6: *Block diagram of the Hewlett-Packard 98032 parallel interface. The parallel interface consists of registers and buffers. One register is for output, the other for input. The 32 unidirectional lines can be used as one set of bidirectional lines. If a peripheral has a bidirectional interface, these two sets of lines can be connected to form a bidirectional peripheral bus. Control circuitry in the interface accepts information from the computer and then sends the information to the peripheral. The same control circuitry can also, at the request of the computer, request information from the peripheral, then signal the computer when the information has been acquired.*

over these lines either into or out of the computer, but not in both directions at the same time.

The 98032A interface splits the I/O bus into two sets of data lines: 16 output lines and 16 input lines (see figure 6). This configuration is more compatible with unidirectional peripherals. Excess lines are left unconnected. Out of 32 data lines, only 8 might be used by a unidirectional, 8-bit peripheral.


As mentioned above, interfaces sometimes serve to transform the signal voltage levels used on an I/O bus to those required by a peripheral. Our sample I/O bus uses TTL (transistor-transistor logic) levels, meaning that a low logic level is represented by a voltage between 0 and +0.7 volts (V). A high logic level is represented by a voltage between +2.0 and +5.5 V. The input lines of the 98032A parallel interface connect to TTL circuitry in the interface, so TTL levels are required from the peripheral. The data output lines of the 98032A are driven by transistor circuits that can withstand +30 V for a high level. The low level is still between 0 and +0.7 V for TTL compatibility.

Remember that when discussing logic signal lines, only two signal levels are allowed. One level corresponds to a logic 1 and the other to a logic 0. If the higher voltage corresponds to a logic 1 and the lower level to a logic 0, the signals are said to be *positive-true*. If the lower voltage level corresponds to a logic 1 and the higher voltage to logic 0, the signal is called *negative-true*.

To sum up:

1. I/O bus lines are the conductors used to transfer data between the computer and the interface.
2. Interface input and output lines are the conductors used to transfer data between the interface and the peripheral.

IBM'S DOS or CP/M-86?™



Confused about operating system options for your IBM Personal Computer? **HAVE IT BOTH WAYS WITH LIFEBOAT'S CP/EMULATOR™.** CP/EMULATOR solves the problem by permitting you to use all the software written for IBM's PC for both DOS and CP/M-86.

This high performance, low cost DOS utility allows you to fully integrate and mix programs. You can use a DOS editor to write a program, compile it under a CP/M-86 compiler and execute the finished application under DOS.

CP/EMULATOR extends the scope and capacity of all of your software. With CP/EMULATOR, CP/M-86 programs run quicker with faster file access than with CP/M-86 itself.

Additionally, your program will enjoy all the other DOS advantages, such as large file size, dated directory displays, and more. The DOS peripherals are already installed and DOS commands are fully available. The package even contains a utility program to transfer programs and data files from a CP/M-86 diskette to a standard DOS diskette.

NO NEED TO LEARN A NEW SET OF UTILITIES AND COMMANDS;

NO NEED TO END UP WITH TWO INCOMPATIBLE SETS OF DISKETTES;

NO NEED TO SPEND HUNDREDS OF DOLLARS ON CP/M-86, WHEN CP/EMULATOR COSTS $75.

NO NEED TO WONDER WHICH OPTION IS BEST FOR YOUR IBM PERSONAL COMPUTER.



PMATE™: Editor-in-Chief

Perform miracles of manipulation on your keyboard with Lifeboat's PMATE.

This new generation text editor is the most sophisticated text editor available today and is bristling with features previously unavailable on microcomputers, making it ideal for virtually any program or data file editing.

PMATE's command set includes full screen single keystroke editing, horizontal scrolling, automatic disk buffering, macro command language, text formatting, expression evaluation, conditional branching, I/O with prompting, and other programming language constructs. PMATE makes use of 11 buffers for storage, and includes commands permitting work on more than one text at a time. Unique to PMATE is the facility for user customization. Keystroke functions can be redefined, and sequences can be programmed to directly execute macros. Video commands can be changed, and macro functions can be written, to emulate any other editor with which you may be familiar. PMATE provides full side-scrolling, and can be used with virtually ANY video terminal on the market. IF you use an editor, you need PMATE.

PMATE is the **only** text editor you'll ever need.

PMATE-86 is available for IBM's Personal Computer DOS, SB-86™ and MS-DOS™. Also available is PMATE for SB-80 and other CP/M-80-compatible operating systems.

Lifeboat Worldwide offers you the world's largest library of software from its offices in the U.S.A., U.K., Switzerland, France, West Germany and Japan.


For more information, send to:

Lifeboat Associates
1651 Third Avenue
New York, New York 10028
Tel: (212) 860-0300
TWX: 710-581-2524 (LBSOFT NYK)
Telex: 640693 (LBSOFT NYK)

2101



LIFEBOAT HAS THE ANSWER



(1a) Input Registers

Register Code	Function
R4	Data Input
R5	Interface Status
R6	High Byte Data Input
R7	(Not Used)

(1b) Output Registers

Register Code	Function
R4	Data Output
R5	Interface Control
R6	High Byte Data Output
R7	Data Transfer Trigger

Table 1: *Interface definitions for the 98032A parallel interface. Table 1a defines the input registers, and table 1b defines the output registers.*

Register Architecture

I stated earlier that each interface would have a unique address on the I/O bus and would be selected by the peripheral address line on that bus. Each interface is divided into registers that are individually addressable by means of a register code. The register model divides the interface into eight different registers. Four of these are output registers that take data from the computer (the computer *outputs* to them). The other four are input registers, supplying data to the computer (the computer gets *input* from them).

Let's now assign a function to each of these interface registers. The 98032A interface uses the definitions shown in tables 1a and 1b.

R4 registers are the primary means of data transfer between the computer and the interface, and in turn, the peripheral. The R4 output data register is directly connected to the output signal lines of the 98032A. The R4 data input register is connected to the interface input lines. The R6 input and R6 output registers allow the 98032A to be used as two 8-bit interfaces instead of one 16-bit interface. The R6 registers read or control the upper eight data lines when the interface is in the byte mode, that is, when the interface is handling data in 8-bit

Invest in Your Children's Future
Send Them to COMPUTER CAMP

Computer Camp makes learning fun! Your children will spend three hours per day zooming through basic BASIC, sailing through PASCAL, or tinkering with ROBOTICS in our electronics lab.

Following formal instruction, your youngsters will have the opportunity to spend up to three hours of "free-time" on the computers. For the advanced computer camper we offer assembly language, Advanced Electronics and Artificial Intelligence.

FACTS

- **Who attends:**
  Girls and Boys, 7-16 years.
- **Program:**
  Learn to program in BASIC, PASCAL and other languages. Complete Electronics Lab, Artificial Intelligence, ROBOTICS, Graphics, and a complete recreational program.
- **Locations:**
  Santa Barbara, CA; Lake Tahoe, CA; Cape Cod, MA; London, England.
- **Price:**
  $795 per child, per session.
- **Dates:**
  Two-week sessions beginning June 13 and ending August 20, 1982.

There is a complete recreational program that compliments the academic schedule...swimming, tennis, sailing, fishing, hiking, field sports, group activities, day and overnight pack trips, and more.

At Computer Camp, we have been teaching children how to program microcomputers for several years now and we would like to use this experience to help your children grow mentally and physically.

Give your children a fun-packed summer they'll always remember. Invest in their future by making a reservation at COMPUTER CAMP, now.

DEALERS

Computer Camp application and information "packets" are available at your local computer dealer. (Dealer inquiries are invited.)

SOFTWARE

Computer Camp, Inc. has a wide variety of educational software available for sale. We will also market your software. Call today for more details.

ADULTS

Now there is a computer training program designed especially for adults. Learn while having fun! Call Computer Camp for complete details.

We're the original Computer Camp as featured on **The Today Show** on NBC, in the **Wall Street Journal** and the **Los Angeles Times.**

Computer Camp Cape Cod

California Computer Camp



COMPUTER CAMP, INC.

805•969-7871 800•235-6965

1235 Coast Village Road, Suite G, Santa Barbara, California 93108

IASSC

R5 Input Register (Interface Status)

Bit #:	7	6	5	4	3	2	1	0
Bit Name:	INT	DMA	1	0	IID	IOD	STI1	STI0

Table 2a: *R5 input register. This register contains interface and peripheral status information.*

R5 Output Register (Interface Control)

Bit #:	7	6	5	4	3	2	1	0
Bit Name:	INT	DMA	RESET	AHS	X	X	CTL1	CTL0

Table 2b: *R5 output register. This register is used to control the interface and peripheral devices.*

units instead of 16-bit units.

When the computer places data in the R4 output register, the pattern of that data appears on the output signal lines. However, when the computer reads the R4 input register, the data reflects only the contents of the R4 input register; it may not reflect the current state of the interface input lines. (To clarify this difference, I'll look closely at how the interface communicates with a peripheral. First, however, I'll finish discussing the remaining registers.)

Control and Status Registers

The computer uses the R5 input and R5 output registers to control the interface and to read the interface and peripheral status. The R5 input register contains several pieces of important status information. Only the lower 8 bits of this register are used. The meanings of these 8 bits are listed in table 2a.

The INT and DMA bits are used for interrupts and direct memory access, both of which were discussed last month. Bits 5 and 4 are interface identification bits. The 10 pattern (bit 5 set to 1, bit 4 set to 0) identifies the 98032A interface as a type 2 interface (10 is 2 in binary). Software in the computer uses the interface ID bits (bits 3 and 2) to decide how to communicate with the interface. The proper *software driver* must be selected to operate the interface. Other types of interfaces have different ID patterns and call for different drivers.

Computer software can also use the IID and IOD bits. IID stands for *invert input data;* IOD stands for *invert output data.* These bits allow the computer to interface with peripherals using either positive-true or negative-true signals. The IID and IOD bits are set with jumper wires in the 98032A interface.


It's important to note that data in-

Circle 89 on inquiry card.

Circle 37 on inquiry card. →

ALPHANUMERIC or GRAPHIC?

If high resolution required, install BMC color/green monitor in your system.



BM-1401RGB



BM-12A

RGB Interface Board for Apple-II is available now.

BM-12A
12" Green P4 Phosphor CRT
Composite Video Signal
80 Char. × 24 Lines

BM-1400CLU
13" Composite Video Signal
40 Char. × 25 Lines

BM-1401RGB
13" RGB Separate Video Signal
5 × 7 Dots, 40 Char. × 25 Lines

BM-1402RGB
13" RGB Separate Video Signal
5 × 7 Dots, 80 Char. × 25 Lines



BMC USA, INC.

LOS ANGELES
20610 Manhattan Place Suite 112, Torrance, CA. 90501
Telex: 698641 BMC USA TRNC Phone: 213-320-9880, 9881

NEW YORK OFFICE
450 Barell Avenue, Carlstadt, N.J. 07072
Telex: 133221 BMC NY CARL Phone: 201-939-7079, 7061




Figure 7: *Representation of the handshake between the HP 98032 parallel interface and a peripheral device. When the computer requests a transaction, the interface uses the FLG line on the I/O bus to signal the computer that it's busy. Then, the PCTL (peripheral control) line is set to request an operation by the peripheral. Later, the peripheral acknowledges the request by setting the PFLG (peripheral flag) line to busy. When the peripheral completes the transaction, it sets the PFLG line to ready, causing the interface to lower the I/O bus flag line and thereby tell the computer that the transaction is complete. This sequence governs both input and output. Direction lines between the computer, the interface, and the peripheral determine the direction of the transaction.*

version occurs in software, not in the interface. The computer may choose to ignore these status bits for certain classes of I/O operations. Other interfaces may implement data inversion in hardware so that, if selected, the inversion will always occur.

The two remaining bits in the interface status register, STI1 and STI0, are status inputs brought out on two signal lines. The peripheral can call on these for any user-defined function. Unlike the R4 input register, the STI1 and STI0 bits reflect the current state of the STI signal lines.

Interface control is through the R5 output register. Table 2b lists the bit pattern for this register. The INT and DMA bits are used in the interrupt and direct memory access modes mentioned earlier. The RESET bit is used to place the interface in the initial power-up state. It can also be used to reset the attached peripheral to a known state if the peripheral has a reset input. I/O processes often stall, for example, when the printer runs out of paper or a disk drive door is left open. A reset capability allows the computer to change its mind and stop what it has started.

The AHS bit enables auto-handshake. When this bit is set, the data-transfer trigger (R7 output) isn't needed. This characteristic is convenient for high-speed transactions and is habitually used with DMA. Bits 3 and 2 are unused in the R5 output register.

CTL1 and CTL0 are general-purpose control bits. These register bits are connected to two signal output lines and can be used to control the attached peripheral device. A signal over these output lines can be given to latch a printer door shut while printing is taking place.

Peripheral Handshaking

Note that the R7 output register is called the *data-transfer trigger*. When used in conjunction with the R4 input and output registers, the data-transfer trigger forms a handshake mechanism that synchronizes the fast computer and the slower peripheral.

Placing data on the output lines or reading the levels on the input lines connecting the interface to a peripheral device isn't sufficient for smooth data flow. A set of signals indicating "new data available" and "ready to accept data" is needed.

These signal lines are called *handshake* lines. The interface and the peripheral each control a handshake line. The meaning of the signal for each line depends on the direction of data flow. If the computer is sending through the interface to the peripheral, the line controlled by the computer means "new data available." The line controlled by the peripheral would then signify "ready for new data." If the data flow is reversed, the signal meanings are also reversed.

Let's call the line controlled by the interface the *peripheral control* (PCTL) and the line controlled by the peripheral the *peripheral flag* (PFLG). With the addition of these two lines, the foundation is laid for discussing the handshake mechanism.

Data Output

Output is simpler than input. As has been mentioned, the computer can set the state of the interface output lines by placing information in the R4 output register. The handshake is started when the computer performs a write to the interface's R7 output register.

The interface recognizes the data-transfer trigger and responds by changing the state of PCTL from "clear" to "set," which indicates to the peripheral that "new data is ready" on the interface's output lines. The peripheral is expected to acquire the data now. The peripheral responds to "new data ready" by changing PFLG from the "ready" to "busy" state. This means the peripheral is busy accepting the data.

From the time the computer performs the R7 output register write until the time the peripheral returns to a "ready" state after processing the data, the interface is busy carrying out the transfer. It's extremely important that the computer not change the R4 output register during this time. Otherwise, there's no way to tell what data the peripheral will get. For this reason, the interface and the computer also have a handshake mechanism. While the interface is busy sending the information to the peripheral, the interface indicates this situation to the computer on the interface flag line. Figure 7 illustrates the peripheral-interface handshake.

Data Input

Data input from a peripheral is more complex. Three steps are involved. First, the computer reads the R4 input register to let the interface know that a data-input operation is pending. (The computer throws away the data obtained.) The interface recognizes this and indicates the situation to the peripheral with a data-direction line (this line tells the peripheral which direction the data is to go).

Next, the computer writes to R7 output, giving the data-transfer trigger. This causes the interface to go busy and to place the PCTL signal line in the "set" state, signifying to the peripheral that data is requested. The peripheral then goes busy until it has acquired the data. It signals its busy state on the PFLG line.

After the peripheral performs the operations necessary to get the requested data, it places the data on the interface input lines and returns PFLG to the ready state. When the peripheral returns to the ready state, the transition of the PFLG signal from "busy" to "ready" causes the data on the input lines to be placed or "latched" into the R4 input register. This causes the interface to signal the computer that the interface is now ready with the requested data. The computer then performs another read from the R4 input register to get the data.

Note that the R4 input register contains the information present on the input lines at the busy-to-ready transition of the PFLG line. Any changes on the input lines after that transition will not be reflected in the R4 input register. Notice also that the peripheral-interface handshake for input is the same as that for output.

Some peripherals, by the way, are so simple that they can't perform a handshake. An example of this would occur if the 98032A were used to drive signal lights directly. Lights have no handshake lines. They always follow their data (power) inputs. In these instances, you can connect the PFLG and PCTL lines to each other so that the 98032A handshakes with itself. This results in 16 "latched" output lines and 16 input lines that

may be read on demand.

Most peripherals using the parallel interface use only 8 bits. This allows 256 combinations (2^8) on the data lines. If these combinations are treated as codes representing characters, then 8 bits can represent numerals, upper and lower case letters, punctuation marks, and other printable characters. Most peripherals communicate this way, but there are exceptions. A floppy-disk drive may require the full 16-bit interface. Some plotters use 12 bits. Analog-to-digital converters come in 10-, 12- or 16-bit sizes. A single 16-bit interface can serve all these kinds of peripherals.

The IEEE-488 Standard Interface

Computer designers strive to incorporate the latest parts and the fastest logic in new and different configurations. In addition, designers of computer peripherals are always creating new classes of devices. The result has been a multitude of interfaces, each optimized for a single kind of computer or peripheral. Few of these interfaces are compatible with any of the others.

This situation is similar to that of the American railroads during the early 1800s. Because dozens of track gauges existed, cars of one railroad couldn't travel on the tracks of another. Reminiscent of the speed with which railroads standardized track gauges, the computer industry quickly agreed on an interfacing standard, published in 1975 by the Institute of Electrical and Electronics Engineers (IEEE). It was the first comprehensive, nearly universal interfacing standard for computers and instrumentation. The first version, IEEE Standard Digital Interface for Programmable Instrumentation (IEEE-STD-488-1975) was slightly revised in 1978 and is now IEEE-STD-488-1978.

This standard defines a general-purpose interface, one designed for instrumentation systems requiring limited-distance communications. The intent of IEEE-STD-488-1978 (hereafter, "IEEE-488") is to pin down as many variables of an interface as possible while still maintaining good flexibility and wide applicability. The interface is also defined without reference to the hardware circuitry required to implement the interface. This allows new products to take advantage of new technologies, resulting in faster and less expensive construction of instruments, peripherals, and systems.

The HP 98032A parallel interface has two separate groups of data lines: 16 for input and 16 for output. This allows interfacing to a wide variety of peripherals with varied interfaces. Devices with 8, 10, 12, or 16 data lines can be accommodated. A popular version of the 98032A has a cable with no connector attached. The system builder must select a connector and assign the pin numbering since there are no standards as to how to connect this type of interface.

By contrast, the IEEE-488 standard precisely specifies signal levels (both voltage and current) and signal timings. Building a system can be as simple as removing components from their boxes and plugging them in. Interconnection hardware is defined so that two interconnected instru-

ments can communicate. Their understanding each other, however, is *not* guaranteed by the standard.

Using the IEEE-488 standard is like using the international telephone system. You can call anywhere on earth because a compatible communications network, the telephone system, exists. Sounds you make can reach the other end of the connection, and you can hear the sounds made by the person at that other end. The hardware for communications is all in place, but there's no guarantee that you'll understand what the other person is saying or vice versa. Hardware compatability does not guarantee language compatibility.

Hewlett-Packard has an implementation of the IEEE-488 standard which it calls the HPIB or Hewlett-Packard Instrumentation Bus. HPIB is a combination of the hardware interface specified by the IEEE-488 standard and a communications technique that makes it possible for instruments to communicate with each other. The standardization also allows the system designer to communicate what's going on in the system.

The IEEE-488 standard is so general that almost any peripheral or instrument can be purchased in an HPIB version. Voltmeters, power supplies, signal generators, printers, plotters, and disk drives are only a few of the devices available. All may be connected on the same bus.

Unlike the parallel interface, which connects a single device with the computer, the HPIB interface makes it possible to connect as many as 15 devices (including the computer). HPIB is indeed a bus, similar in concept to the I/O bus of the computer.

Controllers, Talkers, Listeners

Only two entities reside on the I/O bus: the computer and the interface. The computer is always in control of the I/O bus, and the interfaces are slaves, doing the computer's bidding.

Three types of devices exist on the HPIB: controllers, talkers, and listeners. These types are actually attributes and may exist alone or in combination within any given peripheral. For example, the HPIB interface allows a computer to be a talker, listener, and controller. A voltmeter may only be a talker limited to supplying the system with information, while a printer may only be a listener limited to accepting data from the system. Further, any of the HPIB attributes may or may not be active at a given time.

Figure 8 illustrates how an HPIB system might be structured. The lines on the right of the figure represent the HPIB's 16 signal lines. The 16 signal lines are divided into 3 groups, the first of which is composed of 8 data lines. Forming the data bus, these bidirectional signal lines carry information and messages between devices on the bus. The second group, the data byte transfer control group, is composed of 3 lines: DAV (data valid), NRFD (not ready for data), and NDAC (not data accepted). As the names imply, this group is used to sequence the flow of information over the data lines. The 5 remaining

Performance, Reliability:



Pictured: CompuPro System Enclosure, Dual Disk Drive Enclosure, Disk 1, MPX, Selector Channel, and RAM 16.

Quality,

CPU 8086/8087

Since its introduction in early 1980, CPU 8085/88 — the first board to combine 8 and 16 bit processing — has become an industry standard. No other single board lets you run today's 8 bit software on an 8085 CPU, and tomorrow's 16 bit software on the popular 8088 CPU.

Now CPU 8086/87 delivers ultra-efficient 16 bit operation, with 8 MHz* clock speeds (10 MHz* CSC). This ground-breaking CPU board teams Intel's 8086 16 bit processor with sockets for their 8087 math co-processor (adds number-crunching capability rivalling many minicomputers), and the 80130. CPU 8086/87 is compatible with all 8 bit IEEE 696/S-100 memory and peripherals, as well as with more efficient 16 bit memories. There's even an optional 8 bit CPU board available for use with this, or any other, **CompuPro** 16 bit processor to preserve 8 bit software compatibility.

CompuPro products stand out above the crowd. For business, scientific, and industrial solutions contact your **CompuPro Systems Center**.



CPU 8086/87: $695, CSC $850. With 8087: price upon request.
CPU 8085/88: $425, CSC $525.

*8086 alone; 8087 requires lower clock rates

CompuPro division Godbout Electronics, Oakland Airport, CA 94614-0355 (415) 562-0636

Circle 457 on inquiry card.




Figure 8: *Sample configuration of the IEEE-488-1978 interface bus. Devices on the bus can be talkers, listeners, or controllers. Controllers manage the bus, activating and deactivating listeners. Talkers place data on the bus. Listeners accept data from the bus. A device connected to the bus can be a talker, a listener, a controller, or any combination of the three. Most computers, like device A, are talker, listener, and controller so that the computer can configure the bus, then send and receive information. Device B, a multimeter, can talk and listen, sending readings and receiving set-up information such as range and function. Device C, a signal generator, listens only. Printers are usually listeners. Device D, a frequency counter, talks only, placing readings on the bus. The IEEE-488-1978 bus is divided into three sets of signals. The data bus carries the information being transferred. Data byte transfer control lines sequence the flow of information. The general interface management lines have special functions: IFC (interface clear) resets the bus interfaces; ATN (attention) sends bus commands; and SRQ (service request) signals bus interrupts.*

lines form the third group of signal lines: the general interface management group. These lines carry control and status information about the devices connected to the bus.

Assigning Roles

Figure 8 shows 4 devices attached to the HPIB. Device A has the talker, listener, and controller attributes. As a controller, device A may assign the role of active talker to any device on the bus capable of undertaking that role, including itself. As a talker, device A can supply information to other devices on the bus. As a listener, device A can accept information from the other talkers on the bus. A computer is likely to have all three attributes.

Although device A is the only controller shown in figure 8, more than one controller is allowed in an HPIB system. To prevent conflicts, however, only one controller can be active at a time. Control may be passed from one controller to another by means of a sequence defined in the standard. A controller designated the *system controller* becomes the active controller when the system is turned on. All other controllers must remain passive until control is passed to them.

Device B in figure 8 is both a talker and a listener. It can be addressed by the controller and made an active talker or listener. An active talker controls the DAV signal line in the data byte transfer control group. An active listener controls the NRFD and NDAC signal lines.

Device C can only be a listener. Device D is limited to being a talker. Either of these devices may be made active by the controller. A data transaction is controlled by both the active talker and the active listener. The talker drives the bus with data, while the listener accepts the information transmitted by the talker. To avoid conflict, only one talker can be active at a time. However, several listeners can be active at once.

Transferring Information

The possibility of several active listeners receiving data simultaneously presents a problem because those listeners may not accept data at the same rate. Data-transfer speed must be paced by the slowest active listener, or that listener may lose data.

The data transfer rate on the HPIB is controlled by an electronic voting system called the *open collector*. This voting system requires unanimous agreement among active listeners and the active talker before the data transaction is completed. Information transfer takes place as follows:

1. All active listeners indicate on the NRFD line their state of readiness to accept a new piece of information. This signal line is usually connected to +5 V through a resistor. If an active listener is not ready, it pulls the NRFD line down to 0 V by turning on a transistor con-

Before you C.ITOH, see us.

When you see us we'll tell you about the line of quality printers available from C.Itoh, one of the largest manufacturers of computer peripherals in the world. C.Itoh has a printer to fit your needs.

C.ITOH STARWRITER

C.Itoh's line of letter-quality Daisy Wheel Printers offers an unmatched combination of price and performance. Since the Starwriter is available in two versions — the 25 cps Starwriter I and the 45 cps Starwriter II — you don't have to buy more printer than you need. If you don't need high print speed, the Starwriter I offers you more for your printer dollar. The Starwriter prints up to 136 columns of sharp letter-quality printing using cloth or film ribbons; its Automatic Bi-Directional printing mode assures the highest possible throughput.

The Starwriter uses industry-standard 96-character print wheels and ribbons, so there are no supply problems to worry about. Plug compatible with all major daisy wheel printers, it requires no changes in software or hardware and is available with a Centronics Parallel or RS 232C Serial interface. Optional Accessories: Bi-Directional tractor, Single Sheet Feeder.

The Starwriter is backed by C.Itoh's one-year warranty (90 days parts and labor, 9 succeeding months parts).

STARWRITER I Parallel 25 cps . . 1440.00
STARWRITER I Serial 25 cps 1540.00
STARWRITER II Parallel 45 cps . 1770.00
STARWRITER II Serial 40 cps . . . 1795.00
Bi-Directional Tractor 239.00
Single Sheet Feeder 1395.00

C.ITOH PRO/WRITER

The C.Itoh Pro/Writer offers professional quality at a very low price. Compare the advanced features that are standard on the Pro/Writer with what other printers in its price range offer, and you'll find that none offer so much value for the money; you won't have to buy 'options' to get the performance you want. The Pro/Writer uses the latest in dot-matrix printing technology to provide a productive, cost-effective solution to all your printer needs.

Some of the Pro/Writer's Advanced Features:

- N x 9 MATRIX
- BI-DIRECTIONAL PRINTING
- PROPORTIONAL SPACING
- DOT ADDRESSABLE GRAPHICS
- SPECIAL GRAPHICS CHARACTERS
- ENHANCED PRINTING
- FRICTION & TRACTOR FEED
- 100 CPS PRINT SPEED
- LOGIC SEEKING
- PICAS (10 PITCH) & ELITE (12 PITCH)
- 5 ALPHABETS
- 8 TOTAL CHARACTER FONTS
- DOUBLE-WIDTH PRINTING
- OPTIONAL RS 232C W/ X-ON & X-OFF

PRO/WRITER Centronics Parallel 549.00
PRO/WRITER RS 232C Serial 599.00

Alpha Byte COMPUTER PRODUCTS

We built a reputation on our prices and your satisfaction.

We guarantee everything for 30 days. If anything is wrong, return the item and we'll make it right. And, of course, we'll pay the shipping charges.

We accept Visa and Master Card on all orders; COD orders, up to $300.00.

Add $2.00 for standard UPS shipping and handling on orders under 50 lbs. delivered in continental U.S. Call for shipping charges over 50 lbs. Foreign, FPO and APO orders, add 15% for shipping. Californiana add 6% sales tax.

Prices quoted are for stock on hand and are subject to change without notice.

To order, or for information, call:

(213) 706-0333

31245 LA BAYA DRIVE, WESTLAKE VILLAGE, CALIFORNIA 91362

Circle 19 on inquiry card.




Figure 9: *Diagram of timing on the IEEE-488-1978 bus. Data transfers occur with a unique 3-wire handshake. First, the active talker waits for all active listeners to release the NRFD (not ready for data) line. When this happens, the signal rises to a positive level. The talker then places the data on the data lines, waits 2 microseconds, and drives the DAV (data valid) line low, indicating that the data should now be accepted. Recognizing the transition in the DAV line, the active listeners drive NRFD low. The active listeners have as much time as necessary to release NDAC (not data accepted). When all active listeners do release NDAC, its voltage rises to a positive level. This tells the talker to release DAV. At the release of DAV, the listeners pull NDAC low again. This restores the bus to the original state, where it is ready for another transfer.*

nected to the signal line. The activated transistor acts as a short to ground, pulling the voltage on the NRFD line to ground potential or 0 V. When the listener is ready to accept data, it turns off this transistor. When all active listeners turn off their transistors, the resistor connected to +5 V pulls the NRFD signal line up to around +5 V. The active talker observes the state of the NRFD line and will not start the data transfer until the signal line reaches a high voltage level.

2. The active talker observes that the NRFD line has gone high. It places a data byte on the data lines and waits 2 microseconds (0.000002 seconds). It then asserts DAV by pulling it low to 0 V. This 2-microsecond wait, called *settling time*, allows the data to reach valid logic levels on the data lines. The assertion of DAV is a signal to the active listener(s) to read the information on the data bus. The listeners acknowledge the assertion of DAV by immediately pulling back down on NRFD.
3. Until now, the active listeners have held NDAC low. When DAV is asserted and all of the active listeners accept the data on the data lines, they will release NDAC. As the slowest active listener releases NDAC, the pullup resistor will cause the signal line to go high.
4. The active talker observes the NDAC line in a high state. It acknowledges the listeners' acceptance of the data by releasing DAV. The release of DAV signals the listeners that the data transfer is complete; they again pull NDAC low in preparation for the next transfer.

Figure 9 shows a timing diagram of the complete handshake. Note that control of the data transfer is effected by the *active* talkers and listener(s). Once the controller has configured the bus, it takes no part in subsequent

Information Type	Bit # 7	6	5	4	3	2	1	0
Bus command	X	0	0	C	C	C	C	C
Listen Address	X	0	1	L	L	L	L	L
Talk Address	X	1	0	T	T	T	T	T
Secondary Address	X	1	1	S	S	S	S	S

Table 1: *Interface definitions for the 98032A parallel interface. Table 1a defines the input registers, and table 1b defines the output registers.*

transactions until reconfiguration is desired.

Configuring It Out

Now that data transfer on the HPIB has been covered, let's consider how the bus is configured. One of the general interface management lines is called ATN (attention). The active controller manages this line. ATN signifies whether the data transfers on the bus are data or control information. The active talker controls data transactions, as explained above, but the active controller supervises control transfers.

When the controller wishes to configure the HPIB, it asserts the ATN line. This causes any active talker to relinquish control of the DAV line. Transmission of control information occurs in the same manner as transfer of data. The difference is that when ATN is asserted, the active controller takes the place of the active talker, and both talkers and listeners accept the information. All devices, whether active or not, accept information transmitted by the controller when ATN is asserted.

The active talker and active listeners may be designated during the transmission of control information. The data lines carry control information after ATN has been asserted. Table 3 lists the meanings of the control data bits.

Note that bit 7 is not used. Bits 6 and 5 serve to classify the control information as to command type. A control transfer with bits 6 and 5 set to 0 is a bus command that directly controls devices on the bus. Triggering a function and passing control from the active listener to a passive one are two examples of bus commands.

Transmission of a control byte with bit 6 set to 0 and bit 5 to 1 activates a listener. A listener that observes its address in the lower 5 bits of a listen address control byte becomes active. When ATN is negated, it will assume control of NDAC and NRFD. Listeners that

Circle 368 on inquiry card.

don't observe their listen addresses in a control transfer don't change state, remaining as they were before the controller asserted ATN.

Deactivating Listeners

The HPIB provides a way to deactivate all active listeners. The 5 bits of the listen address allow 32 listen addresses. These addresses range from 0 to 31. Address 31 is the "unlisten" address. Active listeners observing the unlisten address in a listen command's address field will go inactive. The definition of talk addresses is similar to that for listen addresses—with one exception: any active talker that observes a talk command to another device will go inactive. As a result, activating one talker guarantees deactivation of any other active talkers. This prevents conflicts on the bus. Talk-address 31 is the "untalk" address. When the controller issues an untalk command, no active talkers are left on the bus.

Secondary addresses are used to address subunits within a device. Some HPIB instruments are actually clusters of devices, but secondary addressing allows addressing of a device within such a cluster.

The remaining four lines in the general interface-management group serve to control the interface sections of the HPIB devices. IFC (interface clear) may be called on by the active controller to override all bus activity and to place the bus in a known state. This signal aborts any data transfers in progress and is used only when something has gone wrong.

The REN (remote enable) signal allows the HPIB to control a device. The active controller uses the REN line to indicate to an active listener whether or not the listener will use the information sent to it by a talker.

EOI (end or identify) is applied in two ways. First, the active talker may assert it to designate a data byte as the last in a message. EOI is also part of a serial poll, which will be discussed later.

The SRQ (service request) signal enables a device to get the active controller's attention. This signal is a request, not a demand. The controller may ignore SRQ as long as it wishes. When the controller finally does acknowledge SRQ, it has to determine which device is requesting service. Since SRQ is shared by all devices on the bus, the requester isn't identified immediately.

Polling Along

A controller can employ two methods to determine the address of the device requesting service. Both methods are called *polls*. A poll is the controller's request for status information. The controller may request the status of any device individually by addressing the device as a talker and sending that device a serial-poll enable command. This constitutes one of the bus commands a controller can send when it asserts ATN. Using the *serial poll*, the controller can obtain 8 bits of status information from the addressed device. The controller then sends a serial-poll disable command to the device, returning it to data mode.

Once the controller has configured the bus, it takes no part in subsequent transactions until reconfiguration is desired.

Serial polling's advantage lies in the fact that 8 bits of poll information are obtained from each device polled. One bit can be used to indicate whether or not the device is requesting service. The remaining 7 bits are available for other purposes. A disadvantage of the serial poll is speed. Each device on the bus must be polled in turn, since more than one device may be requesting service.

A faster method of polling is the *parallel poll*. The parallel poll is performed when the active controller asserts both ATN and EOI. Up to 8 devices may respond, each on a different data line. The only information obtained in a parallel poll is whether or not a device is requesting service. Since each device has only 1 bit to respond with, obtaining further information is impossible.

You Don't Have to Know

One of the IEEE-488 standard's best features is that a system user doesn't have to know any of the information presented in this article. The standard, if followed by all the manufacturers of the devices put on a bus, guarantees that devices can talk to each other. This assumes that the system builder doesn't violate the standard by placing two devices at the same address, or by connecting two system controllers to the bus.

What then *does* the system user need to know? The standard does not specify the messages and data formats, both of which depend on the application. For example, if a voltmeter wants to tell the computer that it detects +1.234 volts at its input, what does it send to the computer as data? Most computers and computer languages prefer ASCII characters. HPIB specifies that ASCII is to be used. Next, the data format must be determined. Will the digits be sent most significant or least significant first? Again, most computers and languages prefer the digits just as you might type them, from most significant to least.

Thus, the voltmeter might send the following sequence of characters:


+ 1 . 2 3 4 <CR> <LF>


The <CR> and <LF> characters stand for carriage return and linefeed. These characters are often used as message terminators in computer communications. <LF> alone is usually sufficient.

The definition of messages and message formats leaves the IEEE-488 standard and enters the realm of HPIB. This higher-level implementation removes yet another layer of interface problems from the shoulders of the system user.

Next month, I'll discuss two other major types of interface: the BCD interface, often used when a computer receives data from scientific instruments, and the serial interface, used to transmit data over a single wire. We'll see how each evolved to deal with specific problems in communications. ■

ATARI HOME COMPUTERS








ATARI 800
16K . . . $679
32K . . . $749
48K . . . $819

ATARI 400
16K. . . . $329
32K. . . . $478
48K. . . . $555



410 Recorder	$76.00
810 Disc Drive	$449.00
822 Printer	$269.00
825 Printer	$629.00
830 Modem	$159.00
820 Printer	$269.00
850 Interface	$169.00
New DOS 2 System	$29.00

PACKAGES

481 Entertainer	$83.00
482 Educator	$130.00
483 Programmer	$57.00
484 Communicator	$344.00

ATARI HOME COMPUTER PROGRAMS

Home Office

CX404 ATARI Word Processor	$119.00
CX8102 Calculator	$29.00
CX412 Dow Jones Investment Evaluator	$99.00
CX4109 Graph It, Joystick optional	$17.00
CX4104 Mailing List	$20.00
CX4115 Mortgage & Loan Analysis	$13.00
CX406 Personal Financial Management System	$59.00
CX4103 Statistics 1	$20.00
CX8107 Stock Analysis	$20.00
CXL4015 TeleLink 1	$23.00

Home Study

CX4101 An Invitation to Programming 1	$20 00
CX4106 An Invitation to Programming 2	$23.00
CX4107 Biorhythm	$13.00
Conversational Languages (ea.)	$46.00
CX4121 Energy Czar	$13.00
CX4114 European Countries & Capitals	$13.00
CX4108 Hangman, Joystick optional	$13.00
CX4102 Kingdom	$13.00
CXL4007 Music Composer	$47.00
CX4123 Scram, uses joystick	$20.00
CX4112 States & Capitals	$13.00
CX4110 Touch Typing	$20.00

Home Entertainment

CXL4013 Asteroids	$35.00
CXL4004 Basketball	$27.00
CX4105 Blackjack	$13.00
CXL4009 Computer Chess	$33.00
CXL4012 Missile Command	$35.00
CXL4008 Space Invaders	$35.00
CXL4011 Star Raiders	$42.00
CXL4006 Super Breakout	$33.00
CXL4010 3-D Tic-Tac-Toe	$27.00
CXL4005 Video Easel	$24.00

Programming Languages and Aids

CXL4003 Assembler Editor	$47.00
CXL4002 ATARI BASIC	$47.00
CX8126 ATARI Microsoft BASIC	$70.00
CXL4018 PILOT	$72.00
CX405 PILOT	$105.00

CX30 Paddle	$18.00
CX40 Joy Stick	$18.00
CX853 16K RAM	$89.00
Microtek 16K RAM	$75.00
Microtek 32K RAM	$159.00
Ramdisk (128K)	$539.00
One year extended warranty	**$50.00**

THIRD PARTY PROGRAMS

ATARI Program Exchange:


Eastern Front '41	$25.50
Avalanche	$15.50
Outlaw	$15.50
747 Landing Simulation	$15.50
Babel	$15.50
Dog Daze	$15.50
Downhill	$15.50
Attack!	$15.50
Blackjack-Casino	$15.50
Reversi II	$15.50
Domination	$15.50
Solitare	$15.50
Disk Fixer	$15.50
Supersort	$15.50
Data Management	$15.50
Chameleon	$15.50
Instedit	$15.50
Insomnia	$15.50
My First Alphabet	$25.50
Mapware	$18.00
Number Blast	$11.50
Family Cash Flow	$15.50
Weekly Planner	$15.50
Bowler's Data Base	$13.00
Banner Generator	$11.50

Visicalc	$169.00
Letterperfect (Word Processor)	$109.00
Ricochet	$14.50
Crush Crumble & Chomp (cassette or disk)	$24.00
Star Warrior (cassette or disk)	$29.00
Rescue at Rigel (cassette or disk)	$24.00
Datestones (cassette or disk)	$16.00
Invasion Orion (cassette or disk)	$18.50
Mission Asteriod	$22.00
MouskATTACK	$31.00
The Next Step	$34.00
Softporn	$27.00
Wizzard & Princess	$29.00
K-BYTE Krazy Shoot Out (ROM)	$39.00
Protector (Disk 32K)	$32.00
Jaw Breaker (on line disk)	$27.00
Ghost Hunter (cassette)	$24.00
Ghost Hunter (disk)	$30.00

COMING SOON

PAC MAN (May) $35. CENTIPEDE (June) $35
CAVERNS OF MARS (April) $32

Texas Instruments



TI-99/4A $359

PHP 1600 Telephone Coupler	$179.00
PHP 1700 RS-232 Accessories Interface	$179.00
PHP 1800 Disk Drive Controller	$239 00
PHP 1850 Disk Memory Drive	$389 00
PHP 2200 Memory Expansion (32K RAM)	$319.00
PHA 2100 R F Modulator	$43 00
PHP 1100 Wired Remote Controllers(Pair)	$31 00
32K Expansion	$329.00
PHP Printer Solid State	$319.00
PHM 3006 Home Financial Decisions	$26 00
PHM 3013 Personal Record Keeping	$43.00
PHD 5001 Mailing List	$60 00
PHD 5021 Checkbook Manager	$18 00
PHM 3008 Video Chess	$60 00
PHM 3010 Physical Fitness	$26 00
PHM 3009 Football	$26 00
PHM 3018 Video Games I	$26 00
PHM 3024 Indoor Soccer	$26 00
PHM 3025 Mind Challengers	$22 00
PHM 3031 The Attack	$35 00
PHM 3032 Blasto	$22 00
PHM 3033 Blackjack and Poker	$22 00
PHM 3034 Hustle	$22 00
PHM 3036 Zero Zap	$18.00
PHM 3037 Hangman	$18 00
PHM 3038 Connect Four	$18 00
PHM 3039 Yahtzee	$22 00



PRINTERS

Centronics 739-3	$619.00
Centronics 739-1	$519.00
Diablo 630 Special	$1799.00
Epson	
MX70	$359.00
MX80	$469.00
MX80FT	Call
MX100	Call
NEC	
8023	$549.00
7730	Call
7720	Call
7710	Call
Okidata	
82A	$499 00
83A	$769 00
84	$1129 00
Citoh Starwriter	
F10-40 CPS	$1469.00
F10-55 CPS	Call
Paper Tiger	
445G	$699 00
460G	$899 00
560G	$1129.00
Talley	
8024-7	$1399 00
8024-L	$1629 00

HOW TO ORDER: Phone orders invited or send check or money order and receive free shipping in the continental United States. PA and NEV. add sales tax.

computer mail order west


800-648-3351

Franco
Hables
Espanol

IN NEVADA, CALL (702) 588-5654

P.O. BOX 6689, STATE LINE, NEVADA 89449





HP•85 $1999

80 Column Printer	$799.00
HP•125	$1999.00
HP•83	$1699.00
HP•85 16K Memory Module	$169.00
5¼" Dual Master Disc Drive	$1929.00
Graphics Plotter (7225B)	$2079.00
NEW! HP•87	$1999.00
Hard Disk w/Floppy	$4349.00
Hard Disk	$3440.00
"Sweet Lips" Plotter	$1149.00

HP41CV Calculator $259

41 C	$189.00
11 C	$119.00
12 C	$129.00
34 C	$117.00
38 C	$119.00
HP•41 Printer	$340.00

HPIL CALCULATOR PERIPHERALS

IL Modual	$104.00
Digital Cassette	$449.00
Printer/Plotter	$419.00
Card Reader	$164.00
Optical Wand	$99.00

CALL FOR SOFTWARE INFORMATION

XEROX®

Xerox 820

System I 5¼"	$2450.00
System II 8"	$2950.00
CPM 5¼"	$169.00
Word Processing	$429.00
Super Calc	$269.00

CALL FOR MORE INFORMATION

commodore BUSINESS MACHINES




CBM 8032 $1069

SOFTWARE

Word Pro 5 Plus	$319.00
WordPro3 Plus	$199.00
WordPro4 Plus	$299.00
Commodore Tax Package	$589.00
Visicalc	$169.00
Medical Billing	$449.00
The Source	$89.00
OZZ Information System	$289.00
Dow Jones Portfolio	$129.00
Pascal	$239.00
Legal Time Accounting	$449.00
Word Craft 80	$289.00
Power	$79.00
Socket-2-Me	$20.00
Jinsam	$Call
MAGIS	$ Call
The Manager	$209.00
Softrom	$129.00
Real Estate Package	$799.00
BPI Inventory Control	$319.00
BPI Job Costing	$319.00
BPI Payroll	$319.00
BPI General Ledger	$329.00
Creative I SAM	$79.00
Creative General Ledger	$229.00
Creative Accounts Receivable	$229.00
Creative Inventory	$229.00

4032	$969.00
4016	$769.00
8096 Upgrade Kit	$399.00
Super Pet	$1599.00
2031	$529.00
8050	$1299.00
4040	$969.00
8300 (Letter Quality)	$1799.00
8023	$769.00
4022	$599.00
Pet to IEEE Cable	$37.00
IEEE to IEEE Cable	$46.00
Tractor Feed for 8300	$240.00
8010 Modem	$229.00



VIC 20 $259

COMPLETE

Vic 6 Pack Program	$44 00
VIC1530 Commodore Datassette	$69 00
VIC1540 Disk Drive	$499 00
VIC1515 VIC Graphic Printer	$339.00
VIC1210 3K Memory Expander	$32 00
VIC1110 8K Memory Expander	$53 00
VIC1011 RS232C Terminal Interface	$43 00
VIC1112 VIC IEEE 488 Interface	$86 00
VIC1211 VIC 20 Super Expander	$53 00
VT232 VICTerm I Terminal Emulator	$9 00

VIC1212 Programmers Aid Cartridge	$45 00
VIC1213 VICMON Machine Language Monitor	$45 00
VIC1901 VIC AVENGERS	$23 00
VIC1904 SUPERSLOT	$23 00
VIC1906 SUPER ALIEN	$19 00
VIC1907 SUPER LANDER	$23 00
VIC1908 DRAW POKER	$23 00
VIC1909 MIDNIGHT DRIVE	$23 00
VT106A Recreation Pack A	$44 00
VT107A Home Calculation Pack A	$44 00
VT164 Programmable Character/Gamegraphics	$12.00

New VIC Software

Household Finance	$27.00
VIC Games	$19.00
VIC Home Inventory	$13.00
VIC Rec/Ed II	$13.00
VL101 Introduction to Computing	$19.00
VL102 Introduction to BASIC Programming	$19.00
VM110 VIC 20 Programmers Reference Guide	$15.00

Terminal	$13.00
Un Word	$13.00
Grafix Menagerie	$11.00
VIC PICS	$15.00
Ticker Tape	$13.00
Banner Headliner	$13.00
RS 232	$39.00

Modems

Novation Auto	$239.00
D Cat	$169.00
Cat	$159.00
Hayes	
Smart	$239.00
Livermore Star	$119.00

Terminals

Televideo	
910	$579.00
912C	$699.00
920C	$749.00
950	$939.00
Call for computers	
Zenith Z19	$749.00
Adds	$549.00

Monitors

Amdex 12" B&W	$139.00
12" Green	$149.00
13" Color	$349 00
Sanyo 12" B&W	$259.00
12" Green	$269.00
13" Color	$449.00
TI 10" Color	$349 00

Above are cash prices. add 3% for Master Card and Visa purchases

computer mail order east

800-233-8950

IN PA. CALL (717) 327-9575

477 E. THIRD ST., WILLIAMSPORT, PA 17701

Patricio Hables Espanol

Circle 108 on inquiry card.

The Osborne 1, Zeke's New Friends, and Spelling Revisited

A seasoned computer user looks at new products and updates.

Jerry Pournelle
c/o BYTE Publications
POB 372
Hancock, NH 03449

"It's the great software drought," said my mad friend Mac Lean. "Have you noticed? There's no good new software. Just updates and revisions and new versions of old programs."

"Not true," I protested. "Just yesterday I got Sorcim's Supercalc."

"Sure. The CP/M version of a year-old Apple program. Good stuff. Useful. Excellent. But not new."

"Hmm. Maybe you're right. Well, at least they're improving old programs. I have an update for Spellguard."

"Aha," said my mad friend. "Tell me, are you still using Spellguard?"

"Yep."

"Thought you had a whole mess of new spelling programs."

"I do. Here's one of them." I held up Microproof. "But I don't use them. Better to stay with Spellguard. Especially now, with its improved dictionary."

Which is true. I suppose it comes as no surprise that I am very interested in spelling and editing programs.

After all, words are my business . . . I need good spelling programs.

After all, words are my business, and I am, according to Robert Heinlein, one of the "wurst spellurs" he has ever encountered. I *need* good spelling programs, and I have to use them a lot, which means I'm interested in speed and convenience, which is why I stick with Spellguard despite its lack of certain features.

Example: in my previous Spellguard review [see November 1981 BYTE, page 449], I said "it corrects spelling." BYTE's editors, in the interest of accuracy, changed that to "finds and marks spelling errors." Other programs, such as Microproof, *correct* spelling errors. All true, but irrelevant. The job to be performed is spelling correction, and Spellguard does that [also see "Five Spelling-Correction Programs for CP/M-Based Systems" by Phil Lemmons, November 1981 BYTE, page 434].

Example: Microproof's specifications make it sound far better than Spellguard. (Let me call them MP and SG from here on.) MP has a 50,000-word dictionary compared to SG's 20,000. MP knows about plurals and prefixes; you can tag a word as a noun or an adjective or an adverb, and MP will take the root and add suffixes and prefixes and such like. Finally, MP lets you correct the word and will then go off and put that

[redacted]

word in your text file, while all SG does is mark it for you to go fix using your standard editor.

Sounds great, doesn't it?

The trouble comes when you use it. That's presuming you even try; the manual was enough to cause me to leave MP in the box for over a month.

(Digression. The Microproof manual, which, according to its interior blurbs, was written by "an acknowledged expert in the field of programmed learning," is a general-purpose thing, intended for several versions of the program; and because it's never made clear what version you have, it's unutterably confusing. And that sort of thing happens all the time.

TO ALL SOFTWARE PUBLISHERS: look, if you want to charge $100 and more for programs, you can darned well furnish a manual tailored for *each* program!)

In Microproof's favor, I have to say that when you actually start using the program—as opposed to trying to figure out how to use it—it gets simple. The prompts are clear and the procedures are simple.

But it's slow. Ye gods, it's slow to work with. Instead of leaving the instructions on the screen and using the same entry line over and over again, as SG does, MP clears the screen and rewrites it, prompts and instructions and all, for each word it didn't recognize—dozens of them. Eventually you get through that, after which MP reads your text file and corrects it. That, however, takes about as long as it would have taken to load your editor, bring in the file, and search for the marked blocks; and because, if you're like me anyway, you'll want to *see* the corrected text and possibly reformat it before printing it and sending it out, you'll have to load the editor and text file anyway.

Now about those prefix and suffix "features." I suspect they have something to do with the fact that I CANNOT get Microproof to believe that "index," "kilobyte," "milestone," "undoubtedly," "Unix," and "automatic" are words. I went through my third "User's Column" (the one reviewing Spellguard!) as a test file *four times* and each time I patiently entered those words into the MP dictionary; and next pass I got them read back to me as misspellings.

(To make the test fair, I used Microproof on this text too, and not only won't it admit that the above are words after two passes, but until I entered it, it didn't recognize Microproof! Meaning, I would suppose, that they didn't use the program on their own manual. If they won't use it, why should anyone?)

There's worse. MP doesn't know about apostrophes. It gives me the "weren" of "weren't" as a candidate word. It does the same with "doesn." And if you use dashes! Spellguard understands dashes and hyphens, but if you have a double hyphen (which represents a typeset dash) in your text, SP thinks that is two separate words and examines each. Microproof offers me the "program—as" and "it—it" that I used above as candidate words. If you use many dashes in your text, you will, I assure you, go quite mad after about the third pass Microproof makes at your text.

Finally, Microproof doesn't know much about error handling. It takes forever to go through a 6500-word text file; and if you've left insufficient space on your disk for the original file plus a backup (.BAK) file, then when Microproof finds that out, it simply dumps the job, leaving you either in CP/M or the monitor, depending on just how confused MP got. Either way, you've lost all the work you just did.

So. Microproof is a heroic effort to make a more convenient spelling program. They tried to do right. The concept was good. The execution, though, leaves something to be desired.

There's a version geared to work

with either Electric Pencil or Scripsit for the TRS-80 Model I (and III) and TRSDOS. (Microproof has recently fixed most of the problems, partly because I sent a preliminary copy of this review to them. See next column for details; Microproof is now competitive with Spellguard.)

Which, incidentally, has been greatly improved. Now there's an explicit way to remove misspelled words erroneously entered into the dictionary. Also, the updated version packs the dictionary into half the space and runs about twice as fast. It took me just about an hour, using Microproof, to shape up a 6500-word column; with new Spellguard, the whole job (including looking up and entering into the program's dictionary about 100 new words) took fewer than 20 minutes.

The Spellguard documentation remains excellent, as clear and precise as anything I've seen in the field. Still highly recommended.

Zeke's New Friends

A few minutes ago, Arthur C. Clarke called me from Sri Lanka. (He lives there. I think the nation has declared him a national treasure; I know that when Robert Heinlein visited him, Dr. Clarke was able to arrange for a Sri Lanka air force helicopter to take Robert about the country.)

Arthur had seen some of my computer articles, and what he wanted to know was what everyone nowadays wants to know: what do you buy for a first computer?

Unfortunately, the answer is, it depends. But let's look at the problem. It's not unrelated to a second difficulty, one I have myself.

Your guide to the world of microprocessors.

The Micro-Professor™ -A low cost tool for learning, teaching and prototyping.

Here in one attractive package and at a price of only $149.00 is a Z80* based microcomputer to lead you step by step to a thorough knowledge of the world of microprocessors.

The Micro-Professor is a complete hardware and software system whose extensive teaching manual gives you detailed schematics and examples of program code. A superb learning tool for students, hobbyists and microprocessor enthusiasts, as well as an excellent teaching aid for instructors of electrical engineering and computer science courses.

But the Micro-Professor is much more than a teaching device. With it you can do breadboarding and prototyping, designing your own custom hardware and software applications with Z80, 8080 and 8085 compatible code.

The standard 2K bytes of RAM is expandable to 4K, and the standard 2K bytes of ROM can be increased to 8K.


All this plus a built-in speaker, a cassette interface, and sockets to accept optional CTC/PIO. Bus is extendable.

As well as being an exciting learning tool, the Micro-Professor is a great low-cost board for OEM's. Call for details.

* Z80 is a trademark of Zilog Inc.




Multitech Electronics Inc.



SSB-MPF Speech Synthesizer Board $129

A vocabulary of up to 400 words based on the TMS 5200 chip.



EPB-MPF EPROM Programming Board $169

For all +5V 1KB/2KB/4KB EPROMs. Read/Copy/List/Verify Capability.

BASIC-MPF Tiny Basic $19

2KB BASIC interpreter with hardware control capability. Machine-code subroutine accessible.

I'm ready to enter the world of microprocessing

Call toll free to order.

	Price	Qty.	Amount
MPF-I Micro-Professor	$149.00		
SSB-MPF Speech Synthesizer Board	$129.00		
EPB-MPF EPROM Programming Board	$169.00		
BASIC-MPF	$ 19.00		
Shipping and Handling	$ 4.95		4.95
California residents add sales tax.			
TOTAL			

☐ Check or money order enclosed
☐ Visa ☐ Mastercharge

Card No. ________ Expires ________

Signature ________

Name (Please Print) ________

Address ________

City ________ State ________ Zip ________

In U.S. and Canada mail to:
Multitech Electronics Inc.
195 West El Camino Real
Sunnyvale, CA 94086
California Tel. (408) 773-8400
Elsewhere (800) 538-1542

Outside of North America mail to:
Multitech Industrial Corporation
977 Min Shen E Road, 105
Taipei, Taiwan, ROC
Tel. 02-769-1225
TWX 19162 MULTIIC,
23756 MULTIIC

Circle 291 on inquiry card.

I was talking with Ezekial, my friend who happens to be a Cromemco Z-2.

"I'm getting old, boss," he said.

"You were built in 1977!"

"Yeah. In this business, that's *old*. Look, we've written five books and dozens of columns and hundreds of letters. I do all your taxes and accounting. I compile all your programs, in twenty languages. I even play games with you."

"OK, OK, so what do you want?"

"Some rest. A bit of help. Look, I'll make you a deal. I'll help you write books, same as always, but you go get something faster, something new, to do all that compiling and calculating."

"Never thought I'd hear you say it," I said. "Better is the enemy of good enough. And you're plenty good enough!"

"Could use help, boss. Big responsibility, being the only computer around here. Especially now that you're so busy with the Citizen's Advisory Council on National Space Policy stuff and the L-5 Society." (Plug: if you're interested in helping the space program, join L-5. It's $20 a year; send fee to L-5 Society, 1060 E. Elm, Tucson, AZ 85719. Contributions tax deductible within the framework of the law. Secretary this year: Jerry Pournelle.)

"What happens," Zeke continued, "if I get sick?"

I thought about it a long time. He's right, of course. He *is* getting old; and he's utterly spoiled me. I can't conceive of writing without a computer. I live in terror that Zeke is going to quit on me. Actually I don't; he's rarely given cause for alarm. A couple of times in the early days we had glitches that brought Tony Pietsch out—always in the middle of the night; nice chap, Tony—but they always got fixed without having to take Zeke away. But not long ago something gave out in the disk power supply, keeping Zeke shut down for nearly a week. True, I was out of town at the time, but it could have been a disaster.

I needed a second computer. But what?

In the middle of the dilemma, Adam Osborne sent me his new Osborne 1.


That darned near solved my problem. Osborne's machine is *good*. The first models had some faulty characteristics, but Adam is an honorable man—and also smart enough not to risk his reputation by sharp practices. They're planning retrofits to take care of all major difficulties and most minor ones.

The worst of these was the shift lock, which was worse than useless. Then, too, with that tiny screen you needed smooth vertical scrolling (it already had good horizontal scrolling). There have been some other minor annoyances, but as I said, Adam's been fixing them. The new Osborne 1 computers—out by the time this is published—will incorporate the improvements, including true three-key rollover and a decent shift lock, and various other fixes. Those who have already bought the machines will be able to get them retrofitted absolutely free.

One thing I thought would be a pain turned out not to be. That's the tiny video screen. Adam has sent me his larger video monitor, which you can connect to the Osborne 1 with a cable, but I find I don't use it. The little screen turns out to be just at the right focal distance when I sit at the console; and for someone like me, who wears bifocal glasses, that's a real boon.

I carried the Osborne 1 out to Cal Tech's Jet Propulsion Laboratories for the Voyager 2 encounter with Saturn. There were over a hundred members of the science press corps packed into JPL's Von Karman Center (the press facility). Most had typewriters. One or two had big, cumbersome word processors. At least one was a terminal connected through a network to the parent system in New York. Nobody had anything near as convenient as the Osborne 1, which is quiet and fast responding.

How To Sell More Software



With Better User Manuals

An intensive one-day seminar on Writing User Manuals That Sell

If you're an individual software author or a software company in the business of publishing and selling software, or if you'd like to be, you can benefit from this seminar. Unlike seminars that concentrate on the academic do's and don'ts of technical writing and formatting, this seminar gets down to the business value of the user manual as a marketing and sales tool that helps you get more users and keep them.

Developed and conducted by software marketing professionals with over 50 years of collective experience in writing software manuals for the commercial market, this seminar is loaded with facts and ideas on these subjects:

Manual Design

How to make content, organization, page layout, and document format work to your sales advantage. How to publish attractive manuals that speak well of your software without spending a fortune.

Training vs. Reference. Can one manual do both?

How to implement the techniques of tutorial writing into a well organized reference format that provides easy access for later questions.

Packaging That Controls Point of Sale

How to make your manuals work for you at the point of sale to help the dealer present your software in its most competitive light--both on the shelf and on the demonstration machine.

Automated Manual Writing

How to let the software document itself wherever possible, and how to use word processing systems effectively to obtain maximum value from automated publishing tools.

Seminar Manual

All attendants will receive a detailed How To manual on writing and producing user manuals for commercial use. Many past attendants have praised the manual and other handout materials as being worth the price of attendance by themselves.

Schedule:

		Chicago	May 21
Boston	May 18	Dallas	May 25
New York	May 19	Los Angeles	May 26
Philadelphia	May 20	San Francisco	May 27

Only $125 With Our Guarantee

Price includes lunch and materials. We offer a 10% discount for companies sending more than one person.

Get Details at Computerland Today!

Space is limited so make your reservation now. To get enrollment details, simply call (303) 471-9875, or, visit your nearest participating Computerland Store and pick up a complete Seminar Information Packet including an agenda, an outline of the seminar manual, seminar authors' and instructors' resumes and a brochure on Context, Inc.



Everyone came to look at it. "How can you stand that tiny screen?" asked Eric Burgess, senior science correspondent present. (Eric's the chap who first thought of the message plaque to be attached to the space probes. I was there when he got the idea. But that's another story.) He stared over my shoulder. "It's so small."

"Try it," I invited. I got up to give him my place and watched as he realized that when you're sitting at the machine you can read it at least as easily as you can a book. Before the encounter was over, a dozen science writers were ready to go buy an Osborne 1.


I also took it to the meeting of the Citizen's Advisory Council on National Space Policy (which I chair) and used it to take notes during the meeting. It was amazing: I was able to type notes and suggestions and ideas into the Osborne 1 without disrupting the meeting at all. The Osborne 1 is quiet and efficient and not at all distracting.

In other words, I like the Osborne 1. You can't beat it for the price, under $2000 bucks with over a thousand dollars' worth of software. An Osborne and an Epson printer will put you in the computer/word-processing business cheaper than anything I can think of, and the Osborne 1 is a real computer, using the CP/M operating system and adult software like Wordstar and Supercalc and dBase II; it's not a toy.

So. For those who haven't a lot of money to spend and want to get going in computers, I don't hesitate to recommend the Osborne 1—as a first system. However, it is a limited system. It wasn't designed for lots of expansion capabilities, and it's never going to be able to use them. But as a first machine, it has a lot going for it, and not just the price.

When I first got the Osborne 1, I thought I'd solve one of my problems, which is, how can I have someone entering letters and files and old books while I'm using Ezekial? I certainly am not going to have a multiuser microcomputer, which defeats the whole concept of decentralized computing. Our TRS-80 Model I with Omikron's CP/M conversion will do the job, but it's often in use as the boys check out new games and educational stuff; worse, the TRS-80 keyboard is plain awful, driving my editorial associates crazy. Even the boys get weary of it.

No, I needed a second machine, with a good text editor. Aha, says I. I'll use the Osborne 1. Of course the Osborne 1 has only 5¼-inch disks, and Ezekial has 8-inch disks, but that's all right. The TRS-80 has both 5¼-inch and 8-inch Lobo disks, and those work fine, and under CP/M we can copy files from the little disks to



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 39 MARTINSVILLE, NJ

POSTAGE WILL BE PAID BY ADDRESSEE



Subscription Dept.
P.O. Box 590
Martinsville, NJ 08836



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES


BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 10 PETERBOROUGH, NH

POSTAGE WILL BE PAID BY ADDRESSEE



70 Main Street
Peterborough, New Hampshire 03458



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 10 PETERBOROUGH, NH

POSTAGE WILL BE PAID BY ADDRESSEE



70 Main Street
Peterborough, New Hampshire 03458

BYTE Books' reputation is based on providing technically accurate, useful, and timely information. Established on the same principle as BYTE magazine, BYTE Books evolved in response to the rapidly expanding audience of home and business computer users. Computer professionals and enthusiastic newcomers need to keep pace with this unabated growth. This selection of BYTE books can expand your library of knowledge and expertise.

TO ORDER, CALL TOLL FREE 800-258-5420, OR FILL OUT YOUR CHOICES ON THIS COUPON and return it with check, money order, or charge card number to:

70 Main St
Peterborough, NH 03458

Name ______________________________

Address ______________________________

City ____________ State ____________ Zip ____________

- Check enclosed in the amount of __________
- Bill Visa Card Number __________
- Bill Master Charge Card Number __________
- Expiration Date __________

Include 75c per book to cover postage and handling.

TITLE	PRICE	QUANTITY	AMOUNT
		SHIPPING	
		TOTAL	

B4

BYTE Books' reputation is based on providing technically accurate, useful, and timely information. Established on the same principle as BYTE magazine, BYTE Books evolved in response to the rapidly expanding audience of home and business computer users. Computer professionals and enthusiastic newcomers need to keep pace with this unabated growth. This selection of BYTE books can expand your library of knowledge and expertise.

TO ORDER, CALL TOLL FREE 800-258-5420, OR FILL OUT YOUR CHOICES ON THIS COUPON and return it with check, money order, or charge card number to:

70 Main St
Peterborough, NH 03458

Name ______________________________

Address ______________________________

City ____________ State ____________ Zip ____________

- Check enclosed in the amount of __________
- Bill Visa Card Number __________
- Bill Master Charge Card Number __________
- Expiration Date __________

Include 75c per book to cover postage and handling.

TITLE	PRICE	QUANTITY	AMOUNT
		SHIPPING	
		TOTAL	

B4

THE DAWN OF A NEW ERA
"THE COMPUTER-LINE"™

DEC · VISTA · LOBO · NEC · EPSON · ZENITH · XEROX · HAYES · HEWLETT-PACKARD

APPLE · MBI™





Our Volume Sales Are So High
That Our Prices Are The World's Lowest - Period!

CALIFORNIA COMPUTER SYSTEMS		MOUNTAIN HARDWARE	
7710 Async. Serial Int.	$135	CPA Multi-Function Card	$169
7490 GPIB (IEEE-488) Int.	$239	The Clock	$229
7470 Ana. to Dig. Converter	$ 99	Supertalker	$159
7711 Async. Serial (Term)	$135	Music System	$319
7712 Sync. Serial Int.	$149	Expansion Chassis	$599
7721 Apple Parallel Int.	$109	Romwriter	$139
Calendar/Clock Module	$ 99	Ram Plus (32K Board)	$149
Programable Timer	$ 99		

PRINTERS

NEC		**ANADEX**	
Spinwriter 7710	$ 2339	DP9500/9501	$ 1275
8023 A	$CALL	**INTEGRAL DATA SYSTEMS**	
EPSON		Prism 80	$ 1195
MX 80	$CALL	Prism 132 **Color** Printer	$ 1595
MX 80 Ft.	$CALL	**MPI**	
MX 100	$CALL	88 G Printer	$ 659
		99 G Printer	$ 749

BUSINESS SOFTWARE

VISICORP, INC.		**STONEWARE**	
Desktop Plan III	$229	DB Master	$169
Desktop Plan II	$189	DB Utility Pack	$ 69
Visifiles	$189	**MICRO PRO**	
Visiplot	$159	**Apple CP/M**	
Visitrend/Visiplot	$229	Word Star	$219
Visidex	$189	Super Sort	$119
Visiterm	$ 79	Mail Merger	$ 79
Visicalc 3-3	$189	Data Star	$179
Visipak	$539	Spell Star	$119
		Call Star	$119


INFORMATION UNLIMITED
Pro Easy Writer $169

Call For Continental, Dakin 5, Broderbund, Automated Simulations, Avant-Garde, Edu-Ware, Denver, Howard, Sirius, Sensible, Synergistic Software, Etc.

COMPARE!

DRIVES FOR APPLE / WITH CONTROLLER $459
ADD-ON $389

Hard Disks + 8" Disks for Apple, TRS-80 $CALL
Apple Computer Products $CALL



PRODUCTS • PLEASE CALL OR WRITE FOR CATALOG.

MODEMS	
Hayes Micromodem II	$289
Hayes Smartmodem	$229
Hayes Chronograph	$199
Novation Cat	$145
Novation D-Cat Modem	$165
Novation Apple Cat II	$339
Novation Auto Cat	$209

DISKETTES (Boxes of 10)	
Verbatim Datalife	$ 24-95
Verbatim 8" Double-Side/DD	$39-95
RAM CARDS	
Ramex 16 K Card	$ 119
Ramex 128 K Card	$CALL
Wesper 16 K Card	$ 119
Microsoft 16 K Card	$ 139
Dana 16 K Card	$ 119

MONITORS	
Zenith ZVM-121 Phosphor 15 MHZ	$119
NEC 1201 Phosphor 20 MHZ	$179
NEC 0112 Composite Color	$335
NEC 2112 RGB Color	$899
Amdek 300 Phosphor	$199
Amdek Composite Color	$355
Amdek IBM Compatible Color	$899

80 COLUMN CARDS FOR APPLE	
Wesper 80 Card	$259
Vision 80 Card (Vista)	$299
Videx 80 Card	$259
MISCELLANEOUS APPLE PRODUCTS	
Enhancer II	$ 119
Dana Apple Fan	$ 39
Sup R Mod	$27-95

IN COLORADO (303) 279-2727

CALL "THE COMPUTER-LINE"™ 7 DAYS

1-(800)-525-7877

COMPUTERWORLD INTERNATIONAL, INC.
SUITE 133, P.O. BOX 81, WHEAT RIDGE, COLORADO, U.S.A. 80034-0081

IN COLORADO
SUITE 108
THE GOLD OFFICES
607 10TH ST.
GOLDEN, CO 80401

TERMS: RETAIL/MAIL ORDER: MASTERCHARGE/VISA ACCEPTED. WE CALCULATE UPS FREIGHT.

Circle 121 on inquiry card.

the big disks using the PIP utility routine. So all we have to do is to take a disk from the Osborne 1 to the TRS-80 and. . . .

It doesn't work. The Osborne disk format is different from the Omikron's format. And, talking to Mike McCulloch of Osborne Computer Corporation, I find there's no easy solution to the problem. If there were a "standard" 5¼-inch disk format (as there is a standard for 8-inch disks—the IBM single-density soft-sectored format), then Osborne would use it. Indeed, when Osborne goes to double density for disks, it'll use the new IBM 5¼-inch double-density format. But Osborne can't use a standard until one exists.

Which means that the only way to get files from the Osborne 1 to Zeke is to send them out the Osborne 1's serial port. Now the Osborne 1 has such ports, both RS-232C and modem ports, so that's not impossible, and nowadays Osborne will furnish you with software to accomplish the job (well, to accomplish the Osborne 1 end of the job; obviously you'll have to have appropriate software on the other end to catch what the Osborne 1 is pitching).

Moreover, the Osborne 1 format may yet become the "standard" for 5¼-inch single-density disks. According to McCulloch, the major software houses have been given copies of the specifications as well as an Osborne 1 machine and have been invited to offer software on disks readable by the Osborne 1; Adam Osborne has no intention of cutting his users off from the vast marketplace of CP/M software. Just the opposite.

So. By now you get the idea. The Osborne 1 is as good an entry-level system as I have seen. The only products that come close to it are the new IBM Personal Computer and the Heath/Zenith H-89, and both come with only one disk drive and very little software at a price a good bit higher than the Osborne 1.

I did not, however, recommend the Osborne 1 to Arthur Clarke; and I never seriously considered it as the new machine Zeke wanted me to set up as his assistant. It's not that I won't keep mine and use it as a portable for a very long time; but I need more machine than can be bought for $2000, and so does Arthur Clarke.

Candidates

"Maybe," I said to my mad friend, "maybe I'll get an H-89. I can get it with CP/M and a printer and get a company to fit a case for *it*. I see advertised a board that will let it talk to 8-inch disks, which will solve the problem of communicating with Zeke. I can end up with a portable."

"Good thinking, as long as you think of it as a spare. Your real machine needs an expandable bus."

"True. But for a portable. . . . In fact," I said in boyish enthusiasm, "maybe I'll get it as a kit and build it so

Circle 369 on inquiry card.

I can *understand* the machine."

"Sounds like about as much fun as an appendectomy," said Mac Lean.

I can always count on him to prick any silly bubbles like that.

In the middle of all that came another emergency. Dr. Stefan T. Possony, my long-time friend, associate, and collaborator, decided to get a computer. He'd seen Ezekial, and he wanted him. Or one like him.

Not long ago the solution to the problem would have been simple. We'd simply hand money to Tony Pietsch of Proteus Engineering, he would produce an updated clone of Ezekial, and all would be well. Unfortunately, Tony's in great demand as a consultant and has just about gone out of the systems-integration business.

So, what to get? For Stefan, and for me.

It didn't take much research to come to several conclusions. First, a professional system ought to have 8-inch floppy-disk drives. The little disks are fine for entry-level learning systems, but they're just not solid enough—and won't hold enough files—for professional work. Second, the system has to use Digital Research's CP/M operating system. With Xerox, Wang, and DEC (Digital Equipment Corporation) coming into the field, CP/M is more than a de facto standard, it's a necessity. Third, the S-100 bus (in a quiet version and built to the IEEE standard, if at all possible) is still the most versatile small-computer system going and will be for some time. An S-100 with a Z80 processor is *the* way to go.

"But why not the new IBM Personal Computer?" one of my sane friends asked. "It has an expansion bus. Not the S-100, true, but a bus. And CP/M-86, and IBM maintenance and—"

And 5¼-inch floppy disks, which even with IBM behind them are going to be a problem. Furthermore, as of right now (fall, 1981) the local people selling the IBM know nothing about software availability, although with Microsoft's support I expect that to change by the time you read this.

The IBM may sweep the field; heaven knows it's a handsome enough unit. I learned to write with an IBM typewriter keyboard, and I've found few computer keyboards up to the Selectric—and the new IBM computer keyboard is even nicer. Indeed, I'm thinking seriously of getting an IBM. But for all of IBM's prodigious reputation, it hasn't a lot of experience with small computers. Until it gains some, I think I'll wait. Besides, IBM Personal Computers weren't available back last summer when Stefan wanted his machine.

So. What to get? And how to install it long distance? That really presented a problem. Possony knows nothing about computers, and there aren't too many off-the-shelf S-100 systems. I could get a Vector; although I've no direct experience with them, people I trust tell me they're excellent.

But then I remembered: I have a good friend, Dr. Colin Mick (Decision Information Services, POB 5849, Stanford, CA 94305, (415) 327-5797), in the Stanford area, where Dr. Possony lives. A quick phone call, and Colin foolishly volunteered to help Stefan. It turned out well. Colin installed a CCS (California Computer Systems) system with a Heath/Zenith Z-19 terminal in Stefan's house. He chose CCS because that's what he has, and he knows some of the CCS design team; the result has been so successful that Colin is now much in demand as a small-systems consultant.

Another result is that Possony, already one of the world's most prolific writers on foreign affairs and international politics, has more than doubled his output. He *loves* his new system; and when you consider that Stefan is a Viennese intellectual, who got his Ph.D. the year after I was born

Vistavision80

Invisible or Invincible?
It all depends on your perspective.

The Vision 80© is a video display card that gives your Apple™ terminal an industry-standard 80 column by 24 line display screen with a full 128 character set including upper and lower case letters with three dot descenders. It is compatible with all existing Apple™ BASIC software and allows the use of 80 column lower case text with programs written in BASIC, FORTRAN Pascal, Microsoft CP/M™ and ASSEMBLER. Full communications driver support allows the Apple II™ to operate as an intelligent terminal

Definitely invincible. Ask Softalk magazine editors, who rated Vision 80© the Best Apple-video display card on the market.

But the Vision 80© card has an "Apple" command vocabulary including H-tab, V-tab, HOME, TEXT, PR# GRAPHICS).



No changes in operating or programming procedures are necessary to produce whatever sophisticated displays you require. And it doesn't interfere with the operation of popular Apple™ compatible peripherals. Except for the enhanced display, it's as if you had never installed the Vision 80© in your Apple II™ computer.

Definitely invisible.

Ask your local computer dealer for a demonstration of the invincible, invisible Vision 80© video display card by Vista Computer Company. Or correspond with us directly: Vista Computer Company, Inc. 1317 East Edinger, Santa Ana CA 92705, (714) 953-0523. Toll free order line: (800) 854-8017.

Be sure to inquire about our new Vision 40, a softscreen programmable character generator for Apple II™ computers. It's great for graphics and perfect for foreign language applications.

Perceptive Perspective

Vista
COMPUTER COMPANY, INC.
1317 East Edinger • Santa Ana, CA 92705
714-953-0523 800-854-8017

Circle 427 on inquiry card.

and who knows very little about machines, that's quite a statement. It's also a great testimony to Colin's patience and instructional capability.

Decision Information Services got one thing out of it. They're writing a book for first users. Given Colin's understanding of computers and Stefan's ability to ask penetrating questions, I wouldn't be surprised to see it become the best book ever done on the subject.

So. That was one candidate. CCS seemed a very good system, and certainly a lot of them are being sold.

Tony, meanwhile, was putting together a Godbout (Compupro), with the dual 8085/8088 8-bit/16-bit capability. And Richard Frank, of Sorcim, had told me he uses Godbout units for all his development work because he considers them the most rugged and reliable systems available.

I stewed for a while, then called Bill Godbout. The result is that Zeke's big brother is sitting in the next room.

Understand that I've nothing against the CCS system. Quite the opposite. It's an excellent system and one of those I recommend. But the Godbout is more than that. It's built like a Mack truck. You couldn't hurt it with a nine-pound sledge. When it comes to rugged reliability, Godbout is *the* way to go for my money; and Tony says the bus is the quietest he's ever worked with.

What we have is the Godbout (Compupro) S-100 box, Godbout's disk controller and interfacer board, his 8085/88 processors as well as the Z80 processor (obviously you can't use both at the same time), 128K bytes of Godbout memory, and his system support vectored interrupt board. The disk drives are Qume double-sided double-density 8-inch drives with a Vista box and power supply.

I confess to being a bit worried about double-sided double-density disks. Asking for trouble, I thought; but I was wrong. With the Godbout controller and Qume drives my disks are as quiet as the Icom drives ever were—and they're wonderfully fast.

We're still shaking down the Godbout system. When it's all done and checked out, I intend to get another set of Qumes and install them in Zeke. More on both the Qumes and the Godbout another time.

WRITE Arrives

So. Zeke has two new friends, the Osborne and the Godbout; and he's about to get new disk drives.

There's more happening here at Chaos Manor. Tony Pietsch's new text editor, WRITE, is done at last. I'm using it to do this column.

Write is much like Electric Pencil without bugs. It ought to be: back when I started writing with computers, Pencil was the best editor around, and we put together a system to work with it. Unfortunately, Pencil has bugs. One, the tendency to drop letters at the ends of lines, is notorious. Another is a needlessly complex handshaking routine to couple Pencil to the Diablo (that one's so severe we use a special CP/M BIOS [basic input/output system] reserved just for Pencil). There are other problems, and over the years my partner Larry Niven and I have been making lists of Pencil's faults. We've also made notes on just what we'd like in a text creation editor, features that Pencil never had.

Anton (Tony) Pietsch has been collecting those notes and writing an editor to fit. In these columns and in pieces for BYTE's companion *onComputing*, now called *Popular Computing*, I've several times announced that it would be ready "real soon now." I'm happy to say that this time it's here and it works.

But this version will only work for systems with memory-mapped video display. For the Godbout that's simple enough: we use an Ithaca IA-1100 Write-Only Memory video output board addressed to hexadecimal address FC00, and a separate keyboard. The system normally operates through an H-19 terminal, but it can be rigged up to think that Ezekial is its terminal—or to work with my regular keyboard, putting the output up on my big 15-inch monitor screen

LOGO
Language of the 80's


Apple Logo and **Logo** introduce you to a dynamic new computer language that not only enables educators to make full and innovative use of the teaching potential of modern computers but also offers programmers an easy-to-use system of considerable power.


Readers of this book will see that the designers' vision of Logo as a virtually unlimited educational tool has now become a reality. Logo enables even young children to use the computer in rewarding, self-directed projects, while at the same time providing sophisticated users with a powerful and expressive general programming system. This book presents the reader with a complete guide to the exciting applications of this unique procedural language.


The author introduces programming techniques through Turtle Geometry—a series of fascinating exercises involving both Logo programming and geometric concepts. Later chapters illustrate more advanced projects that utilize Logo's sophisticated list-processing capabilities; these include the conversational DOCTOR program with its simulated psychotherapist and an INSTANT program with which parents and teachers can create a programming environment for preschool children. The book also contains reference material of enduring value to sophisticated users.

Get in on the ground floor of the burgeoning Logo movement with this comprehensive, detailed guide to the up-and-coming computer language of the Eighties!

This book is published in two versions: *Apple Logo* is for users of Apple Logo™ software (distributed by Apple Computer Company) and contains an appendix for users of TI Logo™. *Logo* is specifically for users of Logo software developed at MIT for the Apple II computer (distributed by Krell Software and Terrapin, Inc.). *Logo* also contains appendices that enable users of Apple Logo™ and TI Logo™ to carry out the projects in the book. Be sure to specify *Apple Logo* or *Logo* when ordering!









Apple Logo
$14.95
240 pages,
softcover, illustrated

Logo
$14.95
240 pages,
softcover, illustrated







ORDER TOLL FREE
800-258-5420

BYTE Books 70 Main St Peterborough, N.H. 03458

Circle 67 on inquiry card.

through the IA-1100. This is one of the advantages of an S-100 bus system. You can configure it to do nifty things like that.

Anyway, back to WRITE. Why is it so good that I'm willing to overlay some of my memory with video and have special boards, and such like? Can it be as good as *all that*?

It depends on what you want an editor for. I have no doubt that some of the really fancy "window-type" editors based on the MIT EMACS editor or built around special display boards may be more elegant in theory. Moreover, Micropro's Wordmaster remains, in my judgment, the best *programming* editor ever invented.

But for just sitting down and writing I want something as nearly invisible as can be made. I don't want to think about my editor. I don't want it to natter at me about line numbers and column numbers and such. I don't want it drawing funny lines across the screen to mark the ends of pages. I don't want it clicking disks at me, or running out of disk space and giving me no chance to change disks.

And if I want to pull some text in from another disk somewhere, I want to be able to do that. If I want to write some text out onto a safety disk, I want to be able to do that, too. If I want to print out my text on paper, I don't want to have to double-space it on the screen in order to get it double-spaced on the manuscript.

And for heaven's sake, if I fiddle around with a paragraph and snip off words here and add some there, I don't want to have to reformat the text! My editor should do that for me, silently, easily, automatically.

And that's what I have in WRITE. A nearly invisible editor. Add to that a really powerful macro-command capability, with loops and global searches and deletes, and an ability to link disk files so that the program treats them as if they were one enormous file.

Add it all up and it's WRITE, Writers' Really Incredible Text Editor. I'm sure I'll have more to say about it another time. Meanwhile, if your system will run Electric Pencil under CP/M, it will run WRITE, which will be able to read all your old Pencil files. (It will also read Wordstar and Wordmaster files.) If you do creative writing, you'll appreciate WRITE a *lot*. Highly recommended.

One more note on text editors. People ask me what I have against Wordstar. My answer is simple. Lots of friends use Wordstar, and I use it on the Osborne. It's a good editor to run on a terminal. Like all editors on terminals, the scrolling is ugly, but that's not Wordstar's fault. Micropro International continually works to add features and capabilities, and it's done well.


What Micropro can't do is correct the basic deficiency, which is the two-keystroke command system with delay in between strokes. When I want to delete a line, or scroll, or go from the beginning to the end of the text, I want to do that *right now*. I don't want to hit control-Q, then remember that "c" takes me to the end of the text unless I've hit the space bar in between, in which case—

Nor do I want a bunch of prompts and lines and menu items on the screen. OK, so you can suppress those menu descriptions—provided, of course, that you remember all the command items. But you won't. Wordstar has too many features. Now that would be all right if you could ignore most of them, but you can't. They take up single-stroke control characters so that there are none left for the functions you want to have happen *fast*. In contrast, WRITE's approach is to use the single-strokes for such things as toggling insert/delete modes, opening a hole in the text for long insertions, and marking blocks of

COMPUTER WAREHOUSE

CALL TOLL FREE 1-800-528-1054

INTERNATIONAL DEALER INQUIRIES INVITED



ATARI

Special 32K 800 System	
800 w/32K, recorder, star raiders, joysticks	Call
Above w/48K	Call

800 (16K)	$670
400	$340
810 Disk Drive	$440
825 Printer	$590
850 Interface	$170
410 Recorder	$ 75
830 Modem	$155
16K Memory	$70
32K Memory	$125

MODEMS

Novation

CAT	$140
D-CAT	$155
Apple Cat II	$349
Auto Cat	$235

PRINTERS

C. Itoh	
F-10 — Parallel	Call
F-10 — Serial	Call
55CPS — Series	Call
Prowriter	Call
Datasouth	
DS 180	$1260
Diablo	
630 RO w/Tractors	$2260
630 RO wo/Tractors	$2050
Epson	
MX-80	Call
MX-80 F/T	Call
MX-100	Call
Infoscribe	
500	Call
1000	Call
NEC	
PC-8023A	Call
3510	$1690
7710	Call
7720	Call
Okidata	
Microline 80	$330
Microline 82-A	$455
Microline 83-A	$740
Microline 84	Call
Paper Tiger	
560G	$1050
Texas Instruments	
810 Basic	$1275

MONITORS

Zenith	
12" Green Screen	$115
Amdek	
Video 100	Call
Video 300	Call
Color I	Call
Color II	Call

SPECIAL WORD PROCESSING SYSTEM

Altos 8000-2, Televideo 950, Diablo 630RO, Word Star, Cables	$5830
above w/TELEVIDEO 910	$5500

VIDEO TERMINALS

Adds	
Viewpoint	$530
Altos	
Altos I	Call
Soroc	
IQ 120	$630
IQ 130	Call
IQ 135	Call
IQ 140	Call
Televideo	
910 C	$570
912 C	$675
920 C	$735
925 C	$730
950 C	$915
Zenith	
Z-19	$680

DISKETTS

Elephant	
5¼" 0. Sector (100)	$215
Scotch	
5¼" 0.10.16 Sector (100)	$250
8" 0.32 Sector (100)	$260

COMPUTERS

Altos	
ACS 8000-15	$3850
ACS 8000-2 w/CPM®	$2650
Alspa	
ASCI-1	Call
ASCI-2	Call
California Computer Systems	Call
IBM	
Personal Computer	Call
NEC	Call
Northstar	
Advantage	$2990
Horizon II 64K QD	$2690
Televideo Systems	
System I	$2255
System II	$5045
TS-802	$2700
TS-802H	$5050
Zenith	
Z-89 48K w/CPM®	$2160
Z-90 64K w/CPM®	$2385
Both above w/supercalc	

DISK DRIVES

Lobo	
Apple 1st Drive	$400
Apple 2nd Drive	$350



2222 E. Indian School Rd. • Phoenix, Arizona 85016
Order Line: 1-800-528-1054
Other Information: 602-954-6109





Store Hours: Tues.-Fri. 10-5 MST Saturday 10-2 MST

Prices reflect 3% cash discount. Product shipped in factory cartons with manufacturers warranty. Add 2% a minimum of $5 for shipping and handling.

Personal checks will delay shipping two weeks.
Prices & availability subject to change without notice.

text and moving them; and, much as Wordmaster does, it allows you to use the macro-command capability for all the really complicated stuff. WRITE also has the menu available at any time: simply hit Escape and you'll see a whole list of instructions, pages of them if you like. But you don't see them unless you want to. I wish Wordstar had taken that approach.

I do recommend Wordstar for some purposes. First, it works on a terminal. Because it knows where the ends of pages are, it can do indexing. It formats on screen; what you see is what you get, an intolerable disadvantage when what you want is a simple double-spaced manuscript (who wants his *on-screen* text double-spaced?) but a real boon if you're publishing a newsletter or other matter requiring holes for illustration. It has a good mail-merge utility. If you can use any of those features, Wordstar is the only program that has them.

Incidentally, there are a couple of candidates for Wordstar's crown, one of them being MINCE (acronym for MINCE Is Not Complete EMACS) which emulates EMACS, the MIT (Massachusetts Institute of Technology) full-screen editor and is certainly the best editor if you want to write LISP programs. MINCE works on terminals (but not with memory-mapped video; at least I've never been able to get it running on Zeke). Now that the Godbout with the H-19 is up and running, we'll have a more thorough report. But when it comes to creating text, you won't beat WRITE. Or so say I.

muSimp/muMath

Some time ago, I got a copy of muSimp/muMath from the Soft Warehouse. Marketing of these programs has since been taken over by Microsoft, which has probably enhanced the documentation—at least it usually does.

There's nothing quite like muMath [For another review see "The muSimp/muMath-79 Symbolic Math System" by Gregg Williams, November 1980 BYTE, page 324]. The basic concept comes from MACSYMA, the symbolic-algebra programs continually under development at MIT's computer laboratories, which run on the DEC PDP-10. Obviously, there is no way to put the full power of a PDP-10 into a microcomputer—although the Godbout 8085/88 comes closer than I would have thought possible a few years ago.

MuMath consists of a core plus a whole series of auxiliary routines. The programs are written in LISP, but you don't have to know LISP to use them. (It would help, though. Boy would it help.) MuSimp is another package of routines which will also work with muMath. Together they will do a surprising lot of useful work. You could, for example, write a Visicalc in muSimp/muMath, and I suspect it would work quite well. There are also examples of how to write a database system using them.

In other words, muSimp/muMath have a lot more power than appears on the surface (or, indeed, is hinted at in the advertisements).

Their primary purpose, though, is to do symbolic math. And here I have to confess a fault. When I *first* got muSimp/muMath, I tended to compare them to MACSYMA, and of course these programs written for 8-bit microprocessors came up wanting. How could they not? What I should have done was find someone who never had access to MACSYMA and ask what she thought of them, and recently that's what I did.

"Wonderful," said my lovely friend. "I've never even suspected you could do things like that on a computer.

$389.

Made by Seikosha, AXIOM's new GP-100 is the finest printer a little money can buy. It uses standard 8-1/2 x 11 paper and has AXIOM's fabulous graphics interfaces for Apple, TRS-80, Atari, PET, HP and more! See the GP-100 at your AXIOM dealer today!

Seikosha is the leading company of the worldwide Seiko Group.



AXIOM CORPORATION

1014 Griswold Avenue, San Fernando, CA 91340 • Telephone: (213) 365-9521 • TWX: 910-496-1746

Circle 47 on inquiry card.

User's Column

Items Reviewed

Ashton-Tate
Suite 1510
3600 Wilshire Boulevard
Los Angeles, CA 90010
(213) 204-5570

WRITE (Writers' Really Incredible Text Editor)		$395

California Computer Systems
250 Caribbean Drive
Sunnyvale, CA 94086
(408) 734-5811

Model 2210A S-100		$2350

Compupro-Godbout Co.
Oakland Airport, CA 94614
(415) 562-0636

8085/8088 Dual Processor	6 MHz	$425
	8 MHz	$525

Cornucopia Software
POB 5028
Walnut Creek, CA 94596
(415) 524-8098

Microproof	TRS-80 Model I or III	$89.50
	TRS-80 Model III or CP/M	$149.50
	Optional Correcting Feature	$60

Innovative Software Applications
260 Sheridan, Suite 300
Palo Alto, CA 94306
(415) 326-0805

Spellguard 2.0		$295

Micropro International Corp.
1299 Fourth Street
San Rafael, CA 94901
(415) 457-8990

Wordstar 3.0		$495

Microsoft
400 108th Avenue NE, Suite 200
Bellevue, WA 98004
(206) 828-8080

muSimp/muMath	CP/M and Apple	$250
BASCOM BASIC Compiler	CP/M and Apple	$395

Osborne Computer Corp.
26500 Corporate Avenue
Hayward, CA 94545
(415) 887-8080

Osborne 1 portable computer		$1795

Workman & Associates
112 Marion Avenue
Pasadena, CA 91106

PDATA Minimum Data Base		(postpaid) $84.50

TIME MANAGER
FOR APPLE* II AND II PLUS
LIST 150.00
125.00

APPLE® SOFTWARE

MICROPRO
WORDSTAR* 245.00
SUPERSORT* 130.00
MAILMERGE* 85.00
DATASTAR* 207.00

HAYDEN
APPLESOFT COMPILER . 145.00

MICROSOFT
CP/M®
BASIC COMPILER 315.00
TASC APPLESOFT® COMPILER 150.00
FORTRAN 80 .... 165.00
COBOL 80 .... 550.00
ALDS 105.00
ADVENTURE 24.95
OLYMPIC DECATHALON 21.95

Microhouse™ continues to feature the best savings on the best software.

TERMINALS

TELEVIDEO
950 .... CALL
925 .... CALL
920 .... CALL
912 .... CALL
910 .... CALL

PRINTERS

C.ITOH
PRO/WRITER SERIAL ... 650.00
PRO/WRITER PARALLEL 535.00
STARWRITER I SERIAL .... CALL
STARWRITER I PARALLEL . CALL
ALL C. ITOH PRINTER ACCESSORIES .... CALL

EPSON
MX-100 .... CALL
MX-80FT .... CALL
MX-80 .... CALL
EPSON GRAFTRAX .... CALL
ALL EPSON PRINTER ACCESSORIES .... CALL

ANADEX
DP-9501 .... CALL
DP-9500 .... CALL
DP-9001 .... CALL
DP-9000 .... CALL
DP-8000 .... CALL
DP-8000 for APPLE .... CALL
ALL ANADEX PRINTER ACCESSORIES .... CALL

OKIDATA
MICROLINE 84 .... CALL
MICROLINE 83A .... CALL
MICROLINE 82A .... CALL
MICROLINE 80 .... CALL

APPLE® ACCESSORIES

MOUNTAIN COMPUTER
MULTI I/O 178.00

VIDEX
VIDEOTERM 290.00
KEYBOARD ENHANCER . 105.00

MICROSOFT
Z-80 SOFTCARD 299.00
16K RAMCARD 150.00

MODEMS

HAYES
CHRONOGRAPH

RS-232 COMPATIBLE CLOCK/CALENDAR FOR SMALL COMPUTERS. ADDS DIMENSION OF PRECISE TIME-KEEPING TO ALL RS-232-C COMPATIBLE COMPUTERS. USED IN CONJUNCTION WITH USER-DEVELOPED SOFTWARE, THE CHRONOGRAPH CAN LOG REPORTS AND PROGRAMS BY DATE AND TIME. COMPUTER ALARM FEATURE. STAND ALONE UNIT, POWERED INDEPENDENTLY, BATTERY BACK-UP AND WRITE PROTECT SWITCH.

LIST: 249.00
208.00

SMARTMODEM 230.00
MICROMODEM II (APPLE) 307.00

NOVATION
APPLE-CAT 325.00
LIST: 389.00
AUTO-CAT 213.00
D-CAT 156.00

CP/M® SOFTWARE

ASHTON·TATE
dBASE II Version 2.0 .... 599.00

VISICORP
VISICALC† .... CALL
VISIDEX† 159.00
VISIFILE† 200.00
VISIPLOT† 149.00
VISITERM† 128.00
VISITREND-VISIPLOT† ... 220.00
DESKTOP PLAN II† 160.00

SUPERSOFT
TERM II 131.00
DIAGNOSTICS II 84.00
DISK DOCTOR 84.00
FORTRAN 218.00
SSS FORTRAN with RATFOR 285.00
TINY PASCAL 74.00

MICROSOFT
BASIC 80 .... 285.00
BASIC COMPILER 315.00
COBOL 80 .... 568.00
FORTRAN 80 .... 345.00
muSIMP-muMATH 215.00
MACRO 80 .... 140.00

MICROPRO
WORDSTAR 3.0* 299.00
SUPERSORT* 170.00
MAILMERGE* 105.00
DATASTAR* 244.00

How long has this been going on?"

I shrugged.

"You mean I went through three semesters of calculus and did ALL THOSE PROBLEMS while you had a computer program that would do differentiation and integrals? And I mashed through Physics I and II and solved problems with a hand calculator when all that time Ezekial could have done my homework?" By now she was screaming.

"Uh, well—" Under the circumstances I did the only sensible thing a man could do. I hid behind my wife.

But my lovely friend did have a point. True, muSimp/muMath are limited in what they can do, but they can do differentiation, integrals, and algebra. They can factor and expand polynomials. They can do matrix operations and simplify equations, and do it all symbolically, the way you'd mess around with the equations using pencil and paper.

The programs aren't perfect. They tend to run out of memory easily. The way to escape that is to set up a kind of subprogram consisting of those elements of muSimp/muMath that you need for your particular problem, leaving out all the parts that won't affect what you're doing. For example, you can configure a system that understands trigonometry and complex numbers but doesn't know that matrices and integrals exist. And so forth.

There are other limits. The documentation isn't exactly encrypted, but it's pretty dense. You really have to want to use the programs to dig your way through that stuff, and as I said earlier, it would help a lot if you understood LISP. The authors of the muSimp documents plainly do understand LISP, and although they don't expect you to, they keep hoping you will.

Still in all, there's no real competition for muSimp/muMath. If you want to do symbolic algebra, if you want to use your computer to help you get through Calculus 102 and Physics 203, then you probably need muSimp/muMath.

Recommended for those who need it, with reservations as noted.

BASCOM Improves

More good news. Microsoft has done it again. It has improved its BASCOM BASIC Compiler.

What Microsoft has done is twofold: it's added program CHAINing with COMMON storage, meaning that you can break a program apart into pieces and execute it in parts, passing variables to each chunk as called. This greatly reduces the size of the program code that must be in memory at a given time, which means that it saves free memory and that you can run bigger programs with more variables.

Second, Microsoft has greatly cut down on the run-time package, so the total size of the programs is—or can be—smaller, and also larger programs can be compiled and linked.

More good news. Microsoft has partially dropped the restrictive licensing provision that made you pay a royalty on any program you sold that had been compiled with BASCOM.

The bad news on that front is that it has dropped the royalty requirement only for the *old* BASCOM; if you want to use the new, with the CHAIN and COMMON keywords and smaller run-time package and all that nifty stuff, you still have to pay for each copy you sell. Alas. But I suspect free enterprise will end that; it's only a matter of time.

Meanwhile, the new BASCOM is very nice indeed. Take a trivial example: an old Star Trek game I've been playing with. As you might suspect, my Star Trek is the *ultimate* game, with invisible Romulans, and shields for the Klingons, and enemy bases, and attacks on Federation bases, and Federation trading ships, and black holes, and—well, you get the idea.

The game was originally written in EBASIC, a public-domain precursor to Gordon Eubanks' CBASIC. I added to it and translated it into CBASIC, but eventually the program outgrew that. Besides, it was getting awfully slow. What I wanted to do, therefore, was

INCREASE SALES OF CP/M®


ANYONE CAN USE CP/M WITH SUPERVYZ

SUPERVYZ is a revolutionary software concept that serves as a mediator between the user and CP/M, requesting information in plain English and translating the response into the form CP/M recognizes. Users are led from one application to another in a courteous and step-by-step sequence of menus. Aided by descriptive error messages and computer-assisted tutoring, the operator avoids mistakes and is advised of the next step in a polite and friendly manner.

EXPAND YOUR MARKET AND LOWER COSTS

As a Dealer, SUPERVYZ allows you to sell CP/M computers and application software to non-technical markets, without the added expense of teaching the operating system. EPIC supplies the menus or you create your own to meet the exact needs of your customers. Because SUPERVYZ is compatible with over 2,000 programs and 300 computers, you can bundle software from different suppliers and SUPERVYZ does the teaching. This eliminates costly after-the-sale handholding.

For further information about EPIC SUPERVYZ, call or write us today.





Supervyz is a trademark of Epic Computer Corporation. CP/M is a Trademark of Digital Research.



Epic Computer Corporation
7542 Trade Street
San Diego, CA 92121
Tel. 714-695-3560

NOW SOLD THROUGH DISTRIBUTORS
IN POPULAR FORMATS
800-421-0814
DEALERS ONLY PLEASE

Circle 172 on inquiry card.

translate it into Microsoft BASIC and compile it; but I couldn't because the program was just too large. I could break it into pieces for the Microsoft interpreter, but that was even slower than CBASIC.

Comes new BASCOM and I've done it. Now I have a setup program which invents the game universe and makes the maps; then it calls in another program which processes commands; and every now and then still another program comes in and massages the data. It all works, letting me have a Star Trek so complicated that even I am beginning to think it's finished.

Anyway, that's how the new compiler works. On a more serious note, it will compile my tiny database.

And here I have a problem. Should I review software that I have written? Certainly I have an obligation to tell you it's mine. I try to be objective, but certainly I could overlook flaws in my own programs.

Minimum Data Base

Minimum Data Base grew like Topsy. It started a long time ago with a thing called the People's Data Base by Yogesh Gupta and others. It was, in fact, the very first program I ever got running. When I bought Zeke, Mac Lean and Tony Pietsch handed me Debbie (a Microsoft-like BASIC that came with the Icom disk drives and, ugh, FDOS operating system); and they handed me a listing of the People's Data Base.

"Get that running," they ordered.

So I tried. Lord I tried. And I certainly learned that semicolons are not colons, that single quote marks are not double quotes, that BASIC has a *very* precise syntax and improvements are not tolerated, and that I needed to keep my temper well enough so as not to throw anything heavy at Ezekial.

Eventually I got it running. It wasn't a bad little program; more to the point, it was well structured, with a main routine and a series of subroutines, some of which themselves called other subroutines. There were no GOTO statements except within sub-

routines. None of this grasshopper jumping about that so ruins BASIC's reputation.

The program was limited, and soon I ran into the limits. So I began to improve it. The sort algorithm used was a bubble sort. That wouldn't do, so I put in a Shell-sort algorithm. There were no disk operations. I fixed that. The command menu was processed inefficiently, so I rewrote that and renamed most of the commands. The "delete entry" system was asinine, and I set up an entirely new way to handle that. And so forth.

Year after year the silly thing grew—and I found I was using it for *everything*. It keeps phone numbers and addresses. It keeps the list of members of the Space Council and the L-5 Board. When the Boy Scouts go hiking, a PDATA (after the original People's Data Base) lets me make lists by meal (what are we eating for Thursday dinner?), or by who is carrying what (who's got Friday's lunch?), and all that. When I do an anthology, a PDATA file keeps track of who has how many shares and what they've been paid. When new royalties come in, it calculates what the new payment is and then writes the cover letter, makes mailing labels, and writes the checks.

Versatile. And darned easy to use.

"You ought to sell it," said Barry Workman of Workman Associates. "Let me handle it for you. It won't make you rich, but what do you care? People out there need the program."

"Maybe," said I. "What if—gulp—what if someone reviews it and doesn't like the documentation? I can stand not being thought an elegant programmer, but—"

"Don't worry about it. I learned to use it, didn't I?"

I shrugged. "Also, look, there's very little new in there. True, I didn't steal it from Gupta and the People's Data Base; there probably aren't ten lines of code left from their original. But it's all very straightforward code. Nothing elegant at all."

"That's the value," Workman said. "Look, lots of people want a general-purpose do-all program, which is what this is. I notice that when you did all that statistical analysis, you used your PDATA thing."

"Yeah."

"And your Christmas cards are on it, and you used to keep your checkbook balance—"

"I don't do that any more. I use a Journal now."

"Yeah, but you used to," Barry said.

Eventually he wore me down. So. I mention PDATA, a small database and do-all, available from Workman Associates. If I didn't already have it, I'd probably buy it; I can't conceive of living without it, and I wouldn't have time to write it again.

It *is* useful. And it's in both CBASIC and Microsoft BASIC, with the Microsoft version compilable by BASCOM—except that BASCOM will not compile the general program because it won't compile anything with arrays defined by variables. PDATA creates databases and dimensions them according to the number of fields you've specified, but BASCOM wants to know those dimensions in advance. This means that you can compile FONES (the telephone program) or NAND (name and address) or any set whose structure you know in advance, but you can't just compile PDATA.

On the other hand, one reason PDATA is so useful is that you can run it interactively in interpreted Microsoft BASIC and write your own special-purpose routines (such as the one that determines what my contributors ought to be paid, given the total royalty). If you know BASIC at all, you can do a lot with PDATA.

So. Useful, yes. But it is not a rival to dBase II and doesn't claim to be. All it claims to be is a very useful little general-purpose data handler that provides a structure to let you mash data. And it will do all the statistics taught in elementary stat courses: sums, averages, standard deviations, medians, means, and correlations between two variables.

I've always liked it, and I'm happy to share it.

Next time, more on Zeke's new friends and a lot more on financial programs. ■

Circle 62 on inquiry card. →

Screen Director

Screen Director™ retrieves and displays any standard image file on your Apple's video monitor, large screen TV or color printer. For only $150, Screen Director™ gives you a filmmaker's finesse in boardroom presentations, management briefings and demonstrations for clients.

With Screen Director™ you can scroll forwards and backwards through any color displays, with dissolves or cuts from one image to the next — all at the touch of two buttons. You can even enhance your **Apple Business Graphics** with title slides in a variety of fonts and colors.

Spice your Apple with cinema.

Screen Director™ includes both the two-button controller and all necessary software.

For information on dealers of Screen Director™ in your area, call (617) 491-3377.



Business & Professional Software, Inc.
143 Binney Street
Cambridge, MA 02142

Screen Director™ is a product of Business & Professional Software, Inc., creators of **Apple Business Graphics.**
Apple is a trademark of Apple Computer, Inc.

Handbook of Digital IC Applications

by David L. Heiserman
Prentice-Hall Inc.
Englewood Cliffs, NJ
1980, 428 pages, $21.95

Reviewed by
Clifford R. Mosley
Network Test
and Training Facility
Building 25, Code 850.2
Goddard Space Flight Center
Greenbelt, MD 20771

Ordering a book without first reading the fine print is a risky thing to do. I have found that getting what you order is not always the same as getting what you want. When I first saw the title of this book, I thought, naturally enough, "This is a book full of digital IC application projects." Because I'm always anxious to build new gadgets, I promptly ordered the book. When it arrived, I tore open the package, flipped open the book, and found myself totally let down! It was not a collection of projects, but a book about basic digital concepts and devices.

But I had paid good money for the book, and the least I could do was give it a closer look. When I overcame my initial prejudice, I discovered that it did, in fact, have some very good characteristics.

Handbook of Digital IC Applications appears to have been primarily designed as a textbook for a technical school or intermediate engineering course in digital design. At the end of each segment, Heiserman has included an exercise on key points to encourage further study. Answers to selected exercises are included in the back of the book, allowing readers to check the accuracy of their quiz answers. Despite the fact that the book is targeted for a technical audience, I feel that a serious hobbyist with a fair math background could learn a great deal. The text is supported by many helpful illustrations and is written in a pleasantly explicit style.

Basic combinational logic (AND, OR, INVERT, etc.) and Boolean algebra are the dominant subjects of the beginning chapters of the book. These fundamentals are discussed in a little greater detail than in most books of this type. Heiserman then moves into a discussion of digital hardware, detailing the design aspects of interfacing TTL (transistor-transistor logic) and CMOS (complementary metal-oxide semiconductor) logic with some of the more common input and output devices. He also discusses some of the problems encountered when combining TTL and CMOS logic within the same system and describes flip-flops, counters, timers, code converters, display drivers, AOI (AND-OR-INVERT) circuits, and other similar digital devices.

In the final chapters, Heiserman introduces more complex devices such as data selectors, data multiplexers/demultiplexers, parity generators/detectors, arithmetic circuits, and memory circuits.

One of the greatest strengths of the book is Chapter 11, where Heiserman uses a refreshing approach to present an application of the basic theory of the earlier chapters. He leads the reader through the design of a simple digital measuring system (in this case a frequency counter), developing each unit of the system as a separate block, then illustrating the process of integrating all of the blocks into a complete system.

The book has some weak points. It lacks a glossary, and the index is a little skimpy. Both are important in a technical book in order to quickly locate information. These faults reduce the overall effectiveness of the book as a learning aid.

Also, some minor technical (or possibly editing) errors tend to confuse the reader. One example can be found in the first chapter, where the typical power consumption of a CMOS gate is listed at 10 ns (nanoseconds). As it is standard practice to measure power consumption in units of watts, I assume that Heiserman intended the text to read 10 nw (nanowatts).

Conclusion

Handbook of Digital IC Applications is well written and superbly illustrated and would make an adequate digital-design textbook or tutorial for a serious hobbyist. Although it wasn't the book I thought I had ordered, I am nevertheless pleased to have it as a part of my reference library. ■

1982 NATIONAL COMPUTER CONFERENCE

JUNE 7-10 • ASTRODOMAIN • HOUSTON, TEXAS

Computer Image Processing: University of Southern California Institute for Physics and Imaging Science

A D V A N C I N G   P R O F E S S I O N A L I S M

Dramatic strides have been made in computer technology, and at NCC '82, you'll have a unique opportunity to learn about them. Eighty technical sessions will highlight nine specialized areas, and plenaries will feature four of this country's most distinguished speakers.

You'll also see the most impressive display of modern computer technology in the world. More than 650 companies in some 3,200 exhibit booth units will provide you with a panorama of the industry's newest products and services!

And the 17 Professional Development Seminars, constituting a conference within a conference, will probe five subject tracts of vital interest to you.

So, call **800-556-6882** today to pre-register with a major credit card. You'll save time and money, and you can get help with your airline reservations as well.

Then, attend the 1982 National Computer Conference and advance your professionalism.



In Rhode Island and outside the continental U.S., call 401-884-9500.

Sponsored by:
American Federation of Information Processing Societies, Inc.;
Association for Computing Machinery; Data Processing Management Association; IEEE Computer Society; Society for Computer Simulation.

Designing the Star User Interface

The Star user interface adheres rigorously to a small set of principles designed to make the system seem friendly by simplifying the human-machine interface.

Dr. David Canfield Smith, Charles Irby, Ralph Kimball, and Bill Verplank
Xerox Corporation
3333 Coyote Hill Rd.
Palo Alto, CA 94304

Eric Harslem
Xerox Corporation
El Segundo, CA 90245

In April 1981, Xerox announced the 8010 Star Information System, a new personal computer designed for offices. Consisting of a processor, a large display, a keyboard, and a cursor-control device (see photo 1), it is intended for business professionals who handle information.

Star is a multifunction system combining document creation, data processing, and electronic filing, mailing, and printing. Document creation includes text editing and formatting, graphics editing, mathematical formula editing, and page layout. Data processing deals with homogeneous, relational databases that can be sorted, filtered, and formatted under user control. Filing is an example of a network service utilizing the Ethernet local-area network (see references 9 and 13). Files may be stored on a work station's disk, on a file server on the work station's network, or on a file server on a different network. Mailing permits users of work stations to communicate with one another. Printing utilizes laser-driven raster printers capable of printing both text and graphics.

As Jonathan Seybold has written, "This is a very different product: Different because it truly bridges word processing and typesetting functions; different because it has a broader range of capabilities than anything which has preceded it; and different because it introduces to the commercial market radically new concepts in human engineering." (See reference 15.)

The Star user interface adheres rigorously to a small set of design principles. These principles make the system seem familiar and friendly, simplify the human-machine interaction, unify the nearly two dozen functional areas of Star, and allow user experience in one area to apply in others. In reference 17, we presented an overview of the features in Star. Here, we describe the principles behind those features and illustrate the principles with examples. This discussion is addressed to the designers of other computer programs and systems—large and small.

About the Authors
These five Xerox employees have worked on the Star user interface project for the past five years. Their academic backgrounds are in computer science and psychology.

Star Architecture

Before describing Star's user interface, several essential aspects of the Star architecture should be pointed out. Without these elements, it would have been impossible to design an interface anything like the present one.

The Star hardware was modeled after the experimental Xerox Alto computer (see reference 19). Like Alto, Star consists of a Xerox-developed, high-bandwidth, MSI (medium-scale integration) processor; local disk storage; a bit-mapped display screen having a 72-dots-per-inch resolution; a pointing device called the "mouse"; and a connection to the Ethernet network. Stars are higher-performance machines than Altos, being about three times as fast, having 512K bytes of main memory (versus 256K bytes on most Altos), 10

CMC INTERNATIONAL

Price Performance Reliability



CMC IS MEETING TODAY'S HIGH STANDARD OF EXCELLENCE WITH TOSHIBA, CMC'S OWN **SUPERFIVE** AND **SUPERTEN**, 5- AND 10-MBYTE MICROCOMPUTERS, AND OTHER FINE PRODUCTS

TOSHIBA DESKTOP COMPUTERS

CMC International offers dealers the new Toshiba computer line, CP/M® -based micros with lots of flexibility...your choice of one or two drives, either 5¼ or 8 inch. Toshiba computers come with C/PM, Microsoft Basic80 and CBasic® . We're proud to offer a system with day-in, day-out dependability, backed by one of the world's largest electronics manufacturers. And, we offer a comprehensive dealer program including parts and module inventory, and prepaid freight for warranty repairs (if you ever need it).

ALSO DISTRIBUTING:

- Corvus
- NEC
- Dysan
- Epson
- Verbatim
- Tandon
- Seagate
- MPI
- Superbrain
- Compustar
- C.Itoh
- MicroPro
- Accounting Plus
- Peachtree
- dBase II

YOUR STOCKING DISTRIBUTOR



A Division of Computer Marketing Corporation

CMC INTERNATIONAL

11058 Main, Suite 125 Bellevue, WA 98004 PHONE (206) 453-9777

T-200 64k RAM, 80x24 12'' green phosphor screen, complete with CP/M, MBasic80 and CBasic.

Model 3	**Model 2**
One 5¼''280k Disk Drive	Two 5¼'' 280k Disk Drives
List $3700	List $4500

T-250 64k RAM, 80x24 12'' screen, complete with CP/M, MBasic80 and CBasic.

Model 3	**Model 2**
One 8'' 1mbyte Disk Drive	Two 8'' 1mbyte Disk Drives
List $4750	List $5750

EXCELLENT DEALER DISCOUNTS

To Order Call Toll Free

1-800-426-2963

TELEX: 152 556 SEATAC

Circle 452 on inquiry card




Photo 1: *A Star work station showing the processor, display, keyboard, and mouse.*




Photo 2: *The Star keyboard and mouse. Note the two buttons on top of the mouse.*

or 29 megabytes of disk memory (versus 2.5 megabytes), a 10½- by 13½-inch display screen (versus 10½ by 8 inches), and a 10-megabits-per-second Ethernet (versus 3 megabits). Typically, Stars, like Altos, are linked via Ethernets to each other and to shared file, mail, and print servers. Communication servers connect Ethernets to one another either directly or over telephone lines, enabling internetwork communication. (For a detailed description of the Xerox Alto computer, see the September 1981 BYTE article "The Xerox Alto Computer" by Thomas A. Wadlow on page 58.)

The most important ingredient of the user interface is the bit-mapped display screen. Both Star and Alto devote a portion of main memory to the screen: 100K bytes in Star, 50K bytes (usually) in Alto. Every screen dot can be individually turned on or off by setting or resetting the corresponding bit in memory. It should be obvious that this gives both computers an excellent ability to portray visual images. We believe that all impressive office systems of the future will have bit-mapped displays. Memory cost will soon be insignificant enough that they will be feasible even in home computers. Visual communication is effective, and it can't be exploited without graphics flexibility.

Ten reasons why your floppy disk should be a BASF FlexyDisk.®



BASF

BASF FlexyDisk®

More than four decades of experience in magnetic media – BASF invented magnetic recording tape, the forerunner of today's wide range of magnetic media, back in 1934, and was the first independent manufacturer of IBM-compatible floppy disks.

Tough Tyvek sleeve – no paper dust, no static electricity.

Special self-cleaning jacket and liner help eliminate data errors and media wear and tear.

Center hole diameter punched to more accurate standards than industry specifications, for top performance.

Bi-axially oriented polyester substrate – for uniform and reliable performance year after year.

Cross-linked oxide coating – for low head wear and long trouble-free media life.

Total capability – one of two manufacturers in the world that makes both 8″ and 5.25″ models, has tape and disk experience, and manufactures floppy disk drives.

Double lubrication – lubricants both in the formula and on the disk surface, to minimize media wear due to head friction.

Packaging to suit your requirements – standard flip-top box, Kassette 10® storage case, or bulk pack.

100% certification – every single disk is tested at thresholds 2-3 times higher than system requirements, to be 100% error-free.

For the name of your nearest supplier, write BASF Systems, Crosby Drive, Bedford, MA 01730, or call 617-271-4030.

BASF

Floppy Disks Mag Cards Cassettes Computer Tapes Disk Packs Computer Peripherals

Circle 49 on inquiry card.

There must be a way to change dots on the screen quickly. Star has a high memory bandwidth, about 90 megahertz (MHz). The entire Star screen is repainted from memory 39 times per second, about a 50-MHz data rate between memory and the screen. This would swamp most computer memories. However, since Star's memory is double-ported, refreshing the display does not appreciably slow down processor memory access. Star also has separate logic devoted solely to refreshing the display. Finally, special microcode has been written to assist in changing the contents of memory quickly, permitting a variety of screen processing that would not otherwise be practical (see reference 8).

People need a way to quickly point to items on the screen. Cursor step keys are too slow; nor are they suitable for graphics. Both Star and Alto use a pointing device called the mouse (see photo 2). First developed at Stanford Research Institute (see reference 6), Xerox's version has a ball on the bottom that turns as the mouse slides over a flat surface such as a table. Electronics sense the ball rotation and guide a cursor on the screen in corresponding motions. The mouse possesses several important attributes:

- It is a "Fitts's law" device. That is, after some practice you can point with a mouse as quickly and easily as you can with the tip of your finger. The limitations on pointing speed are those inherent in the human nervous system (see references 3 and 7).
- It stays where it was left when you are not touching it. It doesn't have to be picked up like a light pen or stylus.
- It has buttons on top that can be sensed under program control. The buttons let you point to and interact with objects on the screen in a variety of ways.

Every Star and Alto has its own hard disk for local storage of programs and data. This enhances their personal nature, providing consistent access to information regardless of how many other machines are on the network or what anyone else is doing. Larger programs can be written, using the disk for swapping.

The Ethernet lets both Stars and Altos have a distributed architecture. Each machine is connected to an Ethernet. Other machines on the Ethernet are dedicated as "servers"—machines that are attached to a resource and provide access to that resource.

Star Design Methodology

We have learned from Star the importance of formulating the fundamental concepts (the user's conceptual model) *before* software is written, rather than tacking on a user interface *afterward*. Xerox devoted about thirty work-years to the design of the Star user interface. It was designed *before* the functionality of the system was fully decided. It was even designed *before* the computer hardware was built. We worked for two years *before* we wrote a single line of actual product software. Jonathan Seybold put it this way, "Most system design efforts start with hardware specifications, follow this with a set of functional specifications for the software, then try to figure out a logical user interface and command structure. The Star project started the other way around: the paramount concern was to define a conceptual model of how the user would relate to the system. Hardware and software followed from this." (See reference 15.)

In fact, before we even began designing the model, we developed a methodology by which we would do the design. Our methodology report (see reference 10) stated:

> One of the most troublesome and least understood aspects of interactive systems is the *user interface*. In the design of user interfaces, we are concerned with several issues: the provision of languages by which users can express their commands to the computer; the design of display representations that show the state of the system to the user; and other more abstract issues that affect the user's understanding of the system's behavior. Many of these issues are highly subjective and are therefore often addressed in an *ad hoc* fashion. We believe, however,

WICAT 68000 MULTI-USER SYSTEM 150

STANDARD EQUIPMENT

68000 Processor
256KB RAM
10MB Winchester
5¼" Floppy Disk Backup
5 RS-232 C Serial Interfaces
Parallel Port
Multibus™
WICAT Operating System
Choice of One Language

HARDWARE OPTIONS

Graphics CRT
Up to 1.5MB RAM
Communications: Auto Answer and Auto Dial (1200 Baud)
Local Networking
Videodisc Interface

SOFTWARE OPTIONS

UNIX™ V/7
CP/M™ Emulator

LANGUAGE SUPPORT

PASCAL
C
FORTRAN
BASIC
APL*
COBOL
ADA™
LISP
Assembler

WICATsystems

P.O. Box 539 1875 South State Street Orem, Utah 84057 (801) 224-6400

Call or write WICAT Systems for additional information.

*UNIX is a trademark of Bell Labs. Multibus is a trademark of INTEL.
ADA is a trademark of the United States Dept. of Defense
CP/M is a trademark of Digital Research
APL is a product of the Computer Company

that more rigorous approaches to user interface design can be developed. . . .

These design methodologies are all unsatisfactory for the same basic reason: they all omit an essential step that must precede the design of any successful user interface, namely *task analysis*. By this we mean the analysis of the task performed by the user, or users, prior to introducing the proposed computer system. Task analysis involves establishing who the users are, what their goals are in performing the task, what information they use in performing it, what information they generate, and what methods they employ. The descriptions of input and output information should include an analysis of the various *objects*, or individual types of information entity, employed by the user. . . .

The purpose of task analysis is to simplify the remaining stages in user interface design. The *current task description*, with its breakdown of the information objects and methods presently employed, offers a starting point for the definition of a corresponding set of objects and methods to be provided by the computer system.

The idea behind this phase of design is to build up a new *task environment* for the user, in which he can work to accomplish the same goals as before, surrounded now by a different set of objects, and employing new methods.

Prototyping is another crucial element of the design process. System designers should be prepared to implement the new or difficult concepts and then to *throw away* that code when doing the actual implementation. As Frederick Brooks says, the question "is not *whether* to build a pilot system and throw it away. You *will* do that. The only question is whether to plan in advance to build a throwaway, or to promise to deliver the throwaway to customers. . . . Hence *plan to throw one away; you will, anyhow.*" (See reference 2.) The Alto served as a valuable prototype for Star. Over a thousand Altos were eventually built. Alto users have had several thousand work-years of experience with them over a period of eight years, making Alto perhaps the largest prototyping effort ever. Dozens of experimental programs were written for the Alto by members of the Xerox Palo Alto Research Center. Without the creative ideas of the authors of those systems, Star in its present form would have been impossible. In addition, we ourselves programmed various aspects of the Star design on Alto, but all of it was "throwaway" code. Alto, with its bit-mapped display screen, was powerful enough to implement and test our ideas on visual interaction.

Some types of concepts are inherently difficult for people to grasp. Without being too formal about it, our experience before and during the Star design led us to the following classification:

Easy	*Hard*
concrete	abstract
visible	invisible
copying	creating
choosing	filling in
recognizing	generating
editing	programming
interactive	batch

The characteristics on the left were incorporated into the Star user's conceptual model. The characteristics on the right we attempted to avoid.

Principles Used

The following main goals were pursued in designing the Star user interface:

- familiar user's conceptual model
- seeing and pointing versus remembering and typing
- what you see is what you get
- universal commands
- consistency
- simplicity
- modeless interaction
- user tailorability

We will discuss each of these in turn.

Familiar User's Conceptual Model

A *user's conceptual model* is the set of concepts a person gradually acquires to explain the behavior of a system, whether it be a computer

20,000 Programs For The IBM



Baby Blue CPU Plus and Baby Blue are trademarks of XEDEX Corporation.

Are Now Available Personal Computer!

INTRODUCING BABY BLUE CPU PLUS

Baby Blue CPU Plus is an accessory printed-circuit board for your IBM Personal Computer and special software on disk.


As far as normal PC DOS operations are concerned, Baby Blue acts just like any other normal, mild-mannered 64K byte random-access memory board.

But when you invoke a CP/M-80* program, Baby Blue becomes a second computer within your computer, letting you run thousands (literally thousands) of programs written for the CP/M microcomputer operating system.

CP/M, the first microcomputer operating system to gain wide acceptance, has been around since 1975. Not only has it played host to a lot of programs, but those programs are among the most useful, most sophisticated, most thoroughly tested and debugged, most proven programs ever written. More than 200,000 computers were field-testing those programs for you before the IBM Personal Computer even existed.

The total CP/M library is immense. It includes the best efforts of thousands of professional and advanced-amateur programmers. There are time managers, spreadsheet manipulators and professional-office packages. Languages — BASIC, of course, ALGOL, FORTRAN, C, Pascal, LISP, COBOL, PILOT, and FORTH, to name a few. Text editors, text formatters, full-blown word processors, spelling checkers and indexers. Utilities that will massage problem files so that they lie back and purr. Games, including chess, Reversi, Adventure and tournament-level Star Trek. Database managers. Accounting packages that can run a million-dollar business . . . Just about anything you can imagine.

The net result is an integration of CP/M programs into the PC environment that's so smooth, so transparent that you won't need to know or care which operating system a program was originally written for.






WordStar*, the popular CP/M word processor is among thousands of programs that can now be run on the IBM PC with Baby Blue.

Special Baby Blue Features:

- Additional 64K memory, fully available to PC DOS — looks just like the IBM 64K board to the system.
- Will accept CP/M programs on any of several popular 5¼" soft-sectored diskette formats.
- 63K of user memory is available for CP/M programs — 7K more than on any other popular machine.
- Files can be shared — CP/M and PC DOS programs can be mixed in a menu-driven system with common data files.
- IBM Personal Computer peripherals are supported — including keyboard, video boards, printer, Asychronous Communications Adapter.

ONLY **$600**

For only **$60** more than the cost of the IBM 64K Memory Board (**$540**) you get 64K of Memory PLUS an interface to over **20,000** programs!



Plug-in installation takes less than 5 minutes.

For more information call
(212) 247-1400

or write XEDEX Corporation
1345 Ave. of Americas, New York, N.Y. 10105

Circle 443 on inquiry card.

system, a physical system, or a hypothetical system. It is the model developed in the mind of the user that enables that person to understand and interact with the system. The first task for a system designer is to decide what model is preferable for users of the system. This extremely important step is often neglected or done poorly. The Star designers devoted several work-years at the outset of the project discussing and evolving what we considered an appropriate model for an office information system: the metaphor of a physical office.

The designer of a computer system can choose to pursue familiar analogies and metaphors or to introduce entirely new functions requiring new approaches. Each option has advantages and disadvantages. We decided to create electronic counterparts to the physical objects in an office: paper, folders, file cabinets, mail boxes, and so on—an electronic metaphor for the office. We hoped this would make the electronic "world" seem more familiar, less alien, and require less training. (Our initial experiences with users have confirmed this.) We further decided to make the electronic analogues be *concrete objects*. Documents would be more than file names on a disk; they would also be represented by pictures on the display screen. They would be selected by pointing to them with the mouse and clicking one of the buttons. Once selected, they would be moved, copied, or deleted by pushing the appropriate key. Moving a document became the electronic equivalent of picking up a piece of paper and walking somewhere with it. To file a document, you would move it to a picture of a file drawer, just as you take a physical piece of paper to a physical file cabinet.

The reason that the user's conceptual model should be decided *first*

HUNTINGTON COMPUTING

Softlights

By Fred Huntington

NEW

Computer Stocks & Bonds (Avalon Hill) $17.99
Star Blazer (Broderbund) $28.69
Tax Beater (Datamost) $116.89
R.E.A.P. (Datamost) $116.89
Time Manager (Microsoft) $134.99
Foosball (Sirius) $26.99
Twerps (Sirius) $26.99
Snake Byte (Sirius) $26.99
Audex (Sirius) $26.99
Photar (Softape) $26.99
Auto Atlas (CPU) $42.69
Worm Hole (Dakin5) $26.99
Electric Duet (Insoft) $26.99
CalcStar (Micro Pro) $179.99
Wordstar Training Guide (book) $17.99
Marauder (On-Line) $30.99
Sherwood Forest (Phoenix) $30.99
Zoom Grafix (Phoenix) $36.99
The Queen of Phobos (Phoenix) $30.99
GBS (Quality) $599.00
C ompucube (Stoneware) $26.99
DB Utility #2 (Stoneware) $84.99
DB Master Stat. (Stoneware) $84.99
Planetary Guide (Synergistic) $30.99
Atlantis (Synergistic) $36.99
Soft Seventy (Synergistic) $44.99
Castles of Darkness (Logical Choice) $30.99
Ceiling Zero (Turnkey) $26.99
The Gauntlet (Turnkey) $26.99
Survival Adv. (USA) $21.99
Apple Spice (Adv. Inter.) $26.99

AURORA

#4801 Executive Secretary $212.50
#4804 Hebrew II $50.99
#4805 Quicktrace $43.99
#4810 Versacalc 3.3 .... $84.99

BEAGLE BROS.

#3257 Alpha Plot $34.69
#3255 Doss Boss 3.2 .... $ 209
#3250 Doss Boss 3.3 .... $20.39
#3251 Game Pack #1 .... $20.39
#3252 Game Pack #2 .... $20.39
#3253 Game Pack #3 .... $20.39
#3254 Game Pack #4 .... $20.39
#3256 Utility City $25.89

CONDUIT

#7360 Algebra Drill & Practice I $125.99
#7367 Demo-Graphics $91.79
#7362 Group Velocity $44.49
#7368 SAMP – Survey Sample $70.19
#7364 Satellite Orbits $34.89
#7365 Scatter – Nuclear Scatter $34.89

MICRO LAB

#2253 Crown of Arthain $29.69
#2254 Madventure $21.19
#2262 Merger $42.29
#2259 Palace in Thunderland $21.19
#2263 Roach Hotel $30.69
#2260 SAT-English 1 .... $25.49
#2264 Tax Manager $131.99
#2261 U.S. Constitution $25.49

ON-LINE

#1120 Cranston Manor $29.69
#1104 Crossfire $26.29
#1126 The Dictionary $87.89
#1119 Expediter II Compiler $84.89
#1128 General Manager $87.89
#1109 Hi-Res Cribbage $21.19
#1103 Jaw Breaker $26.29
#1123 Lisa $67.89
#1129 Lisa Educational Pkg $105.49
#1125 MMS II $43.89
#1113 Missile Defense $25.39
#1111 Mouskattack $35.09
#1149 Pegasus II $25.39
#1121 Soft Porn Adventure $25.39
#1124 Speed ASM $33.89
#1122 Threshold $33.89
#1127 Time Zone $87.89
#1112 Ulysses $29.69
#1100 The Wizard & the Princess $28.89

SIRIUS

#1068 Beer Run $26.29
#1065 Cops & Robbers $29.69
#1067 Dark Forest $26.29
#1062 Epoch $29.69
#1061 Gorgon $33.89
#1069 Hadron $30.69
#1070 Joyport $67.39
#1055 Phantoms Five $25.39
#1056 Space Eggs $25.39

Time for our latest new program for the Apple®, **Computer Almanac.** Written by David Carman, an honest-to-goodness weatherman, Computer Almanac is a diverse collection of well thought-out programs. It contains sunrise and sunset times, weather forecasts for any year, a wind chill chart, lightning safety rules, a super-duper extra easy to use loan amoritization program that will print out in 80 columns, health chapter (including a nifty calorie counter), a vacation planner, a biorythm chapter (needs printer) and more.

We're very proud of this program and think that at **$24.95**, it's one of the best bargains in the software market today. Also, don't forget our other new program for the Apple®, **Understand Yourself,** also **$24.95.** Dealer inquiries welcome.

Speaking of good programs, we'd like to recommend for either home or school use **Crossword Magic** by L&S Computerware. A super outstanding program with nothing else even close, we thought the original price of **$79.95** was a little steep. So we were able to convince them to lower it to **$49.95,** which is still a little steep for a crossword program, no matter how fantastic. So, to prove a point, we've set the price at **$39.99.** Now it's a bargain.

It will work with most graphic printers, including the Epson, with or without the Grappler.

GREAT GRANDMA HUNTINGTON

Great Grandma Huntington told me when I was a lad that I should always buy my computer media as a diskcount. She also said that a single density disk in the hand was better than a double density disk in the bush.

Great Grandma Huntington said a lot of things, many of which I can't remember. So we're having a contest to see who can come up with the best Great Grandma Huntington sayings. All entries must be postmarked no lat e than June 30, 1982 ad shou ldbe addressed to:

GREAT GRANDMA HUNTINGTON
CONTEST
P. O. Box 787
Corcoran, CA 93212

The top two entries will receive genuine Epson LC Digital Quartz watches (yep, made by the same people who make those great printers). Winners will be used in future Softlights columns. All entries become the property of Huntington Computing and will not be returned. The worst ones may be used in future advertising.

DISKS

Elephant Disks 10/**24.99**
Verbatim 10/**28.99**
(with plastic box)
Maxell 10/**36.99**

PENDULUM PRESS

#6761 20,000 Leagues Under The Sea $29.69
#6758 Time Machine $29.69
#6759 Tom Sawyer $29.69
#6760 Treasure Island $29.69

SPECTRUM

#7555 Action Adventure Game Series $25.39
#7552 Color Calendar $25.39
#7554 Home Finance Pak I $42.29
#7550 Microaccountant $42.49
#7561 Numerical Analysis $17.49
#7560 Statistical Analysis I $17.49

STRATEGIC SIMULATIONS

#1014 Battle Of Shiloh $33.89
#1012 Computer Baseball $33.89
#1002 Computer Quarterback $35.99
#1016 Napoleon's Campaign $52.69
#1015 Tigers In The Snow $33.89
#1007 The Warpfactor $33.89

MISCELLANEOUS

#2651 Apple Doc (Southwestern) $43.99
#6100 Apple Grade Book (J&S) $26.49
#3350 Apple Letter Perfect (LJK) $127.49
#5780 Apple Word Processing (book) (Que) $17.49
#3700 Asteroid Field (Cavalier) $22.49
#6707 Astronomy I (Ed. Courseware) $28.09
#5453 Basic Scientific Sub-Routines Vol II (book) $21.07
#2008 Beneath Apple Manor (Quality) $17.49
#3200 Brain Surgeon (Nikrom) $42.39
#3702 Bug Attack (Cavalier) $26.29
#6101 Computer Chemistry (J&S) $139.99
#2752 Creative Finance (Howardsoft) $127.49
#4401 Cyborg (Sentient) $28.99
#2294 Datadex (IUS) $250.69
#3452 Decision Master (Syntonic) $35.09
#4750 Disk Prep (Sympathetic) $21.19
#218 Dosource 3.3 (Lazer) $33.89
#2290 Easy Writer Pro (IUS) $219.00
#2059 Empire of the Overmind (Avalon Hill) $29.69
#22 Enhancer II (Videx) $131.09
#1408 Escape (Sublogic) $26.29
#4250 Falcons (Piccadilly) $25.39
#6080 Firebird (Gebelli) $25.39
#7401 Fractions Concepts & Operations $50.99
#5920 Free Lance Software Marketing Kern (book) $26.40
#1476 Game Paddles (TG) $33.89
#2210 Goblins (Highland) $23.29
#4300 GRAN PRIX (Riverbank) $25.39
#6102 Hi-res Chemistry (J&S) $197.99
#3391 Mastertype (Zwieg) $35.09
#7975 Investment Decisions (Mesa Research) $84.99
#2058 Major League Baseball (Avalon Hill) $25.49
#5800 Micro Apple I (Micro Ink) $21.19
#5805 Micro Apple II (Micro Ink) $21.19
#2400 Micropainter (Datasoft) $31.99
#2402 Micropainter Refill #1 (Datasoft) $16.89
#2403 Micropainter Refill #2 (Datasoft) $16.89
#1804 Monty Plays Monopoly (Personal) $31.99
#1816 Monty Plays Scrabble (Personal) $33.89
#2211 Mummy's Curse (Highland) $26.39
#90 Music System (Mountain) $349.00
#3300 PFS (Software) $80.69
#3301 PFS-Report (Software) $87.49
#6240 Paddle-Adapple (So. Calif. Research) $26.89
#6709 Physics I – Free Fall (Ed. Courseware) $28.09
#7100 Pool 1.5 (IDSI) $29.69
#6710 Population (Ed. Courseware) $21.09
#7970 Portfolio Master (Investors Software) $63.69
#1900 Prisoner (Edu-Ware) $26.95
#4701 Pro Football (SDL) $44.89
#2355 Programmers Handbook (Comp. Sta.) $26.96
#7008 Race for Midnight (Avant Gard) $25.39
#3400 Raster Blaster (Budge Co) $25.39
#2751 Real Estate Analyzer (Howardsoft) $127.49
#91 Romwriter (Mountain) $148.69
#1150 Sargon II (Hayden) $29.69
#1403 Saturn Navigator (Sublogic) $21.19
#7006 Sentence Diagramming (Avant Gard) $21.19
#2701 Sexoscope(AGS) $26.99
#7101 Shuffleboard (IDSI) $25.39
#3701 Star Thief (Cavalier) $25.39
#4251 Suicide (Piccadilly) $26.29
#3482 Super Sound (Rainbow) $14.39
#1020 SuperCalc (Sorcim) $250.69
#3511 Tablet Shape Maker (Rocky Mountain) $84.09
#2061 Tanktics (Avalon Hill) $24.59
#2750 Tax Preparer '82 (Howardsoft) $131.99
#7102 Trickshot (IDSI) $35.09
#5900 Using 6502 Assembly Lang. (bk) Datamost $16.89
#2804 Valdez (Dynacomp) $16.89
#4700 Win At The Races (SDL) $44.89
#3461 Wizardry (Sir Tech) $42.39
#4350 Word Star (Micro Pro) $289.00
#18 Z Card (ALS) $239.00
#2655 Z-Term (Southwestern) $84.99

Call Toll-Free **800-344-5106** (outside California)

HUNTINGTON COMPUTING
Post Office Box 1297
Corcoran, California 93212

Foreign Orders 209-992-4481
In California 800-692-4146

Apple® is a registered trademark of Apple Computer, Inc.
Pet® is a registered trademark of Commodore.
TRS-80® is a registered trademark of Tandy Corp.
Atari® is a registered trademark of Atari, Inc.

Outside Calif. 800-344-5106

We take **MasterCard, American Express or VISA** (Include card # and expiration date). California residents add 6% tax. Include $2.00 for postage. Foreign and hardware extra. Foreign (excluding Canada): remit U.S. currency, checks on U.S. banks, use listed charge cards, or make direct wire transfers through Security Pacific Bank, Corcoran, for a $6.00 charge. All overseas orders shipped by air. Send for free catalog. Prices subject to change without notice.

Circle 197 on inquiry card.




Figure 1: *In-basket and out-basket icons. The in-basket contains an envelope indicating that mail has been received. (This figure was taken directly from the Star screen. Therefore, the text appears at screen resolution.)*

when designing a system is that the approach adopted *changes the functionality of the system*. An example is electronic mail. Most electronic-mail systems draw a distinction between *messages* and *files* to be sent to other people. Typically, one program sends messages and a different program handles file transfers, each with its own interface. But we observed that offices make no such distinction. Everything arrives through the mail, from one-page memos to books and reports, from intraoffice mail to international mail. Therefore, this became part of Star's physical-office metaphor. Star users mail documents of any size, from one page to many pages. Messages are short documents, just as in the real world. User actions are the same whether the recipients are in the next office or in another country.

A physical metaphor can simplify and clarify a system. In addition to eliminating the artificial distinctions of traditional computers, it can eliminate commands by taking advantage of more general concepts. For example, since moving a document on the screen is the equivalent of picking up a piece of paper and walking somewhere with it, there is no "send mail" command. You simply move it to a picture of an out-basket. Nor is there a "receive mail" command. New mail appears in the in-basket as it is received. When new mail is waiting, an envelope appears in the picture of the in-basket (see figure 1). This is a simple, familiar, nontechnical approach to computer mail. And it's easy once the physical-office metaphor is adopted!

While we want an analogy with the physical world for familiarity, we don't want to limit ourselves to its capabilities. One of the raisons d'être for Star is that physical objects do not provide people with enough power to manage the increasing complexity of the "information age." For example, we can take advantage of the computer's ability to search rapidly by providing a search function for its electronic file drawers, thus helping to solve the long-standing problem of lost files.

IT'S CRISP. IT'S CLEAR. IT'S COMPATIBLE.

Amdek's Video-300 green phosphor monitor is the easy-reading choice for almost any system — including IBM and Apple.

Everything about our 12" Video-300 monitor was designed to be easy. Easy to read. Easy to use. And easy to match up with practically any computer or word processing system, including the popular Apple and IBM personal computers. So it's easy to see why you should choose Video-300 for your text display needs.

Amdek's Video-300 monitor features:

- Non-glare screen to eliminate distracting reflections
- P-31 green phosphor display for no-strain viewing
- 80 x 24 character display
- 18MHz band width 900 lines (center) resolution
- Built-in carrying handle for portability
- Light-weight, industrial-grade cabinetry (only 17 lbs.)
- UL, FCC approved
- Full one-year warranty covering parts and labor

So ask your dealer about Video-300 --part of Amdek's complete line of color, green phosphor and black and white monitors. Then match Video-300's performance and price against any other display monitor. For quality and value, you'll choose Amdek.



Amdek Corporation, 2420 E. Oakton St., Suite E, Arlington Heights, IL 60005. (312) 364-1180 • TLX: 25-4786

Circle 24 on inquiry card.

The "Desktop"

Every user's initial view of Star is the "Desktop," which resembles the top of an office desk, together with surrounding furniture and equipment. It represents your working environment—where your current projects and accessible resources reside. On the screen are displayed pictures of familiar office objects, such as documents, folders, file drawers, in-baskets, and out-baskets. These objects are displayed as small pictures or "icons," as shown in figure 2.

You can "open" an icon to deal with what it represents. This enables you to read documents, inspect the contents of folders and file drawers, see what mail you have received, etc. When opened, an icon expands into a larger form called a "window," which displays the icon's contents. Windows are the principal mechanism for displaying and manipulating information.

The Desktop "surface" is displayed as a distinctive gray pattern. This restful design makes the icons and windows on it stand out crisply, minimizing eyestrain. The surface is organized as an array of one-inch squares, 14 wide by 11 high. An icon can be placed in any square, giving a maximum of 154 icons. Star centers an icon in its square, making it easy to line up icons neatly. The Desktop always occupies the entire display screen; even when windows appear on the screen, the Desktop continues to exist "beneath" them.

The Desktop is the principal Star technique for realizing the physical-office metaphor. The icons on it are visible, concrete embodiments of the corresponding physical objects. Star users are encouraged to think of the objects on the Desktop in physical terms. Therefore, you can move the icons around to arrange your Desktop as you wish. (Messy Desktops are certainly possible, just as in real life.) Two icons cannot occupy the same space (a basic law of physics). Although moving a document to a Desktop resource such as a printer involves transferring the document icon to the same square as the printer icon, the printer immediately "absorbs" the document, queuing it for printing. You can leave




Figure 2: *A Desktop as it appears on the Star screen. Several commonly used icons appear across the top of the screen, including documents to serve as "form-pad" sources for letters, memos, and blank paper. An open window displaying a document containing an illustration is also shown.*

The revolutionary Discovery multiprocessor is the only system that allows the total integration of powerful 16 bit 8086 processors with the more standard Z-80 user processors. The DISCOVERY system may be configured in any 8 bit/16 bit combination, or as a totally exclusive 16 bit system only to provide the ultimate in performance and flexibility in advanced micro systems.

Ultimate performance. The dpc-186 is the most sophisticated single board microcomputer available today offering more power and faster processing time through the 8086 CPU for bigger, more complex programs. Memory starts at 128 K (compared to the Z-80's 64 K), and is expandable to 1 megabyte. And the dpc-186 is fully compatible with the standard DISCOVERY multiprocessor system permitting efficient upgrading as future needs develop, without sacrificing any of your extensive hardware and software investment.

World's best multiprocessor system. The DISCOVERY system provides separate processors and memory for each of its 16 users. It offers full CP/M*and CP/M-86*compatibility, interprocessor communication, and shared and private files. Each user can take advantage of shared peripherals and cross submitting of tasks between processors. The system is controlled by a unique, two board dpc-280 service processor and dpc/os distributed processing operating system.

By the board or by the system. The DISCOVERY multiprocessor is ready for immediate delivery as a complete system, as processor boards, and everything in between. It offers exclusive technology in multiprocessing, yet is fully compatible with existing standards including CP/M and S-100. It is quite simply unmatched in performance, capabilities and offers a far greater degree of flexibility.

DISCOVERY—offering a whole new world of possibilities.

For the first time, 8 and 16 bit processor intermixing.



Action Computer Enterprises, Inc.

ace
The Multiprocessing Company
55 West Del Mar Boulevard, Pasadena, CA 91105 USA
(213) 793-2440, TWX 910-588-1201

Circle 9 on inquiry card.

Dealer and OEM inquiries invited.

*CP/M is a registered TM of Digital Research, Inc.

documents on your Desktop indefinitely, just as on a real desk, or you can file them away in folders or file drawers. Our intention and hope is that users will *intuit* things to do with icons, and that those things will indeed be part of the system. This will happen if:

(a) Star models the real world accurately enough. Its *similarity* with the office environment preserves your familiar way of working and your existing concepts and knowledge.
(b) Sufficient *uniformity* is in the system. Star's principles and "generic" commands (discussed below) are applied throughout the system, allowing lessons learned in one area to apply to others.

The model of a physical office provides a simple base from which learning can proceed in an incremental fashion. You are not exposed to entirely new concepts all at once. Much of your existing knowledge is embedded in the base.

In a functionally rich system, it is probably not possible to represent everything in terms of a single model. There may need to be more than one model. For example, Star's records-processing facility cannot use the physical-office model because physical offices have no "records processing" worthy of the name. Therefore, we invented a different model, a record file as a collection of *fields*. A record can be displayed as a row in a *table* or as filled-in fields in a *form*. Querying is accomplished by filling in a blank example of a record with predicates describing the desired values, which is philosophically similar to Zloof's "Query-by-Example" (see reference 21).

Of course, the number of different user models in a system must be kept to a minimum. And they should not overlap; a new model should be introduced only when an existing one does not cover the situation.

Seeing and Pointing

A well-designed system makes everything relevant to a task visible on the screen. It doesn't hide things under CODE+key combinations or

Systems II Ex a total business system.

JOB COSTING MENU
1. TRANSACTION ENTRY/DATE
2. JOB/TASK TABLE MAINTENANCE
3. JOB COST FILE MAINTENANCE
4. JOB COST REPORTING
5. EMPLOYEE TABLE MAINTENANCE
6. RETURN TO MASTER MENU
SELECT (1-6)?

SYSTEMS II EX
MASTER MENU
1. INVENTORY 7. CHART OF ACCTS.
2. PAYABLES 8. VENDOR MAINT.
3. RECEIVABLES 9. CUST. MAINT.
4. PAYROLL 10. CHANGE DATE
5. LEDGER 11. SYS./BACKUP
6. JOURNAL 12. STOP PROCSS'G.
13. OPTIONAL PROCSS'G.
SELECT (1-13)?

DATABASE MENU
1. FILE MAINTENANCE
2. REPORTS/REPORT MAINT.
3. UTILITIES
4. RETURN TO SYSTEM MENU
SELECT (1-4)?

ACCOUNTS PAYABLES MENU
1. FILE MAINTENANCE
2. PAYMENT SELECTION
3. PRINT CHECKS AND REGISTER
4. MONTH END
5. RETURN TO MASTER MENU
SELECT (1-5)?

RECEIVABLES SYSTEM MENU
1. FILE MAINTENANCE
2. RECEIPT OF PAYMENTS
3. GENERATE BILLING
4. MONTH END
5. PAST DUE REPORT
6. APPLY MONTHLY INTEREST
7. RETURN TO MASTER MENU
SELECT (1-7)?

LEDGER SYSTEM MENU
1. FILE MAINTENANCE
2. BAL SHEET/INCOME STATEMENT
3. YEAR END PROCESS
4. RETURN TO MASTER MENU
SELECT (1-4)?

INVENTORY SYSTEM MENU
TIME DATE
1. FILE MAINTENANCE
2. POINT OF SALES
3. REORDER REPORT
4. RETURN TO MASTER MENU
SELECT (1-4)?

STATE
PAYROLL MENU
1. MISC/TAX TABLE MAINT.
2. TRANSACTION FILE
3. MISC. PAY/DEDUCTION FILE
4. EMPLOYEE MASTER FILE
5. CALCULATE/PRINT CHECKS
6. PRINT W2's
7. RETURN TO MASTER MENU
SELECT (1-7)?

SYSTEMS II EX — EX for EXTENDED PERFORMANCE. Westware brings you the most completely integrated and simplest to use business software for your Apple Computer. The SYSTEMS II EX is complete with an integrated Database. Yes! The DBII Database can move your system's files into Database format for customized reports or labels.

Although the SYSTEMS II EX is a fully integrated system, you may purchase individual modules and later add additional modules, such as Job Costing for contractors. The power of our system is in the KSAM Firmware card that plugs into the Apple. This card permits high speed searches and eliminates running sort routines to get your files in order.

SYSTEMS II is available on 5¼" drives, and also on the Corvus hard disk. A Corvus based system will give you the power and capacity that challenges larger computers.

COMING SOON — Cash flow analysis with graphics, Database II with graphics, and Bill of Materials for small manufacturers.

CURRENT OPTIONS AVAILABLE — Job Costing, Cycle Invoicing, Order entry, and Layaway.

All Checks, statements and invoices use NEBS forms.

Dealer and OEM inquiries invited.

Apple is a trademark of Apple Computers.



2455 S.W. 4th Ave.
Suite 2
Ontario, OR 97914
(503) 881-1477

Circle 435 on inquiry card.

Yes, please send me your Systems II Demo Package.

2455 S.W. 4th Ave.
Suite 2
Ontario, OR 97914
(503) 881-1477

☐ Yes, I would like to sample your software. Please send me the Systems II Demo Package. My check for $25 is enclosed.

Name ____________________

Title ____________________

Company Name ____________________

Address ____________________

City ____________ State ____________ Zip ____________

force you to remember conventions. That burdens your memory. During conscious thought, the brain utilizes several levels of memory, the most important being the "short-term memory." Many studies have analyzed the short-term memory and its role in thinking. Two conclusions stand out: (1) conscious thought deals with concepts in the short-term memory (see reference 1) and (2) the capacity of the short-term memory is limited (see reference 14). When everything being dealt with in a computer system is visible, the display screen relieves the load on the short-term memory by acting as a sort of "visual cache." Thinking becomes easier and more productive. A well-designed computer system can actually improve the *quality* of your thinking (see reference 16). In addition, visual communication is often more efficient than linear communication; a picture is worth a thousand words.

A subtle thing happens when everything is visible: *the display becomes reality*. The user model becomes identical with what is on the screen. Objects can be understood purely in terms of their visible characteristics. Actions can be understood in terms of their effects on the screen. This lets users *conduct experiments* to test, verify, and expand their understanding—the essence of experimental science.

In Star, we have tried to make the objects and actions in the system *visible*. Everything to be dealt with and all commands and effects have a visible representation on the display screen or on the keyboard. You never have to remember that, for example, CODE+Q does something in one context and something different in another context. In fact, our desire to eliminate this possibility led us to





"We provide business programs as individual as your business needs."

"Allow me to introduce myself. I'm a Vector computer, dedicated to the advancement of society. And I'd like to tell you how a computer can help you manage your business more efficiently. Especially if that computer is a Vector, like me. Because we're probably the most flexible and cost-effective computers you can find.

"Our programs are the key. Because they enable me to handle sales forecasting, budgeting, job costing and proposals, commissions, personalized mass mailings, charts and graphs. We Vectors can even talk to each other and to other bigger computers.

"Unique combinations of our individual programs can actually customize me to meet your specific requirements. Any combination of our software packages can be assembled right off the shelf, to help you realize your full potential as a salesman, merchant, stockbroker, clergyman, contractor, real estate or insurance agent or whatever your business.

"Choose from Memorite III for word processing and mail list management, Execuplan for financial planning and forecasting, Business Accounting, Data Management for filing and sorting information, Communications and a host of others. And, of course, all we Vectors come with the popular CP/M operating system.

"For more information and your local dealer, call us at (805)499-5831 or (800) 235-3547. In California, call (800) 322-3577. Or write to us at 500 North Ventu Park Road, Thousand Oaks, CA 91320.

"We'll show you how we small information systems can mean big business for you."

Circle 424 on inquiry card.



Vector Graphic, Inc.

COMPUTERS FOR THE ADVANCEMENT OF SOCIETY.

Sold and supported by 400 dealers worldwide.
Vector Products are approved on General Services Administration authorized ADP scheduled price list.




Figure 3: *The property sheet for text characters.*

abolish the CODE key. (We have yet to see a computer system with a CODE key that doesn't violate the principle of visibility.) You never invoke a command or push a key and have nothing visible happen. At the very least, a message is posted explaining that the command doesn't work in this context, or it is not implemented, or there is an error. It is disastrous to the user's model when you invoke an action and the system does nothing in response. We have seen people push a key several times in one system or another trying to get a response. They are not sure whether the system has "heard" them or not. Sometimes the system is simply throwing away their keystrokes. Sometimes it is just slow and is *queuing* the keystrokes; you can imagine the unpredictable behavior that is possible.

We have already mentioned icons and windows as mechanisms for making the concepts in Star visible. Other such mechanisms are Star's *property and option sheets.* Most objects in Star have properties. A property sheet is a two-dimensional, form-like environment that displays those properties. Figure 3 shows the character property sheet. It appears on the screen whenever you make a text selection and push the PROPERTIES key. It contains such properties as type font and size; bold, italic, underline, and strikeout face; and superscript/subscript positioning. Instead of having to remember the properties of characters, the current settings of those properties, and, worst of all, how to change those properties, property sheets simply *show everything on the screen. All* the options are presented. To change one, you point to it with the mouse and push a button. Properties in effect are displayed in reverse video.

This mechanism is used for *all* properties of *all* objects in the system. Star contains a couple of hundred properties. To keep you from being overwhelmed with information, property sheets display only the properties relevant to the type of object currently selected (e.g., character, paragraph, page, graphic line, formula element, frame, document, or folder). This is an example of "progressive disclosure": hiding complexity until it is needed. It is also one of the clearest examples of how an emphasis on visibility can reduce the amount of remembering and typing required.

Property sheets may be thought of as an *alternate representation* for ob-

"THAT WORKS GREAT!"

Planning an on-time, on-budget project has always been hard work. But our new VisiSchedule™ program can help you and your personal computer make short work of it.

The VisiSchedule program is a fast and easy way to control projects, level resources, meet deadlines, and beat cost targets.

The VisiSchedule program instantly shows you the critical path among your project's tasks. It allocates all costs and personnel, and specifies earliest/latest start dates, slack times, holidays, prerequisites and deadlines for each task. And it produces summaries, time charts, and milestone reports for management.


You can actually develop your project as you enter data, investigate tradeoffs between manpower, costs and time. Ask "what if?"... add, move, slip or change any task, skill level or cost, and the VisiSchedule program automatically displays the impact of your changes. This makes it a snap to keep schedules and costs current, too.

While the VisiSchedule program does a lot by itself, it can do even more for you when used with other Visi™ programs. That's because they're all inter-related, just like your needs and tasks, to give you a fully integrated solution. For example, automatically transfer the cost data to our VisiTrend/Plot™ program and analyze cause-and-effect relationships. Then instantly plot the results in charts and graphs for better communication.

In addition, our series includes the VisiCalc,® VisiFile,™ VisiDex,™ VisiPlot,™ VisiTerm™ and Desktop/PLAN™ programs.

Ask your retail computer store salesperson for a demonstration of the VisiSchedule program. Discover how easy it is to make short work of planning and budgeting all your work.

VISISCHEDULE™ FROM
VISICORP™
PERSONAL SOFTWARE™






Figure 4: *The option sheet for the Find command showing both the Search and Substitute options. The last two lines of options appear only when CHANGE IT is turned on.*

jects. The screen shows you the visible characteristics of objects, such as the type font of text characters or the names of icons. Property sheets show you the underlying structure of objects as they make this structure visible and accessible.

Invisibility also plagues the commands in some systems. Commands often have several arguments and options that you must remember with no assistance from the system. Star addresses this problem with *option sheets* (see figure 4), a two-dimensional, form-like environment that displays the arguments to commands. It serves the same function for command arguments that property sheets do for object properties.

What You See Is What You Get

"What you see is what you get" (or WYSIWYG) refers to the situation in which the display screen portrays an accurate rendition of the printed page. In systems having such capabilities as multiple fonts and variable line spacing, WYSIWYG requires a bit-mapped display because only that has sufficient graphic power to render those characteristics accurately.

WYSIWYG is a simplifying technique for document-creation systems. All composition is done *on the screen*. It eliminates the iterations that plague users of document compilers. You can examine the appearance of a page *on the screen* and make changes until it looks right. The printed page will look the same (see figure 5). Anyone who has used a document compiler or post-processor knows how valuable WYSIWYG is. The first powerful WYSIWYG editor was Bravo, an experimental editor developed for Alto at the Xerox Palo Alto Research Center (see reference 12). The text-editor aspects of Star were derived from Bravo.

Trade-offs are involved in WYSIWYG editors, chiefly having to do with the lower resolution of display screens. It is never possible to get an *exact* representation of a printed page on the screen since most screens have only 50 to 100 dots per inch (72 in Star), while most printers have higher resolution. Completely accurate character positioning is not possible. Nor is it usually possible to represent shape differences for fonts smaller than eight points in size since there are too few dots per character to

TEK 2200 SERIES DUAL TRACE OSCILLOSCOPES | THE PERFORMANCE/ PRICE STANDARD



Introducing a direct line to a 60 MHz Tektronix scope built for your bench!

From the world's most respected name in oscilloscopes: a new scope, plus a new direct order number, that finally makes it practical to put Tektronix quality on your bench . . . at work or home.

Among professional engineers and technicians there is no substitute for the performance and reliability of Tektronix oscilloscopes.

Now, for the first time, Tektronix is offering an advanced scope at an unprecedented low price— and has a direct order line that lets you get your order processed today!

The scope: the 2213. Its radical new design brings you Tektronix quality for well below what you would pay for lesser-name scopes.

The 2213's practical design includes 65% fewer mechanical parts, fewer circuit boards, electrical connectors and cabling. Result: a lower price for you plus far greater reliability.

Yet performance is pure Tektronix: there's 60 MHz bandwidth for digital and high-speed analog circuits. The sensitivity for low signal measurements. The sweep speeds for fast logic families. A complete trigger system for digital, analog or video waveforms. And new high-performance Tektronix probes are included!

2213 PERFORMANCE DATA

Bandwidth: Two channels, dc—60 MHz from 10 V/div to 20 mV/div. (50 MHz from 2 mV/div to 10 mV/div).

Sweep speeds: Sweeps from 0.5 s to 50 ns (to 5 ns/div with X10 mag).

Sensitivity: Scale factors from 100 V/div (10X probe) to 2 mV/div (1X probe). Accurate to ± 3%. Ac or dc coupling.

Delayed sweep measurements: Standard sweep, intensified after delay, and delayed.

(Need dual time-base performance and timing accuracy to ± 1.5%? Ask about our 2215 priced at $1400.)

Complete trigger system: Modes include TV field, normal, vertical mode, and automatic; internal, external, and line sources; variable holdoff.

Probes: High performance, positive attachment, 10-14 pF and 60 MHz at the probe tip.

The price: Just $1100 complete*. Order direct from Tektronix National Marketing Center. Phones are staffed by technical people to answer your questions about the 2213. Your direct order includes a 15-day return policy and full Tektronix warranty.

Now it's easier than ever to get your hands on a Tek scope!

ORDER TOLL-FREE


800-547-1845

Ask for Department 100

(In Oregon, Alaska and Hawaii: 1-503-627-5402 collect.) Lines are open from 8 am EST to 5 pm PST.

*Price F.O.B., Beaverton, OR.





XEROX
8010 Star Information System

User-Interface Design

To make it easy to compose text and graphics, to do electronic filing, printing, and mailing all at the same workstation, requires a revolutionary user-interface design.

Bit-map display - Each of the 827,392 dots on the screen is mapped to a bit in memory; thus, arbitrarily complex images can be displayed. STAR displays all fonts and graphics as they will be printed. In addition, familiar office objects such as documents, folders, file drawers and in-baskets are portrayed as recognizable images.

The mouse - A unique pointing device that allows the user to quickly select any text, graphic or office object on the display.

See and Point

All Star functions are visible to the user on the keyboard or on the screen. The user does filing and retrieval by selecting them with the mouse and touching the MOVE, COPY, DELETE or PROPERTIES command keys. Text and graphics are edited with the same keys.

Shorter Production Times

Experience at Xerox with prototype work-stations has shown shorter production times and lower costs. The following equation expresses this.

$$f(x) = \frac{\int\int_a^b g(x)\,dx}{\sum_{i=1}^{100} \psi(\alpha_i, \beta_i)} + \prod_j A_j^2 e^{x^2}$$

Star users are likely to do more of their own composition and layout, controlling the entire process including printing and distribution.

Text and Graphics

To replace typesetting, Star offers a choice of type fonts and sizes, from 8 point to 24 point.

Here is a sentence of 8-point text.
Here is a sentence of 10-point text.
Here is a sentence of 12-point text.
Here is a sentence of 14-point text.
Here is a sentence of 18-point text.

Figure 5: *A Star document showing multicolumn text, graphics, and formulas. This is the way the document appears on the screen. It is also the way it will print (at higher resolution, of course).*

One of the great masters?


Although the Datasouth DS180 matrix printer may not exactly rate as a work of art, our customers have a *very* high opinion of its value. Over the past year, we have shipped thousands of DS180 printers to customers throughout the world. Many of our sales now come in the form of repeat business—a strong testimonial to the acceptance of a product.

The success of the DS180 in a very competitive market did not happen by accident; rather through our sensitivity to the needs of the industry. This sensitivity we carry through research and development, production and quality control and finally, to after sales support and service.

Recently we introduced new enhancements to make the DS180 printer even more versatile. Dot addressable raster scan graphics produces output of computer generated charts, maps and graphs at a resolution of 75 x 72 dots per inch. Variable horizontal pitch selection allows printing at 10, 12 or 16.5 characters per inch plus double wide printing at 5, 6 or 8.25 characters per inch. The expanded 2K FIFO print buffer handles a full CRT screen dump at up to 9600 baud without delaying the host system. We also offer transparent mode for isolating communications problems, and for APL users, the dual ASCII/APL character set option.



Check our list of features and we think you will agree that the DS180 offers the most complete performance package in matrix printers.



DS180 PRINTER STANDARD FEATURES
- Microprocessor Control
- 180 CPS Print Speed
- Bidirectional/Logic Seeking
- 1000 Character Buffer (Expandable)
- 9x7 Dot Matrix
- Expanded Characters
- Adjustable Printhead/1-6 Copies
- 96 ASCII Character Set
- Cartridge Ribbon
- 132 Column Print Width
- Tractor Feed (Front or Bottom)
- Non-Volatile Format Retention
- Top of Form
- Horizontal Tabs
- Vertical Tabs
- Perforation Skip-Over
- Auto Line Feed
- 6/8 LPI
- Auto End of Line Carriage Return
- 5 IPS Paper Slew
- Parallel and Serial Interfaces
- 110-9600 Baud Communications
- Terminal Status Indicators
- Audio Alarm
- Self-Test
- X-on, X-off
- Paper Out Detection



OPTIONAL FEATURES
- Compressed Print—10, 12, 16.5 cpi
- High Resolution Dot—Addressable Graphics
- 2k Expanded Print Buffer
- APL/ASCII Character Set

The DS180 is available nationwide through our network of sales/service distributors.

datasouth computer corporation

P.O. Box 240947 • Charlotte, NC 28224 • 704/523-8500

be recognizable. Even 10-point ("normal" size) fonts may be uncomfortably small on the screen, necessitating a magnified mode for viewing text. WYSIWYG requires very careful design of the screen fonts in order to keep text on the screen readable and attractive. Nevertheless, the increase in productivity made possible by WYSIWYG editors more than outweighs these difficulties.

Universal Commands

Star has a few commands that can be used throughout the system: MOVE, COPY, DELETE, SHOW PROPERTIES, COPY PROPERTIES, AGAIN, UNDO, and HELP. Each performs the same way regardless of the type of object selected. Thus, we call them "universal" or "generic" commands. For example, you follow the same set of actions to move text in a document and to move a line in an illustration or a document in a folder: select the object, push the MOVE key, and indicate a destination. (HELP and UNDO don't use a selection.) Each generic command has a key devoted to it on the keyboard.

These commands are far more basic than the commands in other computer systems. They strip away the extraneous application-specific semantics to get at the underlying principles. Star's generic commands derive from fundamental computer-science concepts because they also underlie operations in programming languages. For example, much program manipulation of data structures involves moving or copying values from one data structure to another. Since Star's generic commands embody fundamental underlying concepts, they are widely applicable. Each command fills a variety of needs, meaning fewer commands are required. This simplicity is desirable in itself, but it has another subtle advantage: it makes it easy for users to form a model of the system. People can use what they understand. Just as progress in science derives from simple, clear theories, progress in the usability of computers is coming to depend on simple, clear user interfaces.

MOVE is the most powerful command in the system. It is used during text editing to rearrange letters in a word, words in a sentence, sentences in a paragraph, and paragraphs in a document. It is used during graphics editing to move picture elements, such as lines and rectangles, around in an illustration. It is used during formula editing to move mathematical structures, such as summations and integrals, around in an equation. It replaces the conventional "store file" and "retrieve file" commands; you simply move an icon into or out of a file drawer or folder. It eliminates the "send mail" and "receive mail" commands; you move an icon to an out-basket or from an in-basket. It replaces the "print" command; you move an icon to a printer. And so on. MOVE strips away much of the historical clutter of computer commands. It is more fundamental than the myriad of commands it replaces. It is simultaneously more powerful and simpler.

Much simplification comes from Star's object-oriented interface. The action of setting properties also replaces a myriad of commands. For example, changing paragraph margins is a command in many systems. In Star, you do it by selecting a paragraph object and setting its MARGINS property. (For more information on object-oriented languages, see the August 1981 BYTE.)

Consistency


Consistency asserts that mechanisms should be used in the same way wherever they occur. For example, if the left mouse button is used to select a character, the same button should be used to select a graphic line or an icon. Everyone agrees that consistency is an admirable goal. However, it is perhaps the single hardest characteristic of all to achieve in a computer system. In fact, in systems of even moderate complexity, consistency may not be well defined.

A question that has defied consen-

Give your system some NEC, and watch its performance soar.

NEC's crisp, clear, high-performance JC1202 RGB color monitor, an industry standard. Also available: the JC1201 composite video version.

NEC's classic green monitor, (JB1201), one of computing's performance legends. Non-glare screen, easy on the eye. And the checkbook.




The impressive new NEC dot matrix printer. Parallel interface, 100 cps, 2K buffer, pin or friction feed. Stunning performance and versatility in the hottest new peripheral of the year.

Peripherals from NEC can make almost any computer system better.

Owners of Apple®, Radio Shack®, Atari®, IBM®, and many other personal computers will find their equipment to be compatible with NEC's famous monitors, as well as our highly-featured new PC-8023A dot matrix printer. (Some configurations may require a different interface.)

Ask your dealer for a demonstration.



Productivity at your fingertips



NEC Home Electronics (USA)
Personal Computer Division
1401 Estes Avenue
Elk Grove Village, IL 60007

sus in Star is what should happen to a document after it has been printed. Recall that a user prints a document by selecting its icon, invoking MOVE, and designating a printer icon. The printer absorbs the document, queuing it for printing. What happens to that document icon after printing is completed? The two plausible alternatives are:

1. The system deletes the icon.
2. The system does not delete the icon, which leads to several further alternatives:
   2a. The system puts the icon back where it came from (i.e., where it was before MOVE was invoked).
   2b. The system puts the icon at an arbitrary spot on the Desktop.
   2c. The system leaves the icon in the printer. You must move it out of the printer explicitly.

The consistency argument for the first alternative goes as follows: when you move an icon to an out-basket, the system mails it and then deletes it from your Desktop. When you move an icon to a file drawer, the system files it and then deletes it from your Desktop. Therefore, when you move an icon to a printer, the system should print it and then delete it from your Desktop. Function icons should behave consistently with one another.

The consistency argument for the second alternative is: the user's conceptual model at the Desktop level is the physical-office metaphor. Icons are supposed to behave similarly to their physical counterparts. It makes sense that icons are deleted after they are mailed because after you put a piece of paper in a physical out-basket and the mailperson picks it up, it *is* gone. However, the physical analogue for printers is the office copier, and there is no notion of deleting a piece of paper when you make a copy of it. Function icons should behave consistently with their physical counterparts.

There is no one right answer here. Both arguments emphasize a dimension of consistency. In this case, the dimensions happen to overlap. We eventually chose alternative 2a for the following reasons:

1. *Model dominance*—The physical metaphor is the stronger model at the Desktop level. Analogy with physical counterparts *does* form the basis for people's understanding of what icons are and how they behave. Argument 1 advocates an *implicit* model that must be learned; argument 2 advocates an *explicit* model that people already have when they are introduced to the system. Since people do use their existing knowledge when confronted with new situations, the design of the system should be based on that knowledge. This is especially important if people are to be able to *intuit* new uses for the features they have learned.

2. *Pragmatics*—It is dangerous to delete things when users don't expect it. The first time a person labors over a document, gets it just right, prints it, and finds that it has disappeared, that person is going to become *very nervous*, not to mention angry. We also decided to put it back where it came from (2a instead of 2b or 2c) for the pragmatic reason that this involves slightly less work on the user's part.

3. *Seriousness*—When you file or mail an icon, it is not deleted entirely from the system. It still exists in the file drawer or in the recipients' in-baskets. If you want it back, you can move it back out of the file drawer or send a message to one of the recipients asking to have a copy sent back. Deleting after printing, however, is final; if you move a document to a printer and the printer deletes it, that document is gone for good.

One way to get consistency into a system is to adhere to *paradigms* for operations. By applying a successful way of working in one area to other areas, a system acquires a unity that is both apparent and real. Paradigms that Star uses are:

• *Editing*—Much of what you do in Star can be thought of as editing. In addition to the conventional text, graphics, and formula editing, you manage your files by *editing filing windows*. You arrange your working environment by *editing your Desktop*. You alter properties by *editing property sheets*. Even programming can be thought of as *editing data structures* (see reference 16).

• *Information retrieval*—A lot of

Childhood's End: The 68000

ADDRESSING THE NEW FRONTIER... THE MICROCOMPUTER COMES OF AGE.

SAGE II

SAGE COMPUTER TECHNOLOGY IS NOW MANUFACTURING A 68000 BASED SINGLE-BOARD MICROCOMPUTER SYSTEM WHICH DELIVERS THE HIGHEST PERFORMANCE PER UNIT PRICE OF ANY COMPUTER IN HISTORY.

THE SAGE II MICROCOMPUTER HAS THE FOLLOWING FEATURES:

- INTERRUPT DRIVEN, 8 MHZ 68000 MICROPROCESSOR
- 2 MILLION INSTRUCTIONS PER SECOND, NO WAIT STATES
- WILL ADDRESS 16 MEGABYTES WITH UP TO 1/2 MEGABYTE OF PARITY RAM ON BOARD
- UP TO 1.3 MEGABYTES OF 5-1/4 INCH FLOPPY DISK STORAGE
- FULLY SUPPORTED IEEE-488 INTERFACE
- TERMINAL AND MODEM RS-232C SERIAL PORTS
- CENTRONICS COMPATIBLE PARALLEL PRINTER PORT
- UCSD PASCAL*, BASIC, FORTRAN AND ASSEMBLER AVAILABLE

*TM U. OF CALIFORNIA

PRICES FOR THE SYSTEM START AT $3600.
FOR MORE INFORMATION CONTACT OUR MARKETING DEPARTMENT AT 702-322-6868

SAGE COMPUTER TECHNOLOGY

195 NORTH EDISON WAY, SUITE 14 • RENO, NEVADA 89502

Circle 359 on inquiry card.





Figure 6: *The keyboard-interpretation window serves as the source of characters that may be entered from the keyboard. The character set shown here contains a variety of office symbols.*

power can be gained by applying information-retrieval techniques to information wherever it exists in a system. Star broadens the definition of "database." In addition to the traditional notion as represented by its record files, Star views file drawers as databases of documents, in-baskets as databases of mail, etc. This teaches users to think of information retrieval as a general tool applicable throughout the system.

• *Copying*—Star elevates the concept of "copying" to a high level: that of a paradigm for creating. In all the various domains of Star, you *create by copying*. Creating something out of nothing is a difficult task. Everyone has observed that it is easier to modify an existing document or program than to write it originally. Picasso once said, "The most awful thing for a painter is the white canvas . . . To copy others is necessary." (See reference 20.) Star makes a serious attempt to alleviate the problem of the "white canvas" by making copying a practical aid to creation. For example, you create new icons by copying existing ones. Graphics are created by copying existing graphic images and modifying them. In a sense, you can even type characters in Star's 2^{16}-character set by "copying" them from keyboard windows (see figure 6).

These paradigms *change the very way you think*. They lead to new habits and models of behavior that are more powerful and productive. They can lead to a *human-machine synergism*.

Star obtains additional consistency by using the class and subclass no-



Your Atari® Computer: A Guide to Atari® 400/800™ Personal computers by Lon Poole with Martin McNiff and Steven Cook

Your Atari® Computer provides invaluable reference material for Atari® home computer users. This "how-to" guide written for the novice covers all the common external devices, including disk drives and printers. The reader can also learn to program in Atari® BASIC. *Paper $15.00.*

An Introduction To Microcomputers: Volume 0– The Beginner's Book, Third Edition by Adam Osborne and David Bunnell

One of our most popular titles, Volume 0 has been expanded and revised to include new sections on software and communications. Written for the complete novice, this book introduces the construction and operation of microcomputers. *Paper $7.95.*

6502 Assembly Language Subroutines by Lance Leventhal and Winthrop Saville

This book includes over 50 indispensible, ready-to-use subroutines. A boon to every 6502 programmer, it will save hours of programming time. Includes array, bit and string manipulation, sorting and searching operations, much more. *Paper $12.99*

Assembly Language Programming for the Apple II™ by Robert Mottola

This comprehensive, easy to understand introduction provides solid groundwork for getting started in assembly language programming on the Apple II. Many subroutines written in assembly language are provided, and most explanations are shown with equivalent examples in BASIC. *Paper $12.95.*

Discover FORTH: Learning And Programming the FORTH Language by Thom Hogan

Using a friendly approach, the author explains the history and uses of FORTH, as well as how to program to an intermediate level. Includes notes on logical extensions and alterations to the current standard FORTH syntax. *Paper $14.95.*

Trade Secrets: How to Protect Your Ideas and Assets by James Pooley

Attorney James Polley provides legal advice on a "hot" topic: who owns your ideas in today's business world. Employers can learn to tighten company security systems and protect their intellectual assets. Employees can become familiar with their rights to take "commercial" ideas to new jobs or start competing businesses without being sued. *Cloth $19.95.*

A User Guide to the UNIX™ System by Rebecca Thomas and Jean Yates

Designed to ease the novice through the difficult learning stages, this volume is also an excellent reference for those already familiar with the UNIX™ operating system. Computer-side tutorials teach forty basic commands plus there's a list of UNIX™ system resources, and a bibilography for further study. *Paper $15.99.*

VisiCalc®: Home and Office Companion by David M. Castlewitz and Lawrence Chisausky with Patricia Kronberg. Illustrated by L. D. Chukman

Contains 50 models that can be used immediately for personal and business applications. Provides models for loans and investments, advertising and sales, inventory control, personnel, household aids and more. Designed to accomodate most micros and every version of the VisiCalc® program. *Paper $15.99.*

Now at your dealer, or write Osborne/McGraw-Hill, 630 Bancroft Way, Berkeley, CA 94710. Phone orders: CALL TOLL FREE 800-227-2895. In California call 415-548-2805. Canadian orders contact L.A. Varah (416) 561-9311, McGraw-Hill-Ryerson (416) 293-1911.

Osborne/McGraw-Hill

tions of Simula (see reference 4) and Smalltalk (see reference 11). The clearest example of this is classifying icons at a higher level into *data icons* and *function icons*. Data icons represent objects on which actions are performed. Currently, the three types (i.e., subclasses) of data icons are documents, folders, and record files. Function icons represent objects that perform actions. Function icons are of many types, with more being added as the system evolves: file drawers, in- and out-baskets, printers, floppy-disk drives, calculators, terminal emulators, etc.

In general, anything that can be done to one data icon can be done to all, regardless of its type, size, or location. All data icons can be moved, copied, deleted, filed, mailed, printed, opened, closed, and a variety of other operations applied. Most function icons will accept any data icon; for example, you can move any data icon to an out-basket. This use of the class concept in the user-interface design reduces the artificial distinctions that occur in some systems.

Simplicity

Simplicity is another principle with which no one can disagree. Obviously, a simple system is better than a complicated one if they have the same capabilities. Unfortunately, the world is never as simple as that. Typically, a trade-off exists between easy novice use and efficient expert use. The two goals are not always compatible. In Star, we have tried to follow Alan Kay's maxim: "simple things should be simple; complex things should be possible." To do this, it was sometimes necessary to make common things simple at the expense of uncommon things being harder. Simplicity, like consistency, is not a clear-cut principle.

One way to make a system appear simple is to make it uniform and consistent, as we discussed earlier. Adhering to those principles leads to a *simple user's model*. Simple models are easier to understand and work with than intricate ones.

Another way to achieve simplicity is to minimize the redundancy in a system. Having two or more ways to do something increases the complexity without increasing the capabilities. The ideal system would have a minimum of powerful commands that obtained all the desired functionality and that did not overlap. That was the motivation for Star's "generic" commands. But again the world is not so simple. General mechanisms are often inconvenient for high-frequency actions. For example, the SHOW PROPERTIES command is Star's general mechanism for changing properties, but it is too much of an interruption during typing. Therefore, we added keys to optimize the changing of certain character properties: BOLD, ITALICS, UNDERLINE, SUPERSCRIPT, SUBSCRIPT, LARGER/SMALLER (font), CENTER (paragraph). These significantly speed up typing, but they don't add any new functionality. In this case, we felt the trade-off was worth

The Alternative

BASIS 108



Hardware and Software compatible with Apple II™

Standard Features

- 6502 and Z80 Microprocessors
- 64K RAM, expandable to 128K
- 2K Monitor ROM, plus sockets for 10K additional ROM
- RGB and Composite Video Output
- Selectable 80 or 40 column text display
- High Resolution Graphics: 6 colors, 280x192 or 280x160 with four lines of text
- Color Graphic Mode: 15 colors, 40x48 or 80x48: 40x40 or 80x40 with four lines of text
- 8 bit Parallel I/O
- RS-232c Serial I/O
- Detached Keyboard: All standard keyboard functions, Upper/Lower case characters, Numeric keypad, Cursor block, and 15 Programmable special function keys
- Built-in mounting for two 5-1/4 inch floppy disk drives
- Six Apple compatible slots for plug-in peripherals
- Game paddle I/O
- Built-in loudspeaker
- Two switched accessory power outlets
- Mounting for up to six DP-25 plugs

$1949^{00}

without disk drives.



23116 Summit Road
Los Gatos, CA 95030
(408) 353-1102
TWX: 910-590-8000

it because typing is a frequent activity. "Minimum redundancy" is a good but not absolute guideline.

In general, it is better to introduce new *general* mechanisms by which "experts" can obtain accelerators rather than add a lot of special one-purpose-only features. Star's mechanisms are discussed below under "User Tailorability."

Another way to have the system as a whole appear simple is to make each of its parts simple. In particular, the system should avoid overloading the semantics of the parts. Each part should be kept conceptually clean. Sometimes, this may involve a major redesign of the user interface. An example from Star is the mouse, which has been used on the Alto for eight years. Before that, it was used on the NLS system at Stanford Research Institute (see reference 5). All of those mice have three buttons on top. Star has only two. Why did we depart from "tradition"? We observed that the dozens of Alto programs all had different semantics for the mouse buttons. Some used them one way, some another. There was no consistency between systems. Sometimes, there was not even consistency *within* a system. For example, Bravo uses the mouse buttons for selecting text, scrolling windows, and creating and deleting windows, depending on where the cursor is when you push a mouse button. Each of the three buttons has its own meaning in each of the different regions. It is difficult to remember which button does what where.

Thus, we decided to simplify the mouse for Star. Since it is apparently quite a temptation to overload the semantics of the buttons, we eliminated temptation by eliminating buttons. Well then, why didn't we use a one-button mouse? Here the plot thickens. We did consider and prototype a one-button mouse interface. One button is sufficient (with a little cleverness) to provide all the functionality needed in a mouse. But when we tested the interface on naive users, as we did with a variety of features, we found that they had a lot of trouble making selections with it. In fact, we prototyped and tested six different semantics for the mouse buttons: one one-button, four two-button, and a three-button design. We were chagrined to find that while some were better than others, *none of them* was completely easy to use, even though, a priori, it seemed like all of them would work! We then took the most successful features of two of the two-button designs and prototyped and tested them as a seventh design. To our relief, it not only tested better than any of the other six, everyone found it simple and trouble-free to use.

This story has a couple of morals:

- The intuition of designers is error-prone, no matter how good or bad they are.
- The critical parts of a system should be tested on representative users, preferably of the "lowest common denominator" type.
- What is simplest along any one dimension (e.g., number of buttons) is not necessarily conceptually simplest for users; in particular, minimizing the number of keystrokes may not make a system easier to use.

Modeless Interaction

Larry Tesler defines a *mode* as follows:

> A mode of an interactive computer system is a state of the user interface that lasts for a period of time, is not associated with any particular object, and has no role other than to place an interpretation on operator input. (See reference 18.)

Many computer systems use modes because there are too few keys on the keyboard to represent all the available commands. Therefore, the interpretation of the keys depends on the mode or state the system is in. Modes can and do cause trouble by making habitual actions cause unexpected results. If you do not notice what mode the system is in, you may find yourself invoking a sequence of commands quite different from what you had intended.

Our favorite story about modes, probably apocryphal, involves Bravo. In Bravo, the main typing keys are normally interpreted as commands. The "i" key invokes the Insert command, which puts the system in "insert mode." In insert mode, Bravo interprets keystrokes as letters. The story goes that a person intended to type the word "edit" into his document, but he forgot to enter insert mode first. Bravo interpreted "edit" as the following commands:

E(verything)	select everything in the document
D(elete)	delete it
I(nsert)	enter insert mode
t	type a "t"

The entire contents of the document were replaced by the letter "t." This makes the point, perhaps too strongly, that modes should be introduced into a user interface with caution, if at all.

Commands in Star take the form of noun-verb. You specify the object of interest (the noun) and then invoke a command to manipulate it (the verb). Specifying an object is called "making a selection." Star provides powerful selection mechanisms that reduce the number and complexity of commands in the system. Typically, you will exercise more dexterity and judgment in making a selection than in invoking a command. The object (noun) is almost always specified before the action (verb) to be performed. This helps make the command interface modeless; you can change your mind as to which object to affect simply by making a new selection before invoking the command. No "accept" function is needed to terminate or confirm commands since invoking the command is the last step. Inserting text does not even require a command; you simply make a selection and begin typing. The text is placed after the end of the selection.

The noun-verb command form does not by itself imply that a command interface is modeless. Bravo also uses the noun-verb form; yet, it is a highly modal editor (although the latest version of Bravo has drastically reduced its modalness). The difference is that Bravo tries to make

THE ULTIMATE IN COMPUTER CHESS - THE MATE


THE MATE FOR YOUR MICRO

PMK Associates, one of the world's largest dealers of computer chess systems, is pleased to introduce an extraordinary new product for the computer chess enthusiast. The Mate is a strategy game peripheral for your Apple II*, TRS-80† or PET‡ (TRS-80 and PET versions not available until June '82).

It comes complete with the strongest chess program, by far, ever available for a microcomputer (requires 32K), plus a true, magnetic sensor chessboard with magnetic pieces. All you do is move the pieces. The Mate senses your move, enters it into the computer, shows the move on its high-resolution graphic display and responds by lighting two LEDs. There are no distracting codes to type in during a game, and no need to apply pressure on the squares of the board.

UNPRECEDENTED FLEXIBILITY

Developed by Applied Concepts, Inc., whose $600 MCT chess computer was ranked number one in playing strength in *Chess Life*'s January '82 issue, The Mate also incorporates a wide variety of features: 9 levels of play, opening library of over 6,000 moves, computer thinks on opponent's time, Best/Randomize move selection, move suggestions, audio On/Off, move erasing, change sides during game, reverse board, watch replay of finished game, printout entire game. And for hobbyists who want to write their own chess programs, full documentation of the interface software is provided.



As ACI continues to develop new, stronger chess programs your system can be easily upgraded. And additional programs for checkers, Reversi and other strategy games will soon be available. The Mate comes complete with sensory board, magnetic chess pieces, plug-in computer interface card, interconnecting cable, game program on cassette or disk and operation/programming manual for just **$269.95.**

FREE BONUS BOOK

Each unit is covered by our 15-day home trial, money-back guarantee. And we will promptly exchange any defective unit still under the manufacturer's 90 day warranty. We maintain a large inventory, and most orders are shipped within 48 hours of receipt. Order before August '82 and we will include, free of charge, the chess classic *Bobby Fischer Teaches Chess* developed in cooperation with Xerox Learning Systems.


There is no game for your micro more stimulating than chess, and in computer chess there is nothing more powerful than The Mate.

To order, mail your check to: PMK Associates, PO Box 598, East Brunswick, NJ 08816 (please include $5.00 for shipping; NJ residents please add 5% sales tax; include $10.00 extra for disk format). Customers in Alaska, Hawaii and foreign countries please contact us for shipping charges. For fastest service, credit card holders may use our 24 hour Toll Free order number -

1-800-835-2246
ask for Carol

Please call (201)246-7680 for technical questions and further information.

DEALER INQUIRIES INVITED



COMPUTER AND ELECTRONIC PRODUCTS FOR THE HOME

P.O. BOX 598
EAST BRUNSWICK
NEW JERSEY 08816

(201) 246-7680
24 HOURS A DAY

* Apple II TM of Apple Computer Inc. † TRS-80 TM of Tandy Corp. ‡ PET TM of Commodore Business Machines

Circle 332 on inquiry card.

Actual Size

Double Size




Figure 7: *Some of the cursor shapes used by the Star to indicate the state of the system. The cursor is a 16- by 16-bit map that can be changed under program control.*

one mechanism (the main typing keys) serve more than one function (entering letters and invoking commands). This inevitably leads to confusion. Star avoids the problem by having special keys on the keyboard devoted solely to invoking functions. The main typing keys only enter characters. (This is another example of the simplicity principle: avoid overloading mechanisms with meanings.)

Modes are not necessarily bad. Some modes can be helpful by simplifying the specification of extended commands. For example, Star uses a "field fill-in order specification mode." In this mode, you can specify the order in which the NEXT key will step through the fields in the document. Invoking the SET FILL-IN ORDER command puts the system in the mode. Each field you now select is added to the fill-in order. You terminate the mode by pushing the STOP key. Star also utilizes temporary modes as part of the MOVE, COPY, and COPY PROPERTIES commands. For example, to move an object, you select it, push the MOVE key that puts the system in "move mode," and then select the destination. These modes work for two reasons. First, *they are visible*. Star posts a message in the Message Area at the top of the screen indicating that a mode is in effect. The message remains there for the duration of the mode. Star also changes the shape of the cursor as an additional indication. You can always tell the state of the system by inspection (see figure 7). Second, *the allowable actions are constrained during modes*. The only action that is allowed—except for actions directly related to the mode—is scrolling to another part of the document. This constraint makes it even more apparent that the system is in an unusual state.

User Tailorability

No matter how general or powerful a system is, it will never satisfy all its potential users. People always want ways to speed up often-performed operations. Yet, everyone is different. The only solution is to design the system with provisions for user extensibility built in. The following mechanisms are provided by Star:

- You can tailor the appearance of your system in a variety of ways. The simplest is to choose the icons you want on your Desktop, thus tailoring your working environment. At a more sophisticated level, a work station can be purchased with or without certain functions. For example, not everyone may want the equation facility. Xerox calls this "product factoring."
- You can set up blank documents with text, paragraph, and page layout defaults. For example, you might set up one document with the normal text font being 10-point Classic and another with it being 12-point Modern italic. The documents need not be blank; they may contain fixed text and graphics, and fields for variable fill-in. A typical form might be a business-letter form with address, addressee, salutation, and body fields, each field with its own default text style. Or it might be an accounting form with lines and tables. Or it might be a mail form with To, From, and Subject fields, and a heading tailored to each individual. Whatever the form or document, you can put it on your Desktop and make new instances of it by selecting it and invoking COPY. Thus, each form can act like a "pad of paper" from which new sheets can be "torn off."

Interesting documents to set up are "transfer sheets," documents containing a variety of graphics symbols tailored to different applications. For example, you might have a transfer sheet containing buildings in different sizes and shapes, or one devoted to furniture, animals, geometric shapes, flowchart symbols, circuit components, logos, or a hundred other possibilities. Each sheet would make it easier to create a certain type of illustration. Graphics experts could even construct the symbols on the sheets, so that users could create high-quality illustrations without needing as much skill.

- You can tailor your filing system by changing the sort order in file drawers and folders. You can also control the

TRS-80* COMPUTING EDITION

©1981 Percom Data Co., Inc. The Percom Peripheral 35 cents

Percom's DOUBLER II™ tolerates wide variations in media, drives

GARLAND, TEXAS — May 22, 1981 — Harold Mauch, president of Percom Data Company, announced here today that an improved version of the Company's innovative DOUBLER® adapter, a double-density plug-in module for TRS-80* Model I computers, is now available.

Reflecting design refinements based on both theoretical analyses and field testing, the DOUBLER II®, so named, permits even greater tolerance in variations among media and drives than the previous design.

Like the original DOUBLER, the DOUBLER II plugs into the drive controller IC socket of a TRS-80 Model I Expansion Interface and permits a user to run either single- or double-density diskettes on a Model I.


With a DOUBLER II installed, over four times more formatted data — as much as 364 Kbytes — can be stored on one side of a five-inch diskette than can be stored using a standard Tandy Model I drive system.

Moreover, a DOUBLER II equips a Model I with the hardware required to run Model III diskettes.

(*Ed. Note*: See "OS-80®: Bridging the TRS-80* software compatibility gap" elsewhere on this page.)

The critical clock-data separation circuitry of the DOUBLER II is a proprietary design *called a ROM-programmed digital phase-lock loop data separator.*

According to Mauch, this design is more tolerant of differences from diskette to diskette and drive to drive, and also provides *immunity to performance degradation caused by circuit component aging.*



Percom DOUBLER II®

Mauch said "A DOUBLER II will operate just as reliably two years after it is installed as it will two days after installation."

The digital phase-lock loop also *eliminates the need for trimmer adjustments typical of analog phase-lock loop circuits.*

"You plug in a Percom DOUBLER II and then forget it," he said.

The DOUBLER II also features a refined Write Precompensation circuit that more effectively minimizes the phenomena of bit- and peak-shifting, a reliability-impairing characteristic of magnetic data recording.

The DOUBLER II, which is fully software compatible with the previous DOUBLER, is supplied with DBLDOS™, a TRSDOS*-compatible disk operating system.

The DOUBLER II sells for ~~$219.95~~, including the DBLDOS diskette. NOW $169.95!

The Percom DOUBLER II is available from authorized Percom retailers, or may be ordered direct from the factory. The factory toll-free order number is 1-800-527-1222.

Ed. note: Opening the TRS-80 Expansion Interface may void the Tandy limited 90-day warranty. Circle 327 on inquiry card.

Circuit misapplication causes diskette read, format problems.

High resolution key to reliable data separation

GARLAND, TEXAS — The Percom SEPARATOR® does very well for the Radio Shack TRS-80* Model I computer what the Tandy disk controller does poorly at best: *reliably* separates clock and data signals during disk-read operations.

Unreliable data-clock separation causes format verification failures and repeated read retries.

CRC ERROR—TRACK LOCKED OUT

The problem is most severe on high-number (high-density) inner file tracks.

As reported earlier, the clock-data separation problem was traced by Percom to misapplication of the internal separator of the 1771 drive controller IC used in the Model I.

The Percom Separator substitutes a *high-resolution* digital data separator circuit, one which operates at 16 megahertz, for the low-resolution one-megahertz circuit of the Tandy design.

Separator circuits that operate at lower frequencies — for example, two- or four-megahertz — were found by Percom to provide only marginally improved performance over the original Tandy circuit.

The Percom solution is a simple adapter that plugs into the drive controller of the Expansion Interface (EI).

Not a kit — some vendors supply an untested separator kit of resistors, ICs and other paraphernalia that may be installed by modifying the computer — the Percom SEPARATOR is a fully assembled, fully tested plug-in module.

Installation involves merely plugging the SEPARATOR into the Model I EI disk controller chip socket, and plugging the controller chip into a socket on the SEPARATOR.

The SEPARATOR, which sells for only $29.95, may be purchased from authorized Percom retailers or ordered directly from the factory. The factory toll-free order number is 1-800-527-1222.

Ed. note: Opening the TRS-80 Expansion Interface may void the Tandy limited 90-day warranty. Circle 326 on inquiry card.

All that glitters is not gold

OS-80™ Bridging the TRS-80* software compatibility gap

Compatibility between TRS-80* Model I diskettes and the new Model III is about as genuine as a gold-plated lead Krugerrand.

True, Model I TRSDOS* diskettes can be *read* on a Model III. But first they must be converted and re-recorded for Model III operation.

And you *cannot write* to a Model I TRSDOS* diskette. Not with a Model III. You cannot add a file. Delete a file. Or in any way modify a Model I TRSDOS diskette with a Model III computer.

Furthermore, your converted TRSDOS diskettes cannot be converted *back* for Model I operation.

TRSDOS is a one-way street. And there's no retreating. A point to consider before switching the company's payroll to your new Model III.

Real software compatibility should allow the *direct, immediate* interchangeability of Model I and Model III diskettes. No read-only limitations, no conversion/re-recording steps and no chance to be left high and dry with Model III diskettes that can't be run on a Model I.

What's the answer? The answer is Percom's OS-80™ family of TRS-80 disk operating systems.

OS-80 programs allow *direct, immediate* interchangeability of Model I and Model III diskettes.

You can run Model I single-density diskettes on a Model III; install Percom's plug-in DOUBLER™ adapter in your Model I, and you can run double-density Model III diskettes on a Model I.

There's no conversion, no re-recording.

Slip an OS-80 diskette out of your Model I and insert it directly in a Model III.

And vice-versa.

Just have the correct OS-80 disk operating system — OS-80, OS-80D or OS-80/III — in each computer.

Moreover, with OS-80 systems, you can add, delete, and update files. You can read *and write* diskettes regardless of the system of origin.

OS-80 is the original Percom TRS-80 DOS for BASIC programmers.

Even OS-80 utilities are written in BASIC.

OS-80 is the Percom system about which a user wrote, in Creative Computing magazine, "...the best $30.00 you will ever spend."†

Requiring only seven Kbytes of memory, OS-80 disk operating systems reside completely in RAM. There's no need to dedicate a drive exclusively for a system diskette.


And, unlike TRSDOS, you *can* work at the track sector level, defining and controlling data formats — in BASIC — to create simple or complex data structures that execute more quickly than TRSDOS files.


The Percom OS-80 DOS supports single-density operation of the Model I computer — price is $29.95; the OS-80D supports double-density operation of Model I computers equipped with a DOUBLER or DOUBLER II; and, OS-80/III — for the Model III of course — supports both single- and double-density operation. OS-80D and OS-80/III each sell for $49.95. Circle 328 on inquiry card.

PRICES AND SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE. PRICES DO NOT INCLUDE HANDLING AND SHIPPING.

PERCOM DATA COMPANY, INC. 11220 Pagemill Road Dallas, Texas 75243 (214) 340-7081

 †Creative Computing Magazine, June, 1980, page 26.





filing hierarchy by putting folders inside folders inside folders, to any desired level.

- You can tailor your record files by defining any number of "views" on them. Each view consists of a filter, a sort order, and a formatting document. A filter is a set of predicates that produces a subset of the record file. A formatting document is any document that contains fields whose names correspond to those in the record file. Records are always displayed through some formatting document; they have no inherent external representation. Thus, you can set up your own individual subset(s) and appearance(s) for a record file, even if the record file is shared by several users.
- You can define "meta operations" by writing programs in the *CUS*tomer *P*rogramming language CUSP. For example, you can further tailor your forms by assigning computation rules expressed in CUSP to fields. Eventually, you will be able to define your own commands by placing CUSP "buttons" into documents.
- You can define abbreviations for commonly used terms by means of the abbreviation definition/expansion facility. For example, you might define "sdd" as an abbreviation for "Xerox Systems Development Department." The expansion can be an entire paragraph, or even multiple paragraphs. This is handy if you create documents out of predefined "boilerplate" paragraphs, as the legal profession does. The expansion can even be an illustration or mathematical formula.
- Every user has a unique name used for identification to the system, usually the user's full name. However, you can define one or more *aliases* by which you are willing to be known, such as your last name only, a shortened form of your name, or a nickname. This lets you personalize your identification to the rest of the network.

Summary

In the 1980s, the most important factors affecting how prevalent computer usage becomes will be reduced

cost, increased functionality, improved availability and servicing, and, perhaps most important of all, progress in user-interface design. The first three alone are necessary, but not sufficient for widespread use. Reduced cost will allow people to *buy* computers, but improved user interfaces will allow people to *use* computers. In this article, we have presented some principles and techniques that we hope will lead to better user interfaces.

User-interface design is still an art, not a science. Many times during the Star design we were amazed at the depth and subtlety of user-interface issues, even such supposedly straightforward issues as consistency and simplicity. Often there is no one "right" answer. Much of the time there is no scientific evidence to support one alternative over another, just intuition. Almost always there are trade-offs. Perhaps by the end of the decade, user-interface design will be a more rigorous process. We hope that we have contributed to that progress. ■

References

1. Arnheim, Rudolf. *Visual Thinking*. Berkeley: University of California Press, 1971.
2. Brooks, Frederick. *The Mythical Man-Month*. Reading, MA: Addison-Wesley, 1975.
3. Card, Stuart, William English, and Betty Burr. "Evaluation of Mouse, Rate-Controlled Isometric Joystick, Step Keys, and Text Keys for Text Selection on a CRT." *Ergonomics*, vol. 21, no. 8, 1978, pp. 601-613.
4. Dahl, Ole-Johan and Kristen Nygaard. "SIMULA—An Algol-Based Simulation Language." *Communications of the ACM*, vol. 9, no. 9, 1966, pp. 671-678.
5. Engelbart, Douglas and William English. "A Research Center for Augmenting Human Intellect." *Proceedings of the AFIPS 1968 Fall Joint Computer Conference*, vol. 33, 1968, pp. 395-410.
6. English, William, Douglas Engelhart, and M. L. Berman. "Display-Selection Techniques for Text Manipulation." *IEEE Transactions on Human Factors in Electronics*, vol. HFE-8, no. 1, 1967, pp. 21-31.
7. Fitts, P. M. "The Information Capacity of the Human Motor System in Controlling Amplitude of Movement." *Journal of Experimental Psychology*, vol. 47, 1954, pp. 381-391.
8. Ingalls, Daniel. "The Smalltalk Graphics Kernel." BYTE, August 1981, pp. 168-194.
9. Intel, Digital Equipment, and Xerox Corporations. *The Ethernet, A Local Area Network: Data Link Layer and Physical Layer Specifications.* Version 1.0, 1980.
10. Irby, Charles, Linda Bergsteinsson, Thomas Moran, William Newman, and Larry Tesler. *A Methodology for User Interface Design*. Systems Development Division, Xerox Corporation, January 1977.
11. Kay, Alan and the Learning Research Group. *Personal Dynamic Media.* Xerox Palo Alto Research Center Technical Report SSL-76-1, 1976. (A condensed version is in *IEEE Computer*, March 1977, pp. 31-41.)
12. Lampson, Butler. "Bravo Manual." *Alto User's Handbook*, Xerox Palo Alto Research Center, 1976 and 1978. (Much of the design of all the implementation of Bravo was done by Charles Simonyi and the skilled programmers in his "software factory.")
13. Metcalfe, Robert and David Boggs. "Ethernet: Distributed Packet Switching for Local Computer Networks." *Communications of the ACM*, vol. 19, no. 7, 1976, pp. 395-404.
14. Miller, George. "The Magical Number Seven, Plus or Minus Two: Some Limits on Our Capacity for Processing Information." In *The Psychology of Communication*, by G. Miller, New York: Basic Books, 1967. (An earlier version appeared in *Psychology Review*, vol. 63, no. 2, 1956, pp. 81-97.
15. Seybold, Jonathan. "Xerox's 'Star'." In *The Seybold Report*, Media, PA: Seybold Publications, vol. 10, no. 16, 1981.
16. Smith, David Canfield. *Pygmalion, A Computer Program to Model and Stimulate Creative Thought.* Basel, Switzerland: Birkhauser Verlag, 1977.
17. Smith, David Canfield, Charles Irby, Ralph Kimball, and Eric Harslem. "The Star User Interface: An Overview." Submitted to the AFIPS 1982 National Computer Conference.
18. Tesler, Larry. Private communication; but also see his excellent discussion of modes in "The Smalltalk Environment." BYTE, August 1981, pp. 90-147.
19. Thacker, C. P., E. M. McCreight, B. W. Lampson, R. F. Sproull, and D. R. Boggs. "Alto: A Personal Computer." In *Computer Structures: Principles and Examples*, edited by D. Siewiorek, C. G. Bell, and A. Newell, New York: McGraw-Hill, 1982.
20. Wertenbaker, Lael. *The World of Picasso.* New York: Time-Life Books, 1967.
21. Zloof, M. M. "Query-by-Example." *Proceedings of the AFIPS 1975 National Computer Conference*, vol. 44, 1975, pp. 431-438.

Designing a Text Editor? The User Comes First

A system's power is measured in ease of use.

Steven Jong
38 Riverhurst Road
Billerica, MA 01821

In choosing or designing any computer system—hardware or software—the most important consideration is the human interface: if a system doesn't work for the user, it's not a working system. This article presents observations on the crucial relationship between human factors and the design of text editors for video-display terminals. These observations are drawn from my experience with a number of editors on computers of various sizes and from software-design and human-factors literature. All the features described here exist on at least one editor. My aim is to give you some things to look for if you want to buy—or write—an outstanding text editor.

The first and most important design goal is *ease of use*. This should surprise no one. James Martin (see reference 7) pointed out back in 1973: "To be effective [in the next decade], systems will have to be designed from the outside in. The terminal or console operator, instead of being a peripheral consideration, will become the tail that wags the whole dog." Text editors are, to most users, the outermost layer of their computer system—the layer they deal with most. Timesharing users spend over half their time using a text editor, and editing commands account for about fifteen percent of all commands they enter. Personal-computer users may exceed those figures. Ease of use, therefore, weighs most heavily on editor design.

About the Author
Steven Jong, a principal software technical writer, holds a master's degree in science communication from Boston University.

What, then, makes a good text editor? Human-factors literature suggests many characteristics of the laudable text editor. Different authors espouse perfectly reasonable but totally contradictory principles. You'll have to evaluate your needs when designing one feature in and another out (see text box on page 298.)

Screen Display Features

Let's consider what you want or need to see on the text display.

The top or bottom display line (but not both) should provide program and system status information, such as the file name, the current file line number, the last command invoked, the time, and program prompts. This keeps you informed as to the system state and is well worth the overhead. Another line could display the current tab stops and margins, if they are to be controlled by the user (see figure 1).

When you enter a keystroke in the middle of a line of text, one of two things may happen. The character at the cursor position may be overstruck by the new character; or the new character may be inserted at the cursor position and characters from the cursor position on move to the right to accommodate it. Existing editors use both modes, but overstrike editors require a separate insert/stop-insert function and don't prevent you from accidentally replacing text. From the user's viewpoint, a display mode that allows accidental erasure of text is undesirable.

A screen-editor window is limited by the size of the screen. To minimize the effects of this limitation and allow you to browse through text, there must be a command to scroll text, both vertically and horizontally (see figure 2). (An editor that allows horizontal scrolling can display overlong lines as truncated, with the ends of the lines offscreen, which seems most natural.) You should be able to scroll through the file continuously and stop whenever you want. This suggests that scrolling should continue as long as some particular key is depressed and stop the instant the key is released.


How fast should the display scroll? The Honeywell WP 6 word processor lets you scroll at the rate of about ten lines per second. This allows browsing, but is slow if you want to traverse several screens' worth of text. It also limits scrolling to the text within the current page of memory. The scrolling function built into Radio Shack Model II computers gets you from one end of a file to the other very nicely, but too quickly to read anything. It would be nice to scroll and also maneuver using some other mechanism, such as "go to string," "go to page," etc.

You may want to mark blocks of text for movement, reproduction, or

COMMODORE VIC-20®


"THE WONDER COMPUTER OF THE 1980s. UNDER $300."


—WILLIAM SHATNER





"The best computer value in the world today. The only computer you'll need for years to come."





JOYSTICK PADDLE LIGHTPEN

ON/OFF SWITCH

POWER PACK

PLUG-IN PROGRAMS

3K/8K/16K MEMORY EXPANSION

PLUG-IN PROGRAM

EXPANSION MODULE

RF MODULATOR

TELEVISION OR MONITOR

VIDEO CABLE

SINGLE DISK DRIVE

PRINTER


COMMODORE DATACASSETTE

MODEM FOR TELEPHONE AND TELECOMPUTING

VIC-20® VS. OTHER HOME COMPUTERS

Product Features	Commodore VIC-20	Atari® 400™	TI® 99/4A	TRS-80® Color Computer
Price*	$299.95	$458.95	$499.00	$399.00
Maximum RAM Memory	32K	16K	16K	32K
Keyboard Style	Full-Size Typewriter Style	Flat Plastic Membrane	Half-Size Typewriter Style	Calculator Style
Number of Keys	66	57	40	53
Programmable Function Keys	4	0	0	0
Graphic Symbols On Keyboard	62	0	0	0
Displayable Characters	512	256	64	256
Microprocessor	6502	6502	T1990	6809
Accessible Machine Language	YES	YES	NO	YES
Upper/Lower Case Characters	YES	YES	NO	NO
Operates with all Peripherals (Disk, Printer and Modem)	YES	NO	YES	YES
Full Screen Editor	YES	YES	NO	NO
Microsoft Basic	Standard	N/A	N/A	$ 99.00
Telephone Modem	$109.95	$399.95	$450.00	$154.95

*Manufacturer's suggested retail price Jan. 1, 1982. Includes BASIC cartridge required for programming.










VIC SUPER ALIEN · SARGON II CHESS · FIVE ADVENTURE GAMES · DRAW POKER · PERSONAL FINANCE I AND II · WORD PROCESSOR & TYPING PRACTICE · EXPENSE CALENDAR






MIDNIGHT DRIVE/ROAD RACE · RADAR RATRACE · CAR CHASE · CASINO-STYLE BLACKJACK · SPACEMATH · LOAN & MORTGAGE CALCULATOR · HOME INVENTORY



JUPITER LANDER · SUPERSLOT · VIC AVENGER · BIORHYTHM/COMPATABILITY · BLUE MEANIES FROM OUTER SPACE · SLITHER/SUPERSLITHER · VIC-20 SUPER EXPANDER

Read the chart and see why COMPUTE! Magazine[1] calls the VIC-20 computer "an astounding machine for the price." Why BYTE[2] raves: "...the VIC-20 computer unit is unexcelled as a low-cost consumer computer." Why Popular Mechanics[3] says "...for the price of around $300, it's the only game in town that is more than just a game." And why ON COMPUTING INC.[4] exclaims: "What is inside is an electronic marvel... if it sounds as if I'm in love with my new possession, I am."

The wonder computer of the 1980s. The VIC-20 from Commodore, world's leading manufacturer of a full range of desktop computers. See the VIC-20 at your local Commodore dealer and selected stores.

1 April '81 issue 2 May '81 issue 3 November '81 issue 4 Fall '81 issue

VIC-20

commodore COMPUTER

Commodore Computer Systems
681 Moore Rd., King of Prussia, PA 19406
Canadian Residents: Commodore Computer Systems
3370 Pharmacy Ave., Agincourt, Ont., Canada, M1W 2K4

Please send me more information on the VIC-20.

Name ____________________

Address ____________________

City __________ State ______ Zip ______

Phone ____________________

VIC-BY

Circle 92 on Inquiry card.

```
S...!....1.....!...2.........3.........4.........5.........6....◄
Dear.Mom, ◄
◄
►   My.first.day.at.the.computer.camp.has.been.just.swell...You.
wouldn't.believe.what.these.computers.can.do!..And.all.the.kids.
get.their.own.systems.for.their.very.own!..I'm.so.happy.you.and.
Daddy.decided.to.send.me.here. ◄
►   The.bunks.are.kind.of.lumpy,.but.I.guess.I'll.get.used.to.
them...There's.also.lakes,.and.woods,.and.we.can.play.
volleyball.and.baseball.in.the.afternoons...The.food.is.pretty.
good,.and.we.had.ice.cream.today! ◄
►   I'm.going.to.spend.a.few.days.in.the.LISP.class,.so.I.can.
find.out.how.to.do.artificial.intelligence...Then.I.can't.
decide.whether.to.take.data-base.managemet.or.word.processing..
I.think.maybe.I'll.take.word.processing...That.way.I.can.write.
home.to.you.every.day! ◄
►   My.friend.Bobby.wants.me.to.go.play.Space.Invaders.now...I.
bet.I.beat.him! ◄
◄
◄
◄
►  ►          Love, ◄
►  ►          Harold
LETTER       PAGE 1   LINE 16  Press DEL to delete, or RETURN to cancel.
```

Figure 1: *An idealized screen-editor display. The larger the display area, the better. Spaces, tabs, and carriage returns are indicated by special symbols. "S" in the tab line indicates single spacing; "◄" indicates that the line length is 64 characters; "!" indicates a tab stop. Besides showing its user a window of text, the screen highlights selected blocks, prompts for action, and displays program and system status.*

deletion. Text editors on some minicomputers display plain text in low-intensity characters and mark blocks using high-intensity characters. Microcomputer-based word processors tend to use inverse-video characters for the same function.

A useful, advanced feature is multifile editing. The best way to display multiple files on the screen is to use multiple windows. The screen can, for instance, be bisected by a line of dashes, with one file displayed above and the other below. Some editors dedicate a portion of the screen as a message window for prompts and error messages. This window should not be too large, of course; three or four lines is typical.

Many text editors employ the beep signal, a simple and powerful attention-getting device that, unfortunately, is often misused. More than one word-processing system uses the signal in an inconsistent and annoying way: beeping when users enter some things right (sign-in lines, for instance), and yet also beeping when users enter some things incorrectly (a function key during a search); often they remain silent during many other kinds of errors. In my opinion, the beeper is best left to signaling errors.

The coming flood of color computers will soon bring a generation of full-color software. Four colors—red, green, blue, and yellow—are probably sufficient for text displays; green is generally acknowledged as easiest on the eyes. Color could highlight a search string, an error message, or a prompt. Color could also mark portions of a file. For instance, various parts of a document could be marked in green (draft), yellow (comments), red (technical questions), and so forth. However, color should not be the *only* distinguishing feature of important messages, because four percent of the population are color blind.

Word-Processing Features

Certain functions apply strictly to word processing. One is a dot-filled display in which each space character is represented by a dot smaller than a period. The dots simplify counting spaces and aligning text vertically. One might argue that a dot-filled screen appears too "busy," but most users of Wang and Lanier word processors, which feature dot-filled screens, are happy with them.

A good word-processing editor should perform "word wrapping",

BASIC-80
CP/M
Z-80

Turn your Apple into the world's most versatile personal computer.

The SoftCard™ Solution. SoftCard turns your Apple into two computers. A Z-80 and a 6502. By adding a Z-80 microprocessor and CP/M to your Apple, SoftCard turns your Apple into a CP/M based machine. That means you can access the single largest body of microcomputer software in existence. Two computers in one. And, the advantages of both.

Plug and go. The SoftCard system starts with a Z-80 based circuit card. Just plug it into any slot (except 0) of your Apple. No modifications required. SoftCard supports most of your Apple peripherals, and, in 6502-mode, your Apple is still your Apple.

CP/M for your Apple. You get CP/M on disk with the SoftCard package. It's a powerful and simple-to-use operating system. It supports more software than any other microcomputer operating system. And that's the key to the versatility of the SoftCard/Apple.

Circle 275 on inquiry card.

BASIC included. A powerful tool, BASIC-80 is included in the SoftCard package. Running under CP/M, ANSI Standard BASIC-80 is the most powerful microcomputer BASIC available. It includes extensive disk I/O statements, error trapping, integer variables, 16-digit precision, extensive EDIT commands and string functions, high and low-res Apple graphics, PRINT USING, CHAIN and COMMON, plus many additional commands. And, it's a BASIC you can compile with Microsoft's BASIC Compiler.

More languages. With SoftCard and CP/M, you can add Microsoft's ANSI Standard COBOL, and FORTRAN, or Basic Compiler and Assembly Language Development System. All, more powerful tools for your Apple.

Seeing is believing. See the SoftCard in operation at your Microsoft or Apple dealer. We think you'll agree that the SoftCard turns your Apple into the world's most versatile personal computer.

Complete information? It's at your dealer's now. Or, we'll send it to you and include a dealer list. Write us. Call us. Or, circle the reader service card number below.

SoftCard is a trademark of Microsoft. Apple II and Apple II Plus are registered trademarks of Apple Computer. Z-80 is a registered trademark of Zilog, Inc. CP/M is a registered trademark of Digital Research, Inc.



Microsoft Consumer Products, 10700 Northup Way, Bellevue, WA 98004 • (206) 828-8080




Figure 2: *Vertical and horizontal scrolling provide a flexible "window" to text. Conceptually, either the screen or the text can be thought of as moving.*

i.e., a word being typed in that exceeds the specified line length is carried down to start a new line. This relieves you of having to decide when to end a line. Word wrapping is one of the two most useful features of a word-processing editor (the other is character deletion). It is possible both to break lines and justify them at the same time; Micropro International's Wordstar microcomputer-based editor does this.

When characters are inserted into the middle of a line, a word-processing editor should reformat the rest of the text automatically. In practice, this proves difficult. Some editors, for instance, temporarily clear the screen from the cursor position to the end of the screen during text insertion (see figure 3). New text can be entered and formatted; when the user signals that insertion is finished, the rest of the text is reformatted. The ideal editor would reformat text continuously during insertion, but I have seen no editor that does. Instead, most include a separate "reformat" command to reformat the current paragraph after insertion is finished.

Navigating Through the File

Now that we know how to display text, we must deal with the problem of finding our way through it. Addressing text is a prerequisite to manipulating text. The more power and flexiblity you have in addressing, the better.

The basic cursor movement is "quadridirectional," or up/down/left/right, universally offered by screen editors. Boundary conditions, however, may vary from one editor to the next. For instance, if the cursor is in column 1 (the left extreme of the screen) and you try to move the cursor to the left, one screen editor might treat your action as an error; another editor might oblige the request by moving the cursor to the last character of the previous line.

What happens when you try to move the cursor past the end of a line? Usually, editors will not allow cursor movement, or at least text insertion, past the end of a line. In practice this proves a limitation, and there is no ease-of-use justification for it. It could, in fact, imply an attempt to enter spaces (perhaps the user is trying to make columnar text column by column).


Commands that move the cursor a single character at a time are not enough. There should also be commands to move by word, line, sentence, paragraph, screen, page image, and column; the ability to go to the top or the bottom of a file at a single keystroke is also useful. Combining cursor-movement commands with a Repeat key is also very important (an advanced video terminal may include an automatic-repeat function if a key is held down). An alternative for terminals without repeat functions is to allow commands to accept numeric arguments so that a user could, for instance, skip four sentences.

Signaling Commands

Now we turn to the mechanism by which you signal that you are entering a command (the nature of which is not yet important). Single-character command names are best for fast typing. Screen editors must use nonalphanumeric characters, because alphanumeric keystrokes must always appear as entered. The next simplest arrangement is to use control characters, because the CTL (Control) key is standard on most computer keyboards. CTL-W, then, might mean "write file." Of course, entering some command sequences would require two hands.

Designers of some computer systems, thinking of novice users, in-

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES



BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 45 Martinsville, NJ

POSTAGE WILL BE PAID BY ADDRESSEE




Subscription Department
P.O. Box 307
Martinsville, NJ 08836



Introducing "Popular Computing," the key to understanding.

Now you don't have to be a computer professional to unlock all the mysteries, potential, and pleasures of home and small business computers. *Popular Computing*, the new monthly magazine from McGraw-Hill, is the key.

Created in response to growing demand for our informative quarterly *onComputing*, *Popular Computing* explores every aspect of personal computers and their use. All reported in easy-to-understand nontechnical language.



The answer to "Computerphobia."

Even the most computer-unsophisticated reader will find *Popular Computing* interesting and stimulating. Every issue will contain straight-talking product reviews, special news briefs, and feature articles by famous guest contributors (like Isaac Asimov). There'll even be a helpful glossary of computer jargon we couldn't avoid using, and much, much more.

Special Introductory Offer.

Send in this coupon today, and take advantage of *Popular Computing's* Special Introductory Offer.

McGraw-Hill

SUPER SAVINGS FOR ME...I'm taking advantage of this super introductory offer of 12 issues for only $11.97 saving me $3.03 on the basic rate of $15.00—and saving me $18.03 off the 12 issue newsstand rate of $30.00. If my 30-day review of your first issue doesn't 100% please me, I may cancel my subscription and you will promptly refund ALL my money or give me a FULL credit on my charge card marked below:

Mail Today to:
POPULAR COMPUTING
P.O. Box 307, Martinsville, NJ 08836

☐ Check Enclosed for $11.97
☐ Charge $11.97 to: ☐ Visa ☐ Mastercard

Card No. ____ Expires ____
Signature ____
Name (Please Print) ____
Address ____
City ____
State ____ Zip ____

POPULAR COMPUTING
THE KEY TO UNDERSTANDING
P.O. Box 397, Hancock, NH 03449

INTERESTED?



LET'S TALK

CONCEPT: *PRIVATE COMPUTERS*

Our marketplace is maturing. Those of you that were around in 1977 will remember what it took then to make a sale...*(anything that worked!)*

The two beautiful faces at the left are evidence that *changes have occured* in the industry!!!

Besides an excellent, well proven S-100, CP/M, Z-80 4MHZ computer system, we have a few extra things to offer. *(Not the model!)*

Delta specializes in something called a ***Private Computer***. It's for those of you systems integrationists that have matured with the market. You stopped assembling systems in your garage a long time ago, but still need a totally flexible computer line that your customers won't find at *Wards* or *Sears.*

1. **A *Private Computer* means** you will never see one of our computer systems on the shelf of your local department store or computer shop. We only sell to systems integrationists who add value to our product.

2. **A Complete Range of Products** is available. No other micro company in the world offers a more complete line of equipment to satisfy your needs. We have everything from low end single user systems to the top of the line 64 user distributed processing networks.

3. **The DP Software Library** is growing every month. We supply Accounting, Business Management, Code Writing, Medical, Dental, Chiropractic, Word Processing, Property Management and other programs. We have the source code in most cases and can negotiate customization if needed. Video taped training cassetts to aid you and your customers in learning how to use the programs and run the hardware are available.

4. **Factory Support and Service** is available in most large cities. There are 66 fully stocked factory maintainance centers in the U.S. and 12 outside the U.S. In more remote areas, our 24 hour fast turnaround component pool can be used to insure reasonable response times to satisfy customers. We have a customer service *Hotline* independant of sales or service. We have a ***24 Hour Modem Engineering Advisory Billboard.***

5. **Our Engineering Assistance and Software Development Program** can make headaches turn into profits. We maintain a staff of Engineers and Programmers whose services can be leased to expand your range of services. Problems from something as simple as hooking up a new printer or modifying an existing software program to customize a screen display can be resolved with this service.

6. **Financial Assistance** is available through a flexible credit program that can not only get the product to you quickly but keep your cash busy where it will do the most good. 30 - 60 - 90 day flooring plans can be arranged to allow you to collect your money before you have to pay us.

Sherry Starkey is on line right now at Delta to direct you to your area representative. If you have a half inch Beta or VHS video machine, ask Sherry for a sales demonstration in your own home or office. ***See the Plant, the People and the Program.***

DELTA PRODUCTS INC. • 15392 ASSEMBLY LANE, HUNTINGTON BEACH, CA 92649
(714) 898-1492 • MON to FRI - 8 AM to 5 PM • TELEX: 681-367 DELTMAR HTBH

Circle 145 on inquiry card.

```
S...!....1.........2.........3.........4.........5.....◄
and.slowed.to.a.halt.◄
◄
►   Most.of.the.flanges.were.undamaged.by.the.accident.
However,.the.flanges.closest.to.the.input.valve.were.
slightly.scratched,.and.those.actually.struck .by.the.
chain.were.contaminated.with.oil...This.was.judged.not.
serious..█




TRIPREPORT PAGE 12 LINE 44 We.therefore.recommend.the.following: ◄◄►1.► Do.not
```

Figure 3: *Text insertion on a typical minicomputer-based word processing editor. The screen is cleared from the point of insertion; new text is displayed in proper format. The display logic is simpler than for reformatting the screen after every character is entered. In the illustration, inserted text is highlighted.*

variably turn to special-function keys for signal commands. They feel the simplest possible arrangement is to give each function its own labeled key, reinforcing the what-you-see-is-what-you-get nature of screen editors. But before assigning all functions to dedicated keys, a designer should consider what adjustments skilled typists must make to reach function keys located on the periphery of a keyboard, and whether certain functions are too important to be invoked with single keystrokes. The rush toward function keys in the business market may slow as human-factors specialists research these questions. In the microcomputer marketplace, function keys are uncommon, and a general-purpose screen editor would be fatally limited if it required function keys.

Ease-of-use considerations suggest the use of prompts for procedural commands. If you press the Search key on a Wang word processor, the system prompts: "For what?" in the message window. It searches for whatever is typed in response to the prompt. Press the Delete key; it prompts: "Delete what?" Mark text for deletion, and press the Execute key to actually delete it. This prompting helps beginning users, though in time they become conditioned to ignore the prompts.

Commands can be assigned to individual keys mnemonically, physically, or symbolically. For example, to signal quadridirectional cursor movement, a mnemonic assignment scheme could be U, D, L, and R (for up, down, left, and right); a physical assignment scheme could be W, Z, A, and S (spatially simulating a cursor keypad—try it on your own keyboard!); and a symbolic assignment scheme could be ^, V, <, and > (symbolizing arrows). There are other possibilities: another mnemonic could be F, B, P, and N (forward, backward, previous, and next); and another physical scheme could be I, J, K, and M (for the right hand instead of the left). All of these arrangements are used on various systems. Whatever the scheme, commands must be logically arranged, even at the expense of leaving out a function because there is no reasonable key to which it can be assigned. A command that is hard to call will be hard to remember and, ultimately, hard to use.

If key assignments are not completely logical, the results may be

catastrophic. I recall a Boston University student who some years ago ran afoul of the RAX line editor written for the school's IBM 360/50 system. He went to a computing center adviser and explained that he was searching for what he thought was the next line of his file. Although he had checked most of his file, he couldn't find the elusive line. When the adviser examined the file, she discovered that most of it had been deleted. When asked what commands he had been using, the student replied that he didn't know much about the editor, but that U meant go up, and didn't D mean go down? It was a perfectly reasonable assumption; unfortunately, while U did mean up, N (next) meant down, and D meant delete.

The first commands to assign should be the basic ones given in table 1. They form a simple, symmetrical, and complete set of editing functions. Note that the Search command requires some sort of command sequence to signal the editor that the search string has been specified. The Return key is natural for this purpose (at the cost of making the Return character a difficult string to search for).

Unless the editor handles routine file I/O (input/output) operations—creating, deleting, reading from, and writing to files—expect it to work only with an operating system. These operations must be invisible to the user.

Idiot-Proofing

Designers, preoccupied with establishing responses to correct keystrokes, often neglect incorrect ones. Because editors are used so extensively they should never abort, no matter what you enter. The process of "idiot-proofing" interactive programs was described by Anthony Wasserman in 1973 (see reference 11). It involves anticipating incorrect entries, missing input, inadvertent keystrokes (e.g., BREAK, CTL, and ESCape), and transmission errors (which are rare in personal computer terminals). An example of non-idiot-proof hardware is found in some versions of the Apple II computer keyboard. The Reset key is in a hard-to-miss location—just above the Return key; many applications packages carry warnings never to press it while using their programs. One magazine printed a letter suggesting that Apple users place a rubber grommet beneath the key, to make it harder to push. A software example of non-idiot-proofing is the Electric Pencil I's tendency to drop keystrokes entered by fast typists. The very point of word processing is to increase throughput; a program that drops keystrokes invokes paranoia in its users and slows them down.

The use of "kill rings" is a nice, practical application of idiot-proofing. Deletions larger than single characters are not discarded, but stored temporarily in a stack. If text is deleted by accident, it can be retrieved by a command. This truly protects users from themselves. Editors with kill rings actually make it difficult to lose text.

Power versus Ease of Use

In general, the more powerful a system is (i.e., the more capabilities it has), the more difficult it is to use. There are two reasons for this: first, the sheer number of commands makes them hard to remember; second, it becomes impossible to assign commands to keys or names in a consistent manner. Many editors have forty or more commands; for them, any single-key naming scheme soon collapses. Editors on the market today delete text at the keystrokes D (delete), G (gobble), W (wipe), and K (kill). Some compromise between power and ease of use is needed.

Function keys are a liability for a powerful editor. Consider the Atex typesetting system, on which all functions are visible as function keys. There are, however, 32 function keys, and each can be prefixed with the shift key and/or a "supershift" key—making a total of 128 functions, assigned four to a key. Given the complexity of typesetting systems and the desire to provide an easy-to-use system, this end was inevitable.

What is needed is a hierarchy of

DID YOU KNOW THAT THE BEST MEDIA AVAILABLE IS NOW AVAILABLE NEAR YOU?

Well, it is.

For years, we've been supplying discriminating data processing professionals worldwide with the finest magnetic media made anywhere...Dysan diskettes, mini-diskettes, disc packs, disc cartridges and single rigid disks.

Is there any reason why **you** should have to settle for second best?

Now you can buy Dysan precision diskettes and mini-diskettes direct from the Dysan sales office or authorized dealer near you. And they're not just any diskettes. They're certified 100% error-free both on **and** between the tracks to insure you of flawless performance. That means no lost data. No need to re-program. Or de-bug again. Dysan diskettes work the first time, every time. Think about how much time, energy and aggravation you can save.

Why wait for problems to occur to convince you that a bargain diskette is really no bargain? Call the Dysan office nearest you. Or stop in your nearest authorized Dysan dealer. Once you experience the Dysan difference you won't settle for anything less.





Our Media Is Our Message

5201 Patrick Henry Drive
Santa Clara, CA 95050

READ (file)	read a file into the edit buffer at the current cursor location—implies file insertion, concatenation
WRITE (file)	save the contents of the edit buffer—implies file creation, overwriting; if file name is not given, write to current file
DELETE (object)	delete the character to the left, to the right, or at the cursor and reformat the screen; for advanced use, object can be a character, word, sentence, block, screen, etc.
SEARCH (object)	move the cursor to/past the string "object", which can be defined explicitly or, for advanced use, defined using metasymbols
Cursor movement (scroll)	move by character, or, for advanced use, by word, sentence, block, screen, etc.; moving the cursor past the edges of the screen can imply vertical/horizontal scrolling
QUIT	terminate the edit session; prompt for confirmation if changes have not been saved (abandoning changes may be intended)

Table 1: *These basic editing commands form a logical and symmetrical set of commonly used functions. Character insertion is always permitted. Note that the read and write functions imply file creation and deletion functions that an operating system or the editor must perform automatically.*

commands, divided into a basic group and an advanced group. The basic commands, which by definition are used most often, must be the easiest to signal. Some other signaling mechanism can be used for more esoteric functions.

The command hierarchy of the EMACS screen editor is an interesting attempt to reconcile the need for simplicity and logic in commands with the power of a large command repertoire. EMACS is a general-purpose tool that runs on a number of mainframe systems (a microcomputer version, called MINCE, is available from Mark of the Unicorn, POB 423, Arlington, MA 02174). It was originally developed in 1974 at the Massachusetts Institute of Technology by Richard Stallman (see reference 10). Since then, many user-written extensions have been added to the basic package.

The EMACS hierarchy has four levels, using the prefixes CTL (control), ESC (Escape), CTL-X (press the Control and X keys simultaneously), and ESC X (press the Escape key and then the X key). The first two prefixes are for simple commands; the second two are for more advanced commands. For instance, CTL-B moves the cursor back one character, while ESC B moves the cursor back one word; CTL-D deletes the current character, while ESC D deletes the preceding word.

Simple functions are simply named and thus simple to remember. CTL-X precedes some actions considered too important for single keystrokes; the sequence CTL-X CTL-C, for instance, is required to quit the editor. (Requiring multiple keystrokes to exit an editor is one of the simplest and best applications of idiot-proofing I have encountered.)

More powerful functions are called by entering ESC X and a string; for instance, "ESC X fillon" turns on word wrapping. This hierarchy allows an unlimited number of editor functions at the cost of forcing you to learn the hierarchy. EMACS can grow in power without compromising on the integrity of the fundamental command structure.

Text-editing Commands

The simple functions thus far described would be useful for editing any kind of sequential file. Other functions are more suited to editing text.

First, consider searching for a character string. Two popular display mechanisms are *display results* and *incremental search*. In display-results searches, the editor moves the cursor to the end of (and perhaps highlights) the string being sought only after you signal the end of the search string with some sort of escape sequence. This is the more common mechanism.

In incremental searching, the editor searches as each character of the string is entered. In theory, you need enter only the minimum string necessary to locate a desired point. If I

Design Guidelines

The literature abounds with contradictory guidelines for text-editor design, but the following summaries of various sources present widely supported principles for promoting ease of use.

In designing a system, minimize the need for memorization. Optimize operations—common operations should execute rapidly. Also, change the display as little as possible. Engineer for errors: design out common ones, provide good error messages, allow user actions to be reversed, and ensure data structure integrity.

Hansen (1971)

Minimize the need to learn about the system. Provide online help messages for the novice and built-in short cuts for experienced users. Provide a response for every possible user input.

Wasserman (1973)

Keep the system simple and responsive with immediate, unambiguous feedback. The user should initiate all actions and be able to quit at any time. The system should be flexible, allowing abbreviations, command files, prompting, and subsetting of the command structure.

Cheriton (1976)

In the command language, provide a complete and symmetric set of functions as well as convenient and consistent abbreviations for commands and command arguments. Simple functions should be simple to do, and in general the language should do what a reasonably intelligent user would expect. The system should prompt for confirmation before allowing irreversible actions (e.g., deleting files).

Muchnick (1976)

Allow browsing through text, and let the user see corrections as they're made. Provide status messages that give evidence of the system state.

Gebhardt and Stellmacher (1978)

Keep in mind that different users prefer different types of text editors; i.e., sophisticated users prefer a powerful editor, while beginners prefer a simple one. Also, different kinds of text require different editing commands (e.g., "forward paragraph" for editing text as opposed to "forward procedure" for editing PL/I programs).

Stallman (1979)

were searching through a text file for the word "there," I would certainly not enter just "th." Using incremental searching, though, I could safely try it and see if it would suffice; if not, I could continue typing characters until I got where I wanted. Though incremental searching is not as useful in practice as it sounds, the display algorithm is useful for highlighting blocks (see below).

Line editors usually have very powerful string-search functions that use *metacharacters* (characters used to describe or delineate other characters). The usual convention is to use ^ (caret) for the beginning of a line, $ (dollar sign) for the end of a line, . (period) for "any character," and * (asterisk) for "any number of the preceding character." Thus the search string ^the.*fox$ is interpreted to specify a line beginning with "the," ending with "fox," and having any number of arbitrary characters in between. Metacharacter searches are powerful and precise. Sophisticated users find metacharacter searching almost indispensable. But searching for a metacharacter itself requires using an "escape sequence" (pressing a series of keys to escape from one mode of operation into another), a concept beginners find hard to grasp. Ease of use compels us to abandon metacharacters, however reluctantly.

One function built around character searching is search-and-replace. There are four logical variations: replace once, replace-*n*-times, replace interactively, and replace globally. In interactive search-and-replace you should have, at every replacement point, the option of replacing, skipping, or quitting. In practice, all but replace-*n*-times prove useful and should be available.

Most line editors cannot locate strings that span lines. This is a severe limitation, often forcing you to enter text in some artificial manner (such as having every sentence on a separate line). A screen editor should not be so limited.

The basic text-editing command set should include an interactive routine for moving and copying text blocks. Three locations are required: the first and last characters of the block to be operated on and the location the block will be moved (or copied) to. Ease of use suggests that the routines prompt you for this information and highlight the text block.

The Honeywell WP 6 text editor provides a powerful mechanism for outlining text blocks. You position the cursor to the first character of the block and press, for instance, the Copy function key. The system prompts, "Copy What?" in the message area and highlights the character at the cursor position. The system then enters a single-character search mode; you can move the cursor to any character by entering that character. Entering three spaces advances the cursor three words; entering a period, carriage return, or page mark advances the cursor one sentence, paragraph, or page, respectively. The

This is a picture of all the printers in the world that outsell the MX-80.

Epson.


The one thing you can't beat in the marketplace is value. And there simply isn't a better combination of reliability, print quality, features and price in an 80-column printer than the Epson MX-80. Anywhere on earth.

But while we're pleased to make the best-selling 80-column printer in the world, we're hardly surprised. Because we decided a long time ago that the way to succeed in this business is to build a good product, sell it at a fair price, and stand behind it.

So we built our MX-80 with features like a choice of 24 different type faces, graphics that rival plotters, logical seeking, bidirectional printing and the world's first disposable print head. We priced it at under $650. And if it breaks, we'll be here to fix it.

That seems like a straightforward enough policy. But when we first introduced the MX-80, the competition laughed. Now they're cutting prices, introducing "new" models, and running splashy color ads, all in an effort to catch up. And they're not laughing.

But you don't have to take our word for it. You've got a choice: you can buy the printer that's been embraced by several hundred thousand computer fanatics all over the world. Or you can buy something else. And take your chances.



EPSON
EPSON AMERICA, INC.

3415 Kashiwa Street, Torrance, CA 90505 • (213) 539-9140

Circle 174 on inquiry card.

quadridirectional keys also work, either extending or reducing the block. Since the block is highlighted, you know exactly what is being copied. Once the block is marked, you press the Execute key, and the system prompts, "Copy it to where?" Position the cursor to the character before which the block is to be copied and press Execute again to complete the operation.

Messages to the User

System messages are, historically, coded as an afterthought. But because messages are among the most visible aspects of the software they are among the most important, especially for inexperienced users. Time is well invested in good system messages.

Messages should be polite, not imperious; straight, not funny; neutral, not personal. There are good and well-known reasons for this statement. For instance, how many times would you endure an error message like "YOU BLEW IT, BUD!!!" before becoming thoroughly annoyed? Human-factors research involved with large systems has shown that users are uncomfortable with computers that appear to be too lifelike, ordering them around or controlling them instead of vice versa. Ben Shneiderman (see reference 9) cites the Library of Congress database computer, which is available for public use. The programmers had to change prompts like "ENTER NEXT COMMAND" to "READY FOR NEXT COMMAND" because many people felt uncomfortable being ordered around by the computer.

Error messages are often written from an internal point of view and couched in terms of software interfaces, as if the author were peering out at the world from the port of a disk drive. Useful messages can only be written from the user's point of view. Ideally, an error message should say what went wrong, what has happened as a consequence of the error, and how to correct the error. For example, infinitely better than "HOLD BUFFER OVERFLOW," which describes an error in terms of an internal software event, is "LINE TOO LONG; REJECTED. RE-ENTER LINE." The latter succinctly tells what the user did wrong, what happened, and how to rectify the situation.

Help messages, which programmers would never think of providing for themselves, are an important aid to using any computer system. EMACS provides an elaborate, table-driven help system that provides a one-line description of what each keystroke does, a multiline help message for the same command, or a summary of related topics gathered through substring retrieval. Much is possible on a microcomputer system as well. Wordstar boasts an impressive online help facility with four levels of detail. Everyone from an experienced user to a rank amateur can obtain an appropriate level of assistance. It also has a HELP function, which describes the use of each key.

One grace note that seldom appears is the "in progress" message, which notifies you that some function is underway. EMACS, for instance, uses the messages "Reading. . . ," "Read," "Writing. . . ," and "Written" for the common I/O commands. I always include such messages in the command files I write; the system on which I work is subject to great fluctuations in load, and users tell me it's comforting to know their jobs haven't "curled up and died."

Multilingual Editors

Word-processing editors are specialized to the needs of editing English language text; they word-wrap lines and recognize constructs such as words, sentences, and paragraphs. A more generalized editing tool would be more useful to, say, Pascal programmers if it could format Pascal programs, balance parentheses (move the cursor between one parenthesis and its corresponding partner), recognize constructs such as procedures, and insert comment lines in the proper format. One can imagine the utility of an editor that recognizes PL/I, BASIC, FORTRAN, COBOL, LISP, etc. In fact, EMACS does this, making it a general-purpose tool and not just a word-processing editor.

Conclusion

Software designers make many decisions about how their software will behave. There are several reasons for choosing one form of behavior over another, based on established human-factors principles. An inefficient editor with a smooth user interface will be better received, and ultimately more useful, than an efficient editor with an ill-planned user interface. In the long run, software should be designed—and selected—not on the basis of what is most machine-efficient, but on the basis of how well people can use it. ■

References

1. Boies, S. J. "User behavior on an interactive computer system." *IBM Systems Journal*, Vol. 13, No. 1, 1974, pp. 2-18.
2. Cheriton, David R. "Man-Machine Interface Design for Timesharing Systems." *Proceedings of the ACM National Conference*, 1976, pp. 362-380.
3. *DECsystem 10 TECO Text Editor and Corrector Program Programmer's Reference Manual*. (Version 23 of TECO) Maynard, MA: Digital Equipment Corp., 1972.
4. Gebhardt, F., and Stellmacher, I. "Design Criteria for Documentation Retrieval Languages." *Journal of the American Society for Information Science*, Vol. 29, No. 4, July 1978, pp. 191-199.
5. Hansen, Wilfred J. "User Engineering Principles for Interactive Systems." *AFIPS Conference Proceedings*, Vol. 39, Fall Joint Computer Conference. Montvale NJ: AFIPS Press, 1971, pp. 523-532.
6. Kernighan, Brian W., and P. J. Plauger. *Software Tools*. Reading, MA: Addison-Wesley, 1976.
7. Martin, James. *Design of Man-Computer Dialogues*. Englewood Cliffs, NJ: Prentice-Hall, 1973.
8. Muchnick, Steve S. "The Command Interpreter and Command Language Design of the Com-Share Commander II System." *Proceedings of the ACM National Conference*, 1976, pp. 367-379.
9. Shneiderman, Ben. *Software Psychology*. Cambridge, MA: Winthrop Publishers, 1980.
10. Stallman, Richard M. "EMACS: The Extensible, Customizable, Self-Documenting Display Editor." A.I. Memo No. 519. Cambridge, MA: Massachusetts Institute of Technology, June 22, 1979.
11. Wasserman, Anthony I. "The Design of 'Idiot-Proof' Interactive Systems." *AFIPS Conference Proceedings*, Vol. 42, Proceedings of the National Computer Conference. Montvale, NJ: AFIPS Press, 1973, pp. M34-M38.

Managing Words

What Capabilities Should You Have with a Text Editor?

The ideal text editor is defined, drawing on the experience of many users.

Craig A. Finseth
Mark of the Unicorn Inc.
POB 423
Arlington, MA 02174

When moving from a typewriter to a computer-based text editor, you will encounter a bewildering array of new capabilities—some worth more than others. This article will single out the useful features (i.e., those capabilities that make a text editor more powerful or easier to use) from mere gadgetry. Although many of the features described here are often overlooked at first, they will be appreciated long after the first thrill of a new machine has worn off.

When you move from a typewriter to a text editor, expect to spend some time learning the new capabilities available to you. Among text-editor manufacturers, the temptation to cut the learning period short at the expense of providing more sophisticated editing capabilities is ever present. By simplifying, the manufacturer can demonstrate and teach people how to use all of the capabilities in a few minutes. Unfortunately, after these first few minutes there is no more to learn and no easier way of doing editing than by the few, simple operations that have been taught. As a rule of thumb, anything as easy to learn as a typewriter is as useful as a typewriter.

The following is a list of features desirable in a text editor. Not all features, however, will be useful to everyone. If you're planning to buy a text editor, you might want to check the list carefully, noting which features would serve your purposes best.

Study the features of a text editor carefully before you decide to buy it.

Screen Editor: The editor should be a screen editor. This means that the video display is used as a "window" onto the file, showing its current state. Thus, you are quickly given feedback about what your text looks like. You can then immediately see where something needs to be changed.

A screen-oriented editor usually uses some sort of cursor to indicate the active editing point. In general, the cursor must be moved to the text that is to be changed before any changes can be made. There are (usually) a number of commands that move the cursor to different points in the text. For example, one command will place the cursor at the end of a line, another will place it at the beginning of a paragraph, and so on depending on the capabilities of a given unit.

Backup Copy: A good editor allows you to edit a copy of the file and not the file itself, thus creating an implicit backup copy to which you can return if you accidentally destroy the file. Yet this backup copy will not clutter up precious space on your disks.

A good editor will let you read in a file and write it out to several other files, perhaps after making minor changes, without exiting the editor. This capability is much easier to provide (and thus more common) in editors that edit a copy of the file.

Large Files: A good editor will be able to handle very large files smoothly and elegantly. When the file that is being edited becomes too large to fit in memory, parts of it should be stored on disk until needed.

Ask your dealer for a demonstration

Chart your financial future with MicroFinesse™

In this fast-paced business world, the best way to stay competitive is to be able to see your financial alternatives clearly and make decisions fast.

That's why P-E Consulting Group Ltd. developed MicroFinesse, a complete package providing professional financial forecasting PLUS full high-resolution color graphics support, including pie charts, histograms and graphs, for the financial projections you create.

Now this evolutionary financial resource planning tool eliminates the time-consuming reprogramming required for financial model consolidation or expansion. MicroFinesse's menu-driven command format can also generate up to 15 user-defined reports per model, with visuals, without reprogramming.

Previously available only for mainframe applications, the MicroFinesse program can now be purchased at leading Dealers nation-wide. MicroFinesse is specifically designed for the 48K Apple II® with the Apple Language Card.

So when your variables are many and your time is limited, take a good look at the financial artistry of MicroFinesse.



MicroFinesse

Distributed by: OSBORNE/McGraw-Hill
630 Bancroft Way, Berkeley, CA 94710, (415) 548-2805



Apple II is a registered trademark of Apple Computer, Inc.

Circle 316 on inquiry card.

However—and this is most important—none of the internal "breaking into pieces" should be visible to the user. Specifically, you should not have to manually break your file up into pieces, nor should there be commands to "edit the next section of the file." You should always be able to edit any part of your file on demand and never be in a position where backing up before a certain point in the file is impossible.

Multiple Buffers and Windows: When using a typewriter, you can easily switch back and forth between tasks, or you can look at several documents at once. You don't want to give up these abilities when you move to a computer. Thus, an editor should have multiple buffers and multiple windows.

Multiple buffers store each document separately and allow you to switch back and forth between them at will. Any changes that have been made to any of the documents will still be there, intact, if you should switch away from a buffer and then back again.

An editor with multiple windows will "split" your video screen so that you can look at parts of two or more documents at the same time (or two parts of the same document). With this ability, you can make changes in one file based on what you are reading in another one.

Speed: The editor should be fast enough so that it doesn't slow you down. This means that it should scan the keyboard often enough to retain all the characters that have been typed and that there should be little or no delay between a command and its execution. Response time is most important on the frequently executed commands, such as those that move you around in the file or window, and less important on the infrequently used ones, such as those that read or write files.


If two commands are entered quickly, or a second one is entered while the editor is updating the screen after executing the first, it is more efficient if the screen update is aborted and the next command executed immediately. Thus, executing sixteen "next-screen" commands in quick succession will show the sixteenth screen of text only, not all fifteen in between. Note that on some operating system/hardware configurations, it is not possible to detect the second or later commands, so this feature is not always available.

Large Screen: The video-terminal screen should be as large as possible. A standard screen has 24 lines and 80 columns. An 80-column display is usually wide enough for text, but 24 lines represents only about a third of a sheet of paper. This small size can produce a feeling of "blindness" in users because their attention is focused on such a small part of the text. Unfortunately, 24 lines is by far the most common size. However, larger screens do exist: for example, the Ann Arbor Ambassador terminal will display up to 60 lines at once

Circle 453 on inquiry card.

Circle 256 on inquiry card. →

CASH FLOW PROBLEMS?



IT'S NICE TO KNOW SOMEONE WHO HAS THE SOLUTION.



MicroAge is your Solution Store . . . that means at MicroAge Computer Stores we have a wide selection of time-saving computerized business systems designed specifically to solve the daily cash flow problems every businessman faces.

MicroAge has computerized business systems that quickly and affordably allow you to regain control of your critical accounts receivable . . . at last making it possible for you to carry out effective collection procedures on a consistent basis. MicroAge has accounts receivable program packages to automatically display and update account information; prepare trial balance including a balance-due and delinquency aging report, and take care of dozens of other tasks that eat into your time and profit!

Computerized business systems from the MicroAge Computer Store are available in the $5,000 to $15,000 range, to suit the individual budget of your small business or professional practice. MicroAge backs up every system with personalized service, warranty service and repair, installation, systems consulting, even customer training. Visit the MicroAge Computer Store in your area soon with your business problems, and let us help you with the solution.

MicroAge.
COMPUTER STORE
"The Solution Store" SM

VISIT THE STORE IN YOUR AREA:

El Paso, Texas (915) 591-3349
Rockville, Maryland (301) 762-7585
Tucson, Arizona (602) 790-8959
Albuquerque, New Mexico (505) 883-0955
Pleasant Hill, California (415) 680-1489
Aurora, Colorado (303) 696-6950
Rochester, New York (716) 244-9000
Hurst, Texas (817) 284-3413
Salina, Kansas (913) 823-7596
Orland Park, Illinois (312) 349-8080
Milwaukee, Wisconsin (414) 257-1100
Mountain View, California (415) 964-7063
Scottsdale, Arizona (602) 941-8794
Anchorage, Alaska (907) 279-6688
San Diego, California (714) 278-0623
Richardson, Texas (214) 234-5955
Minneapolis, Minnesota (612) 338-1777
Omaha, Nebraska (402) 339-7441
Phoenix, Arizona (602) 265-0065
Columbus, Ohio (614) 868-1550
Indianapolis, Indiana (317) 849-5161
Portland, Oregon (503) 256-4713
Norwalk, Conneticut (203) 846-0851
St. Louis, Missouri (314) 567-7644
Oklahoma City, Oklahoma (405) 728-1837
Houston, Texas (713) 440-7547
W. Palm Beach, Florida (305) 683-5779
Toronto, Canada (416) 487-5551
Houston, Texas (713) 270-9647
Wilmington, Delaware (302) 368-3672
Allentown, Pennsylvania (215) 434-4301

FOR FRANCHISE OPPORTUNITY INFORMATION CALL (602) 968-3168

FMS-80. THE TWO DOOR DATA BASE PLUS



Door # 1: Reports you'll use *today.*
Door # 2: The sky is the limit.

We've split the proven, best-selling FMS-80 micro data base manager into two parts. And we've split the price.

Part one (FMS-81) gives you the essential file and reporting features. You can quickly create programs with input questions a clerk can understand, and with reports a manager can *use.*

And FMS-81 with its new manual, is so easy to use, you'll be generating reports the first day. FMS-81 sells for $495.

Part two (FMS-82) has all the fancy stuff. Including an Extended File Maintenance language that lets you perform virtually unlimited manipulation on up to 19 different data files simultaneously.

Using FMS-82, you or your computer dealer can make FMS-80 do *just about anything.* FMS-82 sells for $495.

Naturally, FMS-82 is fully compatible with all the files and functions you generate with FMS-81.


FMS-81 is so useful, it might seem like you'll never need FMS-82.

But as you expand your use of computers, isn't it nice to know it's there?

The FMS family runs under CP/M, MP/M, CDOS, and Turbodos. Call or write today for a brochure detailing the extensive capabilities of the Two Door Data Base Manager, and the name of your nearest dealer.

You'll be impressed.

Systems Plus, Inc.



1120 San Antonio Road
Palo Alto, CA 94303
(415) 969-7047

a djr product
DJR Associates, Inc.
2 Highland Lane
North Tarrytown,
NY 10591

FMS-80, FMS-81, FMS-82 TM DJR Associates
CP/M, MP/M TM Digital Research
CDOS TM Cromemco
Turbodos TM Software 2000, Inc.

Circle 400 on inquiry card.

(almost a full sheet of paper).

Due to the 24-line size of most screens, it is important that the editor devote as much of the screen as possible to displaying text and minimize the space devoted to unchanging status displays. A video terminal is very good at displaying things that change, and that capability should be used to advantage by a text editor.

Physical Keyboard Characteristics: The physical characteristics of a keyboard are important, too. First and foremost, the keyboard and screen should be in separate cases (commonly called a "detachable keyboard"). By separating the two, the keyboard can be adjusted to fit the user, instead of forcing the user to adapt to the keyboard. This capability is important if you are using the terminal eight hours a day.

A keyboard should have a comfortable, solid feel and should not miss or double type characters (i.e., if you type "forty," it should not send a "orty," "fforty," or "fgorty"). In addition, the Shift and Control keys should work smoothly with the rest of the keyboard so that you indeed get a "Forty" and not a "forty," "FOrty," or "fOrty." Finally, there should be no sharp edges or other nuisances to annoy you. The basic question is "Will I be comfortable typing my next ten *million* characters on this keyboard?" (Ten million characters is about a year's worth of typing and editing.)

Keyboard Setup: The editor should be set up for use by touch-typists. If you cannot touch-type, the specific arrangement will make little difference to you. If you can touch-type, you should look for an editor with a set of commands that will rarely require your fingers to leave the "home position" (the A,S,D,F,J,K,L, and semicolon keys).

Unfortunately for touch-typists, special-function keys (usually located above the number keys or to the right of the basic keyboard) are inefficient. It can take one or two seconds to move a hand off to one side and back again. This amount of time is unacceptably long for a touch-typist, who can easily type ten characters within that time.

Unfortunately for beginners, it takes somewhat longer to learn to use an editor that has all of its commands on the "basic keyboard" than it takes to learn an editor with rows of keys, each carefully labeled with its use. On the other hand, after three weeks, the typist will be able to use the basic-keyboard editor much more quickly than the special-key editor, and the extra learning time will be paid back many times over. (Just think how much longer those ten million characters would take to type if you had to move your hands around to type them.)

Mnemonic Commands: Regarding basic-keyboard editors, there are two schools of thought. One school holds that commands should be mnemonically bound (e.g., ForwardCharacter is on F, BackwardCharacter is on B, NextLine is on N, and PreviousLine is on P). The other school holds that commands should be positionally bound (e.g., ForwardCharacter on D, BackwardCharacter on S, NextLine on X, and PreviousLine on E—a glance at the keyboard will verify that these are indeed arranged in some sort of order).

The arguments for and against these systems are similar to the arguments about function keys. The positionally arranged commands are quicker to learn for a nontypist. However, the mnemonically arranged commands are easier to learn for a typist (who never looks at the keyboard and must stop and think for a while to realize that the E key is, indeed, above the S and D keys). In addition, the mnemonically arranged commands tend to be more evenly spaced around the keyboard. Thus, they are typed with both hands and can be typed quickly.

Commands Should Match What Is Being Edited: The commands given to the editor should match the material being edited. Everything that is edited has characters, lines, and regions (arbitrary blocks of text) as elements. A text file (or document) also has words, sentences, and paragraphs. A computer program (say, in Pascal) has tokens, statements, statement groups, and procedures. There should be commands to move over

and to delete any of these units.

Insert vs. Overwrite: Whether to insert or to overwrite characters is yet another controversy. To enter text, a typed character could overwrite (replace) an existing character. This is useful if you are editing a table of numbers. Another option would be to insert the character between the two surrounding characters. (Think about proofreaders' marks. There are marks to delete and marks to insert, but no marks to overwrite text.)

Consider the basic editing operation of replacing one word with another completely different one. The easiest way to do it is to delete the old word and type the new one (inserting it, of course). The overwrite way is to type the new word. If the new one is shorter, the rest of the old one must be deleted. If the new one is longer, this situation must be noticed in the middle of typing it, and you must enter some sort of "insert mode" in order to finish the word. This is most inconvenient for touch-typists, who think of words as indivisible objects.

The ideal editor has available both ways of entering text and allows you to select between them. However, it should be tailored for inserting new text, as that is more useful for the bulk of editing.

Control Characters: A good text editor should use control characters for commands. By using them as commands, the "ordinary" characters are kept free for what they are most useful: text.

Recovery from Deletions: Assume that you have learned the editor well and are typing away, giving it move and delete commands and merrily inserting text. Suddenly, you realize—too late—that you didn't really want to delete that sentence. What do you do?

A good editor will have some sort of "undelete" operation to bring back the last object or objects that were deleted, thus saving you from having to remember and reenter the deleted text.

State Save: Although you'll probably spend most of your time in the editor, you occasionally must leave it and do something else. However, if you are using multiple buffers to advantage, it can take quite a while to write each buffer to disk and then read them all back in again. Thus, an editor should have either the ability to save what it knows and so pick up quickly where it left off (called *state save*) or the ability to temporarily escape to the operating system and allow you to do some work. The crucial point is that you can resume editing without having to manually reconstruct where you left off.

Modifiability: Even if an editor has all of these features and seems right in every way, there are probably ways to change it to make using it just a little bit easier. You should be able to make modifications in two areas.

First, you should be able to tailor the editor's default values for controlling parameters such as the right margin. By having the editor match your tastes immediately, you will save quite a bit of time and annoyance by not having to reenter



No more waiting!
No more lost time, reduced efficiency, wasted dollars. . . waiting for your printer to complete a task before you can use your micro. That's part of MicroFazer's beauty. But just one part.

All the proper credentials. Our universal parallel in/parallel out data buffer works with all popular microcomputers and parallel printers and plugs in directly to the printer's input port. MicroFazer uses standard 64K RAM chips, standard Centronics signals, and draws power directly from the printer (separate 9 volt, 300 mA power supply available where required). All this in a compact package 3.5 inches by 7 inches by 1 inch. Simple. And simply beautiful.

Now! With MicroFazer you can compute while you print.

At a price that won't faze you. Retail pricing for 8K model ($159); 16K ($189); 32K ($225); and 64K ($299).

What we promise, we deliver. MicroFazer isn't somebody's idea of what an inexpensive printer buffer *should* be. It's available right now for delivery. Don't wait any longer. Let MicroFazer keep things moving.



For further information and the name of your nearest dealer, call (404) 923-6666 or fill in this coupon and mail to: Quadram Corporation, 4357 Park Drive, Norcross, Georgia 30093.

Name ______________________________

Company ____________________ Title __________

Address ______________________________

City ____________________ State ________ Zip ________

Circle 343 on inquiry card.

your preferred values each time you use the editor (this point is slightly less important if the editor has state save).

Second, the people who created the editor have their own ideas about how they think an editor should work. You might not like some of them. Thus, you should be able to change the editor in a basic way. (Perhaps you'd like the StringSearch command to leave you at the end of the file if it can't find the string, instead of leaving you where you were when you gave the command.) To make this sort of change, you need access to at least a portion of the source code. This code must be well written so as to be easy to change, and there must be thorough documentation so that whoever is actually making the changes can make them with a minimum of fuss.

Final Note

The list of features presented here is not the product of any one person's thinking. It was created item by item over a period of several years through the interaction of a large community of users, all of whom had their own ideas about what an editor should be like.

These users were largely at the Massachusetts Institute of Technology, and the editor that is the result of their ideas is called EMACS. Several versions of this editor exist: the original EMACS on DEC PDP-10 and DEC-20 computers, Multics EMACS on Honeywell Multics systems, ZWEI on LISP machines, and MINCE on CP/M systems.■

References

1. Finseth, Craig A. "Theory and Practice of Text Editors." MIT Laboratory for Computer Science Technical Memo 165. Cambridge, MA, June 1980.
2. Greenberg, Bernard S. "Multics EMACS: An Experiment in Computer Interaction." Proceedings, Fourth Annual Honeywell Software Conference, March 1980.
3. Mark of the Unicorn. *MINCE User's Guide*. Arlington, MA, October 1980.
4. Stallman, Richard M. "EMACS: The Extensible, Customizable, Self-Documenting, Display Editor." MIT Artificial Intelligence Laboratory, A.I. Memo #519. Cambridge, MA, June 1979.

Express yourself past check-in lines on TWA.





With TWA's Round-Trip Check-In and Advance Seat Selection you can express yourself past check-in lines.







Express yourself straight to the gate and...

express yourself straight to your seat.

It's easy with TWA's Airport Express.

Nothing gets you past check-in lines and through the airport faster than TWA's Airport Express.® And that's because with TWA's Round-Trip Check-In,® Connection Check-In℠ and Advance Seat Selection you can get boarding passes and seat assignments for your outbound, connecting and return flights before you depart.

So on your trip home you can go straight to your seat on the plane. Instead of straight to the back of a check-in line.

Next trip, ask for TWA's Airport Express. And express yourself past check-in lines. Call your travel agent, corporate travel department or TWA.

Express yourself with the American Express® Card.

Traveling is easy when you carry the American Express Card. Use it to charge your TWA tickets, car rentals, hotels, meals, theatre, shopping, almost



anything you need while traveling.

If you are not already a Cardmember, call toll-free 800-528-8000 for an application.

The American Express Card. Don't leave home without it.®

You're going to like us



Two Word Processors for North Star

Edgar F. Coudal
Coudal and Associates
627 South Crescent Ave.
Park Ridge, IL 60068

Two new word processors for the North Star DOS (disk operating system) offer broad capabilities that rival the leader among CP/M word processors, Wordstar. Each sells for just under $500 and provides high-performance word processing, text editing, and print formatting, although they take vastly different approaches to these tasks.

In brief, the Benchmark word processor, from Metasoft, was seemingly designed for someone who needs retraining after every coffee break. There is a starting command menu, which branches at the touch of a key to six different subsystems (create, revise, view, print, merge, and disk procedures), and each subsystem has *its* own detailed menu. The user can enter a ? almost anywhere along the way and get two screens of concise command information.

The other word processor, Lettergo, from Datek Systems Inc., provides one menu for disk operations and a 10-command print-formatting line at the top of the working screen. The remaining user information is contained in the manual, not the program.

Both programs give a general-purpose computer (the North Star Horizon or another S-100 system) the power of a *dedicated* word processor costing $7500 to $15,000. (A dedicated system is one that performs one job well, but can't do anything else.) Of course, Benchmark or Lettergo programs cannot be used simultaneously with other software (business, scientific, or recreational applications), but they can be used sequentially.

Upon order from the publisher or distributor, both Benchmark and Lettergo can be configured for various manufacturers' hardware or reconfigured to accom-

At a Glance

Software
Benchmark

Type
Word processor

Manufacturer
Metasoft Corporation
711 E. Cottonwood, Suite E
Casa Grande, AZ 85222

Price
$499.95

Format
North Star DOS 5¼-inch double density and quad density; North Star CP/M; CP/M 2.2 8-inch single density; Zenith Z-89; NEC PC-8000; Vector; Superbrain

Language Used
Assembler

Documentation
108-page loose-leaf manual

Audience
Secretarial, especially for offices with large volumes of routine and repetitive material, such as law offices

At a Glance

Software
Lettergo

Type
Word processor

Manufacturer
Datek Systems Inc.
4786 Lee Highway
Arlington, VA 22207

Price
$495

Format
North Star DOS 5¼-inch double density and quad density (CP/M 5¼-inch and 8-inch coming)

Language Used
Assembler

Documentation
84-page loose-leaf manual, 26 pages devoted to beginner tutorial, the rest to the reference manual; appended 11-page manual (same format) for MailMerj mailing-list program

Audience
Secretarial and general word-processing

Circle 184 on inquiry card. →


Who in the world is Joe Larson?

Joe is president of a computer software business. He has been, and still is, in the retail computer hardware business. It was here he recognized the need for more comprehensive software. Joe and his experienced staff developed a software system that is easy to use and understand. Software designed especially for small business accounting and management. Software that won't accept information that isn't logical. Software that takes advantage of the new, more powerful computers. Great Plains Software offers critical, indepth management information including profit by product, profit by salesperson, profit by customer and much more.

What makes Joe Larson's Great Plains Software so different? The Great Plains Software system was created on a hardisk from the ground up for today's multiple uses and tomorrows business expansion. Some special features include a complete data base of every journal entry posted during the fiscal year. The ability to reverse or adjust entries in any general ledger account at any time during fiscal year...a CRT display of accounts payable and receivable...the ability to display any customer or vendor records at a moments notice. The built-in password security system keeps company financial information completely confidential.


Get the most out of your computer investment. Ask your local computer store about the advantages of Great Plains Accounting Software or call (701) 293-8483.

Great Plains Software anticipates the future creating software for today *and tomorrow.*



MDBS: Superior Data Base Management for Application Developers

Mainframe solutions at micro prices.



MDBS solves the problem of expensive, time-consuming application development and maintenance.

Here's what makes the MDBS Data Base Management System so unique:

ECONOMY—Our state-of-the-art system cuts application development costs by up to 80%.

HARDWARE COMPATIBILITY—From 8080, Z80...to the PDP-11, MDBS delivers uniformly excellent results.

PORTABILITY—MDBS operates under most popular operating systems and languages, including CP/M, UNIX, IBM PCDOS, COBOL, BASIC, PASCAL, C, PL/1, FORTRAN, and many more.

INTEGRITY—RECOVERY, RESTART, and ROLLBACK techniques are available. Data base integrity is assured through advanced data structuring techniques.

AUTHENTICITY—MDBS is the first and only true and complete DBMS currently available on microcomputers.

CAPABILITY—Our system includes features you won't find anywhere else, at any price.

- Fully-integrated, dictionary-driven.
- Unparalleled data structuring ability—far superior to hierarchical, CODASYL, and relational approaches.
- Powerful, English-like query system entirely non-navigational. Fully supports spur-of-the-moment "what if" inquiries.
- Query nesting allowed. Automatic sorting of output tables.
- Built-in data security down to the field level plus advanced encryption capability.
- Performance tuning, including the ability to influence physical storage structures.
- Multi-users capabilities including active and passive lockout.

MDBS is not restricted to the limitations of data base "pretenders" like file management systems.

To help make application development more effective and efficient, MDBS also offers extensive consulting services and professional training seminars.

MDBS and other fine products are distributed in most countries through ISE.

For more information please contact:

ISE-USA
P.O. Box 248
Lafayette, Indiana 47902
Tel: (317) 463-2581

ISE-ADV/ORGA GERMANY
Lipowskystr. 26
8000 Munich 70
Tel: (089) 776 023-4

ISE-PACTEL
Rochester House
33 Greycoat Street
London SW1P 2QF
Tel: 01-828 7744

ISE-CEGOS
Tour Chenonceaux
204, Rond-Point du Pont de Sèvres
92516 Boulogne Billancourt Cedex
Tel: 620-61-04

ISE-ADV/ORGA SWITZERLAND
Mainaustraβe 17
CH-8008 Zürich
Tel: (01) 32 02 70-1

Elsewhere:
ISE-INTERNATIONAL
P.O. Box 248
Lafayette, Indiana 47902
Tel: (317) 463-2581

Professionals know the difference.

Note: For more about ISE see page 127

☐ Please call me immediately at ( ) ________
(phone no.)
☐ Please tell me about your half-day seminar
☐ Please tell me about your three-day workshop
☐ I'm enclosing $95 in payment for the MBDS manual ($125 overseas; Indiana residents please add $3.40 sales tax)
☐ Please charge to my VISA ________ or MasterCard ________

Card Number ________ Phone No. ________
Signature ________ Expiration Date ________
Name ________ Title ________
Company ________
Address ________
City ________ State ________ Zip ________
Phone ________
(area code) (ext.)

MAIL TO: ISE P.O. Box 248 Lafayette, IN 47902

Editing:	Benchmark	Lettergo
Cursor movement		
bottom of document	Y	Y
next block or paragraph	N	N
next screen	Y[1]	N[1]
next sentence	Y	N
next word	Y	N
top of document	Y	Y
up, down, right, left	Y	Y
Copy block	Y	Y
Copy from another file	Y	Y
Delete		
block	Y	Y
character	Y	Y[2,3]
Find text	Y	Y
Find and replace (once)	Y	Y
Find and replace (all occurrences)	Y	Y
'Help' screen or aid	Y	N
Insert		
block	Y	Y
character	Y	Y
Move block	Y	Y
Video display		
change margins	Y	Y
change tabs	Y	Y
Printing:		
Justification		
left justified	Y	Y
left ragged	N	N
right justified	Y	Y
right ragged	Y	Y
Line spacing		
set to single or double	Y	Y
set to triple or more	Y	Y
Page layout		
go to new page	Y	Y[4]
set bottom margin	Y	Y
set indentation	Y	Y
set right and left margins	Y	Y
set top margin	Y	Y
maximum characters per line	155	78
Page numbering		
basic	Y	Y
varying position or format	Y	Y[5]
Printer control		
allows pause for positioning form	Y	Y
print draft copy	Y	?
feed single sheets	Y	Y
bidirectional printing	Y	Y
Text variations		
bold face	Y[6]	Y
centering	Y	Y
columnar output	Y	Y
footers	Y	Y
headers	Y	Y
subscripts	Y	Y
superscripts	Y	Y
underlining	Y	Y
All features changeable in middle of document	Y	Y
Miscellaneous Features:		
Attach phrases of 2000 words to a single key	Y	N

Notes:
1. Next page
2. Delete to end of line
3. Delete entire line
4. Force end of page
5. Eight positions, including alternate sides
6. "Shadow" print, darker than bold

Table 1: *Comparison of the features of Benchmark and Lettergo. "Y" stands for Yes and "N" for No.*

modate user changes in hardware. Review copies of each system came ready to run on my double-density North Star and were configured to accommodate my Soroc 120 terminal and Diablo 1610 printer. All I had to do was boot, load, and edit. The Lettergo system is designed to work on a variety of different terminals, printers, and Z80-based computers. The manual has detailed instructions for such printers as the NEC 5500, Diablo 1610/1620, and Anadex 9500/01, and for such terminals as the TVI-900, ACT-V, and Hazeltine 1500. Datek configures the software for a particular user's hardware. The Benchmark system arrives as a "configurator disk," which produces a data disk and a program disk. The configuration disk allows the user to configure Benchmark for various hardware, including Diablo, NEC, TI, Centronics, and Qume printers, and Soroc, Hazeltine, Heath, Televideo, Adds Regent, IMS WP, and Tandy II terminals.

After seeing these two systems in action and using them almost interchangeably for a couple of months, I have the same complaints about both, but they are complaints that extend to many other word processors as well. First, neither shows right-hand justification on the screen, leaving it up to you to imagine what the printed text will look like. Second, neither will spool-print, which means that printing a long manuscript with my relatively slow Diablo can occupy the computer for a long time.

One other complaint is the excess of riches. With either system, you can direct the printer to overstrike, boldface, and underline *simultaneously*. This may be useful for someone drafting legislation or revising a contract, but it seems like overkill; the added complexity gets in the way.

Although both Benchmark and Lettergo were designed with the same mass market in mind—the high-production office secretary—each reflects its origins. Benchmark (according to distributor R & B Computers, of Tempe, Arizona) originated in a lawyer's office, and certain functions, capabilities, and examples in the manual reflect that background. Lettergo, on the other hand, was written by Gregory Heise, owner of a computer shop and a high-class hacker of long standing. Heise had watched many novices struggle with unnecessary complication and poor documentation and, as a result, tried to simplify Lettergo as much as possible.

Both word processors do everything that leading word processors should do: automatic line wraparound on input, block moves, global search and replace, right-margin justification, automatic pagination, automatic headings and footings, underscoring, subscripting and superscripting, and so on (see table 1).

Both can generate personalized form letters with their merge capabilities. Benchmark uses either an internal pattern/letter, keying in the necessary changes from the terminal, or a letter and mail list generated by a separate software package, Mail List, which is a list manager with print capability (suggested retail, $399). Lettergo uses a BASIC language MailMerj program, which is included on the word-processing disk, to produce form letters.

Word-processing packages have evolved to the point where certain specific features—many of them mentioned above—should be taken for granted. When considering a new package, the prospective user should ask, "What can it do that's really useful that the others can't?" and "How easy is it to learn, use, and adapt?"

Benchmark

Designed for use by someone "who doesn't know a byte from a bite," Benchmark merits praise for the time and effort that went into its menus and safeguards. One of the processor's features is that it does not use control characters, except on the least capable of terminals. To instruct the processor to do something, the user enters the command mode and hits a single key: F for Finish, I for Insert, J for Jump to a page, D for Delete, and so on. When you use a command that can make irretrievable changes, such as killing a document or quitting at the wrong place, Benchmark asks if you really mean it. And if you do, you must hit the Rub or Execute key.

Benchmark's Hallmarks

Now, for the especially nice things about Benchmark. It automatically maintains a remarkably detailed directory of what is on the data disks, including titles of up to 30 characters, initials of the author of each document and the operator of the system at the time the document was produced, time and date of last revision, number of K



WHY BUY FROM THE BEST?

Service... Support... Software...

NEECO



commodore

16K 8 (16K RAM-40 Column) - Lim. Qty	$ 995
32K 8 (32K RAM-40 Clm.) - Lim. Qty	$1295
4016 (16K RAM 4.0 Basic-40 Clm.)	$ 995
4032 (32K RAM 4.0 Basic-40 Clm.)	$1295
8032 (32K RAM 4.0 Basic-80 Clm.)	$1495
8050 Dual Disk (1 Meg Storage)	$1795
4040 Dual Disk (343K Storage)	$1295
8010 IEEE Modem	$ 280
C2N Cassette Drive	$ 95
CBM - IEEE Interface Cable	$ 40
IEEE - IEEE Interface Cable	$ 50
VIC 20 Home/Personal Computer	$ 295

CALL NEECO FOR ANY OF YOUR COMMODORE COMPUTER NEEDS

NEC SPINWRITER PRINTERS

5530 (Parallel)	$3055
5510 (Serial)	$3055
5520 (KSR-Serial)	$3415
Tractor Option	$ 225

EPSON PRINTERS

MX-80 PRINTER	$ 645
MX-80 FT	$ 745
MX-100	$ 945
MX-70	$ 459
INTERFACE CARDS	
8141 (RS-232)	$ 75
8150 (2K Buffered RS-232)	$ 150
8161 (IEEE 488)	$ 55
8131 (Apple Card)	$ 85
8230 (Apple Card)	$ 25
8220 (TRS-80 Cable)	$ 35

DIABLO 630 PRINTER

DIABLO 630 - Serial - RS-232	$2710
Tractor Option	$ 250



APPLE

16K APPLE II+	$1330
32K APPLE II+	$1430
48K APPLE II+	$1530
APPLE DISK w/3.3 DOS	$ 650
APPLE DRIVE Only	$ 490
APPLE III 128K - In Stock! w/Monitor + Info Analystpak	$4740

AMDEK MONITORS

Video 100 12" B+W	$ 179
Video 300 12" Green	$ 249
Color I 13" Low Res	$ 449
Color II 13" High Res	$ 999

INTERTEC COMPUTERS

64K Superbrain (360 Disk Storage), CP/M™	$3495
64K QD Superbrain (700K Disk Storage), CP/M™	$3995

*CP/M is a registered trademark of Digital Research.



ATARI COMPUTERS

Atari 400 (16K RAM)	$ 399
Atari 800 (32K RAM) - good thru 8/31	$1080
Atari 410 RECORDER	$ 89.95
Atari 810 DISK DRIVE	$ 599.95

NEECO carries all available ATARI Software and Peripherals.

PROFESSIONAL SOFTWARE

WordPro 1 8K	$ 29.95
Word Pro 3 (40 Clm.)16K	$ 199.95
Word Pro 3+	$ 295
Word Pro 4 (80 Clm.) 32K	$ 375
Word Pro 4+	$ 450

JUST A SAMPLE OF THE MANY PRODUCTS WE CARRY, CALL US FOR OUR NEW 60-PAGE CATALOG.
WE WILL MATCH SOME ADVERTISED PRICES ON CERTAIN PRODUCTS LISTED UNDER SIMILAR "IN STOCK" CONDITIONS.



NEECO

679 HIGHLAND AVE.
NEEDHAM, MA 02194

(617) 449-1760
Telex: 951021

MON-FRI 9:00 - 5:00





MasterCharge and VISA Accepted

Circle 295 on inquiry card.

bytes of disk space used by each document, a running total of the amount of disk space used, and a warning when a disk is getting full. All together, this can be a super filing system. And once the user knows the system, he or she can bypass all the menus and prompts. (The literature claims that the entire system can be learned in one day, but real facility takes longer.)

Printed line length of up to 155 characters is supported, which is useful for spread sheets and other financial documents.

Cursor control includes nine movements: left, right, up, down, home, next word, first character next line, first line any page, and next screen of text.

Finally, the best for last: a simple set of commands allows the user to attach up to 52 separate "phrases" to single-letter keys. Each phrase can be up to *2000 characters long*, and it can be called and inserted at the cursor position with the preset key. This is an excellent feature for repetitive jobs involving such projects as legal documents and form letters. It's hard to understand why Metasoft doesn't place more emphasis on this feature.

On the less positive side, Benchmark operates with a program disk and a data disk, using two drives. (Files *can* be saved to the program disk, but there isn't much room there.) The program is disk buffered, text is read into RAM (random-access read/write memory), then sent to the printer. With my North Star system, which has 56K bytes of memory, the drives are constantly active on long documents and that slows the printing process. Metasoft comments that "64K is nice" for long documents.

Another drawback is that simply having all those menus tends to make the user reliant on them, and as a result slows use of the program. This is probably not a legitimate complaint for an office situation where a secretary is running hard for four or five hours a day and uses the facilities and capabilities until they become second nature, but it can be a problem for those who spend most of their time creating text and very little time formatting and printing.

Finally, as noted earlier, Benchmark provides no spool printing or on-screen right justification.

Lettergo

If Benchmark is the high-performance secretary's ultimate weapon, then Lettergo is for users who rely on a word processor, but not necessarily for high volumes of routine work. Lettergo has one menu, disk-operation commands—and that's it. The menu is so spartan (Save, Load, Directory, Kill, Quit, Merge, and Free) that Heise used part of it for the copyright.

The Control key gets a workout on the Lettergo system because Lettergo uses control characters for editing functions (Control B returns the cursor to the beginning of the document, Control E scrolls toward the end, Control X reverses scrolls, Control P starts output to the printer from the cursor location, and so on, through all the letters of the alphabet). Even after using Lettergo extensively, I'd hate to take a test on the functions of all the keys. About 99 percent of the work can be performed with fewer than half of the control keys, so the demands on human memory are not as great as they seem.

Lettergo's Goodies

For all its versatility, Lettergo is remarkably easy to learn and operate. While Heise's excellent manual does not make any untoward claims about ease of learning, my wife, when faced with the sudden realization that a truly massive work she'd undertaken would require at least one full rewrite and a final retype, learned to use Lettergo (with *no previous computer experience*) in one long afternoon.

Although simple and chatty, the manual doesn't talk down to the user. It presumes virtually no previous computer knowledge and is a basic, step-by-step tutorial, followed by a complete reference manual that expands on the first section, and concluding with a section on how to set up the various types of hardware that can be used with Lettergo.

Lettergo drives the printer from system memory, rather than off the disk, which means that print speed is limited only by the speed of the printer. And the system makes it easy to format for printing by providing a format line across the top of each text screen. The line contains 10 single letters followed by two numbers each, so that a maximum of 30 characters provides full control over what the printer will produce. The formatting commands include L for line length, P for lines to a page, and

Esprit.™

When you compare value in low-cost terminals, there's no comparison.

Feature	Hazeltine Esprit™	ADDS Viewpoint	Televideo TVI-910
Screen			
Matrix	**7 x 11**	5 x 8	8 x 10
Display set	**128**	96	96
Keyboard			
Numeric pad	**14 keys**	11 keys	14 keys
Function keys	**14**	3	10
Display color	**Green**	White	Green
Operation			
Horizontal tabs	**Yes**	No	Yes
Insert/Delete	**Yes**	No	No
Page mode	**Yes**	No	No
Transmit field	**Yes**	No	No
Buffered	**Yes**	No	No
Warranty	*	90 days	90 days

Hazeltine Esprit, ADDS Viewpoint and the Televideo TVI-910 are all competitively priced at the low end of the market. Esprit is at the high end in value.

*Hazeltine, in cooperation with Western Union, offers two warranty options, effective on Esprit terminals purchased after February 1, 1982, for service rendered through December 31, 1982:

1. Return to factory for repair at no cost for materials and labor.
2. On-site service contract through 1982 in any Western Union Zone 1 area for a one-time charge of only $49.95 per terminal.



For more information call your local distributor, or

Hazeltine Corporation
Computer Terminal Equipment
Greenlawn, NY 11740
National Sales: (516) 549-8800
Telex: 96-1435

For additional sales office locations, please call our toll-free number: (800) 645-5300.



by Hazeltine

An editing terminal at a conversational price.

Circle 462 on inquiry card.

S for line spacing—an arrangement that is quick and easy to use. Any of the formatting commands can be changed at any time or any place in the document, through the use of *dot commands*—a period at the left margin, followed by the letter indicating which formatting command is to be changed. For instance, .L78-58 will shorten the line length of text following the command by 20 characters, while .L58-78 will return the text to the original length. This is not a unique system, but many word processors do not show the changes on the screen, as Lettergo does.

If a revised file is longer than the space allotted for the original version of the file, Lettergo will save the new version further along on the disk and kill the original, without telling the user. When disk capacity is reached, the program will automatically compact the disk (rewrite all the disk files in a contiguous manner), thus eliminating all those holes along the way. The user can control this housekeeping if he or she wants, though Heise did not include the command in the disk-operations menu. (Nor did he include the information that you can direct output to devices other than the video display or printer, though that capability is provided in a single control character from the disk menu. This capability is handy if you have a homebrew spooler sitting around in high memory, disguised as another device.)

Among the disadvantages of Lettergo are that two operations are necessary to move a block of type: one to move it to the new location, the second to kill the block at the old location. A command that automatically deletes at the old location while moving to the new location would be more useful. Heise describes the two-step operation as a safeguard.

Another drawback is that maximum output line length is 78 characters. If you are printing at a pitch of 12 characters per inch, that is a bit restricting. Most financial documents are too wide for Lettergo.

Finally, as noted earlier, Lettergo has no spooling capability and no on-screen right-hand justification.

Conclusions

These two systems provide truly flexible, powerful, and complete screen-oriented word processing, something that was previously unavailable to the North Star DOS user. The prices are not excessive (each costs $500), considering the word-processing power that these software packages provide, and each system has advantages for different users. Benchmark is beautifully suited to the office environment, while Lettergo can serve in the office provided there is no need for wide margins. It is even more useful in such word-processing applications as freelance writing.

Neither demands much computer knowledge beyond knowing how to turn on the machine, and both have been thoroughly tested in working environments: Benchmark in legal applications and Lettergo in government offices. Field proof is important in a time when some high-priced software does not deliver anywhere near what is promised. Both of these systems do. ■

Electronics Div. Card #1

RUSH THIS POSTAGE-PAID CARD FOR YOUR FREE CATALOG

NO SALESMAN WILL CALL

NEW!

- Computer electronics with new TRS-80 Model III state-of-the-art computer
- TV/Audio/Video servicing with choice of computerized color TV, RCA videocassette recorder, or stereo system
- Complete communications electronics with microprocessor-based 2-meter transceiver
- Electronic Design Technology with design lab program for creative circuit and equipment design



Name (Please Print) Age

Street

City State Zip

Accredited by the Accrediting Commission of the National Home Study Council


170-042

AA

CHECK ONE:

- ☐ Microcomputers and Microprocessors
- ☐ Color TV, Audio, and Video System Servicing
- ☐ Digital Electronics
- ☐ Electronics Design Technology
- ☐ Communications Electronics • FCC Licenses • Mobile • Aircraft • Marine
- ☐ Basic Electronics
- ☐ Small Engine Servicing
- ☐ Appliance Servicing
- ☐ Automotive Servicing
- ☐ Auto Air Conditioning
- ☐ Air Conditioning, Heating, Refrigeration, & Solar Technology
- ☐ Building Construction

All career courses approved under GI Bill. ☐ Check for facts.



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 10008 WASHINGTON, D.C.

POSTAGE WILL BE PAID BY ADDRESSEE

NRI Schools
McGraw Hill Continuing
Education Center
3939 Wisconsin Avenue
Washington, D.C. 20016

Now NRI takes you inside the new TRS-80 Model III microcomputer to train you at home as the new breed of computer specialist!

NRI teams up with Radio Shack advanced technology to teach you how to use, program and service state-of-the-art microcomputers...

It's no longer enough to be just a programmer or a technician. With microcomputers moving into the fabric of our lives (over 250,000 of the TRS-80™ alone have been sold), interdisciplinary skills are demanded. And NRI can prepare you with the first course of its kind, covering the complete world of the microcomputer.

Learn At Home in Your Spare Time

With NRI training, the programmer gains practical knowledge of hardware, enabling him to design simpler, more effective programs. And, with advanced programming skills, the technician can test and debug systems quickly and easily.

Only NRI gives you both kinds of training with the convenience of home study. No classroom pressures, no night school, no gasoline wasted. You learn at your convenience, at your own pace. Yet you're always backed by the NRI staff and your instructor, answering questions, giving you guidance, and available for special help if you need it.

You Get Your Own Computer to Learn On and Keep

NRI training is hands-on training, with practical experiments and demonstrations as the very foundation of your knowledge. You don't just program your computer, you go inside it...watch how circuits interact...interface with other systems...gain a real insight into its nature.

You also work with an advanced liquid crystal display hand-held multimeter and the NRI Discovery Lab, performing over 60 separate experiments. You learn troubleshooting procedures and gain greater understanding of the information. Both microcomputer and equipment come as part of your training for you to use and keep.



Training includes new TRS-80 Model III microcomputer, 6-function LCD Beckman multimeter, and the NRI Discovery Lab with hundreds of tests and experiments.

(TRS-80 is a trademark of the Radio Shack division of Tandy Corp.)

Send for Free Catalog... No Salesman Will Call

Get all the details on this exciting course in NRI's free, 100-page catalog. It shows all equipment, lesson outlines, and facts on other electronics courses such as Complete Communications with CB, TV/Audio and Video, Digital Electronics, and more. Send today, no salesman will ever bother you. Keep up with the latest technology as you learn on the latest model of the world's most popular computer. If card has been used, write to:



NRI Schools
McGraw-Hill Continuing Education Center
3939 Wisconsin Avenue
Washington, D.C. 20016.

We'll train you for the good jobs!

A Disk Operating System for FORTH

An in-depth look at how a DOS operates

Peter Reece
152 Hillcrest Ave.
Dundas, Ontario
Canada L9H 4Y2

A disk operating system (DOS) is the heart of any computer system. Without a powerful and easy-to-use DOS, creating and maintaining programs and data on the system can be cumbersome if not impossible. This is because the DOS offers utilities of various types which manipulate files and, in general, perform all of the "housekeeping" chores essential to the system's smooth operation. In addition, most DOSes attempt to be user-friendly. That is, they are designed to make operation of the computer as simple and foolproof as possible.

This article describes the creation of a DOS for the FORTH language. FORTH is powerful, but it lacks a DOS in the usual sense. That is, it does not come with utilities to handle the normal operating-system constructs common in computer systems. For example, no options are available to have named files, to query disk space, to run named programs, and so on.

The DOS described here, appropriately called FORTHDOS, allows creating and deleting named files, maintaining directories of named files, listing statistics on disk usage, generating files by type (sequential, random, or block), listing files, allocating disk space, adding named utilities, getting help with commands, write-protecting any disk or file area, file copying, giving error messages, and many other features. FORTHDOS is a powerful, efficient, and easy-to-use DOS for single-user FORTH systems.

A complete listing of FORTHDOS is given in listing 1. Before discussing this listing, however, let's look at some of the rationale involved in producing this or, for that matter, *any* DOS.

FORTHDOS is a powerful, efficient, and easy-to-use DOS for single-user FORTH systems.

Features of DOS Packages

All DOSes contain commands for file manipulation. These commands usually invoke primitive operations or "primitives" responsible for: sequential and random-access file control, commands for creation and deletion of files, file space allocation algorithms, and similar types of file access controls.

Another class of DOS commands contains commands descriptive in nature and used mainly to display information. Examples of this class are those which list a directory of system or user files, show the system status, generate file listings, or alter the write- or security-protection status of files.

A third class of DOS commands concerns program control. These commands are exemplified by compiler calls (the compiler calls the DOS to determine how and where to place compiled files) and by commands allowing you to add primitives to your own software or even to add your own pseudo-DOS commands. An example of the latter is in the CP/M disk-operating system, which allows you to create custom commands via the use of .COM files.

A final class of DOS functions consists of utilities. While not strictly part of the DOS structure itself, utilities are often available as part of a DOS package. For example, a file copy utility such as PIP in CP/M or COPY in TRSDOS may be considered as a separate class of DOS commands.

Table 1 lists by command class FORTHDOS features usually found in typical DOS packages. Note that all of the common commands, ranging from creating a file to allocating disk storage space for random access, are available in FORTHDOS. As this article will discuss, all of these commands depend ultimately on a very simple structure—the *bit map* and the primitives that manipulate it.

Circle 438 on inquiry card. →

$1295 for a 40 CPS Word Processing Printer?



C. ITOH F-10 Printmaster
40 CPS Daisy Wheel Printer

IS THIS THE C. ITOH STARWRITER III?

The **C. ITOH F-10** Printer is manufactured by Tokyo Electric Co., Ltd., **(TEC)**, the same company that made the 25 CPS Starwriter I, and the 45 CPS Starwriter II, and you may even see other people calling it the Starwriter III, **TEC 40 CPS**, or just simply **C. ITOH** 40 CPS Printer. By any name this may be the best word processing printer value on the market today. When you compare the standard features with any printer on the market today, we think you will agree.

INDUSTRY STANDARD FEATURES

Plug compatible with **Diablo, Qume,** and **NEC** Printers. Uses standard 96 character plastic print wheels, and the new dual-plastic print wheels that, unlike metal wheels, provide superior print quality over the entire print life of the wheel. Software control characters that are standard for all major word processing packages.

CONSTRUCTION

Built on a cast aluminum base with high quality metal parts, the unit stands just 6″ high, yet will feed paper from the bottom as well as the rear. The solid construction makes the unit low noise and ideal for office or home.

INTERFACE

RS 232-C interface with XON/OFF and ETX/ACK protocols. Baud rate selectable to 1200 Baud.

APPLICATIONS

Compatible for use with **Apple, Radio Shack, IBM, NEC, Xerox, Vector Graphics, North Star, Altos, etc.**

OPTIONS

Bi-directional tractor feed, printer stand.

SPECIFICATIONS

Print Speed	40 CPS
Character Spacing	1/120″ (minimum)
Line Spacing	1/48″ (minimum)
Paper Width	16″ (maximum)
Print Wheel	Industry standard 96 character wheel
Ribbon	Multi-strike, or fabric cassette
Interface	RS 232-C
Dimensions	22.5″W x 15.9″D x 6″H
Weight	30.8 pounds
Power Requirements	115V±10%, 50/60 Hz, 70W
Reliability Data	MTBF is 1year with a 75% duty cycle

WARRANTY

90 day factory warranty. We pay shipping both ways.

SATISFACTION GUARANTEED

If, for any reason, you are not satisfied, you may return the unit to us within 30 days for a full refund.

SHIPPED BY UPS

Prepaid or COD by money order or cashiers check.

Prices quoted are for stock on hand and are subject to change without notice.

Write Writer, inc.

1703 Stewart Street, Santa Monica, CA 90404

TO ORDER OR FOR INFORMATION, CALL:

(213) 829-6871

Class 1: File Manipulation

WBLK	—Primitive to write a record. This primitive contains machine-language code to access a given sector from a given track on a given drive. (System specific.)
RBLK	—The read-record primitive corresponding to WBLK.
MAKE	—Primitive to enter/create a file in the directory.
READ	—Primitive to perform a sequential-access file read.
WRITE	—Performs a sequential-access write to a file.
RREAD	—Primitive to perform a random-access file read.
RWRITE	—Performs a random-access file write.
MOUNT	—Loads a disk directory into RAM.
REMOVE	—Writes a disk directory from system RAM to disk.

Class 2: Examples of Informative Commands

FREE	—Reports on disk and RAM space used/remaining.
HELP	—Lists information on DOS commands and their uses.
FSIZE	—Reports on the size and status of any file.
FILES	—Types a full directory of the disk plus relevant information.
BLOCKS	—Types a list of all records active for a given file.

Class 3: Examples of Commands for Program Control

NAME	—Enters a file name into the DOS for future use.
RUN	—Compiles and executes a program.
LOOKUP	—Checks to see if a given file name is on disk.
COPYALL	—Copies a file to another file from a program.
DINIT	—Initializes a new directory.
PROT?	—Sees if a given file is write-protected.
DPUTNM	—Saves a given file name into a directory.
KILL	—Deletes a file under program control.

Class 4: Examples of DOS utilities

FCOPY	—Copies a file to another (old/new) file.
XCOPY	—Like FCOPY but copies to a non-current disk.
BCOPY	—Copies records grouped by contiguous record numbers.
PROTECT	—Declares a file as write-protected.
UNPROTECT	—Declares a file to be read/write accessible.
TYPE	—Types a file to the console device.
PTYPE	—Prompts for format information, then prints on printer.
RENAME	—Gives a new name to an old file.
ASSIGN	—Forces DOS to assign a given record number to a file.
LOCK	—Prevents DOS from accessing read/write a record number.
KILL	—Deletes a file from the directory.
TIME	—Prints current time of day.
TIMESET	—Sets time of day.

Table 1: *FORTHDOS commands divided into classes of commands found in typical DOSes.*

Bit Maps

Although a DOS designer has many strategies to choose from in setting up a system, almost all DOSes use a bit map approach to regulating file activity on a disk. A *bit map* is a small byte array in which each bit represents the smallest logical grouping of bytes on a disk. Such a grouping is typically called a *record* or, in a FORTH-based system, a *block*.

Suppose we are designing a DOS using a 5¼-inch, 35-track disk. We could format this disk in many ways (by writing EOR or end-of-record marks onto the disk). We might use the TRSDOS scheme where EOR marks are written to yield a record size of 256 bytes or one record per sector. Since there are 35 tracks per disk and 10 records per sector, this equals 350 records per disk containing 350 times 256 or 89,600 bytes of storage.

We now need some scheme for keeping track of whether or not a given record is available for use, or if it is part of an existing user file. If we used the TRSDOS scheme mentioned above, a simple way to do this would be to create a bit map 350 bits long (just under 45 bytes) in which the first (high-order) bit represents the first record on the disk and the last (low-order) bit represents the last (350th) record on the disk. If a given record were in use, we would set the appropriate bit in the bit map to 1; otherwise we would set the bit to 0. This simple scheme would allow a DOS to keep track of all available records. Notice that since only a small amount of storage would be necessary (45 bytes), the entire activity of the disk could easily fit into free memory in a section reserved for system use. We will use a modified version of this scheme based on the traditional unit of storage in FORTH, the *block*.

In FORTHDOS, since records (blocks) are 1024 bytes long, a 35-track disk having 89,600 bytes of storage would require only 11 bytes of storage plus 1 bit (1 bit represents 1024 bytes):

$$11 \text{ bytes} \times 8 \text{ bits per byte} + 1 \text{ bit} = 89 \text{ blocks per disk}$$


In practice, this value is actually 86 blocks per disk, since a formatted disk has fewer available bytes for data than does the unformatted disk described above. This means that 11 bytes are easily enough to contain information on every data record available to the user. Figure 1 shows how FORTHDOS uses this simple scheme to map disk activity. Having developed this scheme of mapping record activity on the disk (given a specific disk format), we now need to develop a method of mapping file activity (i.e., activity of groups of records).

Bit Maps for User Files

Once we have settled on a format for each disk, we must determine whether or not to allow a file to use all records on the disk if they are available. This will determine the length of a file's bit map. If we refer again to the 35-track disk formatted as discussed above, a possible 86 blocks are available for use by any one file. For simplicity, let's allow files to be 86 blocks long. This would mean that, like the disk activity bit map, each file bit map would be 11

The Lightning One™

8086/8087/8089 CPU Board



Features:

- ☐ 4, 5, 8 or 10 MHz operation jumper selectable
- ☐ 8086 or 8088 main processor
- ☐ Independent I/O and memory waitstate generator
- ☐ Up to 16K bytes of onboard EPROM
- ☐ 9 vectored interrupts expandable to 65
- ☐ EPROM monitor with diagnostics and disk utilities
- ☐ 8087 and 8089 co-processors available onboard
- ☐ CP/M-86* and MS-DOS** software support

**CP/M-86 is a trademark of Digital Research.*
***MS-DOS is a trademark of Microsoft.*
Lightning One is a trademark of Lomas Data Products, Inc.

The *Lightning One*™ is the fastest processor board available on the S100 bus today. It contains not one processor, but three processors all working in parallel. It uses the Intel 8086 as the main processor. The math capability is augmented with the 8087 math processor and the I/O handling capabilities are augmented with the 8089 dual channel I/O processor. The board complies with all IEEE-696 specifications.

If you have an 8 bit system presently, don't despair. The *Lightning One* is available with the 8088. The 8088 is fully software compatible with the 8086, but utilizes an 8 bit bus allowing use of your present 8 bit memories. When you are ready to upgrade to full 16 bit operation, you need only to unplug the 8088 and plug in an 8086 in its place. When using an 8088, the 8087 and 8089 may still be utilized.

In addition to the *Lightning One,* Lomas Data Products has a full line of S100 bus support cards including: memory, disk controllers, and serial and parallel I/O.

Prices for the Lightning One start at $395.

Coming Soon: New Product Announcements:

- ☐ *128 K byte non-volatile static RAM*
- ☐ *M DRIVE for CP/M-86 and MS- DOS*
- ☐ *Dual CP/M-86 and CP/M 2.2 support*
- ☐ *Winchester hard disk controller*

For 16 bit computing on the S100 bus, come to the leader . . .

LOMAS DATA PRODUCTS, INC.

729 Farm Road, Marlboro, Massachusetts 01752 ☐ Telephone: 617-481-2822

Circle 240 on inquiry card.

BIT	1	2	3	4	5	6	7	8	9	10 • • • 86
DOS BIT MAP	0	1	1	1	0	1	0	0	0	0 • • • 0
RECORD NUMBER CORRESPONDING TO BIT POSITION	1	2	3	4	5	6	7	8	9	10 • • • 86

Figure 1: *Sample FORTHDOS disk bit map. A 1 in the bit map indicates that the corresponding record number is in use. In this sample, records 2, 3, 4, and 6 are in use.*

BIT	1	2	3	4	5	6	7	8	9 • • • 86
DOS BIT MAP	0	1	1	1	0	1	0	0	1 • • • 0
FILE 1 BIT MAP	0	1	1	0	0	1	0	0	0 • • • 0
FILE 2 BIT MAP	0	0	0	1	0	0	0	0	1 • • • 0

Figure 2: *FORTHDOS bit map and file activity bit map. FILE1 is shown as using blocks 2, 3, and 6, while FILE2 is shown using blocks 4 and 9. The DOS bit map indicates which blocks are in use regardless of what file the blocks belong to; blocks 2, 3, 4, 6, and 9 are therefore indicated by the DOS bit map as being in use.*

BIT	1 • • • 5	6	7	8	9	10	11	12	13 • • • 86
DOS BIT MAP (NEXT FREE RECORD IS 13)	1 • • • 1	1	1	0	0	1	1	1	0 • • • 0
FILE 1 BIT MAP (CURRENT RECORD IS 10) RECORD 13 IS NOW IN USE	1 • • • 1	1	1	0	0	1	0	0	0 • • • 0
FILE 2 BIT MAP (ADDS RECORD 13 FROM DOS)	0 • • • 1	0	0	0	0	0	1	1	1 • • • 0

Figure 3: *Using DNXT to find the next free record. As indicated in the DOS bit map, the next free record is 13. DNXT will scan the DOS bit map, find the free record, and change its corresponding bit to a 1.*

DOS BIT MAP AREA (11 BYTES)
DOS COMMENT FIELD AREA (64 BYTES)

FILE1 NAME (10 BYTES)	FILE1 BIT MAP AREA (11 BYTES)
FILE2 NAME (10 BYTES)	FILE2 BIT MAP AREA (11 BYTES)
FILE3 NAME (10 BYTES)	FILE3 BIT MAP AREA (11 BYTES)

DOS I/O BUFFER AREA (1024 BYTES)

Figure 4: *FORTHDOS buffer area. FORTHDOS places all file bit maps and the DOS bit map in a common buffer area. This allows you to have as many files open at one time as you need.*

bytes long. Figure 2 shows our bit map structure so far—one disk activity bit map (called DOS bit map) and multiple file activity bit maps.

What of space contention, though? If each file bit map can map any record in the system, how does the DOS determine the file assignment of each record? The answer is very simple. A FORTHDOS primitive (DNXT) scans the disk-activity bit map from high- to low-order bits until it finds a 0 (unused record). That bit is changed to a 1, thereby marking the corresponding record as being in use. DNXT then marks the same bit in the CURRENT file (i.e., the file requesting a free record) as also being in use. In figure 3, record 13 of both the DOS bit map and the FILE1 bit map is initially 0.

When FILE2 in figure 3 requests a free record, a call to DNXT causes the DOS bit map to be scanned. The next free record found by DNXT in this example would be record 13. This record's corresponding bit is then set to 1 in both the DOS and FILE2 bit maps (see figure 3). In this way, free records are allocated on a first-come, first-served basis by the DNXT primitive in the DOS.

Two points are important here. First, note that DNXT does not care if the record number returned is the next consecutive record in the bit map, but it will return consecutive records if possible (i.e., if the record is not in use). This means that DNXT will produce contiguous records for a given file wherever possible. This shortens head-seek times across the disk.

A primitive discussed below— KILL , which deallocates records—may be used by a clever DOS designer to ensure that a maximum amount of contiguous space is available. (Many DOS packages have disk cleanup utilities which periodically remap bit maps so as to maximize the amount of contiguous record allocation per file. For small systems, this is not needed.) A second point to note about this file bit map scheme is that it provides a simple method for inserting both sequential- and random-access file primitives into FORTHDOS.

Sequential and Random Access

In a *sequential-access file,* data records are accessed one after the other, without any gaps in the numeric sequence of records in the file. The ninth record cannot be accessed after the tenth has been read without starting over at the first record and reading up to the ninth again. In a *random-access file,* on the other hand, data from any record number may be accessed at any time. The ninth record may be accessed after the tenth or, for that matter, after any other record. *Relative pointers* are used in a random-access file. The record which the DOS has mapped in the bit map as record 341 may be relative record 10 to the user. That is, it may be the tenth record relative to the first record in the file. The DOS takes care of the correct translation of this relative record 10 into absolute record 341 on the disk.

To minimize access time and max-

YOUR COMPUTER HEADQUARTERS



SUPER SPECIAL!
THE NEW APPLE III
- Apple III plus 128K
- Apple III SOS package
- 12" High Resolution Green Monitor

$2999.00

HIGHLY RATED BY TAX PROS!
- Apple II plus 48K
- Apple Disc Drive II w/interface DOS 3.3
- 12" High Resolution Green Monitor
- HOWARD Tax Preparer 1982

$1999.00

WORD PROCESSOR SYSTEM
- Apple II plus 48K
- Apple Disc Drive II w/DOS 3.3
- 12" High Resolution Monitor
- OKIDATA Microline 80 Printer
- Printer cable w/interface
- IUS Orig. Easywriter

$2399.00

ACCESSORIES FOR APPLE

Videx Videoterm - 80 Col . $279.50
Videx Keyboard Enhancer II $119.50
DC Hayes Micromodem II $298.00
Microsoft Z-80 CP/M Card $289.00
Microsoft 16K Ram Card . $159.95
Saturn 32K Ram Card . . . $200.00
VC Expand for Saturn Card $85.00
Mountain CPS Multifunction Card $189.00
Mountain Clock $239.95
Keyboard Company Numeric Keypad . . . . . [illegible]
Apple Language System with Pascal . . . . [illegible]
Apple High Speed Serial Interface . . . . . [illegible]
Dan Paymar Lower Case Chip . . . . [illegible]
R.H. Superfan II . . . . [illegible]

WORD PROCESSORS

IUS - Pro Easywriter $200.00
IUS - Pro Easymailer $120.00
Orig. Easywriter $79.95
Apple Pie (W/P 40 Col.) . . [illegible]
LJK Letter Perfect . . [illegible]
Supertext II . . . . . . [illegible]
Superscribe II . . . . . [illegible]
Executive Secretary . [illegible]
Magic Window . . . . . [illegible]

EDUCATIONAL F/APPLE

Edu-Ware Math/Fractions . $34.[illegible]
Math/Decimals $34.95
Arithmetic Skills $43.00
Algebra I $34.95
Compuspell System $26.50
Data Disc Lev. 4-5-6-7-8 . ea. $18.00
CMA Teacher Plus $44.95
CMA Teacher Plus Pack . . $60.00
PDI New Step-by-Step $69.95

SOFTWARE FOR APPLE

Fortran 80 . . . . $154.50
A.L.D.S. $99.95
Basic Compiler $295.00
Tasc Compiler $149.95
Cobol - 80 . . . . $595.00
Context Connector $145.00

MICRO PRO

Wordstar 3.0 . . . . $269.95
Spell Star $170.50
Mail Merge $95.00
Super Sort-1 . . . . $139.00

MICROLAB

Data Factory $120.00
Invoice Factory $159.95

HOWARD SOFTWARE

Tax Preparer New 1982 . . $120.50
Real Estate Analyzer $129.95

PERSONAL SOFTWARE

Visicalc 3.3 . . . . $159.95
Visiplot . . . . $[illegible]59.95
Visidex . . . . $[illegible]59.95
Visitrend/Visiplot . . . . . [illegible]
Visiterm . . . . [illegible]
Visifile . . . . [illegible]
Desktop Plan II . . . . [illegible]

THE SOURCE

Telecommunication . . . . [illegible]

[illegible]

Personal [illegible]
Individual [illegible] . . . . $200.[illegible]

[illegible]STEM PLUS

Accounting Plus II . . . . . CALL

ASHTON TATE

dBase II . . . . [illegible]

HIGH TECHNO[illegible]

Info. Master . . . . [illegible]
Store Manager . . . . $199.[illegible]
Data Master $79.00
Job Control System $595.00

SOUTHEASTERN SOFTWARE

Data Capture 4.0 40 Col. . . $49.95
Data Capture 4.0 80 Videx . $69.95

SOFTWARE PUBLISHING

PFS $77.00
PFS Report $77.00

PHOENIX SOFTWARE

Zoom Graphics $35.00

Master Diagnostic
(Formerly Brain Surgeon) . $42.95

STONEWARE

DB Master Vers. 3 . . . . . . $179.95
Utility Pack I $90.00
Z-Term (CP/M) $80.00
ASC II Express 3.3 . . . . $65.00
Brodebund Payroll $300.00

GAME AND HOBBY

Temple of Asphai $32.95
Hellfire Warrior $32.95
Rescue at Rigel $24.95
Crush, Crumple & Chomp . $25.00
Jabber Talky $24.95
Major League Baseball . . . 26.95
Alien Rain $21.50
Apple Panic $24.95
[illegible] Attack $24.95
[illegible]aker $24.95
[illegible] Quarks $24.95
[illegible]c Drift $24.95
[illegible]ert $24.95
[illegible] $32.95
[illegible]hief $24.95
[illegible] Attack $24.95
[illegible]gon II $30.00
[illegible] 1.5 . . . . $30.00
Shuffle Board $24.95
Trick Shot $32.95
Dog Fight $24.95
Olympic Decathlon $24.95
Three Mile Island $32.95
[illegible] $21.00
[illegible] $32.95
Castle Wolfenstein $24.00
Zork $32.95
Zork II $32.95
Falcons $24.95
Beer Run $30.00
Raster Blaster $24.95
Space Eggs $24.95
Gorgon $32.95
Cops and Robbers $30.00
Tigers in the Snow $32.95
The Battle of Shiloh $32.95
The Shattered Alliance . . . $48.50
Computer Baseball $32.95
Computer Quarterback . . . $32.95
Sneakers $24.95
TG Joystick $48.95
TG Game Paddles $34.00
NEW! LOGO for Apple . . . $149.95

apple®

BUSINESSMAN'S SPECIAL
- Apple II plus 48K
- Apple Disc Drive II w/interface DOS 3.3
- 12" High Resolution Green Monitor
- Visicalc 3.3 Software

$2039.00

THE COMMUNICATOR PACKAGE
- Apple II plus 48K
- Apple Disc Drive II w/controller DOS 3.3
- DC Hayes Micromodem II
- 12" Green Monitor
- Source Telecommunication

$2255.00

THE FAMILY SYSTEM
NOW ONLY
$2099.00

NEW! FIBERBUILT CASE FOR APPLE!
- Fits Apple & 2 Disc Drives

$79.95

commodore




PERSONAL COMPUTER

VIC 20 w/5K memory, and RF Modulator

PRICE TOO LOW TO PRINT

8K Memory Expansion 53.95
Phone Modem f/VIC by Bizcom 152.95
DATACORDER (f/Cass. Prog.) 69.95
Jupiter Landers (cart.) 24.95
Super Alien (cart.) 24.95
Midnight Driver (cart.) 24.95
Household Finance (cass.) 29.95
Car Cost (cass.) 13.95
Loan Analyzer (cass.) 13.95
Home Inventory (cass.) 13.95
Amok (cass.) 15.95
Alien Blitz (cass.) 21.00
VT 106A Recreational Program A. *Consists of:* 6 Pack of (Cassettes) (1) Biorythem (2) Car Chase (3) Black Jack (4) Space Game (5) Math (6) Slither 49.95
VT-107 . . . . 49.95





TI 99/4A COMPUTER

$329.95

W/FREE! RF Modulator

Full line of Hardware, Software & Accessories IN STOCK!

CALL FOR LOW PRICES.

FREE! Buy any 4 TI modules from us & get the **New MUNCHMAN ARCADE** game free from TI.
OFFER EXPIRES 5/15/82

ATARI 800 w/16K $719.00
ATARI 400 . . . . $329.00
810 Disc Drive $459.00
410 Programmable Recorder . . . $79.95
MOST POPULAR ATARI GAMES IN STOCK!

HEWLETT PACKARD



HP-85A

A Complete Computer System In One Small Package.

The HP-85A is a powerful BASIC language computer, complete with keyboard, CRT display, printer and disc drive all in one self contained 20 lb. unit. 16K RAM memory, expandable to 32K. The HP-85 has been designed for your needs of today and tomorrow with a wide range of peripherals. General and customized software available.

HP-85A *New Low Price* **$1982.00**

PLUS! **2 Free Software Application Packs $190.00 Value!**
(WHILE SUPPLY LASTS).

HP-125 *New Low Price* **$1982.00**

HP 82091M 5¼" Disc Drive . . . $1650.00
HP 7225B Graphics Plotter $1939.00
HP 82905B Serial Printer $749.00

We carry the full line of TI and HP Programmable Calculators.

PRINTERS

OKIDATA 82A Graphics, 120 CPS, Bidirectional, Friction and Tractor Feed, 80/132 Columns **499.95**

OKIDATA 83A Graphics, 120 CPS, Bidirectional, Friction & Tractor, 136 Columns, Takes 15" Paper **729.95**

CENTRONICS 739 Graphics, 100 CPS Monospaced Mode, Right Justification, Friction and Tractor **525.00**

XEROX Diablo 630 with word processing enhancement **2399.00**
Bi-directional Tractor (optional) . . **205.00**

NEW! C.ITOH F10-40 Daisy Wheel, Letter Quality Printer **1595.00**

C.ITOH 8510 Pro Writer, 120 CPS, 136 Columns, Parallel , Bidirectional, T/F, High Resolution Graphics **519.00**

NEC 8023 Pro Writer, 100 CPS, 136 Col. Parallel, Bidirectional, Tractor and Friction, High Resolution Graphics . . **519.00**

EPSON
MX-70, MX-80, MX-80FT, MX-100FT
IN STOCK! CALL FOR LOW PRICES

MONITORS

SANYO VM-4509 9" B&W 169.95
SANYO DM-8112CX 12" Green 269.95
SANYO DMC-6013 13" Color 449.95
NEC JB1201 12" Green 179.95
NEC JC1201 12" Color 349.95

CORPORATE ACCOUNTS WELCOME



©1982

67 West 47th Street, New York, N.Y. 10036
115 West 45th Street, New York, N.Y. 10036
MAIL ORDER ADDRESS: 36 E. 19th St. New York, N.Y. 10003

OPEN SUNDAY



(212) 260-4410

TOLL FREE OUT-OF-STATE

800-221-7774
800-221-5858
800-223-5661

Items on sale for limited time only, and are subject to limited availability. Not responsible for typographical errors. This ad supersedes all other ads prior to April '82. Prices effective as of February 28, 1982, and are subject to change without notice. All orders subject to verification and acceptance. Minimum shipping and handling $4.95

FORTH and Punctuation

FORTH uses punctuation in some of its words, which makes representing them in text a difficult problem. For example, one FORTH word is ("), which could be taken to mean one of several character combinations. (For your information, the word has three characters and is made from a left parenthesis followed by a double quote mark and a right parenthesis.)

To decrease the chance of confusion while trying not to clutter text unnecessarily, we will sparingly *use braces, { }, to isolate the character string within as a FORTH word or phrase. (For example, the above word would be written { (") } .) Braces will be used only under the following situations:*

- *When the material being quoted is a phrase of FORTH words (e.g., { 26 LOAD }* or *{ 3 5 + })*
- *with the FORTH words { . } (period), { , } (comma), { : } (colon), { ; } (semicolon), { ? } (question mark), { ! } (exclamation point), { ' } (single quote mark), and { " } (double quote mark)*
- *with any word using the above punctuation marks (e.g., { $. }* or *{ ." }).*

All other FORTH words will be set apart by a space on either side of the word; braces will always *signal a FORTH word or phrase. The braces are not part of the word or phrase, and FORTH words will never use braces within the body of a figure or listing. . . .* **GW**

FORTHDOS on Floppy Disk

The author has agreed to make listings 1 and 2 available for a fee of $8 plus a floppy disk and a self-addressed return envelope. Due to the author's Canadian address and the expense of cashing foreign checks, the $8 must *be paid with an international money order. Also, do not put postage on the return envelope; Canadian postage is included in the $8 fee.*

imize use of contiguous blocks of disk space for sequential and (particularly) random access, many DOS implementations utilize complex memory allocation techniques. FORTHDOS, however, uses multiple-file bit maps, a single DOS bit map, and a common I/O (input/output) buffer to avoid these complications without sacrificing speed or ease of use for small systems. Before describing how this is done for sequential- and random-access files, we must first look at file device control blocks.

File Device Control Blocks

It is common DOS design practice to build OPEN and CLOSE primitives (e.g., OPEN and CLOSE commands in BASIC). The OPEN primitive creates a device control block (DCB) area in memory; this contains information on the file (its size, bit map, etc.) for use by the DOS until the CLOSE primitive writes the information back to the system area of the disk. In addition, OPEN creates a buffer area of RAM (random-access memory) within the DCB into which data is swapped back and forth from the file to other (user) areas of memory. This last point means that as the number of open files increases (as might be the case in a complex program), the amount of memory used by the file DCBs grows very rapidly. This is why many DOS systems limit the number of files which may be open at any given time. This manifests itself as the OUT OF FILE SPACE messages you get while executing a favorite program.

Suppose we use a different method. Suppose that instead of using a DCB area for each file containing file statistics plus buffer space, we use a common small buffer area for all files and keep all file bit maps in memory at one time (they're only 11 bytes long). This allows you to have as many files open at one time as you wish without using up more than 11 bytes per open file (for 35-track disks). Figure 4 illustrates this.

In other words, FORTHDOS uses two buffer areas. The first contains the file bit maps for all files in the system as well as their names and the DOS bit map. I've made this area 1024 bytes long, but it may be any length desired or even swapped in and out of memory as wished, with only current files kept in the buffer. The second buffer area is the one used for file I/O (which I have also made 1024 bytes long). Again, this may be of any length the user wishes.

Since FORTH is a virtual system using a 1024-byte buffer (i.e., FORTH blocks can be seen as virtual memory that is swapped into memory when needed), I have set up the DOS to use this same buffer for all file I/O. Therefore, the total cost to the system for implementing FORTHDOS without a DCB structure is only 1024 bytes of buffer space regardless of the number of open files per disk buffer.

Armed with the conceptual tools of bit maps and DCB usage, let's examine the way in which sequential- and random-access files are accessed through FORTHDOS.


Bit Maps for Sequential and Random Access

Notice in figure 5 that five files are in use (open) and that the record number that would be returned by the next use of DNXT is 53. Suppose we wish to add data to the next record available in the file, labeled ORANGE in figure 5. Assume that ORANGE is a sequential-access file. By using the DOS primitive WRITE , we would add our data from the buffer to ORANGE at record 53. WRITE would work as follows:

1. Call DNXT to calculate where the next free record is on disk (scan DOS bit map). Return with 53.
2. Set bit 53 in the DOS bit map to a 1 (i.e., in use).
3. Set bit 53 in ORANGE bit map to a 1.
4. Write any previous data from BUFF (the FORTHDOS I/O area in memory) if necessary.
5. Write the data from BUFF to record 53.

Note the following points: the file bit map, ORANGE bit map, is filled according to the next available free record in the DOS bit map, not from

If it flies on aerospace software, Kearfott...and you... may well help create it.



As a company engaged in dozens of major projects that depend on software advances in flight, orbiting, command, communications or controls, we can offer you the opportunity to work in a DP complex that's as sophisticated as the ring laser gyroscope system we're developing for the Tomahawk-2 MRASM Cruise Missile. Or as advanced as our JTIDS communications terminal.

In engineering and scientific programming, your realtime software designs will operate airborne computers and support everything from aircraft navigation systems to inertial measurement units on the Space Shuttle... guidance controls for the Trident missile... ASW ...scanning beam landing systems...and much, much more. Have a background in simulation, linear systems, firmware for SW validation, Kalman filtering or FORTRAN? Then find out about our firmware projects.

In MIS—the expanding sphere that helps give Kearfott's rarefied environment a very solid basis—you'll run the gamut. Accounting. Finance. Payroll. Inventory and manufacturing controls. All involve COBOL programming, CICS, MVS, IMS, and data base design and telecommunications.

At our Data Center, you'll be joining an elite software systems group that maintains IBM and Amdahl mainframe computers with supporting software that includes MVS/SE-2, SE/A, JES 2, IMS DB/DC, CICS, TSO, WYLBUR, ACF/VTAM, ACF/NCP, SAS, information systems. And more.

So whatever your software specialty may be, there's a career path for you at Kearfott. You'll need at least 3 years experience in a large-scale IBM environment or HP 2100 MUX. If you're looking to accelerate your career, please send your resume to: Carol Batte, Singer Company, Kearfott Division, 1150 McBride Avenue, Little Falls, NJ 07424.



An equal opportunity employer, m/f, who creates opportunities.

```
FILE NAME                          RECORDS USED IN BIT MAP

  ORANGE    (3 RECORDS)            2, 10, 14,
  PEAR      (5 RECORDS)            1,  3,  4,  5,  6
  APPLE     (5 RECORDS)            7,  8,  9, 11, 12
  BANANA    (25 RECORDS)           13, 17, 18 ——► 40, 41
  TREE      (14 RECORDS)           11, 15, 16, 19, 42——► 51, 52

A CALL TO NEXT WOULD RETURN RECORD 53 (i.e., LAST RECORD
USED WAS 52 IN FILE TREE). AFTER A SEQUENTIAL WRITE TO
FILE ORANGE, ITS BIT MAP WOULD CONTAIN:

  ORANGE    (4 RECORDS)            2, 10, 14, 53
```

Figure 5: *Adding records to a sequential-access file.*

```
 RELATIVE RECORDS   1     2     3     4     5     6
RECORD NUMBERS     |34    45    72    67    68   |84|   RECORD 84 IS
IN THE BIT MAP                                         CURRENT RECORD
FOR FILE PEAR
         RECORD 34 ——— SEQUENTIAL READ ———► RECORD 84
```

Figure 6: *Random-access record retrieval. To sequentially read record 72, you would have to start at record 34 and go forward. A random read of record 72 would be done by calling RREAD to relative record 3, then doing a direct head move to that record.*

the ORANGE bit map. No other files are affected, regardless of how many are in use. Step 4 above is carried out only if the DOS has not previously taken care of writing the FORTH-DOS I/O buffer through prior processing.

Reading such a sequential file is extremely simple. If we look again at figure 5, we see that the ORANGE bit map shows the file ORANGE to consist of records 2, 10, and 14. The DOS primitive READ scans the ORANGE bit map from high- to low-order bits, moving the next record whose corresponding bit is 1 to the I/O buffer BUFF.

Since the ORANGE bit map contains 1s in positions occupied by corresponding record numbers used by the sequential file ORANGE and 0s elsewhere, it is unnecessary to mark the file on disk with an EOF (end-of-file) marker. It's easier and just as efficient to total the number of ones in ORANGE bit map and have the DOS read only that number of records from the file. Because only 11 bytes are involved, this can be done very rapidly. The only data that gets written to a file is user data without the need for EOR or other such markers. Random access is handled in a slightly different manner.

Random Access

In figure 6, the bit map for PEAR shows that records 34, 45, 72, 67, 68, and 84 are in use. If this were a sequential-access file and we wanted to read record 72, it would be necessary to go to the beginning of the file and scan through until record 72 was found.

By designating the file as random access, however, you can go immediately to record 72. Do so by entering a call to the FORTHDOS primitive RREAD (random-access read) with a relative pointer 3. This tells the DOS to scan PEAR bit map for the third 1 (i.e., the "in-use" bit) encountered. The record number corresponding to this bit will then be read by the same primitive used to read a disk record for a sequential file. The only difference between random and sequential access in FORTHDOS is that the former scans a file bit map prior to an access to locate the absolute record number desired, while the latter must access the DNXT available record.

Scanning is performed (in this example) over 11 bytes only—clearly much faster than forcing the DOS to sequentially read through as many as 86 blocks (an entire disk) before arriving at the desired record. This




Figure 7: *Interchangeable random/sequential accessing. To change from a sequential- to a random-access read, FORTHDOS would save the value of the current record number being read (84) in the variables TMP and NBLK. FORTHDOS would then call RREAD to read relative record 3 and change the value of NBLK to 72. Then NBLK would be restored to the value of TMP (84), and the sequential read would continue.*




Figure 8: *Swapping disk directories. As each disk is accessed, the disk directory is read from the disk and placed into RAM.*

scheme works quite well and even has a side benefit that adds extra versatility to the DOS; a given file can be sequentially or randomly accessed at any time!

To further clarify this scheme, suppose you are accessing the file PEAR through the FORTHDOS primitives DNXT and READ (sequential read) at record 84. As figure 7 shows, no indicators are present in PEAR bit map to tell us that the file is sequential; only the variable NBLK is associated with current file activity. This variable stores the current record number being accessed from the current file. In figure 7, NBLK contains an 84 (i.e., record 84 is being accessed). If the file is accessed again (refer to figure 7) but this time by the DOS primitive RREAD to access record 72, the DOS will set NBLK to 72 and retrieve that record. Also, if the value of NBLK (72) had been saved prior to invoking RREAD , you can restore this value at any time and continue with sequential access by using the sequential READ again.

As you can see, any FORTHDOS file may alternate between sequential- and random-access read without destroying the integrity of the bit map! This may also be done with write access, but more variables are involved. Consult listing 1 for the names of these variables.

FORTHDOS

Having discussed the basics of the DOS structure, we can now look at the actual implementation in more detail. Table 2 (on page 348) gives an abbreviated listing of the table 1 commands. All are available in FORTHDOS, with special provisions in the DOS for bypassing terminal interaction when you wish to issue the commands under program control. Some of the functions of the commands change and require parameter passing when accessed through a user's program. Let's briefly step through a few of these commands.

Loading a Directory

Enter the MOUNT command whenever a new disk is inserted into a drive, and enter REMOVE when the disk is taken out. The former reads the file names and bit maps into the DOS memory (1024 bytes, as mentioned earlier). The latter writes this FORTHDOS RAM area back to disk. Figure 4 gives a simplified version of

Text continued on page 348

Listing 1: *Disk operating system for FORTH. This DOS is written in the MMSFORTH (version 1.8) dialect of the FORTH language for use on the TRS-80 Model I computer running Level II BASIC. The listing is in two parts, a core package that resides in memory and a utilities package that resides on disk for use as needed. Set DIRBLK and AUXBLK to match your system before LOADing words from { :DOS } to { :BCOPY } inclusive. Also, in this listing the left bracket in the MMSFORTH word 2[(the sixth colon definition in this listing) should actually be an up-arrow symbol.*

```
(" FORTHDOS - a disk operating system - by Peter Reece (c) 1981
: DOS ;      : CARRAY 0 CCONSTANT H +! ;CODE HL POP DE DAD PSH
#TRACKS 256 * 100 / 3 - #DV @ *        ( Use # of disk tracks &)
     CCONSTANT DSKSZ                   (  # of drives to get size)
15360 CONSTANT VIDEO                   ( Start adrs of video ram)
86 VARIABLE DIRBLK                     ( Adrs of directory block)
34 VARIABLE AUXBLK                     ( Adrs of utility progs)
DSKSZ 8 / 1+ CCONSTANT MAPSZ           ( Size of bitmap)
MAPSZ CARRAY BITMAP                    ( Create system bitmap tabl
MAPSZ CARRAY QMAP                      ( Create file bitmap table)
1024 CARRAY DBUFF                      ( Directory holding buffer)
64 CARRAY FNAME     5 CARRAY ONAME     ( File name buffers)
0 DBUFF VARIABLE DADRS                 ( Start of directory buffer
0 VARIABLE NBLK                        ( Currently accessed block#
0 CVARIABLE BM1     0 CVARIABLE BM2    0 CVARIABLE BM3 ( Temporary
0 VARIABLE N        0 VARIABLE N1      5 CARRAY TMP     ( storage)

: T# <# # #S #> TYPE ;                       ( Type a number)
: C+! DUP C@ ROT + SWAP C! ;                 ( Add tos to cvar)
: C-! DUP C@ ROT - SWAP C! ;                 ( Subtract from cvar)
: 2[ DUP 0= IF DROP 1                        ( Raise 2 to tos power
         ELSE 1 SWAP 0 DO 2* LOOP            ( Used to determine a
       THEN ;                                ( record's bit number)
: DZONK 0 0 BITMAP MAPSZ FILL ;              ( Clear the bitmap)
: DGT DUP 8 / DUP ROT ROT 8*                 ( Translate the block#
       - SWAP DUP ROT 2[ ;                   ( in tos to bitpostion
: DON DGT SWAP BITMAP C@                     ( Set a block to 'on')
       OR SWAP BITMAP C! ;
: DOFF DGT BM2 C! BITMAP C@                  ( Set a block 'off')
       255 BM2 C@ - AND SWAP BITMAP C! ;


: DON? 0 BM2 C! DUP DGT SWAP BITMAP C@       ( If block# in tos is)
       AND SWAP DROP 0=                      ( used, bm2=block#)
          IF DROP ELSE BM2 C! THEN ;         ( else bm2=0)

0 CVARIABLE 1SB                            ( 1st block in a thread)
: DNXT  0 BM1 C! DSKSZ    DO I DON?  ( Find next free)
    BM2 C@ 0= I 1SB C@ >= AND        ( Chk thread integrity)
    IF I BM1 C! LEAVE THEN LOOP      ( Get block into bm2)
    BM2 C@ 0 <> BM1 C@ 0= OR         ( or issue a -1 flag)
    IF  -1 BM2 C!                    ( issue error msg)
        " *** Thread Full ***" ENTER
    THEN ;

( * Access the directory through a virtual buffer)
: DREAD DADRS @ DIRBLK @ RBLK ;                ( Read directory)
: DWRITE DADRS @ DIRBLK @ WBLK ;               ( Write directory)
: DRD DADRS @ 0 BITMAP MAPSZ MOVE ;            ( Read the bitmap)
: DWR 0 BITMAP DADRS @ MAPSZ MOVE ;            ( Save the bitmap)
: MOUNT DZONK DREAD DRD ;                      ( Mount diskette)
: DSAVE DWR DWRITE ;                           ( Save directory)
: REMOVE DSAVE FLUSH CR " REMOVE DISKETTE" ;   ( Remove diskette)
: DINIT MOUNT 0 DADRS @ 1024 FILL DZONK ;      ( Initialize dir)
```

```
( * Lookup fname: exit tos & bm1=position in directory, or -1)
: LOOKUP -1 BM1 C! DADRS @ 128 + N !       ( 1st 4 letters only)
  13 0 DO                                  ( are valid in fname)
        N @ C@ 0 <>
            IF N @ C@ 0 FNAME C@ =
                IF N @ 1+ C@ 1 FNAME C@ =
                     IF N @ 2+ C@ 2 FNAME C@ =
                         IF N @ 3 + C@ 3 FNAME C@ =
                               IF I BM1 C! LEAVE
                               THEN
                         THEN
                     THEN
                THEN
            THEN 64 N +!
    LOOP BM1 C@ ;


( * Add a new filename to the directory)
: DPUTNM LOOKUP 255 <>
      IF " * FILE ALREADY EXISTS" ENTER
         ELSE DADRS @ 128 + N !
            13 0 DO N @ C@ 0 =
                     IF 0 FNAME N @ 15 MOVE LEAVE 0 N !
                         ELSE 64 N +!
                     THEN
                LOOP N @ 0 <>
            IF " * FILE NAME SPACE IS FULL" ENTER
            THEN
      THEN ;

( * Prompt for and input a filename)
: NAME 0 0 FNAME 15 FILL SPACE " FILENAME:" SPACE
  0 FNAME 15 EXPECT ;

( * Obtain the filemap for the file named in 'fname')
: DGTMAP LOOKUP 255 <>
     IF DADRS @ 128 + BM1 C@ 64* + 20 +
        DUP N ! 0 QMAP MAPSZ MOVE
     THEN ;

( * Add a block to thread for 'fname' & leave # on tos, or 0)
: DADD
      DGTMAP DNXT BM2 C@ -1 <>                ( find bitmap for)
      IF BM1 C@ DUP DON DGT SWAP              ( this file, get )
           QMAP C@ OR SWAP QMAP C!            ( next in chain  )
           0 QMAP N @ MAPSZ MOVE BM1 C@       ( put it on tos  )
               ELSE 0
      THEN
  ;
```

Listing 1 continued on page 336

Computer Exchange

Ad # 930B

P.O. Box 1380, Jacksonville, OR 97530

APPLE® SUPPLY CENTER

HARDWARE for Apple II/II+

NEW

Direct Substitute for Apple Drives

Micro-Sci A2 is a direct substitute for Apple II drives. Save $300 on a dual disk system.

Micro-Sci 5" Drives for Apple II		SAVE
A2, 143K, 5" Drive	$ 395	18%
A2 Controller and DOS	$ 95	15%
A70, 286K, 5" Drive	$ 489	20%
A40, 160K, 5" Drive	$ 369	18%
Controller Card for A70 and A40	$ 79	21%

NEW

320K RAM substitute for Disk System		
AXLON,		
RAMDISK 320K Memory System	$ 1145	20%
Sorrento Valley		
8" Disk Drive Controller	$ 199	60%

MONITORS:

NEC	12" Color	$ 359	24%
	12" Green	$ 169	22%
	9" B&W	$ 149	31%
SANYO:	9" Green	$ 159	31%
	12" B&W	$ 219	30%
	12" Green	$ 229	30%
	13" Color	$ 399	28%
	NEW 13" RGB Color	$ 899	25%
ZENITH	12" Green	$ 119	20%

DISKETTES, 5", box of 10:

Maxell	$ 39	33%
Memorex	$ 25	45%

80 COLUMN VIDEO CARDS:

Videx Videoterm	$ 249	18%
M&R Sup R Term	$ 295	22%
ALS: Smarterm	$ 269	30%

MISCELLANEOUS:

Apple:		
Graphics Tablet (CLOSE OUT)	$ 650	20%
CCS: Serial Interface 7710A	$ 139	22%
Parallel Interface 7720A	$ 99	20%
Other CCS Cards In Stock,	CALL	CALL
Hayes: Micromodem II	$ 289	25%
Smartmodem	$ 229	20%
Keyboard Company:		
Joystick II	$ 45	10%
Game Paddle	$ 25	17%
Numeric Keypad	$ 119	21%
M&R: RF Modulator	$ 25	27%
SUP R FAN	$ 39	25%
★ **Microsoft:** Z80 Softcard	$ 279	33%
16L RAM Card	$ 159	20%
Mountain:		
CPS Multifunction Card	$ 209	13%
Clock/Calendar	$ 239	15%
Novation Applecat Modem	$ 329	16%
Orange Micro Grappler	$ 129	21%
Dan Paymar LCA (NEW)	$ 34	33%
Saturn System 32K RAM Board	$ 149	36%
SSM AIO Serial/Para. Interface	$ 159	20%
★ **ALS:** Smarterm 80 Col Card	$ 269	30%
★ Z-Card (Z-80)	$ 209	22%
★ Addram 16K Card	$ 119	20%
★ Synergizer Package	$ 549	27%
NEC		
16K Expansion Chips for Apple II	$ 39	35%

LETTER QUALITY PRINTERS:

Qume Sprint 9 45RO	$ 2195	23%
Sprint 5 45RO	$ 2395	20%
Olympia (Typewriter/Printer)		
ES-100, 18CPS w/full interface to Apple II	$ 1695	22%

PRINTERS:

Epson, See special Epson section at right		
Intergral Data		
445 Tiger w/Graphics & 2K	$ 695	23%
460 Tiger w/Graphics	$ 895	20%
560 Tiger w/Graphics	$1095	22%
Prism color printer w/Graphics	$1695	16%
Okidata Microlin 82A	$ 495	25%

ORDERING INFORMATION:

Minimum order $100. Money Orders, Cashier Checks welcomed. Visa and MC orders add 3%. Personal or company checks accepted (allow 20 days to clear). Add 3% for shipping, handling and insurance; UPS ground is standard. 6% total for UPS Blue or 10% total for APO or US Parcel Post. Include your telephone number. No COD's. Prices are subject to change without notice. Call to verify prices; ad errors do occur. Order desk hours are 8 to 6 PDT, 10 to 3 Saturdays.

REFERENCES:

We have been a computer dealer since 1978. Our bank reference is First Interstate Bank (503) 776-5620. We belong to the Chamber of Commerce, (503) 772-6293.

SOFTWARE on disk for Apple II/II+

Apple Software:		
Apple Fortran (CLOSE OUT)	$ 149	25%
Apple Pilot	$ 119	27%
Apple Plot	$ 49	30%
Dow Jones News & Quotes	$ 69	28%
Dow Jones Portfolio Eval.	$ 40	20%
Microcourier	$ 189	24%
Many others	CALL	CALL
Artsci Magic Window	$ 75	25%
★ **Ashton-Tate**		
dBase II for Apple II	$ 495	30%
Aurora Systems		
Executive Secretary-WP	$ 189	25%
Broderbund Software		
Payroll	$ 269	30%
General Ledger	$ 349	30%
Apple Panic	$ 21	30%
Arcade Machine	$ 32	30%
Red Alert	$ 21	30%
Space Warrior	$ 18	30%
Many Others In Stock	CALL	CALL
Budgeco, Raster Blaster	$ 22	27%
Calf. Pacific, Ultima	$ 30	25%
★ **Central Point Software:**		
Copy II Plus ver. 4	$ 35	10%
Will copy most copy protected software for your backup in 45 seconds! NEW		
Continental Software		
Home Accountant	$ 56	25%
Home Money Minder	$ 26	25%
Data Most		
Snack Attack	$ 22	25%
Thief	$ 22	25%
Denver Software		
Financial Partner	$ 185	25%
Epson, MX 80 Graphics Dump	$ 9	30%
Hayden, Sargon II (chess)	$ 29	22%
High Technology		
Store Manager	$ 189	25%
Job Control System	$ 469	40%
Howard Software		
Tax Preparer 1982 ver.	$ 115	25%
Real Estate Analyzer	$ 115	25%
Creative Financing	$ 115	25%
Info Unlimited,		
Easywriter (PRO)	$ 189	25%
Innovative		
Apple Spellguard	$ 219	26%
★ **Insoft:**		
Electric Duet NEW	$ 25	20%
ALD System II or III	$ 110	10%
TransFORTH II or III	$ 110	10%
Insoft Accountant	$ 355	66%
A full professional quality integrated GL, A/R, A/P, Payroll package. Hotline support available. Send for free sample printouts. Requires Z80 and 16K RAM card.		
ISA Spellguard	$ 219	25%
Micro Lab		
Data Factory, ver. 5.0	$ 249	20%
Invoice Factory	$ 129	35%
Tax Manager	$ 95	38%
★ **Micro Pro**		
Calc Star	$ 189	36%
Word Star	$ 239	36%
Super Sort	$ 129	36%
Mail Merger	$ 79	36%
Data Star	$ 189	36%
Spell Star	$ 159	36%
Microsoft		
A.L.D.S.	$ 110	10%
BASIC Compiler	$ 299	25%
Cobol 80	$ 559	25%
Fortran 80	$ 149	25%
Olympic Decathlon	$ 24	24%
TASC Compiler	$ 159	22%
Typing Tutor II	$ 19	30%
Muse		
Super Text II	$ 113	25%
Castle Wolfenstein	$ 23	25%
Robot War	$ 29	25%
On-Line		
Expediter II	$ 75	25%
Superscribe II	$ 95	27%
Lisa 2.5	$ 59	26%
Pegasus II	$ 22	25%
Threshold	$ 30	25%
Cranston Manor	$ 26	25%
Mission Astroid	$ 15	25%
Mystery House	$ 19	25%
★ **Osborne** (Disk and Book)		
Some Common Basic Programs, 75 Business, Statistics and Math programs for the Apple	$ 49	50%
Peachtree Software		
Magic Wand	$ 250	37%
GI, AR, AP, PR or Inv	$ 189	38%

* Apple is a registered trademark of Apple Computer, Inc.

IBM 3101-10 Terminal	$ 1195	SAVE 20%

HEWLETT PACKARD H/P 85A $ 1,995

		SAVE
★ **HP-85A** Microcomputer with built-in printer and monitor	$ 1,995	27%
HP-125 New! Microcomputer		
64K CPU/Terminal/Keyboard/Monitor	$ 3095	18%
HP-87 New!	CALL	CALL
HP-41CV New! 2.2K Memory Calculator	$ 245	25%
HP-41C Calculator	$ 185	26%
Memory module for HP41C	$ 25	25%

Call for other HP equipment, software and accessories!



VIC 20 Home Computer	$ 249	16%
CBM 8032 Computer	$1059	20%
CBM 4032 Computer	$ 959	22%
CBM 4040 Disk Drives (2) 343K	$1019	21%
CMB 8050 Disk Drives (2) 1 Meg	$1295	28%



COMPUTER SYSTEMS

8000-15 208K, 4 User, 2 Disks	$3995	20%
8000-10 208K, 4 User, 10 Meg	$6495	25%
MTV-1 HD Mag Tape Backup	$2795	25%
Others in stock	CALL	CALL

INTERTEC DATA SYSTEMS® — While They Last — SUPERBRAIN

Superbrain 64K QD	**$ 2895**	**28%**

EPSON PRINTERS

MX 70 w/Graftrax	$ 359	20%
MX80	$ 449	31%
MX80 F/T	$ 555	25%
MX100 F/T w/graphics	$ 729	27%
70/80/100 Apple Interface and Cable	$ 95	15%
MX80Friction feed adapter	$ 59	22%
MX80 Graftrax	$ 79	20%
MX80/100 Atari Cable	$ 29	22%
MX80/100 TRS 80 Cable	$ 29	22%

NEC Microcomputer

32K Computer PC8001	$ 750	25%
286K Total Dual Drive PC8031	$ 750	25%
32K addon and I/O Unit PC8012	$ 495	24%
NEC PC Software	CALL	CALL

Corvus

5 Meg Hard Disk	$ 2995	21%
10 Meg Hard Disk	$ 4345	20%
20 Meg Hard Disk	$ 5245	20%
Omni-Net, Constellation, Mirror. In Stock	CALL	CALL

XEROX® 820 System II

Complete system includes monitor, keyboard, CPU and two disk drives

		SAVE
With 5¼ inch dual drives	$ 2495	18%
With 8 inch dual drives	$ 3095	19%

Personal Software/VisiCorp		
VisiCalc 3.3	$ 189	25%
VisiDex	$ 189	25%
VisiFile	$ 189	25%
Desktop Plan II	$ 189	25%
VisiPlot	$ 159	20%
Desktop Plan III	$ 209	30%
VisiSchedule	$ 239	20%
VisiTrend and VisiPlot	$ 239	20%
VisiTerm	$ 79	20%
Zork	$ 33	20%
Softech Int'l		
Stockfile	$ 250	60%
Stockseller	$ 423	30%
Software Publishing:		
PFS II or III	$ 69	26%
Report II or III	$ 69	26%
Sorcim Supercalc	$ 219	25%
Stoneware,		
DB Master (new version)	$ 179	22%
Sub Logic Flight Simulator	$ 28	20%

Free gift with your order if you mention this ad.

Ad # 930B

master charge — VISA



Circle 103 on inquiry card.

Listing 1 continued:

```
( * Make a new file & allocate directory space for it)

: 1STBK DGTMAP 85 0 DO I FON?        ( set 1sb)
  BM2 C@ DUP DUP 0 <> IF 1SB C! LEAVE ELSE DROP THEN LOOP ;
: MAKE 0 1SB C! NAME DPUTNM 1STBK ; ( Create/open a file)

( * See if the file in fmap is using the block# in tos)
: FON?
     DUP DGT SWAP QMAP C@
                        AND SWAP DROP 0=
        IF DROP 0 BM2 C!
           ELSE BM2 C!
        THEN
  ;

( * Routine to caluculate adress of a file from DOS RAM)
: RENM DADRS @ 128 + BM1 C@ 64* + N ! ;

( * Kill the file named in fname)
: KILL
   NAME LOOKUP 255 <>
    IF DGTMAP DSKSZ 0
       DO I FON? BM2 C@ 0 <>
           IF BM2 C@ DOFF
           THEN
       LOOP RENM 0 N @ 64 FILL
    THEN ;

( * Read the next block in 'fname' into the buffer at tos)
: READ N1 ! DGTMAP BM1 C@ -1 <>
    IF
      BEGIN NBLK @ DSKSZ >
          IF 0 NBLK !
          THEN
          1 NBLK +! NBLK @ FON? BM2 C@ 0 <>
                IF N1 @ BM2 C@ RBLK 1
                   ELSE 0
                THEN
      END
    THEN
  ;

( * Print the # of blocks used by the file in fname)
: FSIZE
    DGTMAP BM1 C@ -1 <>
      IF 0 BM1 C! DSKSZ 0
         DO I FON? BM2 C@ 0 >
            IF 1 BM1 C+!
            THEN
         LOOP
         BM1 C@ SPACE T# SPACE " Blocks"
      THEN
   ;

: PROT?      ( * Returns 1 if the file is protected, 0 therewise
 LOOKUP 255 <> IF RENM N @ 63 + C@ 170 = IF 1 ELSE 0 THEN THEN

( * Write buffer on tos to the file 'fname')
: WRITE
   N1 ! PROT? 0=                          ( don't write if rec)
     IF DADD DUP 0 >                      ( is protected      )
         IF N1 @ SWAP WBLK
            ELSE DROP
         THEN
     THEN
  ;

( * Random access of relative block# on tos to buffer at tos2)
: RFIND
    DUP N ! BM1 C! N1 ! DSKSZ 0
        DO I FON? BM2 C@ 0 >                     ( loop to find )
           IF 1 BM1 C-! BM1 C@ 0 > NOT           ( relative rec#)
                 IF I N ! LEAVE
                 THEN
           THEN
        LOOP
   ;

( * Random read block# at tos to buff at tos2, exit=1 if okay)
: RREAD RFIND BM1 C@ 0 >
     IF 0
        ELSE N1 @ N @ RBLK 1
     THEN ;

( * Random write block# at tos to buff at tos2, exit=1 if okay)
( * Note that user may only write to a block already allocated)
: RWRITE RFIND BM1 C@ 0 >
      IF 0
         ELSE N @ PROT? 1 =
            IF DROP 0
               ELSE N ! N1 @ N @ WBLK 1
            THEN
      THEN ;

( * These words alter the write protect status of a file)
: PROTECT
   NAME LOOKUP 255 <>
     IF RENM 170 N @ 63 + C!
     THEN
   ;

: UNPROTECT
   NAME LOOKUP 255 <>
     IF RENM 0 N @ 63 + C!
     THEN
   ;
```

Listing 1 continued on page 338

Listing 1 continued:

```
( * Prints the number of free blocks on the current disk)
: FREE 0 BM1 C! DSKSZ 0
   DO I DON? BM2 C@ 0 >
       IF 1 BM1 C+!
       THEN
   LOOP
    CR DSKSZ BM1 C@ - T# SPACE " Free disk blocks"
    SPACE " out of" SPACE DSKSZ T# CR ;

( * Loads - compiles - a given filename for execution)
: RUN NAME LOOKUP 255 <> IF CR DSKSZ 0 DO I FON?
  BM2 C@ 0 <> IF I LOAD THEN LOOP THEN CR ;


( * List the file named in 'fname')
: SHOW NAME LOOKUP 255 <> IF FSIZE BM1 C@ DUP 0= IF DROP ELSE
  0 DO VIDEO READ LOOP THEN THEN ;

( * List the file names from the directory)
: FILES DADRS @ 128 + N1 ! CLS 0 23 PTC " Disk Directory"
  1 23 PTC 14 0 DO 131 ECHO LOOP CR CR DADRS @ 64 + 64 TYPE
  0 BM3 C! CR 13 0 DO N1 @ C@ 0 <> IF N1 @ 0 FNAME 15 MOVE
  PROT? 1 = IF " *" ELSE SPACE THEN 0 FNAME 10 TYPE
  FSIZE BM3 C@ 0= IF 1 BM3 C! 220 ECHO ELSE 0 BM3 C! CR THEN
  THEN 64 N1 +! LOOP CR 'S PAD - T# SPACE " Free bytes of"
  SPACE " memory" FREE " (* - write protected file)" CR ;


( * From here on utilities only are listed.  Note that
(   the utilities take space, so they are not core resident
(   unless the user calls them in.  This is done by typing
(   in the name of the utility or command desired.  FORTHDOS
(   then loads the utility from the system area of the
(   appropriate disk, executes the utility, erases the utility
(   from core when done, and returns control to the user.
(   Note that 'assign', 'time', and 'timeset' are not included
(   in this listing since their function is peculiar to my
(   computer system. There are, however, some utilities listed
(   which are not given in the text.
(     You may easily add your own utilities or programs to
(   FORTHDOS by following the scheme used to call utilities.


( * Add any utilities you wish to FORTHDOS starting here.)
: GAUX AUXDOS @ + LOAD ;            ( This word loads the utility
: LOCK 0 GAUX ;
: SETDIR 1 GAUX ;
: RENAME 2 GAUX ;
: COPYALL 3 GAUX ;
: FCOPY 4 GAUX ;
: BLOCKS? 5 GAUX ;
: PSHOW 6 GAUX ;
: BCOPY 7 GAUX ;


( * Lockout any blocks the user wishes to be write protected)
: *LOCK
       BEGIN
           " Block# to be locked out (-1 if none):"
           #IN DUP -1 =
               IF DROP 1
                    ELSE DON 0
               THEN CR
       END
   ;

*LOCK FORGET *LOCK

( * Set up a new directory via prompts to the user)
: *SETDIR CLS 0 23 PTC " NEW DIRECTORY" CR CR
    " Build a new directory (& destroy all files)" Y/N NOT
        IF DINIT CR " Write protect below block#"
            SPACE #IN 0
                DO I DON
                LOOP
            CR LOCK 0 0 FNAME 64 FILL
            DIRBLK @ DON DWR DADRS @ 64 + N !
            " Diskette description: "
            0 FNAME 64 EXPECT
            0 FNAME N @ 64 MOVE 0 0 FNAME 64 FILL
            DSAVE
        THEN CR ;
*SETDIR FORGET *SETDIR


( * Give an old file a new name via the console of a program)
: *RENAME SPACE BM1 C@ -2 <>
  IF " OLD" NAME LOOKUP -1 =
       IF SPACE " * NOT FOUND" ENTER
           ELSE RENM SPACE " NEW"
                NAME 0 FNAME N @ 15 MOVE CR
       THEN
     ELSE LOOKUP 255 <>
           IF @ 0 FNAME SWAP 15 MOVE
           THEN
  THEN ;
*RENAME FORGET *RENAME


( * Copy tos blocks of the file in 'oname' to 'fname')
: *COPYALL 0 DO
```

Listing 1 continued on page 340

Listing 1 continued:

```
                  0 FNAME 0 TMP 5 MOVE
                  0 ONAME 0 FNAME 5 MOVE
                  VIDEO READ
                  0 TMP 0 FNAME 5 MOVE
                  VIDEO WRITE
            LOOP
    CLS 0 ONAME 5 TYPE
    SPACE " copied to" SPACE
    0 FNAME 5 TYPE CR
   ;
*COPYALL FORGET *COPYALL


( * Copy one file to another)
: *FCOPY SPACE " Copy from" NAME LOOKUP -1 =
    IF " * NO SUCH FILE" ENTER
       ELSE FSIZE BM1 C@ N1 !
         0 FNAME 0 ONAME 5 MOVE SPACE " To" NAME
         SPACE LOOKUP 255 =
           IF CR " (New File)" DPUTNM N1 @ COPYALL
              ELSE CR " (Copy over old file)" Y/N NOT
                 IF N1 @ COPYALL
                 THEN
           THEN
    THEN ;
*FCOPY FORGET *FCOPY


( * Print the blocks used by a given file name)
: *BLOCKS?
           NAME LOOKUP 255 <>
              IF CR " Blocks in use:" SPACE
                 DSKSZ 0 DO
                                I FON? BM2 C@ 0 <>
                                IF I T# SPACE
                                THEN
                            LOOP
              THEN
            CR ;
*BLOCKS? FORGET *BLOCKS?

( FORTHDOS Printer routines - header, pagesize, number, etc.)
: PIT ;  0 VARIABLE PAGESZ 0 VARIABLE SPC (" (C) P. Reece 1981"

0 VARIABLE PG 0 VARIABLE START VARIABLE KNT 64 CARRAY TITLE
: GET# CR " Lines/page" #IN PAGESZ ! CR BL 0 TITLE 64 FILL
  " Spacing" #IN SPC ! CR " Starting Page #" #IN PG ! CR
  " Title:" SPACE 0 TITLE 63 EXPECT CR ;
: HEAD KNT @ 0= IF " Page" PG ? SPACE
   30 ECHO 0 TITLE 64 TYPE 29 ECHO CR CR 1 PG +! THEN ;
: KNTDO SPC @ 1 DO 1 KNT +! CR LOOP ;
: GO CLS PCRT 0 KNT ! HEAD  BEGIN START @ FON? BM2 C@ 0 <>
  IF 16 0 DO I BM2 C@ LINE DROP 64 TYPE KNTDO KNT @ PAGESZ @ >=
              IF CR CR CR 7 ECHO KEY DROP 0 KNT ! HEAD THEN LOOP
  THEN 1 START +! START @ DSKSZ > IF 1 ELSE 0 THEN END ;
: *PSHOW NAME LOOKUP 255 <> IF GO CRT CRT CR " Finished"
  15 ECHO 176 CURSOR ! THEN CR ; *PSHOW FORGET PIT


(" Single Drive BLOCK copy - Peter Reece (c) 1980" : TASK ;
0 VARIABLE K  'S PAD - 1024 / 1024 * 1024 - K ! 0 VARIABLE FROM
K @ CONSTANT MAXSZ MAXSZ CARRAY TXT 0 VARIABLE TO 0 VARIABLE EN
: RD CLS 10 0 PTC 23 ECHO " Insert SOURCE Disk" ENTER
   WHILE N @ MAXSZ < END @ FROM @ >= AND PERFORM N @ TXT
   FROM @ RBLK 1024 N +! 12 0 PTC FROM ? " ->" 1 FROM +! PEND ;
: WT CLS 10 0 PTC 23 ECHO " Insert DESTINATION Disk" ENTER
   0 N ! WHILE N @ MAXSZ < K @ TO @ >= AND PERFORM N @
   TXT TO @ WBLK 1024 N +! 12 0 PTC " ->" TO ? 1 TO +! PEND ;
: CYCLE WHILE K @ TO @ >= PERFORM RD WT 0 N ! PEND ;
: *BCOPY CLS 5 0 PTC " START BLOCK#" #IN FROM ! CR " END BLOCK#
   #IN END ! CR " DESTINATION BLOCK#" #IN TO ! END @ FROM @ -
   TO @ + K ! CYCLE CLS " Bcopy Done" CR ; *BCOPY FORGET TASK


( * Same drive FILE copy - minimal RAM, so lots of swaps)
: *XCOPY DSAVE SPACE " Copy from" NAME LOOKUP -1 = ( source?
     IF " * NO SUCH FILE" ENTER                    ( not there
        ELSE DSAVE FSIZE BM1 C@ N1 !               ( get its sz
             0 FNAME 0 ONAME 5 MOVE SPACE " To" NAME
             N1 @ 0 DO                             ( 1 at a time
                   CR " Insert SOURCE Disk" ENTER MOUNT
                   0 FNAME 0 TMP 5 MOVE 0 ONAME 0 FNAME 5 MOVE
                   VIDEO READ 0 TMP 0 FNAME 5 MOVE
                   CR " Insert DESTINATION disk" ENTER MOUNT
                   I 0= IF LOOKUP 255 =            ( if a new file
                           IF DPUTNM THEN          ( build it in
                        THEN  VIDEO WRITE DSAVE ( then save it
             LOOP CLS " Xcopy Completed" CR
        THEN
     THEN ;    *XCOPY FORGET *XCOPY    (" (C) Peter Reece 1981"
```

The FORTHDOS Demonstration Program

The FORTHDOS demonstration program (see listing 2) enables you to easily familiarize yourself with all of the primitives (and two utilities—by way of example) described in the article on FORTHDOS. In addition, it illustrates how the basic primitives can be configured to use a shorter record length (here, 64 bytes per record) in a very simple manner. The demonstration program is an application program that illustrates some of the ways to issue calls to FORTHDOS and then deal with the results of those calls. The program has been designed for use on the TRS-80 Model I with 48K bytes of memory running the MMSFORTH system version 1.8. (If you have version 2.0, this program may require modification.)

Applications Programs

Before using the demonstration program, it is important that you realize the role of FORTHDOS in programming. FORTHDOS is a list of primitives that perform various functions in response to calls from a user-written program. Most primitives return status flags for use by the applications software. The software then uses those flags to determine subsequent action following the FORTHDOS call.

The demonstration program given here is an example of a very simple means of issuing calls to FORTHDOS and viewing the results. It is a straightforward applications program.

The program has been kept simple for ease in following the logic of accessing FORTHDOS. It should be noted, however, that the resulting limitations of the program are not limitations of FORTHDOS.

For example, upon selecting a sequential-write option from the command menu, the demonstration program makes a call to FORTHDOS to write the appropriate record to the file currently opened (i.e., in FNAME). FORTHDOS does so, returning status flags regarding the success of the write operation. It is the demonstration program, not FORTHDOS, that puts the entire block just accessed on the screen, ignoring end-of-file marks, for you to see more clearly what is going on. The DOS acts normally; it is the demonstration program that performs the apparently strange task (as a learning aid) of displaying an entire block of data—even if the block contains data from another file.

The demonstration program is designed as a simple and easy-to-follow application program that calls FORTHDOS primitives. As such, its simplicity may be misleading. Look carefully at the apparent mistakes you discover in the program. They exist for a reason—namely, to illustrate various approaches to calling the primitives. Remember, FORTH-DOS primitives perform transparent actions and return flags (in most cases) to indicate the results of those actions. What your applications program does with the results of FORTHDOS calls or how it uses them (as illustrated by the demonstration program) is strictly up to you.

How to Use the Program

To use this program, first make a backup copy of your MMSFORTH disk. Then type in and save this program (listing 2) on that disk. To use the disk, place it in drive 0 and boot the system. Load the demonstration program by typing { 20 12 LOAD }, then type FORTHDOS and press ENTER. The demonstration program command menu will be displayed on the screen (see figure 12).

Begin checkout by selecting item 1 on the command menu. This option will cause FORTHDOS to read the directory. When this has been done, select item 14 from the menu. This will list the files available for use by the program.

Records vs. Blocks

A word is in order regarding the program's ability to access and deal with 64-character records. FORTHDOS is quite versatile. It is really a series of subroutines callable by a user-written drive program (e.g., the demonstration program). As such, the record length is external to the primitive subroutines and may be controlled totally by the READ and WRITE calls from the user's program. For example, the routines DSKIO and WRITE1 in the program use a 64-character record and count 16 of these records per 1024-byte block (via the variable RREC). This record length could just as easily have been 16 bytes, with RREC counting 64 records before a new block is called into memory by FORTHDOS.

The examples in the program should enable the careful reader of both the article and code to configure his or her system for any record size or even variable record sizes. The program allows you to familiarize yourself with the innards of FORTHDOS. It also allows you to make mistakes and see the results of incorrect calls (potentially by your own software) to the FORTHDOS primitives.

For instance, if in reading to the end of a sequential file you forget to reset the file (item 18 in the menu), you will not be able to read an earlier record (unless you first CLOSE or RESET it). (Note that LIST, item 7, automatically resets the file prior to a list, then returns it to its original state once the listing is completed.) Experimentation will be the best teacher here.

Finally, unlike the wealth of comments and structured code of FORTHDOS as presented in the body of the artcile, this program (listing 2) has a very compact version of FORTHDOS. This is meant to be a run-time package for direct implementation on your system. To incorporate it directly into your own software, eliminate the menu and associated routines by deleting the following words and recompiling:

MENU1 MENU FORTHDOS TITLE

This will leave you with a core of FORTHDOS primitives compactly squeezed into a minimum number of screens and ready to use.

Listing 2: *FORTHDOS demonstration program. Once the program in listing 2a has been loaded, the demonstration program is started by executing the word FORTHDOS. This listing contains a slightly simplified version of the FORTHDOS program as given in listing 1. The differences are as follows: some constants and variables are precalculated to assume a 1-drive, 48K-byte system; the disk-resident utilities at the end of listing 1 are not included in listing 2; some definitions in listing 2 are slightly different from their counterparts in listing 1, although they are functionally the same; other definitions have been changed to reflect a 64-byte record size (see "The FORTHDOS Demonstration Program" text box). Also, in this listing, the apostrophe in the MMSFORTH word { 2' } (block 22) is actually an up-arrow symbol. Listing 2b (block 32) executes a 1-drive block copy routine.*

(2a)

```
BLOCK : 20

 (" FORTHDOS DEMO 1 - (C) Peter Reece 1981"      : DOS ;
 : CARRAY 0 CCONSTANT H +! ;CODE HL POP DE DAD PSH
 15 CARRAY BITMAP    15 CARRAY QMAP           ( Dos - bitmaps)
 15 CARRAY FNAME                              ( Dos - filename)
 1024 CARRAY DBUF                             ( Dos - directory buf)
 0 CVARIABLE RREC     0 CVARIABLE WREC        ( Dos - current recrd)
 0 VARIABLE RDBK      0 CVARIABLE WRBK        ( Dos - current block)
 0 CVARIABLE BM1      0 CVARIABLE BM2         ( Dos - dummy vars)
 0 VARIABLE N         0 VARIABLE M            ( Dos - dummy vars)
 0 VARIABLE 1SB                               ( Dos - 1st blk in fl)
 0 DBUF VARIABLE DADRS                        ( Dos - start of buf)
 0 CVARIABLE EOF                              ( Dos - end of file)
 31 CONSTANT BREAK                            ( Break key defntn)
 0 VARIABLE P 0 VARIABLE K 0 VARIABLE Q       ( Dummies for demo)
 64 CARRAY AR1 64 CARRAY AR2                  ( Dummies for demo)
 0 CVARIABLE F1                               ( Dummy for fsz1 demo)
BLOCK : 21

 (" FORTHDOS DEMO 2 - (C) Peter Reece 1981"
 ( * Put/clear a message on the bottom of the crt.)
 : S$ 0 DO 140 ECHO LOOP ;      : Z1AR BL 0 AR1 64 FILL ;
 : MSG 14 0 PTC 63 S$ 15 0 PTC 30 ECHO SPACE ;
 : CMSG ENTER 14 0 PTC 30 ECHO 15 0 PTC 30 ECHO ;

 ( * Here lie some general purpose utilities.)
 : T# <# # #S #> TYPE ;                     ( Type a formatted #)
 : DELAY 5000 0 DO LOOP ;                   ( Delay a bit)
 : NAME BL 0 FNAME 15 FILL MSG              ( Get file name)
   " FILENAME:" SPACE 0 FNAME 15 EXPECT CMSG ;
 : C+! DUP @ ROT + SWAP C! ;                ( Byte add)
 : C-! DUP C@ ROT - SWAP C! ;               ( Byte subtract)
 : -! DUP @ ROT - SWAP ! ;                  ( Word subtract)
 : TITLE CLS 0 12 PTC " FORTHDOS DEMONSTRATION DISKETTE"
   1 12 PTC 31 S$ 0 50 PTC " (C) P.Reece" ;
BLOCK : 22

 (" FORTHDOS DEMO 3 - (C) Peter Reece 1981"
 ( * Dos primitives.)
 : 2' DUP 0= IF DROP 1 ELSE 1 SWAP 0 DO 2* LOOP THEN ;
 : DGT DUP 8 / DUP ROT ROT 8* - SWAP DUP ROT 2' ;
 : DON DGT SWAP BITMAP C@ OR SWAP BITMAP C! ;
 : DOFF DGT BM2 C! BITMAP C@ 255 BM2 C@ - AND SWAP BITMAP C! ;
 : DON? 0 BM2 C! DUP DGT SWAP BITMAP C@ AND SWAP DROP 0=
   IF DROP ELSE BM2 C! THEN ; : DNXT 0 BM1 C! 85 1 DO I DON?
   BM2 C@ 0= I 1SB C@ >= AND IF I BM1 C! LEAVE THEN LOOP BM2 C@
   0 <> BM1 C@ 0= OR IF -1 BM2 C! MSG " THREAD FULL" CMSG THEN ;
 : DREAD DADRS @ 0 RBLK ;              : DWRITE DADRS @ 0 WBLK ;
 : DRD DADRS @ 0 BITMAP 15 MOVE ;      : DZONK 0 0 BITMAP 15 FILL ;
 : DWR 0 BITMAP DADRS @ 15 MOVE ;
 : MOUNT DZONK DREAD DRD ;             : DSAVE DWR DWRITE ;
 : REMOVE DSAVE FLUSH MSG " Remove disk now" CMSG ;
 : DINIT MOUNT 0 DADRS @ 1024 FILL DZONK ;
```

```
BLOCK : 23

 (" FORTHDOS DEMO 4 - (C) Peter Reece 1981"
 : LOOK1 -1 BM1 C! N @ C@ 0 FNAME C@ <> IF -1 BM1 C! ELSE
   15 0 DO I FNAME C@ N @ I + C@ =
       IF I BM1 C! ELSE -1 BM1 C! LEAVE THEN
   LOOP THEN BM1 C@ ;
 : LOOKUP DADRS @ 128 + N ! 14 0 DO LOOK1 255 =
   IF 64 N +! ELSE I BM1 C! LEAVE THEN LOOP BM1 C@ ;
 : DPUTNM LOOKUP 255 = IF DADRS @ 128 + N ! 14 0 DO N @ C@ 0=
   IF 0 FNAME N @ 15 MOVE LEAVE 0 N ! ELSE 64 N +! THEN LOOP
   N @ 0 <> IF MSG " FILE SPACE FULL" CMSG 22 M ! THEN THEN ;
 : DGTMAP LOOKUP 255 <> IF DADRS @ 128 + BM1 C@ 64* + 20 +
   DUP N ! 0 QMAP 15 MOVE THEN ;
 : DADD DGTMAP DNXT BM2 C@ -1 <> IF BM1 C@ DUP DON DGT SWAP QMAP
   C@ OR SWAP QMAP C! 0 QMAP N @ 15 MOVE BM1 C@ ELSE 0 THEN ;
 : NREC RDBK @ 1SB C@ - 16* RREC C@ + SPACE
   " (" T# " )" ENTER ;
BLOCK : 24

 (" FORTHDOS DEMO 5 - (C) Peter Reece 1981"
 ( * Dos primitives.)   : CLOSE BL 0 FNAME 15 FILL ;
 : RENM DADRS @ 128 + BM1 C@ 64* + N ! ;
 : FON? DUP 86 < IF DUP DGT SWAP QMAP C@ AND SWAP DROP 0=
   IF DROP 0 BM2 C! ELSE BM2 C! THEN ELSE DROP 0 BM2 C! THEN ;
 : KILL LOOKUP 255 <> IF DGTMAP 85 0 DO I FON? BM2 C@
   0 <> IF BM2 C@ DOFF THEN LOOP RENM 0 N @ 64 FILL CLOSE THEN ;
 : DTNM SPACE 0 FNAME 15 TYPE ;                  ( Print filenm)
 : FSZ1 DGTMAP BM1 C@ -1 <> IF 0 BM1 C! 85 0 DO I FON? BM2 C@ 0
   > IF 1 BM1 C+! I F1 C! THEN LOOP 0 ELSE 1 THEN ;
 : FSIZE FSZ1 0= IF BM1 C@ MSG T# " Blocks" CMSG THEN ;
 : FREE 0 BM1 C! 85 0 DO I DON? BM2 C@ 0 > IF 1 BM1 C+! THEN
   LOOP 85 BM1 C@ - 16* MSG T# SPACE " free records left" CMSG ;
 : BLOCKS? CLS 2 20 PTC " LIST OF BLOCKS IN" DTNM CR 63 S$ CR
   DGTMAP BM1 C@ 255 <> IF 85 0 DO I FON? BM2 C@ 0 >
   IF I . THEN LOOP THEN CR CR ENTER ;
BLOCK : 25

 (" FORTHDOS DEMO 6 - (C) Peter Reece 1981"
 ( * These routines read a 64-byte record from disk.)
 : 1STBK DGTMAP 85 0 DO I FON? BM2 C@   ( Get 1st block in fl)
   DUP 0 <> IF DUP RDBK ! 1SB C! LEAVE ELSE DROP THEN LOOP ;
 : MEOF MSG " END OF FILE REACHED" CMSG ;
 : GRDBK RDBK @ M ! DGTMAP BM1 C@ -1 <>
   IF BEGIN M @ FON? BM2 C@ 0 <> IF BM2 C@ RDBK ! 1 ELSE
   1 M +! 0 THEN M @ 85 > IF -1 M ! DROP 1 THEN END THEN ;
 : DSKIO RDBK @ 1+ 85 > IF MSG " DISK FULL" CMSG
   ELSE RREC C@ RDBK @ LINE DROP 0 AR1 64 MOVE
     1 RREC C+! 0 AR1 60 TYPE
     RREC C@ 15 > IF 0 RREC C! 1 RDBK +! GRDBK THEN
     EOF C@ 1 = IF MEOF THEN M @ -1 = IF 1 EOF C! MEOF THEN
     0 AR1 C@ 127 = IF 1 EOF C! MEOF THEN THEN ;
 : ZPNTRS 0 RREC C! 1STBK ;
 : READ MSG 14 0 PTC DTNM 15 0 PTC DSKIO 14 40 PTC NREC ;
```

Listing 2 continued on page 346

Listing 2 continued:

```
BLOCK : 26

 (" FORTHDOS DEMO 7 - (C) Peter Reece 1981"
 : RENAME DGTMAP N @ 20 - M ! MSG DTNM " to be renamed as:"
   SPACE Z1AR O AR1 15 EXPECT 15 O DO I AR1 C@ M @ I + C! LOOP
   O AR1 O FNAME 15 MOVE MSG " DONE" CMSG ;
 : RG 1SB C@ RDBK ! DUP 16 / DUP 16* ROT SWAP - RREC C!
   DUP O > IF O DO 1 RDBK +! GRDBK LOOP ELSE DROP THEN ;
 : SHOW MSG NAME LOOKUP 255 <> IF FSZ1 O= BM1 C@ O > AND IF RREC
 C@ P ! RDBK @ Q ! O RREC C! 1STBK CLS BEGIN DSKIO CR EOF C@
 ?KEY BREAK = OR END P @ RREC C! Q @ RDBK ! O EOF C! THEN THEN ;
 : PFILE MSG " Enable the printer" CMSG PCRT SHOW CRT ;
 : EOF? FSZ1 DROP O K ! F1 C@ BLOCK N ! 15 O DO I 16* N @ +
  C@ 127 = IF I K ! LEAVE THEN LOOP FSZ1 DROP BM1 C@ 16* K @ + ;
 : EOFMSG MSG " Last record is #" EOF? T# SPACE DTNM CMSG ;
 : RREAD MSG " Record number:" RDBK @ Q ! RREC C@ P ! #IN DUP
   EOF? > IF MSG " Past eof" DROP CMSG ELSE RG MSG DSKIO
   P @ RREC C! Q @ RDBK ! 14 40 PTC ENTER THEN ;

BLOCK : 27

 (" FORTHDOS DEMO 8 - (C) Peter Reece 1981"
 : FILES O FNAME O AR2 15 MOVE DADRS @ 128 + K !
   CLS O 23 PTC " Disk Directory" CR DADRS @ 64 + 50 TYPE
   CR 12 O DO K @ C@ O <> IF K @ O FNAME 15 MOVE O FNAME 15 TYPE
   10 SPACES FSZ1 O= IF BM1 C@ 16* T# SPACE " records" LOOKUP
   DROP RENM N @ 63 + C@ 170 = IF 5 SPACES " Write protected"
   THEN CR THEN THEN 64 K +! LOOP O AR2 O FNAME 15 MOVE FREE ;
 : DSET MSG " Build a new directory" Y/N NOT IF CLS MSG DINIT
   O DON 1 DON O DADRS @ 1024 FILL MSG " Description:" SPACE
   O AR1 60 EXPECT O AR1 DADRS @ 64 + 60 MOVE 42 DADRS @ 20 + 5
   FILL DSAVE ELSE THEN ; : GDSK MSG " INSERT DATA DISK" CMSG
     O PBLK ! MOUNT DADRS @ 20 + C@ 42 <> IF CLS 23 ECHO
     CR CR 5 SPACES " UNINITIALIZED DISK" DSET THEN ;
 : PROT MSG " Protect" DTNM LOOKUP 255 <> IF Y/N NOT
   IF RENM 170 N @ 63 + C! ELSE RENM O N @ 63 + C! THEN
   ELSE MSG " NO SUCH FILE" THEN CMSG ;

BLOCK : 28

 (" FORTHDOS DEMO 9 - (C) Peter Reece 1981"
 ( * These routines perform write operations.)
 : WCK 1 RREC C+! RREC C@ 15 > IF O RREC C! 1 RDBK +! FSZ1
   DROP F1 C@ RDBK @ < IF DADD RDBK ! THEN THEN ;
 : WSHOW K @ 15360 1024 MOVE MSG " BLOCK:" RDBK @ T# ;
 : WRITE1 1SB C@ O= IF DADD DUP 1SB C! RDBK ! O RREC C! THEN
   RDBK @ BLOCK K ! WSHOW O AR1 RREC C@ 64* K @ + 64 MOVE RENM
   N @ 63 + C@ 170 = IF MSG " Write protected" ELSE K @ RDBK @
   WBLK WSHOW FLUSH WCK MSG " Written to rec#" THEN NREC ;
 : WRITE MSG " Write what:" SPACE Z1AR O AR1 64 EXPECT WRITE1 ;
 : RWRITE MSG " Record #" RDBK @ Q ! RREC C@ P ! #IN DUP O >
   IF 1 - THEN DUP EOF? > IF MSG " Past eof" DROP CMSG
   ELSE RG MSG DSKIO DELAY WRITE THEN ;
 ( * More menu commands.)
 : MENU1 13 O PTC " 23 - Write EOF mark" 13 32 PTC
   " 24 -- END this demo" ;

BLOCK : 29

 (" FORTHDOS DEMO 10 - (C) Peter Reece 1981"
 ( * Open or create a file.)
 : MAKE O 1SB C! NAME DPUTNM O RREC C! 1STBK ;
 ( * Copy a file to another file, same disk.)
 : FCOPY MSG " COPY FILE" DELAY Z1AR O FNAME O AR1 15 MOVE
   EOF? 16 / K ! O 1SB C! O EOF C! MAKE
   O FNAME O AR2 15 MOVE O AR1 O FNAME 15 MOVE ZPNTRS
       WHILE K @ O > M @ -1 <> AND ?KEY BREAK <> AND
       PERFORM 15360 RDBK @ RBLK
       O AR2 O FNAME 15 MOVE   15360 DADD WBLK FLUSH
       O AR1 O FNAME 15 MOVE   1 RDBK +! GRDBK
       MSG " FROM BLOCK" RDBK C@ T# DELAY 1 K -!
   PEND O AR1 O FNAME 15 MOVE O EOF C! O M ! ZPNTRS CLS
   MSG " COPY COMPLETED" CMSG ;
 : CBLK MSG " To max space: select #24," SPACE
   " type 'FORGET DOS 52 LOAD'" CMSG ;

BLOCK : 30

 (" FORTHDOS DEMO 11 - (C) Peter Reece 1981"
 : MENU TITLE 2 O PTC " 1 - MOUNT a disk" 2 32 PTC " 2 - " SPACE
   " UNMOUNT a disk" 3 O PTC " 3 - OPEN (or create) a file" 3
  32 PTC " 4 - CLOSE a file" 4 O PTC " 5 - Seq READ a file" 4
   32 PTC " 6 - Seq WRITE a file" 5 O PTC " 7 - LIST a file"
  SPACE " (CLEAR to stop)" 5 32 PTC " 8 - LIST blocks" 6 O PTC
   " 9 - Random READ a record" 6 32 PTC " 10 - Random"
   SPACE " WRITE a record" 7 O PTC " 11 - RENAME a file"
   7 32 PTC " 12 - KILL a file" 8 O PTC " 13 - Show"
   SPACE " FREE disk space" 8 32 PTC " 14 - Show disk DIRECTORY"
   9 O PTC " 15 - COPY to another file" 9 32 PTC " 16 - COPY"
   SPACE " sequential blocks" 10 O PTC " 17 - PRINT a file"
   10 32 PTC " 18 - RESET Seq File to Begining" 11 O PTC
   " 19 - Write PROTECT a file" 11 32 PTC " 20 - Show file SIZE"
   12 O PTC " 21 - CURRENT seq rec number" 12 32 PTC
   " 22 - Find LAST record" MENU1 MSG " Which number:" ;

BLOCK : 31

 (" FORTHDOS DEMO 12 - (C) Peter Reece 1981"
 : ENDIT -5 M ! ;
 : RESET MSG O EOF C! ZPNTRS MSG DTNM SPACE " reset" DELAY ;
 : WEOF MSG " Write eof to current record" Y/N NOT IF
   127 O AR1 C! 127 1 AR1 C! WRITE1 THEN CMSG ;
 ( * Command driver rests here.)
 : FORTHDOS O PBLK ! BL O FNAME 15 FILL Z1AR ZPNTRS
   BEGIN MENU O M ! 15 46 PTC DTNM 15 16 PTC #IN
      NCASE 1    2      3     4      5      6      7     8
            9    10     11    12     13     14     15    16
            17   18     19    20     21     22     23    24 "
            GDSK  REMOVE MAKE   CLOSE READ   WRITE  SHOW  BLOCKS?
            RREAD RWRITE RENAME KILL  FREE   FILES  FCOPY CBLK
            PFILE RESET  PROT   FSIZE NREC   EOFMSG WEOF  ENDIT
     CASEND M @ -5 =
   END CLS 8 17 PTC " END OF FORTHDOS DEMO" 15 O PTC ;

BLOCK : 32
```

(2b)

```
 ( 1 DRIVE BLOCK COPY - PETER REECE/80) : TASK ;
 : CARRAY O CCONSTANT H +! ;CODE HL POP DE DAD PSH
 O VARIABLE K           PAD 1024 / 1024 * 1024 - K !
 K @ CONSTANT MAXSZ     MAXSZ CARRAY TXT            O VARIABLE N
 O VARIABLE FROM        O VARIABLE END              O VARIABLE TO
 : READ CLS 10 O PTC 23 ECHO " Insert SOURCE disk" ENTER
     WHILE N @ MAXSZ < END @ FROM @ >= AND PERFORM N @ TXT
     FROM @ RBLK 1024 N +! 12 O PTC FROM ? " ->" 1 FROM +! PEND ;
 : WRITE CLS 10 O PTC 23 ECHO " Insert DESTINATION disk"
     ENTER O N ! WHILE N @ MAXSZ < K @ TO @ >= AND PERFORM N @
     TXT TO @ WBLK 1024 N +! 12 O PTC " ->" TO ? 1 TO +! PEND ;
 : CYCLE WHILE K @ TO @ >= PERFORM READ WRITE O N ! PEND ;
 : START CLS 5 O PTC " Start Block#" #IN FROM ! CR " End Block#"
     #IN END ! CR " Destination Block#" #IN TO ! END @ FROM @ -
     TO @ + K ! CR CYCLE CLS " **Done to" TO @ 1 - . " **" CR ;
 START FORGET TASK
```

FORTHDOS COMMANDS

Help.........type this listing	Setdir......set up directory
Mount.......mount disk	Assign....set start for file
Remove....remove disk	Run.........compile a file
Files.........show all files	Read.......sequential read
Make........create a file	Write......sequential write
Name.......set up a file	Read.......random read
Kill...........delete a file	Rwrite.....random write
Fsize........get size of file	Copyall...copy a file
Type.........type a file	Lookup...does a file exist
Rename....rename a file	Prot?.......is it protected
Lock.........lock out records	Dinit........initialize a directory
Free.........print free space	Dsave.....save a directory
Fcopy.......on disk file copy	Mount.....get a directory
Protect.....write protect	Dputnm..save a file name
Unprotect.unwrite protect	Xcopy.....off disk file copy
Ptype........format, then print	Blocks?..list files record numbers
Time.........print time of day	Timeset..set time of day
Bcopy.......copy by record numbers	DADD.....add record to file bit map
T#...type formatted number	

Table 2: *An abbreviated list of FORTHDOS commands*

Text continued from page 332:

the part of FORTHDOS memory which contains the file names and bit maps. This layout may be adjusted by the DOS to contain as many files and file bit maps as will fit into 1024 bytes. For example, if there are 11 bytes per bit map, 6 bytes per file name, and 11 bytes for DOS bit map, there is space for a maximum of 64 ((1024−11)/17) open files per 35-track disk. To simplify the layout of the following DOS program, I have lowered this value to 14 files per 35-track disk (86K bytes). This number has proved to be sufficient for my own needs.

While there is room to have a single DOS memory area contain files for up to four 35-track drives, you can at your option have a separate "DOS directory" area on each drive. That area is swapped into memory when the pertinent drive is accessed. In the program discussed below, I have followed this latter scheme for ease of explanation. Figure 8 illustrates this swapping.

Building a Directory

The SETDIR command is a FORTHDOS utility which interactively allows you to customize the setup of a directory. It then allocates space on disk for the directory (at a default record number) and initializes the DOS RAM and bit maps.

One interesting function of the SETDIR command allows you to lock out any records which you do not wish to be available to FORTHDOS for later use. This may be done in two ways. SETDIR will first prompt for any record numbers which you wish to be locked out. It will then prompt for a record number below which FORTHDOS is not to be allowed to use for files. This latter feature can be used to automatically lock out whole areas of the disk or, in a multidrive system, entire drives.

This is done in a remarkably simple manner. Suppose that during directory creation (via SETDIR) you indicate that all records below number X are to be locked out. FORTHDOS simply uses the DON primitive (see "Determining Record Status" below) to set 1s into the corresponding record numbers of DOS bit map. Any future calls to DNXT will find these records to be in use already. To protect an entire file, however, FORTHDOS uses a different approach.

Write-Protecting a File

A bit in a file bit map is assigned to indicate the write-protect status of all record numbers active in that bit map. All FORTHDOS primitives that write information to files first check the status of this bit before attempting a write operation. If the bit is 1, no information will be written to the file. (FORTHDOS will return an error indication to the user program if the file has been write-protected.) The UN-

Tired Of Your GENERAL LEDGER?



★ THE ULTIMATE PERSONAL CHECK REGISTER
★ A PROFESSIONAL ACCOUNTING SYSTEM
★ A PERSONAL FINANCIAL MANAGER
★ A SMALL BUSINESS ACCOUNTING SYSTEM
★ A COMPLETE GENERAL LEDGER

FOR YOUR TRS-80 MODEL I, II, III or COLOR COMPUTER • APPLE II • I.B.M. • XEROX • ATARI
ALL MICROSOFT BASIC COMPUTERS

HOW IT WORKS . . . .

VERSALEDGER is a complete accounting system that grows as you or your business grows. To start, your VERSALEDGER acts as a simple method of keeping track of your checkbook. Just enter your check number, date and to whom the check is made out to. As you or your business grows, you may add more details to your transactions . . . . account number, detailed account explanations, etc.

- VERSALEDGER can give you an instant cash balance at anytime. **(IF YOU WANT IT TO)**
- VERSALEDGER can be used as a small personal checkbook register. **(IF YOU WANT IT TO)**
- VERSALEDGER can be used to run your million dollar corporation. **(IF YOU WANT IT TO)**
- VERSALEDGER prints checks. **(IF YOU WANT IT TO)**
- VERSALEDGER stores all check information forever. **(IF YOU WANT IT TO)**
- VERSALEDGER can handle more than one checkbook. **(IF YOU WANT IT TO)**
- VERSALEDGER can be used to replace a general ledger. **(IF YOU WANT IT TO)**

VERSALEDGER

YOUR FIRM NAME HERE
CHECK Nº 1001
DATE
AMOUNT
PAY TO THE ORDER OF

INTRODUCTORY PRICE
$99.95

- VERSALEDGER HAS AN ALMOST UNLIMITED CAPACITY . . . .
  (300 checks per month on single density 5¼" disk drives such as the TRS-80 Model-I)
  (500 checks per month on the Apple II)
  (2400 checks per month on the TRS-80 Model III)
  (6000 checks per month on the TRS-80 Model II)
  (3000 checks per month on single density 8" CP/M)
- VERSALEDGER will soon have an add-on payroll package. **(IF YOU NEED IT)**

— CAN BE USED WITH 1 or MORE DISK DRIVES —

VERSALEDGER HAS BEEN CREATED WITH THE FIRST TIME COMPUTER USER IN MIND

COMPUTRONICS
MATHEMATICAL APPLICATIONS SERVICE

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

★ ADD $3.00 FOR SHIPPING IN UPS AREAS
★ ADD $4.00 FOR C.O.D. OR NON-UPS AREAS
★ ADD $5.00 TO CANADA AND MEXICO
★ ADD PROPER POSTAGE OUTSIDE U.S., CANADA & MEXICO





(914) 425-1535

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

*** ALL PRICES & SPECIFICATIONS SUBJECT TO CHANGE ***

Circle 192 on inquiry card.

```
BIT NUMBERS      | 1   2   3   4   5 • • • |
 DOS BIT MAP:      1   0   0   0   0 • • •

1) CALL DNXT TO DETERMINE THE NEXT FREE RECORD
   AVAILABLE. DNXT RETURNS RECORD 2.

2) CALL DON TO SET THE RECORD NUMBER RETURNED
   BY DNXT TO A 1 (i.e., 'IN USE'). BIT MAP NOW:
                   1   1   0   0   0

3) CALL |DON?| WITH A 2 AS THE ENTRY VALUE. |DON?|
   RETURNS A 1, INDICATING THAT RECORD 2 IS IN USE.
   CALL |DON?| WITH A 3 AS THE ENTRY VALUE; AND
   |DON?| RETURNS A 0, INDICATING THAT RECORD 3
   IS AVAILABLE.

4) CALL DOFF WITH A 2 AS THE ENTRY VALUE, AND
   RECORD 2 IS FREED FOR FUTURE USE:
                   1   0   0   0   0
```

Figure 9: *Using DON, DON?, and DOFF.*

```
a) RECORDS IN USE      ORANGE:   100, 101, 102, 105
   AT FIRST            PEAR:     96, 97, 98, 99
                       APPLE:    90, 91, 95
                       DOS:      0, 1 → 100

                       ORANGE:   100, 101, 102, 105
b) AFTER KILLING       APPLE:    90, 91, 95
   THE FILE PEAR       DOS:      0, 1 → 95, 100

                       ORANGE:   100, 101, 102, 105, 96
c) AFTER DADDOING      APPLE:    90, 91, 96
   TO ORANGE           DOS:      0, 1 → 96, 100
```

Figure 10: *Killing a file. This shows the results of removing the PEAR file from the disk.*

FILE1	*LINK BYTES* (TO/FROM) (e.g., RECORD 4 LINKS TO 8)	TRACK	HEAD MOVEMENT
RECORD 4	8	2	LITTLE
RECORD 8	72/4	4	LITTLE
RECORD 72	20/8	30	LOTS
RECORD 20	10/72	15	LOTS
RECORD 10	22/20	7	SOME
RECORD 22	85/10	17	SOME
RECORD 85	22/4	35	LOTS

Figure 11: *Link-listed file chains. To read FILE1, the disk head has to cross over 43 tracks for only 3 records.*

PROTECT command writes a 0 to the write-protect bit for the appropriate file. Since this bit is checked before any other write operations are performed, the delay time to check for write-protect status is negligible while the benefits of being able to write-protect individual files at will are many.

Printing a Directory and Determining File Size

The write-protect status of all files on the disk is always reported whenever the FILES command is used to print a directory listing to the terminal. In addition, other DOS information such as file name, size, free disk space, disk comment field, and amount of RAM is also given.

Calculating file size for a directory listing is straightforward. First, the number of 1s in a file bit map are added. The sum is the number of records (or size) of the file. Similarly, to calculate the number of free records remaining on disk, the number of 1s in the DOS bit map are summed. This number is then subtracted from the variable DSKSZ to determine the number of free records remaining. DSKSZ is in turn calculated by the following formula:

$$R = \mathrm{INT}((T * S)/100 * D$$

where R is the number of records per system, T is the number of tracks on the disk, S is the record size, and D is the number of disk drives. The INT function in the formula rounds down the quotient $(T * S)/100$ to an integer.

The manner in which FORTHDOS determines whether a given record bit in the file bit map is a 1 is interesting, given that FORTH is a high-level language which lacks bit manipulation capability. To do this, FORTHDOS makes use of three primitives— DON ,{ DON? } , and DOFF . [*"Primitive" here means an MMSFORTH word that performs an elementary function frequently used by later words in the system. . . .* **GW**] Since these three primitives are used by practically every other primitive in FORTHDOS to determine record status, it will be useful to investigate their use.

Determining Record Status

Look at the DON, DOFF, and DON? primitives in the program listing; then look at figure 9. In the example, DON (disk access on) turns on the bit in the bit map which corresponds to the record number being accessed by the file. This means that the file now "owns" that record, and no other file may write to it unless it is reclaimed by the DOFF (disk access off) primitive. DON? is used to return the record's status (on or off) to other primitives. For instance, DNXT makes frequent use of DON? to scan the DOS bit map when seeking a free record to give to a file.

These three primitives translate the calling record number according to the following formula:

$$2^{[\text{mod } r/n]}$$


where r is the record number, n is the number of bytes in the file bit map, and [mod (r/n)] is the remainder of dividing r by n. This has the effect of translating the calling record number into a power of 2 and hence into a bit position within the 11 bytes of the bit map. (In the FORTHDOS listing, 8 bytes are used simply because that is how my own personal system is set up.)

You might argue that it is easier and faster to resort to machine language and simply use a bit rotation command to access more rapidly the status of the appropriate bit. However, for the purposes of maintaining generality in this article I have instead given a high-level language solution in the listing. It works almost as well as a machine-language implementation of this part of FORTHDOS. You can translate the command to the lower-level language of your choice if you wish to increase the overall speed of FORTHDOS through these central primitives.

File Deletion and Allocation

Having followed the development of FORTHDOS thus far, you should have a pretty good idea of the strategies used, but let's review a couple of points for further clarification. As mentioned earlier, many DOS systems use an allocation scheme to adjust file space periodical-

RM/COBOL[TM 1] MAKES IT ACROSS!



...FROM ONE OPERATING SYSTEM TO ANOTHER! A VITAL WAY TO PROTECT YOUR SOFTWARE INVESTMENT FOR THE FUTURE!!

The RM/COBOL language runs on more different Operating Systems and more different-sized computers than any other similar language. For starters, it runs on NCR and TI minicomputers and, in the micro field, on the CP/M[2], MP/M[2], CP/M86[2], MP/M-86[2], TRSDOS[3], OASIS[4], MOASIS[4], and UNIX[5], (ONYX version) Operating Systems . . . to mention only a few.

RM/COBOL and CRT![TM 6] from CYBERNETICS ARE GOING STEADY...



...AND YOU'RE GONNA LOVE 'EM TOO!!

Use your computer to program itself. **CRT!** (Cobol Reprogramming Tool!) from Cybernetics is a program generator for RM/COBOL that produces error-free RM/COBOL source programs for data input, file maintenance, and report printing programs.

A full feature interactive program generator, not a subset! **Call Now!** 714/848-1922.

Until now, serious business software of the scope and flexibility seen in the minicomputer world has not been available on micros. RM/COBOL now allows transfer of such software with a minimum of fuss.

We have participated in such a mini-to-micro transfer of a major set of general business software . . . using RM/COBOL as the transfer mechanism, of course. Running on literally thousands of minicomputers, these refined, enhanced, and proven software packages cover A/R, A/P, G/L, P/R, Order Entry (with Invoicing and Inventory Control) as well as Sales Analysis. The Packages define a new level of achievement for features and flexibility in micro applications software and offer top quality at a reasonable price.

For immediate information, call 714/848-1922 for your complete product descriptions.

Trademarks of:
1-Ryan-McFarland Corp.; 2-Digital Research, Inc.; 3-Tandy Corp.; 4-Phase One Systems, Inc.; 5-Bell Telephone Laboratories, Inc.; 6-Cybernetics, Inc.



8041 NEWMAN AVE., SUITE 208
HUNTINGTON BEACH, CA 92647
714/848-1922

ly so as to maximize contiguous blocks of records. Another reason for periodically using such an adjustment is to clean up empty records.

To understand what this means, look at parts a, b, and c in figure 10. Figure 10a shows the file ORANGE containing four entries in its bit map; records 100, 101, 102, and 105 are in use. The DOS bit map indicates that all records below 100 are in use by other files. The file named PEAR occupies records 96 through 99, and the file APPLE takes records 90, 91, and 95.

Now look at figure 10b. Here, the FORTHDOS command KILL has been used to reclaim records 96, 97, and 98, thereby effectively deleting the file PEAR from disk. (KILL also deletes the name from the directory and performs a number of other housekeeping chores.) In figure 10c, a sequential write is being made to the file ORANGE by issuing a call to the FORTHDOS primitive WRITE. WRITE in turn calls DADD to find the next free block on the disk (through the DNXT primitive) and then return this value to WRITE for I/O transfer of the data in BUFF to disk. A problem arises if we stick to the scheme described (using the first record with a bit-map bit of 0). DNXT will return the value 96 to WRITE, since this was the first free block it found when scanning the DOS bit map, seeking a bit whose value is 0 (i.e., record not in use). This would mean that WRITE would write to record number 96, then 97, 98, 99, and finally 106 as more information is written to the disk.

If this scheme were used, the ORANGE bit map would look like this following the deletion of the file PEAR and five calls to the WRITE primitive:

96 97 98 99 100 101 102 105 106

In addition, this is the order in which records would be read from the file. But this would be incorrect. The true record order is:

100 101 102 105 96 97 98 99 106

There is no way that a simple bit-map scheme can know that record 96 comes after record 105.

FORTHDOS avoids this problem by specifying that no new record added to a FORTHDOS file can have a record number lower than the highest record number already allocated to that file. This ensures that the correct, logical order of records will be given by a series of increasing record numbers. The CVARIABLE named 1SB makes sure this occurs.

Even this method can, however, lead to a more subtle problem. To understand why, let's study a different approach to preserving continuity in a file, that of link-listed record chains.

Link-Listed Records

Link-listing in this context means that whenever a record is written, 2 of its bytes are used to point to the previous record number, and 2 point to the next record (if any). Hence, for a 350-record disk, we are looking at an extra 1400 bytes of storage per disk to maintain the linked chain (or 344 bytes for FORTH, where there are 86 records (blocks) per disk.

While this concept is relatively simple, it is important in any type of link listing to keep the chain from spanning too many different tracks. Otherwise disk-head movement can become excessive as more and more files are killed and created. The disk's seek action across tracks to follow a chain can become slow and "chunky," as figure 11 demonstrates. Linked pointers tend to cause a lot of disk-head movement when the physical distance between the linked records is large, as is the case when several files are killed between writes to the current file.

The scheme outlined so far for having FORTHDOS maintain logical integrity of a file handles two of the link-listed scheme's three problems. First, FORTHDOS requires fewer bytes on disk to handle record allocations. It therefore avoids the problem of needing extra storage. Second, in a

In Los Angeles, your great escape could take place in minutes.

As a Data Processing specialist at Northrop, you'll surround yourself with the benefits of a climate and location that lets you enjoy it all -- the arts, educational opportunities and the great outdoors. Every day. All year round.

Located in Southern California, Northrop offers the professional opportunities you seek plus the flexibility of lifestyle that makes hours off the job exceptionally pleasurable. And, you'll appreciate our location with easy access to beach, desert, and mountains.

If you're up for the challenge of membership in a department that supports corporate information systems activities at every level, look into career opportunities at Northrop.

Make the Great Escape that could last a life time.

Low Desert – 45 min.
High desert – 98 min.
Beaches – 10 min.
Forest – 25 min.
Mountains – 30 min.
Big mountains – 40 min.
Very big mountains – 240 min.

Skiing – 70 min.
Better skiing – 180 min.
Sailing – 15 min.
Golf – 17 min.
Running – change your shoes
Cricket – 23 min.
Disneyland – 45 min.

Hollywood Bowl – 45 min.
Universities – 30 min.
Surfing – 10 min.
Knott's Berry Farm – 45 min.
Rollerskating – change your shoes again
Universal Studios – 50 min.

Scientific Applications Programmer Analysts
Experience with IBM 3033, Engineering and Graphics Applications, FORTRAN.

MVS Systems Programmers
Using SMP4, TSO and SPF maintenance tools.

Computer Operations Personnel
Console Operators, Control Clerks, Tape Librarians.

Numerical Control Systems Support
Knowledge of IBM, APT-AC systems, FORTRAN, ASSEMBLY and familiarity with numerical control environment.

Data Base Analysts
Experience in IMS Data Base and Data Communications.

Business Applications Programmers
To design and maintain business, finance, and manufacturing applications on large scale IBM computers.

Documentation Control Analysts
Analyze, coordinate and develop programmer and operations documentation for business applications.

We will arrange a personal interview for you. We will fly you to California, travel and accommodations paid, or we will send a representative to your location. Investigate the opportunities outlined above by sending your resume to:

Barbara Nettles, Dept. NDP-BY 2851
P.O. Box 4625, Long Beach, CA 90804

NORTHROP

Making advanced technology work

Northrop Corporate Data Processing Center
Equal Opportunity Employer M/F/H / Proof of U.S. Citizenship Required

Circle 301 on inquiry card.

```
                FORTHDOS DEMONSTRATION DISKETTE          (C) P.Reece
                ...............................
1 - MOUNT a disk                          2 -  UNMOUNT a disk
3 - OPEN (or create) a file               4 - CLOSE a file
5 - Seq READ a file                       6 - Seq WRITE a file
7 - LIST a file (CLEAR to stop)           8 - LIST blocks
9 - Random READ a record                  10 - Random WRITE a record
11 - RENAME a file                        12 - KILL a file
13 - Show FREE disk space                 14 - Show disk DIRECTORY
15 - COPY to another file                 16 - COPY sequential blocks
17 - PRINT a file                         18 - RESET Seq File to Begining
19 - Write PROTECT a file                 20 - Show file SIZE
21 - CURRENT seq rec number               22 - Find LAST record
23 - Write EOF mark                       24 - END this demo
.......................................................................
 Which number:    ?
```

Figure 12: *Screen display of commands for the FORTHDOS demonstration program.*

On Converting FORTHDOS to fig-FORTH

Since a large part of the FORTH community uses the version standardized by the FORTH Interest Group (fig), I have included some notes about MMSFORTH that would help you convert FORTHDOS to fig-FORTH or other versions of FORTH. Peter Reece's thoughtful design has minimized the number of FORTH words that might not be in other FORTH dialects, but here is some information that might not be obvious to non-MMSFORTH users:

- *CCONSTANT and CVARIABLE are like CONSTANT and VARIABLE except that they store a simple 8-bit value (rather than a 16-bit value). CONSTANT and VARIABLE can probably be substituted without harm.*
- *ARRAY defines a one-dimensional array of 16-bit values. CARRAY defines a one-dimensional array of 8-bit variables. Both of these can easily be simulated using the { <BUILDS ... DOES> } construct in FORTH.*
- *The MMSFORTH word { " }, when used at the beginning of a string to be printed, is replaced by { ." } in fig-FORTH.*
- *The { NCASE ... " ... CASEND } construct is best explained by example. The FORTH phrase { NCASE 22 60 114 " WORD22 WORD60 WORD114 CASEND }. If the number on top of the stack is 22, the word CASE22 is executed; if it is 60, CASE60 is executed; if it is 114, CASE114 is executed. If the number is not any of these, control passes to the word after CASEND . One simple though inelegant substitution is a series of nested IF statements.*
- *The MMSFORTH { BEGIN ... END } construct is equivalent to the fig-FORTH { BEGIN... UNTIL } construct.*
- *The MMSFORTH word Y/N prints "(Y/N)?" and waits until either the Y or N key is pressed. In the former case, a 1 is put on the top of the stack; in the latter, 0 is put on top of the stack.*

*I hope the above information makes the conversion easier....*GW

link-listed chain, if one record in the chain is lost (the unhappily common lot of small systems) the entire chain integrity is lost. FORTHDOS keeps all file-record pointers in a memory-resident bit map (a copy of which is stored on the disk), thereby largely avoiding this problem.

The third problem: excessive head movement occurs if files are killed as described above. The solution is to reallocate space on a disk. As figure 11 indicates, the head-movement problem seems likely to occur with most DOSes. Mainframe vendors have hit upon the solution of periodically reallocating disks to decrease the number of non-contiguous records.

The method, used by mainframe computers, involves gathering records scattered throughout the disk into an unused portion of that disk. (These portions are contiguous.) Then the original file(s) is destroyed, and the new file, now in a contiguous area, is used. (Actually, more complex methods are applied, but this is the essence of the scheme.)

FORTHDOS uses a similar system. If the disk heads seem to be moving excessively (listen to them) while typing a file, or if FORTHDOS returns from a disk-write operation with the THREAD FULL message, it is probably time to use the FORTHDOS utility FCOPY (or XCOPY or BCOPY; see table 1). Reallocating with FCOPY is simple enough. Assuming enough contiguous records are on the disk to hold the file you are copying, FCOPY will pull all the records from a scattered file and neatly place them within the new file area in close physical proximity. It will then KILL the old file. The file will have been reallocated to a contiguous area on the disk, which will probably relieve disk-head movement and file-full problems.

This very simple technique can be done to all files on a disk by simply FCOPYing a disk full of files to an empty disk. The new disk will then consist of files whose records are all in contiguous areas. This solution to the allocation problem is easy to perform and memory efficient; if done periodically, it will speed up your disk operation.

FORTHODS in Use

By now, you should have a sufficiently good idea of how FORTHDOS works to be able to use the listing to understand the workings of other commands and features. We can now look at an actual application of FORTHDOS.

Assuming FORTHDOS has been loaded into RAM, you would first MOUNT a formatted disk and interactively initialize it by issuing the SETDIR command. Next, you might create a file for further use by issuing the MAKE command either from the terminal or through transparent calls from a program. Having created some files, you might next write information to one of them sequentially by filling the I/O buffer BUFF and making repeated calls to WRITE. This would probably be done through calls to FORTHDOS from within a user program.

To look at the contents of the file(s) just written, issue a TYPE command from your program or directly from the terminal. To get a formatted listing on the system printer, you can make a call to the PTYPE utility, which would output the file to the printer with page numbers, titles, etc.

At this point, you may wish to

query the disk contents so far. To do this, you type FILES; file names, sizes, space allocations, comments, free space, RAM usage, time of day, etc. will appear on the terminal. To protect any files from subsequent inadvertent writing by a program, you could type PROTECT plus the file name. No further writing could then be done to the protected file until UNPROTECT was issued for that file.

Suppose a disk hardware error occurred during a WRITE, putting bad data and checksums into a record. To prevent FORTHDOS from accessing that record in the future, the LOCK command could be given. This would lock out that record from any subsequent read/write operations by FORTHDOS. To make a backup of a file, you could issue the FCOPY command (or XCOPY if copying to a different disk on the *same* drive), which will prompt for information prior to automatically performing the copy. Now that a copy has been made, you might wish to rename some of the old files. To do so, you would issue the RENAME command for a given file. At this point, you might wish for help with the FORTHDOS commands. Assistance can be obtained at any time by simply typing HELP on the terminal or from within a program.

The preceding discussion should give you some idea of the actual usage of FORTHDOS. The other commands in the system are just as easy to use. Some are issued from user software, some by you directly, and others transparently without your knowledge. At the end of the session, you *must* type REMOVE (or have your program call the primitive DSAVE) to ensure that the directory will be saved to disk.

Conclusion

FORTHDOS is a simple but effective single-user DOS. Since it is modular, only the modules required for a given application need to be stored in RAM. This makes FORTHDOS a "tight" and straightforward system. For all its simplicity, it gives the FORTH user all of the capabilities found in most microcomputer DOSes but without the disadvantages of complex structures or high system overheads.

I have been using FORTHDOS for over a year now. Most of its use has been as an integral part of a word processor (which I used, among other things, to write this article). Even after a year of considerable use, I have found no errors in the software, and it gives me all the advantages of a conventional DOS with none of the disadvantages of the traditional "blocks" storage system in FORTH. An added feature: this system remains compatible with the concept of blocks. At any time, I can still edit any block of a file with a conventional FORTH block editor.

FORTHDOS is easily understood (after a little study and experimentation) and easily modified to suit your needs. I hope that you will find it as practical and enjoyable as I have. ■

Now you can do all accounting with...



the filing, typing and

Silicon Office is the latest microcomputer software program from the Bristol Software Factory.

Designed specifically for use with the Commodore PET 8096, it'll help you run your office with the minimum amount of effort and maximum efficiency.

Think of it like three normal software packages in one, each separate package totally interactive with the other.

For around $7,000, you can have the complete electronic office, the solution to practically all your business problems. The price includes Commodore hardware, a high quality daisy wheel printer and Silicon Office software.

Silicon Office is made up from a flexible information management system which lets you create and maintain an extensive filing arrangement. Allowing you to search quickly through your records, making cross references between files in order to gain the facts you require.

A highly sophisticated word processing program allows you to generate letters, documents and reports. Letting secretaries get on with the more important tasks.

And a fully comprehensive calculator means you can handle all the number crunching you're ever likely to do in a business situation. Leaving the accounts department to concentrate on more profitable things.

But that's not all by any means.

Silicon Office also has a special programmability feature which means you or your dealer can expand and tailor the Silicon Office program to your business.

When Silicon Office is used in an everyday business situation, certain command sequences are inevitably repeated. By writing short, very simple programs which are entered into the computer's memory, Silicon Office can perform the necessary tasks, automatically.

And last, but by no means least is an optional communications facility.

It doesn't take much imagination to see the potential of Silicon Office in virtually any line of business.

So to get a better grasp, send away for our brochure. It'll only cost you a stamp. And it could save you a fortune. Or talk to your local Commodore dealer who has all the facts at his fingertips.

You'll soon see how you're much better off with Silicon Office. Than without.

Circle 60 on inquiry card.





I can't wait to get my hands on a free copy of the Silicon Office brochure.

Name____________________________

Position____________________________

Company____________________________

Address____________________________

A-BY1

I own a Commodore PET (Please tick box) YES ☐ NO ☐

bsf Send to: The Bristol Software Factory, c/o Associated Marketing Systems Inc., 55 Central Drive, Farmingdale, New York NY 11735





MicroShakespeare$_3$

Andrew Kalnik
3201 Wamath Drive
Charlotte, NC 28210

The substitute instructor walks into your programming class wearing a ruffled collar. You enrolled in evening courses at Avon Community College hoping that the sessions would be intellectually stimulating. Your expectations are high; this instructor is, well—very interesting.

The spade beard is common enough, but his long, velvet-trimmed coat and high stockings resemble the garb Errol Flynn wears in the old movies.

Everything comes together when the instructor turns to sign his name for the class to see. You recognize the script with the ornamental scrollwork under it and realize that if you can only walk away with that autographed slab of chalkboard, you can sell it for millions. The substitute instructor has signed William Shakespeare.

He tells you to call him "Master Will." He says he comes from Stratford—just down the road. His opening remarks come in an Elizabethan accent. Master Will tries to encourage the class:

"...We were not born to sue, but to command...."
(*Richard II*, Act I, scene i)

Continuing, he says he knows that you all have problems making your computer systems do what you want:

"...I see your brows are full of discontent,
Your hearts of sorrow...."
(*Richard II*, IV, i)

"...You know not what you do...."
(*Romeo and Juliet*, I, i)

The instructor of Avon has no doubt that you can all put your systems in good order. He stresses that he doesn't want to make *Much Ado About Nothing* but that attention to detail is important. He's sure that you'll be careful not to write any self-destroying programs, and thus you'll avoid having your *Love's Labour's Lost*.

Master Will suggests the class talk over its programming difficulties. Bring on your problems, he says. He enjoys challenges:

"The bugs which you would fright me with I seek...."
(*The Winter's Tale*, III, ii)

Master Will's confident air makes you certain that he'll be able to help. He assures you that he can show you useful programming techniques:

"...make that appear where it seems hid..."
(*Richard III*, I, ii)

His slightly bulging eyes seem melancholy and very wise as he inspects the flowcharts he has asked you to draw as an exercise:

"...leave these sad designs..."
(*Richard III*, I, ii)

You feel better after he marks your block diagram with a few strokes of his quill pen. Now, he says,

"...What thou woulds't it do
Is done into thy hand...."
(*Antony and Cleopatra*, IV, xiv)


As he leaves (erasing the chalkboard and with it your dreams of avarice), his words fill you with enthusiasm for the nearly limitless horizons of microcomputing:

"...and the end of it
Unknown to the beginning...."
(*Coriolanus*, *III*, i)

He leaves a little quiz scratched in that old-fashioned script. Let's see if you paid attention to what Master Will taught. We've collected some of his writings and translated them into modern computing terms.

All you need is a sharp quill and brain. Match each Shakespearean quote on pages 364 and 366 with the most pertinent modern phrase. Only you will know whether you have ended up *As You Like It* or in the middle of *The Comedy of Errors*. The answers and MicroShakespeare ratings are on page 374.

[**Editor's note:** *Each of the items 1 through 20 matches one of the answers "a" through "t," so read through all the answers before you attempt a match...***PL**]



The hard facts about Software from Byte Books

BASIC Scientific Subroutines, Vols. I and II

Valuable programs for professional and hobbyist

by Fred R. Ruckdeschel

Designed for the engineer, scientist, experimenter, and student, this series presents a complete scientific subroutine package featuring routines written in both standard Microsoft and North Star BASIC.

- Volume I covers plotting, complex variables, vector and matrix operation, random number generation, and series approximations.
- Volume II includes least-squares approximation, special polynomial functions, approximating techniques, optimization, roots of functions, interpolation, differentiation, and integration.

Volume I
ISBN 0-07-054201-5
336 pages; hardcover
19.95

Volume II
ISBN 0-07-054202-3
800 pages; hardcover
23.95

Threaded Interpretive Languages

How to implement FORTH on your Z80

by Ronald Loeliger

This book develops an interactive, extensible language with specific routines for the Zilog Z80 microprocessor. With the core interpreter, assembler, and data type defining words covered in the text, it is possible to design and implement programs for almost any application and equivalent routines for different processors.

ISBN 0-07-038360-X
272 pages; hardcover
18.95

Beginner's Guide for the UCSD Pascal System

The most popular Pascal version explained by its creator

by Kenneth L. Bowles

Written by the originator of the UCSD Pascal System, this informative book is an orientation guide to the System. For the novice, this book steps through the System, bringing the user to a sophisticated level of expertise. Once familiar with the System, the reader will find the Guide an invaluable reference tool for creating advanced applications.

ISBN 0-07-006745-7
204 pages; softcover
11.95

The BYTE Book of Pascal

A powerful, structured language

Blaise W. Liffick, Editor

Based on articles, language forums, and letters from BYTE magazine, this work is a valuable software resource. Pascal continues to be popular as a structured programming language. Written for both potential and established users, this book introduces the Pascal language and examines its merits and possible implementations. Featured are two versions of a Pascal compiler, one written in BASIC and the other in 8080 assembly language; a p-code interpreter written in both Pascal and 8080 assembly language; a chess-playing program; and an APL interpreter.

ISBN 0-07-037823-1
334 pages
hardcover
$25.00

Beyond Games: *Systems Software for Your 6502 Personal Computer*

Creating programs for the Apple, Atari, Challenger and PET computers

by Kenneth Skier

At last, a complete programming guidebook. A self-contained course in structured programming and top-down design, this book presents a powerful set of tools for building an extended monitor, disassembler, hexadecimal dump routine and text editor programs.

ISBN 0-07-057860-5
440 pages; softcover
14.95

Name
Address
City State Zip
Check Enclosed Amount
Bill Visa/Master Card Number
Expiration Date

Title	Price	Quantity	Amount

Add 75¢ per book to cover shipping costs: ______

Total ______

BYTE Books 70 Main Street Peterborough, N.H. 03458

ORDER TOLL FREE 800/258-5420

Circle 64 on inquiry card.

Technical Forum

1. ( )	Well, go to— there were no more comparison... *Troilus and Cressida*, I, i	a.	Well, GO TO; there were no more comparisons.
2. ( )	I'll do and I'll do, and I'll do. *Macbeth*, I, iii	b.	Oh, I see—the EQUAL flag is set.
3. ( )	The search so slow! *Cymbeline*, I, ii	c.	What do you think of that function we're tracing on the screen?
4. ( )	A block moved with none... *Much Ado About Nothing*, III, i	d.	It's not responding when you key in binary.
5. ( )	With character too gross... *Measure for Measure*, I, ii	e.	Let's see—it's two NAND's make an OR, and two NOR's make an AND—or is it?
6. ( )	Your memory is bad.... *Love's Labour's Lost*, IV, i	f.	I want to design a board that uses nothing but NAND's and NOR's
7. ( )	I have lost command.... *Antony and Cleopatra*, III, ii	g.	Check where we've halted and what the stack has in it.
8. ( )	On what condition stands it and wherein...? *Richard II*, II, iii	h.	Make sure the 4 MHz pulse is getting through.
9. ( )	...corrupt current of the world... *Hamlet*, III, iii	i.	It filled the area reserved for input with zeros.

10. ( ) Lead off this ground, and let's make further....
The Tempest, I, ii

11. ( ) Against this coming end thou should'st prepare.
Sonnet, XIII

12. ( ) Jump after the inquiry on your own peril....
Cymbeline, V, iv

13. ( ) Four negatives make two affirmatives....
Twelfth Night, V, i

j. We're coming up with persistent errors during MEMCHK.

k. Even hitting "RESET" doesn't get us out of this loop!

l. You'll be in trouble if you follow the COMPARE with a GO TO.

m. OK, right here we get a reading of zero volts. Let's see where this line ends up.

14. ( ) Assay the power you have....
Measure for Measure, I, iv

15. ( ) Dost thou like the plot?
The Tempest, II, i

16. ( ) I would by contraries execute all things....
The Tempest, II, i

17. ( ) Go, clear thy crystals....
Henry V, II, 3

18. ( ) Thou art too base to be acknowledged....
The Winter's Tale, IV, iv

19. ( ) That action, hence borne out may waste the memory of former days....
II Henry IV, IV, v

20. ( ) Now I perceive that she hath made compare....
A Midsummer Night's Dream, III, ii

n. ...We get all sorts of garbage on the 115 V AC line whenever the dryer or refrigerator goes on.

o. It'll take all day to find a match.

p. ...if you do that, you'll erase your backup files.

q. Why don't you scope the output of the 7805?


r. You need to sum all the variables as you go along, so that you can get the final totals easily.

s. We need finer resolution than we can get with a 5 by 7 dot matrix.

t. I'll take care of those iterations in nested loops.
in nested loops.

See answers on page 374.■





NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 42 HIGHTSTOWN, N.J. 08520


POSTAGE WILL BE PAID BY ADDRESSEE

Computer Professionals' Book Club

P.O. Box 582
Hightstown, New Jersey 08520



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES





BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 42 HIGHTSTOWN, N.J. 08520

POSTAGE WILL BE PAID BY ADDRESSEE

Computer Professionals' Book Club

P.O. Box 582
Hightstown, New Jersey 08520

COMPUTER PROFESSIONALS' BOOK CLUB

MEMBERSHIP ORDER CARD

Please enroll me as a member and send me either the ENCYCLOPEDIA OF COMPUTER SCIENCE, billing me only $3.00, or any 3 other books, billing me only $1.00 each, plus local tax, shipping and handling charges. I agree to purchase a minimum of three additional books during my first year as outlined under the Club plan described in this ad. A shipping and handling charge is added to all shipments.

- ☐ Check here if you want ENCYCLOPEDIA OF COMPUTER SCIENCE (769/01X).
- ☐ Check here if you prefer three other volumes, and indicate below by number the books you want. A few expensive books (noted in the descriptions) count as more than one choice.

Name ______________________

Address/Apt. # ______________________

City, State, Zip ______________________

Corporate Affiliation ______________________

This order subject to acceptance by McGraw-Hill. All prices subject to change without notice. Offer good only to new members. Orders from outside the U.S. cannot be accepted.



COMPUTER PROFESSIONALS' BOOK CLUB

MEMBERSHIP ORDER CARD

Please enroll me as a member and send me either the ENCYCLOPEDIA OF COMPUTER SCIENCE, billing me only $3.00, or any 3 other books, billing me only $1.00 each, plus local tax, shipping and handling charges. I agree to purchase a minimum of three additional books during my first year as outlined under the Club plan described in this ad. A shipping and handling charge is added to all shipments.

- ☐ Check here if you want ENCYCLOPEDIA OF COMPUTER SCIENCE (769/01X).
- ☐ Check here if you prefer three other volumes, and indicate below by number the books you want. A few expensive books (noted in the descriptions) count as more than one choice.

Name ______________________

Address/Apt. # ______________________

City, State, Zip ______________________

Corporate Affiliation ______________________


This order subject to acceptance by McGraw-Hill. All prices subject to change without notice. Offer good only to new members. Orders from outside the U.S. cannot be accepted.



BYTE

P39554

EXPERIENCE!



THE DEVIL'S DP DICTIONARY. By Stan Kelley-Bootle. *160 pp., softbound.* This devilishly clever little book is guaranteed to fill anyone who has ever slaved over a hot terminal with savage delight. Some 500 computer words and terms are misdefined, from abacus to your program.
340/226 $7.50

MICROCOMPUTER INTERFACING. By Bruce Artwick. *352 pp., 117 illus.* In this up-to-date, *complete* design guide you'll find the detailed descriptions and explanations necessary to enable you to select, build, and interface microcomputer systems to virtually all applications. Advanced interface devices and methods are thoroughly examined and illustrated.
789/436 $24.95

PERSONAL COMPUTING: Hardware and Software Basics. Electronics Book Series. *224 pp., 175 illus., 8½ x 11 format.* Gives you comprehensive guidance to the present state of the art in personal computers—an overall survey of the technology and methods available to perform various tasks, facts about the work others are doing—and just how they are doing it.
191/514 $24.50

PROGRAMMING AND INTERFACING THE 6502—With Experiments. By Marvin L. De Jong. *414 pp., heavily illus., softbound.* This guide not only teaches you all you must know about programming and interfacing the 6502, but it also carries you to a high level of understanding and proficiency quickly and painlessly.
582080-3 $15.95

Z80 USERS MANUAL. By Joseph Carr. *326 pp., with diagrams, charts and tables.* Takes you through every opportunity the ZAP can offer. It covers Z80 pin definitions, CPU control signals, support ships, interfacing peripherals, and much more. It also includes a 177-page Z80 instruction set so you can study the instructions on a one-by-one basis.
582336-5 $18.95

ELECTRONIC GAMES: Design, Programming, and Troubleshooting. By W. H. Buchsbaum and R. Mauro. *335 pp., 338 illus.* Information you need to design, program, and troubleshoot electronic games is right here in this widely popular hands-on guide.
087/2108 $26.95
(Counts as 2 of your 3 books)

PROGRAMMING LANGUAGES. By Allen B. Tucker, Jr. *439 pp., illus.* Gives you not only the *principles* of design but the *applications* of six major programming languages. Shows you their strengths and weaknesses in solving various representative "benchmark" problems.
654/1588 $28.50
(Counts as 2 of your 3 books)

BIT-SLICE MICROPROCESSOR DESIGN. By John Mick and Jim Brick. *398 pp.* All in one place—the crucial information you've been needing about the 2900 family of bit-slice microprocessor components. This remarkable "first" designs right before your eyes not just one but *two* complete 16-bit machines!
417/814 $24.00

Be sure to consider these important titles as well!

6502 SOFTWARE DESIGN. By L. J. Scanlon
582138-9 $10.50

THE GIANT HANDBOOK OF COMPUTER PROJECTS. By the Editors of 73 Magazine
582012-9 $15.95

SYNTAX OF PROGRAMMING LANGUAGES: Theory and Practice. By R. C. Backhouse
582064-18 $25.95
(Counts as 2 of your 3 books)

STRUCTURED PROGRAMMING: Theory and Practice. By R.C. Linger, H.D. Mills, & B.I. Witt
788/5378 $22.95
(Counts as 2 of your 3 books)

THE BYTE BOOK OF PASCAL. Edited by B. W. Liffick
789/6738 $25.00
(Counts as 2 of your 3 books)

THE Z-80 MICROCOMPUTER HANDBOOK. By W. Barden, Jr.
784/914 $8.95

COMPILER DESIGN AND CONSTRUCTION. By A. Pyster
582026-9 $24.50

COMPUTER PERIPHERALS FOR MINICOMPUTERS, MICROPROCESORS AND PERSONAL COMPUTERS. By L.C. Hohenstein
294/518 $19.50

16-BIT MICROPROCESSOR ARCHITECTURE. By T. Dollhoff
582003-X $24.95

PRINCIPLES OF INTERACTIVE COMPUTER GRAPHICS. By W. M. Newman & R. Sproull
463/3878 $28.95
(Counts as 2 of your 3 books)

*If you join now for a trial period and agree to purchase three more books—at handsome discounts—during your first year of membership. (Publishers' prices shown)

Why YOU should join now!

■ **BEST AND NEWEST BOOKS IN YOUR FIELD**—Books are selected from a wide range of publishers by expert editors and consultants to give you continuing access to the best and latest books in your field.

■ **BIG SAVINGS**—Build your library and save money too! Savings ranging up to 30% or more off publishers' list prices—usually 20% to 25%.

BONUS BOOKS—You will immediately begin to participate in our Bonus Book Plan that allows you savings of between 70%—80% off the publishers' prices of many professional and general interest books!

■ **CONVENIENCE**—12-14 times a year (about once every 3-4 weeks) you receive the Club Bulletin FREE. It fully describes the Main Selection and alternate selections. A dated Reply Card is included. If you want the Main Selection, you simply do nothing—it will be shipped automatically. If you want an alternate selection—or no book at all—you simply indicate it on the Reply Card and return it by the date specified. You will have at least 10 days to decide. If, because of late delivery of the Bulletin you receive a Main Selection you do not want, you may return it for credit at the Club's expense.

As a Club Member you agree only to the purchase of 3 books during your first year of membership. Membership may be discontinued, by either you or the Club at any time after you have purchased the 3 additional books.

Other McGraw-Hill Book Clubs:
Accountants' and Controllers' Book Club • Architects' Book Club • Chemical Engineers' Book Club • Civil Engineers' Book Club • Electronics and Control Engineers' Book Club • Mechanical Engineers' Book Club

For more information, write to:
McGraw-Hill Book Clubs
1221 Avenue of the Americas, 26th fl., New York, NY 10020

MAIL THIS COUPON TODAY

McGraw-Hill Book Clubs
Computer Professionals' Book Club
P.O. Box 582, Hightstown, New Jersey 08520

Please enroll me as a member and send me either the ENCYCLOPEDIA OF COMPUTER SCIENCE. billing me only $3.00, or any three other books, billing me only $1.00 each, plus local tax, shipping and handling. I agree to purchase a minimum of three additional books during my first year of membership as outlined under the Club plan described in this ad. A shipping and handling charge is added to all shipments.

☐ Check here if you want ENCYCLOPEDIA OF COMPUTER SCIENCE (769/01X).

☐ Check here if you prefer three other volumes, and indicate below by number the books you want.
A few expensive books (noted in the description) count as more than one choice.

Name ______________________

Address/Apt. ______________________

City/State/Zip ______________________

Corporate Affiliation ______________________

This order subject to acceptance by McGraw-Hill. All prices subject to change without notice. Offer good only to new members. Orders from outside the U.S. cannot be accepted.

P39552

$395 BASIC DIVORCE

Announcing the new quick and easy way to write custom business applications in hours instead of weeks.

At last, you can get a microcomputer business application development system that is designed for one purpose only . . . fast production of bug-free professional-looking custom business applications.

"Thinks" the Way Business Thinks
Quic-N-Easi is the revolutionary screen-format-oriented application development system that thinks in terms of transactions, records and fields. The same way business thinks. **Quic-N-Easi** expects an application to include custom formatted key entry. It lets you set up the character, field, and record validity checks business wants by merely filling in the blanks. It automatically signals in real time when errors occur and "explains" what is wrong in plain English messages you select for each custom application.

Much Faster than BASIC
Quic-N-Easi programming is much faster than BASIC because the standard business applications (key input, file handling, and output reporting) are handled via pre-programmed parameter driven_subroutines. To produce finished professional looking custom business programs, you merely:

- Draw the business formats directly on the CRT in minutes.
- Fill in the blanks for field attributes, validations, tables, etc.
- Invoke the **Quic-N-Easi** interpreter to check fields against tables, check limits, access data files, and perform business calculations, etc.
- Optionally define file and output formats right on the screen.

Pays for Itself in a Week
By eliminating the coding drudgery of writing screen, field, file, and format programs in BASIC, programmers are free to concentrate on the unique business aspects of each custom application. No professional programmer can afford to develop one more business application without **Quic-N-Easi**. The savings are so significant with **Quic-N-Easi**, it can actually pay for itself in only one week.

Gives You Much More than a Screen Builder . . . the Only Complete Business Development System for Microcomputers
Quic-N-Easi handles the entire application development job from key entry to final output. You get everything you need, including detailed documentation to begin writing professional programs the first day. **You get . . .**

- A singularly capable **Quic-N-Easi** screen builder
- A comprehensive parameter driven **Quic-N-Easi** content editor
- A full **Quic-N-Easi** interpreter language
- A complete **Quic-N-Easi** file management system with Index Sequential, Random, and Sequential File Access Method
- A complete **Quic-N-Easi** print format handler
- A detailed **Quic-N-Easi** reference manual
- A **Quic-N-Easi** self-teaching guide
- A **Quic-N-Easi** quick reference card
- An interface to other program files

ORDER NOW—Don't Waste One More Day Coding BASIC
Your time is too valuable to waste hours on end writing BASIC code. The first week you use **Quic-N-Easi**, your finished business programs will look better, run better, and return more dollars to you. Don't delay. Order **Quick-N-Easi** today.
Phone . . . 215 968-0689

QUIC-N-EASI™

STANDARD MICROSYSTEMS INC.
136 GRANITE HILL COURT, LANGHORNE, PA 19047

Pricing Information

- Complete **Quic-N-Easi** system **$395**
- Manual only **$60**
- **Visa** and **Mastercard** accepted
- **Dealer Inquiries Invited**

Minimum System Requirements
Z80 • 48K • Floppy Disc
• CP/M (except TRS80 Mod III)

Disk Formats
8" Single Density • VECTOR GRAPHICS • MICROPOLIS Mod 2 • TRS80 Mod II • TRS80 Mod III • APPLE • OSBORNE • INTERTEC • ZENITH

Apple, CP/M, Intertec, Micropolis, and TRS80 are trademarks of Apple Computer, Digital Research, Intertec Data Systems, Micropolis Corp., and Tandy Corp.

Circle 381 on inquiry card.

Selector IV by Micro-Ap
An Information-Management Program

Jack L. Abbott
8525 North 104th Ave.
Peoria, AZ 85345

Selector, nationally advertised as an information-management program, was developed by Micro-Ap of San Ramon, California. This is an overview of Selector's capabilities and limitations. You should look at the program with regard to your particular application before deciding whether to buy it.

For those of you who may be unfamiliar with database or data-management programs, here is a brief description of what they do. They accept data in a format that you establish, sort the data in the order that you wish, and excerpt, summarize, and mathematically manipulate the data according to your instruction. They then present the data in a report format of your design. Potential uses for database programs are limited only by the user's imagination: examples include programs for inventory, form generation, mailing lists, appointment calendars, library document lists, check making, and check-book listing.

At a Glance

Name
Selector IV
Type
Database management program
Manufacturer
Micro-Ap
9807 Davona Dr.
San Ramon, CA 94583
(415) 828-6697
Price
$295
Format
5- or 8-inch floppy disk, or hard disk (running under CP/M 2.2)
Language
CBASIC, version 2.05/35 or later
Computer System
System with 52 K (or more) bytes of RAM running CP/M 1.4x or 2.xx operating system, with 24-line by 80-column cursor-addressable display terminal and a printer
Documentation
Preliminary version, 210 pages in three-ring binder
Audience
Everyone who has a microcomputer

Selector IV, the current version of this program, succeeds version III-C2. Version IV represents a quantum leap forward, especially in its usefulness to someone who is not a skilled programmer. Selector IV lists at $295 and Selector III at $195. My comments in this article address version IV, but for those who have been using version III, Selector IV provides a program for convenient conversion of your data files to a suitable format for version IV.

Selector IV requires a CP/M-compatible (version 1.4, 2.0, or 2.2) operating system, CBASIC version 2.05/35 or later, and a 24-line by 80-column (or larger) video-display capability with absolute cursor addressing and erase-screen functions. Micro-Ap supplies two disks, one with the Selector IV source code and one with the compiled programs. No compilation is necessary, and the program as received runs under CBASIC2. Micro-Ap recommends using a printer: I would say one is essential.

You can adapt Selector to your terminal and computer by menu selection. Micro-Ap will provide Selector in any microcomputer disk format that is in general use, but I had to wait about six weeks to get a disk formatted for Micropolis Mod II (Vector Graphic) drives. Some of the printed descriptions furnished by Micro-Ap state that Selector IV will run in "48 K or more of user memory space" (i.e., 48 K bytes of random-access read/write memory). Micro-Ap interprets this statement to mean that additional memory is required for CP/M, etc., which means that a user needs at least 52 K, and operation is better with 56 or 64 K.

The program documentation is a preliminary version, but this is not a serious limitation. All the required information is present, although a large portion is included in addenda and is not listed in the index. The program explanations in the documentation are very good—the Micro-Ap writer does not presuppose extensive engineering or programming experience.

Running Selector

To initialize the program, tell Selector what kind of equipment you are using, as well as company or personal information that you want the program to use in report headings. Next, define the format of the information you wish to enter. The written instructions are explicit and are supplemented by detailed prompts on the display screen. Configuration of the data "fields" (individual data items) making up one data record (a collection of related items) is simple, and there can be up to eighty fields in one record. These individual fields contain all the information about one subject. In a mailing-list program the subject would be one person or business; in an inventory program the subject would be one product or component. Record length cannot exceed 255 characters. All related records are stored in one file. There is no reasonable data-table format that Selector cannot generate.

After you establish the format of the data to be input, the program presents the format whenever requested and assists in making certain that no mistakes are made in entering the data. On completion of a data-entry session, Selector automatically merges the new data into the existing database and then asks for further instructions.

Once the input format has been defined and the data entered, tell Selector which records you want to select for printing or display by specifying select or sort requirements, called "definitions." Upon request, the program executes these "definitions" by going through the database and picking and sorting the appropriate records.

The final step is to establish how you want the selected data to be presented. Selector provides two ways: "page reports" and "line reports." Selector can send these reports to either the terminal or the printer. A total of as many as 80 different fields from six different files may be presented. You can specify mathematical operations (+, −, /, *) and logical operations (equals, greater than, less than, etc.) on or between data fields. The data fields can be summed.

The page-report function, used to generate forms like invoices or purchase orders which require that data be placed on a specific place on a page, should be one of the most valuable features. However, defining the parameters for this function and troubleshooting its operation take so much time that much of the potential is wasted. Using a series of single-letter and number codes, you must tell the program exactly where each data field is to be placed on the form. Learning the codes is like learning another programming language and it takes a long time to get the report right.

The line-report function is easy to define. It consists of as many data fields as you choose, taken from the records you select, placed one after another on as many lines as required. The line-report function includes mailing-list processing. The mailing list label-printing subprogram is outstanding. It is easy to define, will print from one to

LETTER PERFECT T.M. LJK

WORD PROCESSING

ATARI 400/800 — APPLE II & II+

EASY TO USE — Letter Perfect is a single load easy to use program. It is a menu driven, character orientated processor with the user in mind. FAST machine language operation, ability to send control codes within the body of the program, mnemonics that make sense, and a full printed page of buffer space for text editing are but a few features. Screen Format allows you to preview printed text. Indented margins are allowed. Data Base Merge with **DATA PERFECT** by LJK, form letters, accounting files and mailing labels only with MAIL MERGE/UTILITY by LJK. **FEATURES** — Proportional/ Incremental spacing * Right Justification * File Merging * Block movement * Headers * Footers * Print Multiple Copies * Auto Page Numbering * Scroll forward/backward * Search and Replaces * Full cursor control * Underlining * Boldface * Superscripts * Subscripts * Auto page numbering * Insert character/line * Delete character/line * Centering * Horizontal tabs/changeable * Multifunction format line (line spacing — left margin — page width — lines/page — change fonts — top/ bot margin adjust) **MUCH MORE! $149.95**

ATARI VERSION 2.0 #2001

Uses proportional font, right justified with Atari 825/Centronics 737, 739 printers. Uses EPSON MX* Series + Graftrax/italicized font. Can mix type fonts on same page; mix boldface and enhanced font in same line with justification. Can be used with 16K Atari/400.*

"Compared to the price of many other word processors, this package is a steal. It does everything the advertisement claims and more. On top of this the software is very easy to use." **A.N.A.L.O.G. MAGAZINE**

APPLE VERSION 5.0 #1001

DOS 3.3 compatible — Use 40 or 80 column interchangeably (Smarterm — ALS; Videoterm-Videx; Full View 80 — Bit 3 Inc.; Vision 80 — Vista; Sup-R-Term — M&R Ent.) Reconfigurable at any time for different video, printer, or interface. **USE HAYES MICROMODEM II*** LCA necessary if no 80 column board, need at least 32 K of memory. Files saved as either Text or Binary. Shift key modification allowed. Data Base Merge compatible with **DATA PERFECT*** by LJK.

"For $150, Letter Perfect offers the type of software that can provide quality word processing on inexpensive micro-computer systems at a competitive price." **INFOWORLD**

DATA PERFECT T.M. LJK

APPLE & ATARI
DATA BASE MANAGEMENT **$99.95**

Complete Data Base System. User orientated for easy and fast operation. 100% Assembly language. Easy to use. You may create your own screen mask for your needs. Searches and Sorts allowed, Configurable to use with any of the 80 column boards of Letter Perfect word processing, or use 40 column Apple video. Lower case supported in 40 column video. Utility enables user to convert standard files to Data Perfect format. Complete report generation capability. **Much More!**

EDIT 6502 T.M. LJK

This is a coresident — two pass **ASSEMBLER, DIS-ASSEMBLER, TEXT EDITOR, and MACHINE LANGUAGE MONITOR.** Editing is both character and line oriented. Disassemblies create editable source files with ability to use predefined labels. Complete control with 41 commands, 5 disassembly modes, 24 monitor commands including step, trace, and read/write disk. Twenty pseudo opcodes, allows linked assemblies, software stacking (single and multiple page) plus complete printer control, i.e. paganation, titles and tab setting. User can move source, object and symbol table anywhere in memory. Feel as if you never left the environment of **BASIC.** Use any of the 80 column boards as supported by **LETTER PERFECT,** Lower Case optional with **LCG.**

LJK DISK UTILITY — APPLE $29.95

This menu driven program allows the user to manipulate a variety of different file types. Binary, Text, and Source files may be easily converted into each other. The program may be used with **APPLESOFT*, VISCALC*,** and other programs. These program files may be readily adapted for multiple use including editing with **LETTER PERFECT** word processings.


MAIL MERGE/UTILITY — $29.95 ATARI

This menu driven program combined with **LETTER PERFECT** allows user to generate form letters and print mailing labels. With the Atari, you may **CONVERT ATARI DOS FILES,** or Visicalc files compatible for editing with **LETTER PERFECT.** Utility creates Data Base files for Letter Perfect.

LOWER CASE CHARACTER GENERATOR — $24.95



Lower Case Character Generator for the Rev. 7, Apple II or II+ computers. When installed, this Eprom will generate lower case characters to the video screen. Lower case characters set has two dot true descenders. Installation instruction included. Manual includes listing of software for full support and complete instructions for shift key modification. Compatible with **LETTER PERFECT.**



COMPUTER BASED SOFTWARE

LJK T.M. ENTERPRISES Inc

LJK ENTERPRISES INC.
P.O. Box 10827
St. Louis, MO 63129
(314) 846-6124

DEALER INQUIRES INVITED

*Trademarks of: Apple Computer — Atari Computer — Epson America — Hayes Microcomputers — Personal Software — Videx — Bit 3 Inc. — M&R Ent. — Advanced Logic Systems — Vista Computers

eight labels across, and prints slightly less than 600 labels an hour (using a Dynabyte 8/2 and an Epson MX-80 printer in a two-across format). Unfortunately, this subprogram works effectively only in batch mode (this in more detail later).

A Sample Application

Listing 1 shows the data-input format of the mailing-list program that I developed to meet my own requirements and to learn the program. In the "Type" column "A" is alphanumeric, "N" is numeric, and "K" is for key. The user can designate any field as key. The program will then have the capability of sorting or selecting data records based upon one or a combination of key fields. In the sample shown, you could select all the records for a state with a given zip code, then select all the people in that state whose last names begin with A, and so on. You could print as many of the individual data fields as you wished, in addition to the key fields, in a given record. My use of field 13 in listing 1 is a good example. I assign "B" for all business entries, "P" for personal entries, and "A" for entries that are both business and personal. When I print a mailing list, I can select and print all the labels for personal entries by selecting "P", all the labels for business entries by selecting "B", and all those that are both business and personal by selecting "A". Based on the records I have selected I can then set up the report to include any other desired fields as well as the key fields, e.g., home address, business address, and city.

A limitation of the Selector program is the inability to function in other than a "batch mode." It takes several minutes to bring Selector up and load the program module that inputs data records. You can then enter data records rapidly. When you exit the data-entry function, Selector will automatically merge the new data with the old and reload the operating program and menu. Before you output a report, you must run the select and sort

Listing 1: *A Selector IV record-definition file. Fields are numbered and named in the first two columns. Key size is the number of characters taken from a key field that actually make up the key. The last column shows the "byte offset" for each field, i.e., the number of bytes into the record counting from the beginning to the first byte in the field.*

```
=========================================================
Record definition file: B:MALIST.DEF   as of APR 23, '1
    Data  file   drive: B       Key/Support drive: B
    Data record length: 218    Key record Length:  19
=========================================================
 ##      Name        Type  Data Size  Key Size  Byte Offset
=========================================================
  1   FRSTNAME        A       25                       1
  2   LASTNAME        AK      20         10           26
  3   TITLE           A       15                      46
  4   CMPNYNAM        AK      25         10           61
  5   CMPNYADD        A       25                      86
  6   HOMEADDR        A       25                     111
  7   CITY            A       20                     136
  8   STATE           AK       2          2          156
  9   ZIPCODE         NK       5          5          158
 10   HOMPHONE        A       14                     163
 11   BUSPHONE        A       14                     177
 12   REMARKS         A       25                     191
 13   BPCODE          AK       1          1          216
=========================================================
```

Answers to MicroShakespeare Quiz

1 - a	6 - j	11 - r	16 - f
2 - t	7 -k	12 - l	17 -h
3 - o	8 - g	13 - e	18 - d
4 - i	9 - n	14 - q	19 - p
5 - s	10 - m	15 - c	20 - b

Number of Correct Matches	MicroShakespeare Rating
20	You're making the best of BYTE and Bard.
17 - 19	Software almost ready to burn into ROM.
13 - 16	Something wrong with housekeeping; GO TO ORG.
9 - 12	Make sure you have the right chips installed.
5 - 8	Clear memory and start over.
4 or fewer	Send for a new processor. ■

An Improved Selector

As this article goes to press, we at BYTE find ourselves once again trying to catch up with an industry that changes faster than we do. The final documentation is now available for Selector IV and the package allows CODASYL-type record-accessing conventions (including one-to-many, many-to-one, and many-to-many record accesses).

Micro-Ap has also introduced Selector V, a machine-language database (compiled from BASIC code through Digital Research's CB80 package) that does not require purchase of any additional language. According to Bob Goodman of Micro-Ap, Selector V works in the same way as Selector IV, but is 3½ to 6 times faster. Added features include the extended record-accessing conventions mentioned above, a removal of the 256-byte record-length restriction of Selector IV, and file and record locking and unlocking capabilities (which can be used when Selector V is used under the MP/M operating system). Selector V lists at $495.

INTRODUCING CALCSTAR.™ ANOTHER INDISPENSABLE BUSINESS PROGRAM FROM MICROPRO,™ THE WORDSTAR™ PEOPLE.

Presenting CalcStar—another standard-setting software product in the WordStar tradition.

CalcStar is MicroPro's new electronic spread sheet and financial modeling program—a sophisticated, yet easy to use, calculating and planning tool for CP/M®-based computers.

The ultimate electronic spread sheet. CalcStar calculates solutions to complex numerical problems in business and finance. Helps you make budget plans and sales forecasts with greater speed and accuracy. And projects figures into the future to answer the "what if" questions you face in business. And CalcStar also has a unique MicroPro advantage: It joins with WordStar to combine spread-sheet and word-processing capabilities in several powerful ways.

CalcStar software eliminates the need to use ledger paper ever again. It turns your video screen into a "window" on a giant electronic ledger sheet, with up to 600 entries arranged the way you want. Then, by inserting formulas into CalcStar, you create financial models that simulate the future numerically. And predict the outcomes of your business decisions.

When you notice what CalcStar can do for your business, you'll wonder how you ever got along without it. (If you're now a WordStar user, you probably already know the feeling.)

The MicroPro bonus. Like WordStar, CalcStar is packed with innovative features that make it versatile and easy to use. Features like Automatic Forms Mode, which lets an inexperienced user enter data into a spread sheet quickly and with less chance of error.

CalcStar's greatest innovation is its ability to join with WordStar. Which means, for example, you can use WordStar's printing options, like boldface and underlining, to dress up financial documents. And you can insert sections of CalcStar's spread sheets into your WordStar documents.

This kind of flexibility should come as no surprise if you're already familiar with the MicroPro software family—a line of programs designed to work together to multiply your problem-solving power. Visit your MicroPro dealer to find out just how big a difference *all* our products can make in your business. We predict you'll discover it's not just CalcStar or WordStar that's indispensable. It's MicroPro.



A glance at CalcStar features

Runs on CP/M version 2.0 or above, with 80-column screen, addressable cursor, and at least 48K memory. 56K or more is recommended for fullest utilization.

Highly user friendly: Call up full screen of help or use help menu. WordStar-like cursor commands. User's guide shows you the basics. Install from menu OR a WordStar file.

Stores formulas and formats along with data, for convenience and less chance of error.

Math functions include average, minimum, maximum, logarithms, exponents, and regression analysis.

SOFTWARE THAT MEANS BUSINESS™



INTERNATIONAL CORPORATION

1299 Fourth Street, San Rafael, California 94901
(415) 457-8990; Telex: 340-388

CP/M is a trademark of Digital Research, Inc.
Dealer and distributor inquiries invited.

DataStar™ MailMerge™ WordStar™ WordMaster™ SuperSort™ SpellStar™ CalcStar™

Listing 2: *A CBASIC program for printing a single label or envelope. The program pulls information about an addressee from the Selector IV database as soon as the user gives enough information to identify a record uniquely. If the user doesn't reference a data file, the program lets the user type an address onto an envelope in the system's printer.*

```
REM ***********************************************************
REM PROGRAM TITLE:TYPMAL.BAS
REM JACK ABBOTT, PEORIA AZ 6/16/81
REM THIS PROGRAM WILL TYPE ENVELOPES WITH NO OTHER FILE, OTHERWISE
REM PUT MALIST DATA ON B DRIVE, AND THEN RUN THIS PROGRAM.
REM THIS PRO. TYPES ADDRESSES, ENVELOPES, OR LABELS.
INPUT "PUT MALIST.DAT ON B DRIVE THEN PRESS RETURN-";LINE DUMB$
22 T%=0
OPEN "B:MALIST.DAT" AS 1
INPUT "NAME WANTED OR OWN ENVEL. ADDRESS(OWN)-";N$
IF N$="OWN" THEN 150
28 READ #1;LINE MALIST$
T%=T%+1
A%=1
S$=MALIST$
IF MATCH(N$,S$,1)>0 THEN 112
IF END #1 THEN 21
GOTO 28
21 INPUT "NAME NOT FOUND, MORE? Y/N";M$
CLOSE 1
IF M$="Y" THEN 22
GOTO 777
112 INPUT "ENV. OR LABEL,E OR L?";F$
INPUT "BUSINESS OR PERSONAL? B OR P";Z$
IF F$="E" THEN 222
INPUT"PHONE# WANTED?Y/N";E$
INPUT "# OF LABELS WANTED?";I%
G%=1
IF I%>1 THEN Q%=I% ELSE Q%=1
GOTO 666
150 A%=5
GOTO 222
444 CONSOLE
INPUT "MORE?Y/N?";P$
E$="N"
CLOSE 1
IF P$="Y" THEN 22
GOTO 777
666 LPRINTER
C%=25
FOR H=1 TO Q%
670 IF Z$="8" THEN 680
676 B$=LEFT$(S$,C%)
IF RIGHT$(8$,1)=" " THEN 446
PRINT TAB(G%);LEFT$(S$,C%);" ";MID$(S$,26,20)
PRINT TAB(G%);MID$(S$,111,25)
681 PRINT TAB(G%);MID$(S$,136,20)
PRINT TAB(G%);MID$(S$,156,2);CHR$(32);CHR$(32);MID$(S$,158,5)
IF E$="Y" THEN 445
PRINT
677 PRINT
NEXT
GOTO 444
680 PRINT TAB(G%);MID$(S$,61,25)
PRINT TAB(G%);MID$(S$,86,25)
GOTO 681
445 PRINT TAB(G%);MID$(S$,163,13)
GOTO 677
446 C%=C%-1
GOTO 676
222 INPUT "LEGAL OR REGULAR?L OR R";K$
G%=20
IF K$="L" THEN G%=40
INPUT "READY TO PRINT?Y/N";D$
IF D$="N" THEN 444
LPRINTER
PRINT "JACK L. ABBOTT"
PRINT "8525 N. 104TH AVE."
PRINT "PEORIA, ARIZ. 85345"
PRINT:PRINT:PRINT:PRINT:PRINT:PRINT:PRINT:PRINT:PRINT
CONSOLE
IF A%>1 THEN 180
GOTO 666
180 INPUT "NAME-FIRST LINE?";LINE O$
INPUT "STREET ADDRESS-SECOND LINE?";LINE J$
INPUT "CITY, STATE, ZIP? LAST LINE";LINE V$
LPRINTER
PRINT TAB(G%);O$:PRINT TAB(G%);J$:PRINT TAB(G%);V$
PRINT:PRINT
CONSOLE
GOTO 444
777 STOP
```

definitions on the updated database. These operations take several minutes. The overhead time is acceptable when you're processing lots of records, but unacceptable when you're processing just a few. This may or may not be a problem, depending on what you're using the program for. If you want to enter and then recall a record, as in the case of inputting the data for a single invoice or receipt and then printing it, the time overhead is too great. A printer is a necessity because you can print out data, mark changes on the sheet in pencil, and then enter all the changes at once. In the case of mailing-list information there is no way to pull out and print a single name and address other than to generate a report, and that takes several minutes.

One way to save time is to use the program in listing 2. This CBASIC program scans the data files created by Selector, picks out individual addresses, and prints labels or envelopes. The program also types individual envelopes with your return address and lets you type the addressee, line by line, from the console. Apart from accessing the mailing-list database, the program operates independently of Selector, so it can be compiled separately. You choose functions from a menu and the program will pick any address record if you enter enough letters or numbers to give a unique identity—these identifiers can be first names (as long as there are no duplicates), street numbers, or whatever you decide.

A minor annoyance is Selector's use of the terminal alarm, which sounds whenever anything "noteworthy" happens. Unfortunately the designers find many things noteworthy that I do not (including disk transfers, entry of the day's date, improper inputs), and initially I kept wondering what mistakes I had made whenever the alarm went off. A program toggle should be provided to disable this feature. Another confusing factor is a display heading that tells you when a disk operation is going on so you won't attempt any keyboard action. The heading appears most, but not all of the time, so after a while I forgot to look at the disk-select light. Later, when I started poking at the keys, I wondered why nothing was happening during some disk operations.


Conclusions

The Selector program is written entirely in CBASIC, but the merge and sort functions are fast, so the program as a whole runs rapidly. The program can enter and retrieve many records at a time extremely well, but if you want to switch back and forth between data entry and display, or print in less than several minutes, you will have to modify or supplement program operation.

The mailing-list module is excellent, easy to define, and executes quickly. In addition, the program shown in listing 2 allows you to select and print individual addresses. The line-report function is also excellent and easy to use; unfortunately, the page-report function requires a great deal of effort and time. I find that a printer, preferably with 132-column print capability, is essential for most uses.

Selector should be purchased with the final documentation package, but the program description is clear and well written in the preliminary version, and the program performs exactly as the documentation says it will. Selector has the potential to perform a number of different functions well. If it meets the requirements of your task, it represents a good value when compared to the cost and time of developing custom software. ■

Double your disk storage capacity...



simply by switching to Omni's new reversible disk.

If you have an Apple, TRS-80, Zenith, North Star or any other single-sided 5¼" disk drive, you can double disk capacity by simply switching to the Flip/Floppy disk from Omni. It works just like your present disks, except you can flip it over and record on the reverse side. So you can consolidate programs and files that used to require two disks. You can halve your disk requirements. And save money.

Each disk comes with some impressive specifications: They're certified error-free at more than twice the error-threshold of your system. Rated for more than 12 million passes without disk-related errors or significant wear. And precision fabricated with such standard features as reinforced hub rings.

Call Omni toll-free today. Get premium disks. Twice the capacity. A full money-back guarantee. Unbeatable price. And if you order a ten pack now, a free $5.00 storage case as well.

OMNI

Omni Resources Corporation
4 Oak Pond Avenue, Millbury, MA 01527
(800) 343-7620 In Mass. (617) 799-0197

Dealer inquiries invited.
Software Houses: We also offer duplicating and formatting services.

$26.00-Five pack
(Equivalent to 10 single-sided disks)

$50.00-Ten pack
(Equivalent to 20 single-sided disks)



Free
Protective plastic storage case with each 10 pack ordered by 5/1/82

Order toll-free (800) 343-7620. In Mass. (617) 799-0197.

Send the following Flip/Floppy disks.
I understand they have a full 90 day money-back guarantee if I'm not completely satisfied.

System & model # ______________________

____ Five packs @ $26.00 $__________

____ Ten packs @ $50.00* $__________
* includes plastic case

Shipping and handling $ 1.50

5% sales tax (Mass. only) $__________

Total $__________

____ Check (to Omni Resources) ____ C.O.D.

____ Master Card ____ Visa

Card #______________________ Exp.__________

Name ______________________

Address ______________________

____

Tel ______________________

Circle 305 on inquiry card.

DYNACOMP

Quality software for:*

ATARI
PET/CBM
APPLE II Plus
OSBORNE-1
ALTAIR****
TRS-80 (Level II)**
NORTH STAR***
CP/M Disks/Diskettes
(See Availability box MBASIC/CBASIC)
SUPERBRAIN*****

CARD GAMES

NEW **BRIDGE MASTER (North Star only)** Price: $21.95 Diskette
If you liked DYNACOMP'S BRIDGE 2.0, you will absolutely love BRIDGE MASTER. BRIDGE MASTER is a comprehensive bridge program designed to provide hours of challenging competition. Bidding features include the Blackwood convention, Stayman convention, pre-emptive openings, and recognition of demand bids and jump-shift responses. After playing a specific hand, you may replay the same hand, with the option of switching cards with your computer opponents. This feature allows you to compare your bidding and playing skills to BRIDGE MASTER. Bonuses for game contracts and slams are awarded as in duplicate bridge. Doubled contracts are scored based upon a computer assigned vulnerability. A score card is displayed at the conclusion of each hand. The score card displays a summary of total hands played, total points scored, number of contracts made and set, and % bids made. BRIDGE MASTER is clearly the best computer bridge program available.
DYNACOMP'S previous BRIDGE 2.0 customers may upgrade to BRIDGE MASTER for a nominal charge of $5.00 plus postage and handling (see ordering information box).

NEW **BACCARAT (Atari only)** Price: $18.95 Cassette/$22.95 Diskette
This is the European card game which is the favorite of the Monte Carlo jet set. Imagine yourself at the gaming table with 007 to your left and Goldfinger to your right. Learn and play BACCARAT at your leisure on the Atari. Contains full high resolution color graphics and matching sound. Runs in 16K. Requires one joystick.

NEW **GIN RUMMY (Apple diskette only)** Price: $22.95 Diskette
This is the best micro computer implementation of GIN RUMMY existing. The computer plays exceptionally well, and the HIRES graphics are superb. What else can be said?

NEW **POKER PARTY (Available for all computers)** Price: $17.95 Cassette/$21.95 Diskette
POKER PARTY is a draw poker simulation based on the book, POKER, by Oswald Jacoby. This is the most comprehensive version available for microcomputers. The party consists of yourself and six other (computer) players. Each of these players (you will get to know them) has a different personality in the form of a varying propensity to bluff or fold under pressure. Practice with POKER PARTY before going to that expensive game tonight! Apple cassette and diskette versions require a 32 K (or larger) Apple II.

NEW **GO FISH (Available for all computers)** Price: $14.95 Cassette/$18.95 Diskette
GO FISH is a classic children's card game. The opponent is a friendly computer with user inputs that are simple enough for small children to easily master. The Apple and Atari versions employ high resolution graphics for the display of hands. A must for children!

NEW **BLACKJACK COACH (32K TRS-80 only)** Price $29.95 Cassette/$33.95 Diskette
BLACKJACK COACH is both a game and an educational tool. With this program you may quantitatively test standard and special playing and betting methods, including the several card count schemes. You can simply play, play with the computer as a coach, or statistically test your method under long run automatic play. All the standard player choices are included: insurance, splitting pairs, double downs and surrender (optional). The computer analyzes the technique and provides detailed summary reports which statistically pinpoint the strengths and weaknesses of your play. Don't risk your money at the tables until you have practiced with BLACKJACK COACH!

THOUGHT PROVOKERS

MANAGEMENT SIMULATOR (Atari, North Star, OSBORNE and CP/M only) Price: $19.95 Cassette $23.95 Diskette
This program is both an excellent teaching tool as well as a stimulating intellectual game. Based upon similar games played at graduate business schools, each player or team controls a company which manufacturers three products. Each play er attempts to outperform his competitors by setting selling prices, production volumes, marketing and design expenditures etc. The must successful firm is the one with the highest stock price when the simulation ends.

FLIGHT SIMULATOR (Available for all computers) Price: $17.95 Cassette/$21.95 Diskette
A realistic and extensive mathematical simulation of take-off, flight and landing. The program utilizes aerodynamic equations and the characteristics of a real airfoil. You can practice instrument approaches and navigation using radials and compass headings. The more advanced flyer can also perform loops, half-rolls and similar aerobatic maneuvers. Although this program does not employ graphics, it is exciting and very addictive. See the software review in COMPUTRONICS. Runs in 16K Atari.

VALDEZ (Available for all computers) Price: $15.95 Cassette/$19.95 Diskette
VALDEZ is a computer simulation of supertanker navigation in the Prince William Sound/Valdez Narrows region of Alaska. Included in this simulation is a realistic and extensive 256 × 256 element map, portions of which may be viewed using the ship's alphanumeric radar display. The motion of the ship itself is accurately modelled mathematically. The simulation also contains a model for the tidal patterns in the region, as well as other traffic (outgoing tankers and drifting icebergs). Chart your course from the Gulf of Alaska to Valdez Harbor! See the software reviews in 80 Software Critique and Personal Computing.

BACKGAMMON 2.0 (Atari, North Star, OSBORNE and CP/M only) Price: $14.95 Cassette/$18.95 Diskette
This program tests your backgammon skills and will also improve your game. A human can compete against a computer or against another human. The computer can even play against itself. Either the human or the computer can double or generate dice rolls. Board positions can be created or saved for replay. BACKGAMMON 2.0 plays in accordance with the official rules of backgammon and is sure to provide many fascinating sessions of backgammon play.

CHESS MASTER (North Star and TRS-80 only) Price: $19.95 Cassette/$23.95 Diskette
This complete and very powerful program provides five levels of play. It includes castling, en passant captures and the promotion of pawns. Additionally, the board may be preset before the start of play, permitting the examination of "book" plays. To maximize execution speed, the program is written in assembly language (by SOFTWARE SPECIALISTS of California). Full graphics are employed in the TRS-80 version, and two widths of alphanumeric di play are provided to accommodate North Star users. See review in onComputing.

FOREST FIRE! (Atari only) Price: $14.95 Cassette/$18.95 Diskette
Using excellent graphics and sound effects, this simulation puts you in the middle of a forest fire. Your job is to direct operations to putout the fire while compensating for changes in wind, weather and terrain. Not protecting valuable structures can result in startling penalties. Life-like variables are provided to make FOREST FIRE! very suspenseful and challenging. No two games have the same setting and there are 3 levels of difficulty.

BLACK HOLE (Apple only) Price: $14.95 Cassette/$18.95 Diskette
This is an exciting graphical simulation of the problems involved in closely observing a black hole with a space probe. The object is to enter and maintain, for a prescribed time, an orbit close to a small black hole. This is to be achieved without coming so near the anomaly that the tidal stress destroys the probe. Control of the craft is realistically simulated using side jets for rotation and main thrusters for acceleration. This program employs Hi-Res graphics and is educational as well as challenging.

NEW **SPACE EVACUATION! (Apple, Atari and TRS-80 only)** Price: $15.95 Cassette/$19.95 Diskette
Can you colonize the galaxy and evacuate the Earth before the sun explodes? Your computer becomes the ship's computer as you explore the universe to relocate millions of people. This simulation is particularly interesting as it combines many of the exciting elements of classic space games with the mystery challenge of ADVENTURE.

MONARCH (Atari only) Price: $11.95 Cassette/$15.95 Diskette
MONARCH is a fascinating economic simulation requiring you to survive an 8-year term as your nation's leader. You determine the amount of acreage devoted to industrial and agricultural use, how much food to distribute to the populace and how much should be spent on pollution control. You will find that all decisions involve a compromise and that it is not easy to make everyone happy. Runs in 16K Atari.

CHOMPELO (Atari only) Price: $11.95 Cassette/$15.95 Diskette
CHOMPELO is really two challenging games in one. One is similar to NIM; you must bite off part of a cookie, but avoid taking the poisoned portion. The other game is the popular board game REVERSI. It fully uses the Atari's graphics capability, and is hard to beat. This package will run on a 16K system.

AVAILABILITY

DYNACOMP software is supplied with complete documentation containing clear explanations and examples. Unless otherwise specified, all programs will run within 16K program memory space (ATARI requires 24K). Except where noted, programs are available on ATARI, PET, TRS-80 (Level II) and Apple (Applesoft) cassette and diskette as well as North Star single density (double density compatible) diskette. Additionally, most programs can be obtained on standard (IBM 3740 single density/double density compatible format) 8" CP/M floppy disks for systems running under MBASIC or CBASIC (for example, Altos, Xerox 820 and many others). 5¼" CP/M diskettes are available for the North Star and Osborne computer systems.

**ATARI, PET/CBM, NORTH STAR, CP/M, IBM, OSBORNE, SUPERBRAIN and XEROX are registered tradenames and/or trade marks.*

***Except where noted, all TRS-80 Model I software is available on cassette (only) for the TRS-80 Model III. Exceptions: VALDEZ, CRIBBAGE, GRAFIX, CHESSMASTER. TRS-80 diskettes are not supplied with either DOS or BASIC.*

****For most North Star disk-based systems. DYNACOMP presently does not support the new North Star Advantage.*

*****For Altair systems having Microsoft BASIC.*

******For SUPERBRAIN systems running under MBASIC or CBASIC (state which).*

DYNACOMP OFFERS THE FOLLOWING

- Widest variety
- Guaranteed quality
- Fastest delivery
- Friendly service
- Free catalog
- Toll free order phone

AND MORE...

STARTREK 3.2 (Available for all computers) Price: $11.95 Cassette/$15.95 Diskette
This is the classic Startrek simulation, but with several new features. For example, the Klingons now shoot at the Enterprise without warning while also attacking starbases in other quadrants. The Klingons also attack with both light and heavy cruisers and move when shot at! The situation is hectic when the Enterprise is besieged by three heavy cruisers and a starbase S.O.S. is received! The Klingons get even! See the software reviews in A.N.A.L.O.G., 80 Software Critique and Game Merchandising.

NEW **LIL' MEN FROM MARS (Atari only)** Price: $19.95 Cassette/$23.95 Diskette
Defend yourself! The little men from Mars are out to get you if you don't get them first. This is a hilarious high resolution animated graphics (arcade) game which exercises much of the Atari's power. Requires one joystick.

SPACETILT (Apple and Atari only) Price: $10.95 Cassette/$14.95 Diskette
Use the game paddles to tilt the plane of the TV screen to "roll" a ball into a hole in the screen. Sound simple? Not when the hole gets smaller and smaller! A built-in timer allows you to measure your skill against others in this habit-forming action game.

NEW **ESCAPE FROM VOLANTIUM (Atari only)** Price: $15.95 Cassette/$19.95 Diskette
Bring the action and excitement of an arcade into your home with ESCAPE FROM VOLANTIUM! To escape you must maneuver your space ship around obstacles and laser blast the dragon (without being eaten). If he is killed with a direct shot (not just a leg lopped off), a door opens to the outside. However, the door does not stay open indefinitely. If you fail to escape in time, the door closes and a new dragon appears. Sometimes you can smash through the door by repeatedly chipping away at it. Other times it is impervious. At the higher levels of play more obstacles and dragons appear, adding to the excitement. Uses high resolution graphics and sound. Runs in 16K.

ALPHA FIGHTER (Atari only) Price: $12.95 Cassette/$16.95 Diskette
Two excellent graphics and action programs in one! ALPHA FIGHTER requires you to destroy the alien starships passing through your sector of the galaxy. ALPHA BASE is in the path of an alien UFO invasion; let five UFO's get by and the game ends. Both games require the joystick and get progressively more difficult the higher you score! ALPHA FIGHTER will run on 16K systems.

THE RINGS OF THE EMPIRE (Atari only) Price: $14.95 Cassette/$18.95 Diskette
The empire has developed a new battle station protected by rotating rings of energy. Each time you blast through the rings and destroy the station, the empire develops a new station with more protective rings. This exciting game runs on 16K systems, employs extensive graphics and sound and can be played by one or two players.

INTRUDER ALERT (Atari only) Price: $14.95 Cassette/$18.95 Diskette
This is a fast paced graphics game which places you in the middle of the "Dreadstar" having just stolen its plans. The droids have been alerted and are directed to destroy you at all costs. You must find and enter your ship to escape with the plans. Five levels of difficulty are provided. INTRUDER ALERT requires a joystick and will run on 16K systems.

NEW **MIDWAY (Atari only)** Price: $14.95 Cassette/$18.95 Diskette
MIDWAY is an exciting extension of the game of Battleship. It mixes the challenges of strategy and chance. Your opponent can be another human or the computer. Color graphics and sound are both included. Runs in 16K.

TRIPLE BLOCKADE (Atari only) Price: $14.95 Cassette/$18.95 Diskette
TRIPLE BLOCKADE is a two-to-three player graphics and sound action game. It is based on the classic video arcade game which millions have enjoyed. Using the Atari joysticks, the object is to direct your blockading line around the screen without running into your opponent(s). Although the concept is simple, the combined graphics and sound effect lead to "high anxiety".

GAMES PACK I (Available for all computers) Price: $10.95 Cassette/$14.95 Diskette
GAMES PACK I contains the classic computer games of BLACKJACK, LUNAR LANDER, CRAPS, HORSERACE, SWITCH and more. These games have been combined into one large program for ease in loading. They are individually accessed by a convenient menu. This collection is worth the price just for the DYNACOMP version of BLACKJACK.

GAMES PACK II (Available for all computers) Price: $10.95 Cassette/$14.95 Diskette
GAMES PACK II includes the games CRAZY EIGHTS, JOTTO, ACEY-DUCEY, LIFE, WUMPUS and others. As with GAMES PACK I, all the games are loaded as one program and are called from a menu. You will particularly enjoy DYNACOMP's version of CRAZY EIGHTS.
Why pay $7.95 or more per program when you can buy a DYNACOMP collection for just $10.95?

MOON PROBE (Atari and North Star only) Price: $11.95 Cassette/$15.95 Diskette
This is an extremely challenging "lunar lander" program. The user must drop from orbit to land at a predetermined target on the moon's surface. You control the thrust and orientation of your craft plus direct the rate of descent and approach angle. Runs in 16K Atari.

SPACE TRAP (Atari only, 16K) Price: $14.95 Cassette/$18.95 Diskette
This galactic "shoot'em up" arcade game places you near a black hole. You control your spacecraft using the joystick and attempt to blast as many of the alien ships as possible before the black hole closes about you.

NEW **CHIRP INVADERS (PET/CBM only)** Price: $14.95 Cassette/$18.95 Diskette
CHIRP INVADERS is an addictive game using action graphics. A Federation space station must be reached before the Chirps conquer the Earth. Stationary obstacles, moving meteors, and the attacking Chirps must all be avoided for a successful journey. Good luck.

NEW **SUPERSUB CHASE (Atari only)** Price: $19.95 Cassette/$23.95 Diskette
SUPER SUB CHASE simulates a search and destroy mission. Set your course and keep an eye on the sonar readings as you hunt for the hidden submarine. Set the depth charge explosion depth and watch them sink towards the sub. This is an addictive game which takes advantage of the Atari's graphics and sound capabilities. One or two players. Joystick(s) required.

ADVENTURE

CRANSTON MANOR ADVENTURE (North Star and CP/M only) Price: $19.95 Diskette
At last! A comprehensive Adventure game for North Star and CP/M systems. CRANSTON MANOR ADVENTURE takes you into mysterious CRANSTON MANOR where you attempt to gather fabulous treasures. Lurking in the manor are wild animals and robots who will not give up the treasures without a fight. The number of rooms is greater and the associated descriptions are much more elaborate than the current popular series of Adventure programs, making this game the top in its class. Play can be stopped at any time and the status stored on diskette. Not available in 5¼" CP/M format.

GUMBALL RALLY ADVENTURE (North Star only, 48K) Price: $21.95 Diskette
Take part in this outlaw race from the east coast to the west coast. The goal is to find your way to the finish line while maintaining the highest possible speed. You may choose one of five cars available at the garage. The choice will affect your speed and range. Remember to take spare parts and don't get caught speeding!

NEW **UNCLE HARRY'S WILL (North Star only, 40K)** Price: $24.95 Diskette
Uncle Harry has died and has left you everything. However, he has neglected to mention where everything is! Instead, his will consists of a poem which contains clues. You will have to travel all over the United States both by car and on foot to solve the puzzle, and there are over 300 locations to probe. Be careful and watchout for red herrings!

SPEECH SYNTHESIS

DYNACOMP is now distributing the new and revolutionary TYPE-'N-TALK™ (TNT) speech synthesizer from Votrax. Simply connect TNT to your computer's serial interface, enter text from the keyboard and hear the words spoken. TNT is the easiest-to-program speech synthesizer on the market. It uses the least amount of memory and provides the most flexible vocabulary available anywhere!

TYPE-'N'-TALK List price $375. DYNACOMP'S price $319.95 plus $5.00 for shipping and handling.

TALK TO ME (T'N'T Atari only, 24K) Price: $14.95 Cassette/$18.95 Diskette
This program presents a superb tutorial on speech synthesis using the Atari 800 and TYPE 'N TALK™. TALK TO ME will illustrate normal word generation as well as phoneme generation. The documentation includes many helpful programming tips. TALK TO ME has been demonstrated on network (CBS) TV!

MISCELLANEOUS

CRYSTALS (Atari only) Price: $ 9.95 Cassette/$13.95 Diskette
A unique algorithm randomly produces fascinating graphics displays accompanied with tones which vary as the patterns are built. No two patterns are the same, and the combined effect of the sound and graphics are mesmerizing. CRYSTALS has been used in local stores to demonstrate the sound and color features of the Atari. Runs in 16K Atari.

NORTH STAR SOFTWARE EXCHANGE (NSSE) LIBRARY
DYNACOMP now distributes the 23 volume NSSE library. These diskettes each contain many programs and offer an outstanding value for the purchase price. They should be part of every North Star user's collection. Call or write DYNACOMP for details regarding the contents of the NSSE collection.
Price: $9.95 each/$7.95 each (4 or more)
The complete collection may be purchased for $149.95

NEW **5¼" DISKETTES (soft sectored/ten sectored)** Price: $39.95/20 Diskettes
As you might imagine, DYNACOMP purchases diskettes in large quantities and at wholesale prices. We want to pass the savings along to you!

Circle 158 on inquiry card.

BUSINESS and UTILITIES

NEW

MAILMASTER (Atari diskette only) — **Price: $39.95 Diskette**
MAILMASTER is a very versatile software package for managing and manipulating mail lists and mini data bases. Each disk can hold over 600 customer entries containing name, address, 38 letter key words and a phone number. The display is marked so that entries may be made and edited with ease. The status (e.g., disk space left, options, etc.) is shown at all times. Labels may be printed 1,2 or 3 up, and all sorting (zip code and alphabetic) is performed by a fast machine language program.

PERSONAL FINANCE SYSTEM (Atari and North Star only) — **Price: $39.95 Diskette**
PFS is a single diskette, menu-oriented system composed of ten different programs. Besides recording your expenses and tax deductible items, PFS will sort and summarize expenses by payee, and display information on expenditures by any of 26 user defined codes by month or by payee. PFS will even produce monthly bar graphs of your expenses by category! This powerful package requires only one disk drive, minimal memory (24K Atari, 32K North Star) and will store up to 600 records per disk (and over 1000 records per disk by making a few simple changes to the programs). You can record checks plus cash expenses so that you can finally see where your money goes and eliminate guesswork and tedious hand calculations. Contains high speed machine language sort. PFS has been demonstrated on network (CBS) TV!

FAMILY BUDGET (Apple and Atari only) — **Price: $34.95 Diskette**
FAMILY BUDGET is a very convenient financial record-keeping program. You will be able to keep track of cash and credit expenditures as well as income on a daily basis. You can record tax deductible items and charitable donations. FAMILY BUDGET also provides a continuous record of all credit transactions. You can make daily cash and charge entries to any of 21 different expense accounts as well as to 5 payroll and tax accounts. Data are easily retrieved giving the user complete control over an otherwise complicated (and unorganized!) subject.

INTELINK (Atari only) — **Price: $49.95 Diskette**
This software package contains a menu-driven collection of programs for facilitating efficient two-way communications through a full duplex modem (required for use). In one mode of operation you may connect to a data service (e.g., The SOURCE or MicroNet) and quickly load data such as stock quotations onto your diskette for later viewing. This greatly reduces "connect time" and thus the service charge. You may also record the complete contents of a communications session. Additionally, programs written in BASIC, FORTRAN, etc. may be built off-line using the support text editor and later "uploaded" to another computer, making the Atari a *very* smart terminal. Even Atari BASIC programs may be uploaded. Further, a command file may be built off-line and used later as controlling input for a time-share system. That is, you can set up your sequence of time-share commands and programs, and the Atari will transmit them as needed; batch processing. All this adds up to saving both connect time and your time.

NEW

PAYFIVE (Apple II plus diskette, two drives required) — **Price: $149.95**
This is an enormously flexible employee payroll system with extraordinarily good human engineering features. PAYFIVE prints checks and compiles the required federal, state and local forms for up to 148 employees. The pay methods may be hourly, salary, commission or any combination. There are multiple options for pay periods, and they also can be used in any combination. PAYFIVE includes *many* other features and comes extremely well documented with a 200 page manual. The manual may be purchased separately for $30, and that payment later applied to the software purchase.

SHOPPING LIST (Atari only) — **Price: $12.95 Cassette/$16.95 Diskette**
SHOPPING LIST stores information on items you purchase at the supermarket. Before going shopping, it will remind you of all the things you might need, and then display (or optionally print) your shopping list and the total cost. Adding, deleting, changing and storing data is very easy. Runs with 16K.

TAX OPTIMIZER (North Star only) — **Price: $59.95 Diskette**
The TAX OPTIMIZER is an easy-to-use, menu oriented software package which provides a convenient means for analyzing various income tax strategies. The program is designed to provide a quick and easy data entry. Income tax is computed by all tax methods (regular, income averaging, maximum and alternate minimum tax). The user may immediately observe the tax effect of critical financial decisions. TAX OPTIMIZER has been thoroughly field tested in CPA offices and comes complete with the current tax tables in its data files. TAX OPTIMIZER is tax deductible!

NEW

UTIL (Apple only, 48K) — **Price: $19.95 Diskette**
UTIL is a disk-oriented utility system which permits examining and changing of the contents of DOS 3.2 and 3.3 diskettes at the bit (nibble or byte) level. With UTIL you can easily examine the contents of a diskette sector by sector, restructure the sector pointers, reallocate sectors (e.g. bad sectors may be "hidden"), and perform many other sophisticated operations. For the experienced programmer.

NEW

TURNKEY AND MENU (Atari only) — **Price: $17.95 Diskette**
TURNKEY is a utility program which allows you to create autoboot/autorun diskettes easily. Simply load and run TURNKEY, load the program diskette to be modified, and answer the questions! The TURNKEY diskette also comes with DOS 2.0 and includes another program, MENU. MENU lists the contents of your diskette alphabetically, and permits the running of any BASIC program on the diskette by typing a single key. TURNKEY and MENU provide you with the ability to run any program on your diskette by simply turning on the computer and pressing a single key.

NEW

STOCKAID (Atari only) — **Price: $29.95 Diskette**
STOCKAID provides a powerful set of tools for stock market analysis. With STOCKAID you can display point and figure charts, as well as bar charts with oscillators. You can also examine long term moving averages and on-balance volume features. STOCKAID allows you to input daily data with a single diskette storage capability of 239 days × 16 stocks. Included are stock dividend and split adjustment capabilities. A very professional package!

NEW

SHAPE MAGICIAN (Apple II, 48K, diskette only) — **Price: $29.95**
At last! An utility for painlessly creating graphics shapes for the Apple. Create, edit and save up to 30 shapes which can then be used to develop arcade games or to simply enhance your programs. Add that professional touch!

EDUCATION

HODGE PODGE (Apple only, 48K Applesoft or Integer BASIC) — **Price: $14.95 Cassette/$18.95 Diskette**
Let HODGE PODGE be your child's teacher. Pressing any key on your Apple will result in a different and intriguing "happening" related to the letter or number of the chosen key. The program's graphics, color and sound are a delight for children from ages 1½ to 7. HODGE PODGE is a non-intimidating teaching device which brings a new dimension to the use of computers in education. See the excellent reviews of this very popular program in INFOWORLD and SOFTALK.

NEW

TEACHERS' AIDE (Atari only) — **Price: $13.95 Cassette/$17.95 Diskette**
TEACHERS' AIDE consists of three basic modules contained in one program. The first module provides addition and subtraction exercises of varying levels of difficulty. The second module consists of multiplication problems in which the student may be tested both on the final answer and/or on the subtotal answers in the long hand procedure. Several levels of complexity are provided here as well. The third module consists of division problems; one particularly nice feature of the division module is that the long hand division steps can be displayed along with the remainder in order to clearly demonstrate the procedure by which the remainder is derived. Using TEACHER'S AIDE is not merely a drill, but rather a learning experience.

NEW

PHARMACOLOGY UPDATE (PET only) — **Price: $169.95 Cassette/$149.95 Diskette**
This is DYNACOMP's first educational software entry for the medical profession (more are coming!). PHARMACOLOGY UPDATE was written by a R.N. as a masters project, with the aid of a practicing pharmacologist and an electronics instructor. This package comes in two parts. The first part is a 200 page manual which is divided into 11 sections. Each of these sections provides both concise information and probing questions. The second part consists of 11 programs that are keyed to the text and which test the degree of your understanding of the text material. This package has great educational value for the beginning student as well as the professional interested in an efficient way to review and update his or her knowledge. Available on cassettes (11) or diskette.

NEW

TEACHER'S GRADEBOOK (Apple 48K dual/single drive) — **Price $49.95 Diskette**
TEACHER'S GRADEBOOK is a *complete* password protected record-keeping system for the classroom. It supports up to nine users, and each user may have data for up to nine classes on one disk (with up to 90 students per class). Typical information which can be entered, edited and processed includes rosters, absences and grades. Summary reports may be displayed (on the screen) or printed in various ways, with automatic weighted averaging and conversion to letter grades. This system has been tested ("goof-proofed") in the class environment and is both well-written and well-documented.

ORDERING INFORMATION

All orders are processed and shipped within 48 hours. Please enclose payment with order and include the appropriate computer information. If paying by VISA or Master Card, include all numbers on card. Purchase orders accepted.

Shipping and Handling Charges
Within North America: Add $2.00
Outside North America: Add 15% (Air Mail)

Delivery
All orders (excluding books) are sent First Class.

Quantity Discounts
Deduct 10% when ordering 3 or more programs. Dealer discount schedules are available upon request.

8" CP/M Disks
Add $2.50 to the listed diskette price for each 8" floppy disk (IBM soft sectored CP/M format). Programs run under Microsoft MBASIC or BASIC-80.

5¼" CP/M Disks
All software available on 8" CP/M disks is also available on 5¼" disks, North Star and Osborne format.

Ask for DYNACOMP programs at your local software dealer. Write for detailed descriptions of these and other programs from DYNACOMP.

DYNACOMP, Inc. (Dept. B)
1427 Monroe Avenue
Rochester, New York 14618
24 hour message and order phone: (716)442-8731
Toll free order phones: (800)828-6772
(800)828-6773
Office phone (9AM-5PM EST): (716)442-8960

VISA



New York State residents please add 7% NYS sales tax.

STATISTICS and ENGINEERING

DIGITAL FILTER (Available for all computers) — **Price: $39.95 Cassette/$43.95 Diskette**
DIGITAL FILTER is a comprehensive data processing program which permits the user to design his own filter function or choose from a menu of filter forms. In the explicit design mode the shape of the frequency transfer function is specified by directly entering points along the desired filter curve. In the menu mode, ideal low pass, high pass and bandpass filters may be approximated to varying degrees according to the number of points used in the calculation. These filters may optionally also be smoothed with a Hanning function. In addition, multi-stage Butterworth filters may be selected. Features of DIGITAL FILTER include plotting of the data before and after filtering, as well as display of the chosen filter functions. Also included are convenient data storage, retrieval and editing procedures.

DATA SMOOTHER (Not available for Atari) — **Price: $19.95 Cassette/$23.95 Diskette**
This special data smoothing program may be used to rapidly derive useful information from noisy business and engineering data which are equally spaced. The software features choice in degree and range of fit, as well as smoothed first and second derivative calculation. Also included is automatic plotting of the input data and smoothed results.

FOURIER ANALYZER (Available for all computers) — **Price: $19.95 Cassette/$23.95 Diskette**
Use this program to examine the frequency spectra of limited duration signals. The program features automatic scaling and plotting of the input data and results. Practical applications include the analysis of complicated patterns in such fields as electronics, communications and business.

TFA (Transfer Function Analyzer) — **Price: $19.95 Cassette/$23.95 Diskette**
This is a special software package which may be used to evaluate the transfer functions of systems such as hi-fi amplifiers and filters by examining their response to pulsed inputs. TFA is a major modification of FOURIER ANALYZER and contains an engineering-oriented decibel versus log-frequency plot as well as data editing features. Whereas FOURIER ANALYZER is designed for educational and scientific use, TFA is an engineering tool. Available for all computers.

HARMONIC ANALYZER (Available for all computers) — **Price: $24.95 Cassette/$28.95 Diskette**
HARMONIC ANALYZER was designed for the spectrum analysis of repetitive waveforms. Features include data file generation, editing and storage/retrieval as well as data and spectrum plotting. One particularly unique facility is that the input data need not be equally spaced or in order. The original data is sorted and a cubic spline interpolation is used to create the data file required by the FFT algorithm.

FOURIER ANALYZER, TFA and HARMONIC ANALYZER may be purchased together for a combined price of $51.95 (three cassettes) and $63.95 (three diskettes).

REGRESSION I (Available for all computers) — **Price: $19.95 Cassette/$23.95 Diskette**
REGRESSION I is a unique and exceptionally versatile one-dimensional least squares "polynomial" curve fitting program. Features include very high accuracy; an automatic degree determination option; an extensive internal library of fitting functions; data editing; automatic data, curve and residual plotting; a statistical analysis (eg: standard deviation, correlation coefficient, etc.) and much more. In addition, new fits may be tried without reentering the data. REGRESSION I is certainly the cornerstone program in any data analysis software library.

REGRESSION II (PARAFIT) (Available for all computers) — **Price: $19.95 Cassette/$23.95 Diskette**
PARAFIT is designed to handle those cases in which the parameters are imbedded (possibly nonlinearly) in the fitting function. The user simply inserts the functional form, including the parameters (A(1), A(2), etc.) as one or more BASIC statement lines. Data, results and residuals may be manipulated and plotted as with REGRESSION I. Use REGRESSION I for polynomial fitting, and PARAFIT for those complicated functions.

MULTILINEAR REGRESSION (MLR) (Available for all computers) — **Price: $24.95 Cassette/$28.95 Diskette**
MLR is a professional software package for analyzing data sets containing two or more linearly independent variables. Besides performing the basic regression calculation, this program also provides easy to use data entry, storage, retrieval and editing functions. In addition, the user may interrogate the solution by supplying values for the independent variables. The number of variables and data size is limited only by the available memory.

REGRESSION I, II and MULTILINEAR REGRESSION may be purchased together for $51.95 (three cassettes) or $63.95 (three diskettes).

ANOVA (Not available on Atari cassette or for PET/CBM) — **Price: $39.95 Cassette/$43.95 Diskette**
In the past the ANOVA (analysis of variance) procedure has been limited to the large mainframe computers. Now DYNACOMP has brought the power of this method to small systems. For those conversant with ANOVA, the DYNACOMP software package includes the 1-way, 2-way and N-way procedures. Also provided are the Yates 2^{K-P} factorial designs. For those unfamiliar with ANOVA, do not worry. The accompanying documentation was written in a tutorial fashion (by a professor in the subject) and serves as an excellent introduction to the subject. Accompanying ANOVA is a support program for building the data base. Included are several convenient features including data editing, deleting and appending.

BASIC SCIENTIFIC SUBROUTINES, Volumes 1 and 2 (Not available for Atari)
DYNACOMP is the exclusive distributor for the software keyed to the popular texts *BASIC SCIENTIFIC SUBROUTINES, Volumes 1 and 2* by F. Ruckdeschel (see advertisements in BYTE magazine). These subroutines have been assembled according to chapter. Included with each collection is a menu program which selects and demonstrates each subroutine.

Volume 1
Collection #1: Chapters 2 and 3 - Data and function plotting; complex variables and functions.
Collection #2: Chapter 4 - Extended matrix and vector operations.
Collection #3: Chapters 5 and 6 - Random number generators (Poisson, Gaussian, etc.); series approximations.
Price per collection: $14.95 Cassette/$18.95 Diskette
All three collections are available for $39.95 (three cassettes) and $49.95 (three diskettes).

Volume 2
Collection #1: Chapter 1 - Linear, polynomial, multidimensional, parametric least squares.
Collection #2: Chapter 2 - Series approximation techniques (economization, inversion, reversion, shifting, etc.).
Collection #3: Chapter 3 - Functional approximations by iteration and recursion.
Collection #4: Chapter 4 - CORDIC approximations to trigonometric, hyperbolic, exponential and logarithmic functions.
Collection #5: Chapter 5 - Table interpolation, differentiation and integration (Newton, LaGrange, splines).
Collection #6: Chapter 6 - Methods for finding the real roots of functions.
Collection #7: Chapter 7 - Methods for finding the complex roots of functions.
Collection #8: Chapter 8 - Optimization by steepest descent.
Price per collection: $14.95 Cassette/$18.95 Diskette
All eight collections are available for $99.95 (eight cassettes) and $129.95 (eight diskettes).
Because the texts are a vital part of the documentation, *BASIC SCIENTIFIC SUBROUTINES, Volumes 1 and 2* are available from DYNACOMP:

BASIC SCIENTIFIC SUBROUTINES, Vol 1 (319 pages): $19.95 + 75¢ postage
BASIC SCIENTIFIC SUBROUTINES, Vol 2 (790 pages): $23.95 + $1.50 postage

See reviews in KILOBAUD and Dr. Dobbs.

NEW

SOFTNET (Apple II, 48K, diskette only) — **Price $129.95**
SOFTNET may be used to create models of liquid pipeline systems to evaluate their flow performance. Up to 150 nodes with up to 150 connecting elements may be simulated, and models may be combined to form yet larger models. If you are involved in water distribution systems, chemical fluid flow problems, building plumbing, or similar situations, this is an ideal analysis tool.

NEW

MATCHNET (TRS-80 only) — **Price: $19.95 Cassette/$23.95 Diskette**
It often takes days to iteratively optimize an L, Pi or T matching network for a particular application. Take a few minutes with MATCHNET and you will have the Q, frequency response and reflection coefficients for any of twelve matching networks. You input the source and load impedance and MATCHNET calculates the R, C, (and L) values and plots (and/or prints) the frequency response and reflection coefficients for each configuration. The reviewer of this program remembers when he use to do this by hand and loves MATCHNET!

ACTIVE CIRCUIT ANALYSIS (ACAP) (48K Apple only) — **Price: $25.95 Cassette/$29.95 Diskette**
With ACAP you may analyze the response of an active or passive component circuit. The circuit may be probed at equal steps in frequency, and the resulting complex voltages at each component juncture examined; the frequency response of a filter or amplifier may be completely determined with respect to both amplitude and phase. In addition, ACAP prints a statistical analysis of the range of voltage responses which result from tolerance variations in the components. ACAP is easy to learn and use. Circuit descriptions may be saved onto cassette or diskette to be recalled at a later time for execution or editing. ACAP should be part of every circuit designer's program library.

LOGIC SIMULATOR (Apple only; 48K RAM) — **Price: $24.95 Cassette/$28.95 Diskette**
Test your complicated digital logic design with respect to given set of inputs to determine how well the circuit will operate. The elements which may be simulated include multiple input AND, OR, NOR, EXOR, EXNOR and NAND gates, as well as inverters, J-K and D flip-flops, and one-shots. Inputs may be clocked in with varying clock cycle lengths/displacements and delays may be introduced to probe for glitches and race conditions. A timing diagram for any given set of nodes may be plotted using HIRES graphics. Save your breadboarding until the circuit is checked by LOGIC SIMULATOR.

NEW

NUMBERKRUNCHER (TRS-80 only) — **Price: $69.95 Cassette/$73.95 Diskette**
This program is the most complete numerical analysis system available for the TRS-80. It can handle up to 255 data sets, each set having a six character name. It includes complete data editing facilities and convenient data input/output capability. The analyses available are multiple linear regression and correlation determination of residuals, data transformations and extensive graphics generation, including axis naming, and more. The supporting documentation is extremely well written and well organized, and includes appendices which describe the numerical procedures used in the program.

NEW

STATSORT (TRS-80 only) — **Price: $39.95 Cassette/$43.95 Diskette**
STATSORT consists of several menu selected programs which allow the user to create (build, edit, merge), format and print files, (machine) sort them on any field, and numerically analyze (maximum, minimum, average, variance, standard deviation) tabulated data. STATSORT is well documented and easy to use. The cassette version can also be employed to create a data type which can be read by the Radio Shack Advanced Statistical Package.

NEW

STATTEST (TRS-80 only) — **Price: $19.95 Cassette/$23.95 Diskette**
This is a statistical inference package which helps you make wise decisions in the face of uncertainty. In an interactive fashion you can build and edit data files and test the differences in means, variances and proportions. STATTEST will also perform data analysis as well as do linear correlation and regression. This menu-directed statistical workhorse is rounded out with a chi-square contingency test and a (uniform and normal) random sample generator. The documentation is written by a college professor who guides you through the various tests.

ABOUT DYNACOMP

DYNACOMP is a leading distributor of small system software with sales spanning the world (currently in excess of 50 countries). During the past three years we have greatly enlarged the DYNACOMP product line, but have maintained and improved our high level of quality and customer support. The achievement in quality is apparent from our many repeat customers and the software reviews in such publications as COMPUTRONICS, 80 Software Critique, A.N.A.L.O.G., Softalk, Creative Computing and Kilobaud. DYNACOMP software has also been chosen for demonstration on network television. Our customer support is as close as your phone. It is always friendly. The staff is highly trained and always willing to discuss products or give advice.

MOD III

TRS-80 Model III Features for Your Model I

Add video line print, selectable cursor, and automatic key repeat to your TRS-80 Model I.

Joe W. Rocke
224 West Benson
Ridgecrest, CA 93555

I'm a satisfied owner of a Radio Shack TRS-80 Model I, but I can't help envying some of the features of the new Model III. Its video line print, block cursor, and automatic key repeat are indeed useful additions to the TRS-80's repertoire of programming features.

Numerous video-line-print and cursor routines have been published as individual utility programs; however, because they are individual programs, only one can be used at a time. My working with a friend's Model III spawned dreams of a single utility program that would provide all these capabilities for my Model I. My file of programs included video-line-print and cursor routines, so my thoughts turned to combining the two into a single utility program. An automatic key repeat, a user-selectable cursor, and an audible key beep also crept into this programming daydream.

The dream became reality only after several unsuccessful attempts to combine existing program routines. Initial efforts produced workable programs, but not without adverse side effects. High memory overhead offset the benefits provided, and the key-beep feature resulted in slow keyboard response time. When used with my editor/assembler, the utility routines preempted the memory occupied by the automatic key repeat.

Programming is somewhat akin to building construction. It is often easier to build anew than to remodel the old. With this in mind, I took a fresh program approach, literally starting with a blank video screen. This effort resulted in a utility program that I call MOD III.

The MOD III utility program uses fewer than 170 bytes of RAM, making it practical even on a 16K-byte memory system.

MOD III Features

The MOD III program source code presented in listing 1 provides video line print, a block cursor, and automatic key repeat. This program also provides two added side benefits: the cursor style is user-changeable, and the key repeat automatically provides key debounce. Better still, the program uses fewer than 170 bytes of random-access read/write memory (RAM). This low memory overhead makes the program practical for use with a 16K-byte memory system.

MOD III is compatible with most disk operating systems (DOS), the Beta cassette system, the EDTASM+ editor/assembler, and Level II BASIC. It is written for a Level II 48K-byte system, but may be modified for a 16K- or 32K-byte RAM system by changing the starting address. Changes required for DOS are annotated in the source code remarks (see listing 1).


MOD III was initially written in assembly language to conserve memory space and provide the quick response required for the automatic key-repeat feature. The original plan was to place the program at a low RAM location just under the BASIC block and reset the BASIC pointers. This would eliminate the need to set memory size before loading MOD III. However, in this location it would be wiped out by disk BASIC or by programs such as EDTASM+. Changing the program to load to high memory provided the system and program compatibility desired.

Memory Protect

Because MOD III starts at a high RAM address, it's necessary to set memory size before loading the program. By calculating the number of bytes required for the program, you can establish the starting address that will load the program to the very top of memory to conserve RAM space.

Text continued on page 386

WE'LL "DRIVE" YOU WILD



with our variety of quality disk drives.

ASAP carries only the highest quality floppy disk drives, to provide you with years of trouble-free service and superior performance.

Data Trak™ double-sided, double-density drives from Qume® feature state-of-the-art technology. You get superior data integrity through improved disk life, data reliability and drive serviceability.

Data Trak™ 5 (ANSI 5¼" compatibility) .... Call for price
Data Trak™ 8 (IBM compatibility) .... Call for price

Shugart drives have been setting industry quality and reliability standards for years. Shugart's Bi-Compliant™ head assembly provides superior media compliance and high reliability.

Model 801 (standard floppy) $400.00
Model 850 .... $640.00

ASAP also provides a full line of high reliability disk drive subsystems. For superior quality, high reliability disk drives, contact ASAP today.

Part No. — Description* **Price**

HDC8/1-HD — Cabinet with (1) Priam 10 megabyte hard disk drive with Microbyte Controller .... Call for price

HDC8/1F+1HD — Cabinet with (1) Qume® DT-8 double-sided, double-density drive, and (1) Priam 10 megabyte hard disk drive with Microbyte Controller .... Call for price

CAB8H — Dual cabinet for 8" floppy disk drives (horizontal mounting) .... $ 225.00

CAB8V — Cabinet for 8" floppy disk drives (vertical mounting)........................... $ 225.00

CAB8H/V+1S — Dual cabinet with (1) Shugart SA801R installed (horizontal or vertical mounting) .... $ 675.00

CAB8H/V+2S — Dual cabinet with (2) Shugart SA801R's installed (horizontal or vertical mounting) $1055.00

CAB8H/V+1Q — Dual cabinet with (1) Qume® DT-8 double-sided double-density drive installed (horizontal or vertical mounting) .... $ 755.00

CAB8H/V+2Q — Dual cabinet with (2) Qume® DT-8's double-sided double-density drive installed (horizontal or vertical mounting) $1225.00

X5 — Cabinet for desk top mainframe (small power supply) .... $ 200.00

800D — Cabinet for desk top mainframe (standard power supply) .... $ 255.00

*All cabinets come complete with power supply, fan and internal cables.



1198 E. Willow St., Signal Hill, CA 90806

Toll free outside California:
(800) 421-7701
Inside California:
(213) 595-6431
(714) 891-2663

ASAP offers a 30-day buyer protection policy: full money-back guarantee if not totally satisfied.

Ordering information: name, address, phone, ship by: UPS or truck. Please call for shipping charges.

Terms: We accept cash, check, money orders, Visa and Master Charge (U.S. funds only). Tax: 6% Calif. res. COD's and terms available on approval (school PO's accepted).

Circle 460 on inquiry card.

Listing 1: *The source code listing for MOD III. The key-beep feature has been disabled (see lines 850 through 1100). Remove the semicolons to use that feature.*

```
00010 ;****************************************************************
00020 ;**                  KEY-REPEAT AND BLOCK CURSOR               **
00030 ;** WORKS WITH 'DOS' - 'EDTASM' - 'BASIC' - ETC.               **
00040 ;****************************************************************
00050 ;
00060 ;
00070 ;
00080 ;****************************************************************
00090 ;**  FOR JUST 'BLOCK CURSOR' -  USE LINES 1730 UP  ---          **
00100 ;**  SEE 'HOOK' LINES:     1170 THRU 1270                       **
00110 ;****************************************************************
00120 ;
00130         ORG     0FF4DH          ;48K - CHANGE FOR LESS!!!
00140 ;
00150 ;**  IF KEY BEEP IS USED THEN 'ORG' MUST BE CHANGED             **
00160 ;
00170 START   LD      HL,START1       ;PUT A 'HOOK' INTO
00180         LD      (4016H),HL      ;KEYBOARD CONTROL
00190         LD      HL,BEGIN        ;FOR 'ZX' AND BLOCK
00200         LD      (401EH),HL      ;CURSOR ROUTINES
00210         LD      A,8FH           ;'BLOCK CURSOR'
00220         LD      (16409),A       ;PUT IT IN 'POKEABLE ROM'
00230 ;
00240         JP      402DH           ;NEWDOS80 SYSTEM
00250 ;
00260 ;       JP      1A19H            FOR BETA, TC-8 BASIC OR
00270 ;                                NO SYSTEM AT ALL
00280 ;                                OR NOTE: BELOW
00290 ;****************************************************************
00300 ;** NOTE:  TRSDOS, NEWDOS+, ECT. MAY NOT ACCEPT THE             **
00310 ;** ROM III PROGRAM IN COMMAND MODE BUT WILL RUN IN             **
00320 ;** DISK BASIC.  LOAD ROMIII/CIM (ENTER) THEN BASIC             **
00330 ;** DEFUSR1=&HFF4D:PRINT USR1(0)                                **
00340 ;****************************************************************
00350 ;
00360 ;
00370 ;****************************************************************
00380 ;**        MEMORY SIZE?  PROTECTION STARTS HERE                 **
00390 ;**        EQUALS   65375  FOR 48K                              **
00400 ;****************************************************************
00410 ;
00420 START1  LD      HL,4036H        ;HL = KEYBOARD BUFFER
00430         LD      BC,3801H        ;BC = ROW ADDRESS POINTER
00440         LD      D,00H           ;'D' = ROW COUNT 0 TO 6
00450 LP1     LD      A,(BC)          ;ANYTHING PRESSED ??
00460         LD      E,A             ;PUT IT IN 'E' FOR TEST
00470         AND     E               ;CHECK ALL BITS FOR 0
00480         JR      NZ,LP4          ;NOT ZERO GOTO COUNTER
00490         LD      (HL),A          ;LOAD IT TO MEMORY
00500 LP2     INC     D               ;NEXT KEYBOARD ROW
00510         INC     L               ;BUMP KEYBOARD BUFFER
00520         RLC     C               ;POINT TO NEXT ROW
00530         LD      A,C             ;PUT IT IN A FOR TEST
00540         SUB     80H             ;SUBTRACT 128 DECIMAL
00550         JR      NZ,LP1          ;NOT ZERO? CHECK AGAIN!
00560         LD      A,(HL)          ;GET COPY OF OUR CHAR.
00570         LD      B,07H           ;COUNT OF SEVEN
00580 LP3     DEC     L               ;BACKUP KEYBOARD BUFFER
00590         ADD     A,(HL)          ;ADD MEMORY TO 'A'
00600         DJNZ    LP3             ;GO FOR COUNT IN 'B'
00610         CP      00H             ;CHECK FOR ZERO IN 'A'
00620         LD      A,00H           ;ZERO 'A' REGISTER
00630         RET     NZ              ;RETURN WITH CHARACTER
00640         LD      (401AH),A       ;PUT 0 IN KEY CONT. BLK
00650         RET                     ;RETURN TO PROGRAM
00660 LP4     AND     (HL)            ;CHECK EACH BIT FOR 0
00670         JR      Z,LP5           ;GO IF IT IS
00680         LD      A,(401AH)       ;GET BYTE FROM CONT. BLK
00690         INC     A               ;ADD (1) TO IT
00700         LD      (401AH),A       ;PUT IT BACK FOR COUNT
00710         CP      0FFH            ;= 255 DECIMAL ?
00720         JR      NZ,LP2          ;NO = LOOP BACK
00730         DEC     A               ;SUBTRACT (1)
```


Listing 1 continued on page 384

Do you have a restless urge to program?

Do you want the instant respect that comes from being able to use technical terms that nobody understands?

Do you want to strike fear and loathing into the hearts of DP managers everywhere?

If so, then let the Famous Programmers' School lead you on . . . into the world of professional computer programming.



The staff of the Famous Programmers' School includes some of the best known names in the microcomputing field. From left to right: **Bennett Lisp** (with cigar), **Rod Snobol** (with feelers), **Bruce Fortran** (eating cigar), **Rudolf Forth** (natty attire), **Ignatious "Call Me Blaise" Pascal** (feelers, cigar and flowchart), and the immortal **Red Basic** (smug look).

What Do Top Programmers Earn?

Despite popular myths, some programmers actually do earn a living doing the work they love. Other, less fortunate programmers work in their spare time at home while watching television. Either way, your potential earnings as a computer programmer could reach into the millions, possibly even into the billions, of dollars. Of course, your success depends a lot on your abilities, luck, shoe size, the phase of the moon, etc.

Is Programming for You?

Programming is not for everyone. But if you have a desire to learn, we can help you get started. All you need is the Famous Programmers' Course and enough money to keep those lessons coming month after month.

Take Our Free Aptitude Test

To help you determine if you are qualified to be a programmer, take a moment to try this simple test:

1) Write down the numbers from zero to nine and the first six letters of the alphabet (Hint: 0123456789ABCDEF).

2) Whose picture is on the back of a twenty-dollar bill?

3) What is the state capital of Idaho?

If you managed to read all three questions without wondering why we asked them, you may have a future as a computer programmer.

A New Kind of Programming.

They say a good programmer can write 20 lines of effective program per day. With our unique training course, we'll show you how to write 20 lines of code and lots more besides. Our training course covers every programming language in existence, and some that aren't. You'll learn why the on/off switch for a computer is so important, what the words FATAL ERROR mean, and who and what you should blame when you make a mistake.

Student Successes

Many of our students have gone on to achieve great success in all fields of programming. One former student developed the concept of the personalized form letter. Does the phrase, "Dear Mr. (insert name), You may already be a winner!," sound familiar? Another student writes, "After only five lessons I sold a 'My Most Unforgettable Program' article to Corrosive Computing magazine."

Another of our graduates writes, "I recently completed a database-management program for my department manager. My program touched him so deeply that he was speechless. He told me later that he had never seen such a program in his entire career. Thank you, Famous Programmers' School; only you could have made this possible."

Don't Delay

Send for our introductory brochure that explains in vague detail the operation of the Famous Programmers' School, and you'll be eligible to win a possible chance to enter a drawing, the winner of which can vie for a set of free steak knives. If you don't do it now, you'll hate yourself in the morning.

Famous Programmers' School
Dept. APRFOL
P.O. Box 463
Paulsborough, NH
03458-0463

Yes, I want the brochure describing this incredible offer. I enclose $1000 in small unmarked bills to cover the cost of postage and handling. (No live poultry, please.) Send the information to:

Name: ____________

Address: ____________

City, State: ____________ Zip: ______

Our Slogan: Top down programming for the masses.

Listing 1 continued:

```
        LD      (401AH),A       ;STORE NEW VALUE
        LD      A,E             ;CHAR. WAS SAVED IN 'E'
LP5     LD      (HL),E          ;ADD IT TO MEMORY
        PUSH    BC              ;SAVE COPY IN STACK
        LD      BC,600          ;SHORT DELAY COUNT
        CALL    0060H           ;ROM DEC. BC TO 0
        POP     BC              ;NOW RESTORE 'BC'
        LD      A,(BC)          ;TRANSFER TO 'A'
        AND     E               ;CHECK OUR COPY
        RET     Z               ;RETURN IF ZERO
;
;***************************************************************
;**      KEY BEEP IS HERE BUT 'NOT' BEING USED               **
;***************************************************************
;
;       PUSH    BC              ;SAVE 'BC'
;       PUSH    HL              ;SAVE 'HL'
;       PUSH    AF              ;SAVE 'AF'
;       LD      B,40H           ;= 64 DECIMAL
;       LD      A,(403DH)       ;PRINT SIZE FLAG
;       AND     0FDH            ;= 253 DECIMAL
;       LD      H,A             ;RESULT TO 'H'
;       OR      02H             ;OR WITH '2' FOR SOUND
;       LD      L,A             ;TRANSFER TO 'L'
;LP6    LD      A,L             ;BACK TO 'A' FOR OUTPUT
;       OUT     (0FFH),A        ;OUT CASSETTE PORT
;       LD      A,H             ;GET BYTE FROM 'H'
;       OUT     (0FFH),A        ;OUT CASSETTE PORT
;       PUSH    BC              ;SAVE 'BC' FOR COUNT
;       LD      B,40H           ;= 64 DECIMAL
;LP7    DJNZ    LP7             ;DELAY HERE FOR COUNT
;       POP     BC              ;RESTORE 'BC'
;       DJNZ    LP6             ;LOOP UNTIL ZERO
;       POP     AF              ;RESTORE REGISTERS
;       POP     HL              ;DONE WITH BEEP
;       POP     BC              ;DON'T FORGET 'BC'
;
;***************************************************************
;**  FOLLOWING JUMP HAS TO BE USED BEEP OR NOT!!!             **
;***************************************************************
;
        JP      03FBH           ;ROW COUNTER IN ROM
;
;***************************************************************
;**      TO USE JUST 'ZX' AND CURSOR ROUTINE                  **
;**    YOU HAVE TO PUT A 'HOOK' IN 401EH AS FOLLOWS           **
;***************************************************************
;                                                              *
;       ORG     0EF00H          ;START SOMEPLACE!              *
;                                                              *
;START  LD      HL,BEGIN        ;GET ADDRESS                   *
;       LD      (401EH),HL      ;STORE IN VIDEO BLOCK          *
;       JP      402DH           ;1A19H FOR 'BASIC'             *
;***************************************************************
;
;***************************************************************
;**  'ZX'  LINEPRINT STARTS HERE CAN BE CHANGED TO            **
;**  ANY VALUE THE USER PLEASES AS LONG AS THE RIGHT          **
;**  ROW AND KEY VALUE ARE USED TO CHECK FOR IT ----          **
;***************************************************************
;
BEGIN   EX      AF,AF'          ;SWAP REGISTERS
        EXX                     ;ALL OF THEM !
        LD      A,(3808H)       ;= 'ZX' ROW
        CP      05H             ;= 'ZX' PRESSED ??
        JR      NZ,OUT          ;NO = EXIT FAST
        LD      HL,3C00H        ;THEN POINT TO VIDEO
        LD      E,10H           ;= 16 VIDEO LINES
LOOP    LD      C,40H           ;= 64 CHRS./LINE
LOOP1   CALL    TEST            ;CHECK ON PRINTER
        LD      A,(HL)          ;GET FIRST CHARACTER
        LD      (37E8H),A       ;OUTPUT TO PRINTER PORT
        LD      A,(3840H)       ;SPACEBAR ROW
        CP      80H             ;= SPACEBAR PRESSED?
```

Listing 1 continued on page 386

There's great business ahead!

And here is THE DATA BASE to get you there.

Meet **GBS**...the most complete, most powerful **relational** database management system available. It was designed to go beyond the capabilities of ordinary DBM systems. And it does. Where others may possibly be state-of-the-art...GBS, our General Business System, is **ahead-of-the-art**!

Because it is **relational,** GBS is far more valuable to you and your business. It has the capability to access an almost unlimited amount of data from a variety of files, then combine that data and display or print it in a format that **you** specify.

Relational, Efficient & Automatic

GBS can automatically search for, locate, and interrelate information from many files. For example, on each order entry it can automatically decrement inventory; automatically post the data to your Accounts Receivable and automatically update your General Ledger. You don't have to spend countless hours making redundant entires, with the chance for numerous errors. GBS' inter-file relationships and adjustments save you considerable time, and thus many hours of high-cost labor.

Most other business programs are limited single file systems, whereas GBS allows you to work with 3 different files at the same time. All Indexes are updated automatically. What's more, a large GBS data file can extend over 4 different disk drives...not merely one. No other data base system has the power and flexibility of GBS!

A program generator, par excellence

Included as a part of GBS is a very powerful applications development tool, called QUICK GEN. Basically, this function allows almost anyone -- even those unsophisticated about computers -- to generate useful business programs. Think of the efficiency you gain when anyone on your staff can quickly generate a needed program to solve a particular problem! But, GBS versatility doesn't stop there. GBS is also ...

...a Fully Programmable system...

... which allows you, or those with deeper computer interest, to create almost any business application program, such as accounts payable/receivable ... payroll ... general ledger ... order entry ... mailing lists ... personnel files ... cost accounting ... real estate listings ... time/expense management, and many more. And each one will be a personalized program ... individualized to the specific requirements of **your** firm!

Start using GBS now

You can. Because GBS is up and running on most popular CP/M* based computers, like those made by Apple, Tandy, Xerox, Sharp, NEC, Hewlett Packard, Toshiba, Osborne, Televideo, Vector, Altos and more.


You can. Because GBS documentation is written in a friendly, free-flowing, style...and it leads you by the hand with plenty of tutorials and easily understandable examples. And, the entire documentation is typeset for ease of reading.

You can. Because GBS is fully supported by QUALITY SOFTWARE. So, if you ever have a question, or need assistance, simply contact QUALITY SOFTWARE and our professional support people will be happy to help.

You can. Because we offer a special **30-Day Money Back Guarantee.** Order your edition of GBS at $700 (on disk, with complete professional documentation) and try GBS in your own business environment. If GBS isn't all we say it is, and more, simply return it within 30 days for a full refund. This offer is for a limited time only, so please act immediately.

Call Today

There's great business ahead. And GBS is the **relational** data base management system which can help you control your information and data quickly, efficiently and effectively. Call us today for additional information or to take advantage of our special **30-Day Money Back Guarantee.**



GBS -- it's the best business decision you can make, for today and the future.



QUALITY SOFTWARE
6660 Reseda Blvd., Suite 107
Reseda, CA 91335 (213) 344-6599

*CP/M is a registered trademark of Digital Research.

Circle 347 on inquiry card.

Listing 1 continued:

```
01480          JR      Z,OUT1          ;YES = EXIT
01490          INC     HL              ;ADD NEXT CHARACTER
01500          DEC     C               ;MINUS (1) CHARACTER
01510          JR      NZ,LOOP1        ;LOOP FOR 64 CHARACTERS
01520          CALL    TEST            ;PRINTER BUSY?
01530          LD      A,0DH           ;CARRIAGE RETURN
01540          LD      (37E8H),A       ;DO IT!
01550          DEC     E               ;NEXT LINE - PLEASE
01560          JR      NZ,LOOP         ;ALL 16 LINES?
01570          JR      OUT             ;GO IF ALL DONE
01580 TEST     LD      A,(37E8H)       ;CHECK BYTE AT PRINTER
01590          CP      3FH             ;63 DEC. = PRINTER BUSY
01600          JR      NZ,TEST         ;LOOP UNTIL READY
01610          RET                     ;RETURN TO CALLER
01620 OUT1     CALL    TEST            ;CHECK ON PRINTER
01630          LD      A,0DH           ;CARRIAGE RETURN
01640          LD      (37E8H),A       ;DO IT ON PRINTER!
01650 OUT      EX      AF,AF'          ;RESTORE REGISTERS
01660          EXX                     ;ALL OF THEM
01670 ;
01680 ;*************************************************************
01690 ;**        CURSOR ROUTINE STARTS HERE AND                  **
01700 ;**        CAN BE USED SEPERATELY ALSO --                  **
01710 ;*************************************************************
01720 ;
01730 CURSOR   CALL    0458H           ;CALL VIDEO ROM DRIVER
01740          PUSH    AF              ;SAVE 'AF'
01750          PUSH    DE              ;SAVE 'DE'
01760          LD      DE,(4020H)      ;CURSOR POSITION
01770          LD      A,(DE)          ;PUT CHARACTER IN 'A'
01780          CP      5FH             ;= NORMAL CURSOR
01790          JR      NZ,EXIT         ;NOT NORMAL = GO
01800 ;
01810 ;*************************************************************
01820 ;**     MEMORY ADDRESS 16409 DECIMAL IS USED TO  --         **
01830 ;**     STORE THE CURSOR CHARACTER OF USER'S CHOICE         **
01840 ;*************************************************************
01850 ;
01860          LD      A,(16409)       ;** POKE 16409 WITH
01870          LD      (DE),A          ;ANY CHARACTER TO SUIT
01880 EXIT     POP     DE              ;YOUR NEEDS FOR A CURSOR
01890          POP     AF              ;EXAMPLE:  POKE 16409,176
01900          RET                     ;RETURN TO PROGRAM
01905          NOP
01910          END     START           ;AUTO STARTS WITH *? /
```

Text continued from page 380:

Subtracting the starting address (in decimal) from the ending address provides the byte count. Subtracting the byte count from the top of memory (in decimal) indicates where the program would have to start to load to the top of memory. Since it is necessary to protect only that portion of memory into which MOD III is loaded, this figure also represents the memory-size value that must be entered upon power-up.

The starting address in listing 1 is for a 48K-byte system. To calculate the starting address for a 16K- or 32K-byte system, subtract 169 (the minimum byte count) from 32,767 (16K) or 49,151 (32K) as applicable. Convert the result to the equivalent hexadecimal notation and use it for the ORG (origin) address in line 130.

The foregoing is applicable to the program as written. If you want to add additional lines or include the key-beep feature, be aware that doing so will increase the program byte count. The memory space occupied by the program must be increased by changing the starting address accordingly.

Very "tight" code was used in writing the MOD III source code to keep memory overhead low. Read-only memory (ROM) routines were used frequently, although not many ROM calls are evident. The approach to im-

NOW. OASIS-16: STRICTLY BUSINESS.

The 16 bit operating system designed specifically for *business micro-computing.*
Application software?—it's here, NOW!

OASIS-16*: the operating system designed for business. Not just a hobby or development system rewritten for business use, it is the natural evolution of OASIS**: the multi-user system with a world-wide reputation as *the* standard for those who take business seriously.


And here's more good news: there's no waiting for *application software* because what now runs on OASIS is upward compatible to run on OASIS-16. That means plenty of proven software, *available immediately*.

OASIS-16 puts it all in one package. *For manufacturers:* one source for operating systems, languages, tools; custom implementation to maximize hardware potential; international support & training; flexible licensing agreements. *For software developers:* complete portability keeps application software machine independent; integrated tool set makes development easier, faster. *For end-users:* user-friendliness; data security; portability simplifies system expansion; plus an extensive application software library.

Computing professionals have long told us 'OASIS makes micros run like minis' —with OASIS-16, it's truer than ever. And that's strictly good business.

*For 8086, 68000, Z8000, LSI-11, & others.
**For Z80.

THE OASIS-16 PACKAGE CONTAINS: Operating System; EXEC JCL Language; Editor; Script Output Text Formatter; Assembler; Linkage Editor; Diagnostic & Conversion Utilities; BASIC Interpreter & Compiler; 'C' Compiler.



OASIS 16
STRICTLY BUSINESS

FEATURES: File & Automatic Record Locking; Logon, Password & Privilege Level; User Accounting; Re-Entrant BASIC Interpreter & Compiler; ISAM, Keyed, Direct & Sequential Files; and more. Plus some of the best, most extensive documentation in the industry.

OPTIONS: COBOL; PASCAL; FORTRAN; RDBMS; 2780/3780 Bisync; Networking; and others.


PHASE ONE SYSTEMS, INC.
7700 Edgewater Drive, Suite 830
Oakland, CA 94621-3051
Telephone 415/562-8085 TWX 910-366-7139

I'm serious about my business—
please send me quick:

☐ OASIS-16 Manual, $75
☐ OASIS Manual, $60
☐ Free Application Software Directory
and put me on your mailing list.
(Add $3 for shipping; California residents add sales tax.)

Name__________
St. (No Box#)__________
City______ State___ Zip___
☐ Check enclosed ☐ UPS C.O.D.
☐ VISA ☐ Mastercharge
Card No.______ Exp. date______
Signature__________

Circle 329 on inquiry card.





plementing the key-repeat feature was to intercept the ROM keyboard buffer and thus minimize the calls required for this feature.

Hook Lines

Although the program actually starts at the ORG address, the first 20 bytes are used as hook lines that establish conditions for program operation. These lines are used only once each time the program is loaded; therefore, they can be written over after the program is executed. The main program starts at the key-repeat module. This is where memory size must be set. To calculate the memory-size protect number, subtract 21 from the decimal equivalent of the line 130 starting address (the additional byte is used as a safety factor).

Key Beep

A modular approach was used in developing MOD III. Each of the three main features of the program was originally written as a stand-alone routine. Each routine was debugged, tested, and proven workable before the three were combined into a single program. Note that although the key-beep module has been included in the source listing, it is not a part of the assembled program. (This is due to the use of semicolons, which cause the assembler to treat the program lines as remarks.)

The key-beep feature introduced a few disadvantages. It is necessary to plug the AUXiliary cord into an amplifier to get an audible beep; however, this activates the cassette tape recorder (CTR) OUT line. (I discovered this when loading a program. With key beep active, the CTR started when the PLAY button was pressed.) This isn't a problem as long as you are aware of it.

I use a Radio Shack miniamplifier as a sound source. Beep volume is controlled by the amplifier volume control. At a low level, the beep is barely discernible, reminding me of a "squeaky" key. At a higher level, a sharp, short beep is heard as each key is depressed. But I found that the beep became annoying during long sessions at the keyboard.

EPSON

PRINTERS & ACCESSORIES

Common Features of the MX80, MX80FT & MX100 Printers

- 80 characters per second
- Replaceable print head by user
- User programable from BASIC
- Bi-directional logic seeking printhead
- 96 ASCII characters
- Programable tabs (vert./horz.)
- Cartridge ribbons
- Self-test mode
- Tractor/pin feed paper flow
- Extreme reliability
- 12 type fonts under software control
- 9x9 & 9x18 matrix
- Programable form feeds
- Compressed/expanded letters
- Parallel interface standard
- Double strike & emphasized modes

MX80....The Printer that started it all. All of the above features plus extreme ease of use. Complete TRS80 block graphics set as well as user selectable international symbols. Gives correspondence quality printing in several user selectable modes. Dip switch pins may be set for dedicated applications. Complete forms programability from BASIC software.

MX80FT....All the features of the MX80 but with FRICTION feed as well for the use of single sheets of paper or roll paper. An exceptional buy for the user needing the single sheet capability. In the compressed mode 132 characters can be printed across the width of a page which means it can be used for any printouts that normally need a 15 inch wide printer.

MX100... An exceptional printer with a extra quiet printhead and extra heavy duty construction for the intense use of a business environment. Does not have the TRS80 graphic blocks but comes standard with Bit-Image graphics which allow the user control of individual dots for designing specialized graphs, symbols, etc. A best buy for business use.

MX70....For the budget minded a excellent entry level printer. It has most all of the features mentioned above including Bit-Image graphics in place of the TRS80 graphic blocks set. The Printer is unidirectional only. Expandable text can be printed but not compressed. Only single density printings is supported on the MX70. An inexpensive heavy duty printer.

$CALL for BEST prices on Epson Printers All Printers & accessories in STOCK now!!!

If you buy your EPSON somewhere else you'll probably pay too much!

EPSON ACCESSORIES, INTERFACES & CABLES

GRAFTRAX 80 option (bit-image & italics)..$79
CABLE Model I interface & Model III..........$35*
* $25 if purchased with printer
CABLE & INTERFACE to Model I Keyboard..$85
APPLE interface & cable..........................$89
PET IEEE interface & cable (Pet).............$79
SERIAL RS232 unbuffered int.card.........$65
SERIAL RS232 2k buffered int.card........$149
Epson to Color Computer card/cable.....$59
All RIBBONS and CARTRIDGES in Stock



800-433-5184

Radio Shack LINE PRINTERS

Daisy Wheel II	$1695
Line Printer V	$1580
Line Printer VI	$988
Line Printer VII	$325
Line Printer VIII	$699

CUSTOM SOFTWARE FROM TCS

Completely Integrated **BINARY SEARCH TREE** programs now available. This series of programs fully implements the B-TREE structures including INSERTION, DELETION, EDITING & TRAVERSAL. No more sorting or long data file searches and yet files can be larger than memory. Duplicate keys are fully supported. Files can be retrieved in sorted order via B-TREE Traversal. Each of the programs come with fully commented source code so that you can use the modules in your own programming. A Screen oriented Input routine is also included in each module. The following B-TREE programs are now available and each includes all of the mentioned modules and full documentation:

B-TREE Library (organize your home library keyed by author)..........................$39.95
B-TREE Video (organize your video cassette library, prints labels, etc)............$39.95
B-TREE Mailing List (keyed by name or zip,label printing,etc).........................$49.95

EPSON PACK A Utility Software package for MX80 & 80FT.
MX80/CMD will send all printer commands from DOS. BIGLETT/BAS prints large Graphic Letters. EPSON/SUB merges with BASIC programs allowing 2 letter mneumonic commands to be sent to printer. JKL Patchs allow JKL in NEWDOS 80 1.0 & NEWDOS 2.1 to send graphics properly. DEMO/BAS tutorial program of use of printer.LABEL/BAS custom label making program with graphics. DEFSTATE/SUB allows one word BASIC commands for centered titles, titles with borders, etc. A great program package for EPSON fans.
SPECIAL DEAL: $24.95 with printer $34.95 seperately. Specify Model 1 or III..disk only

EPSON PACK 2 - GRAFTRAX version for MX80, 80FT & MX100. This package includes updated versions of modules in original Epson Pack. A screen oriented BIT IMAGE GRAPHICS generator utility is provided. Create your special characters, symbols, etc. directly on your monitor and then send to printer. Printout includes code to generate graphics and will save needed code as BASIC program line to disk. Then MERGE these into your BASIC pro gram. Also demo programs showing use of Bit-Image graphics. Full documentation.
INTRO SPECIAL: $24.95 with printer or GRAFTRAX. $34.95 separately. $7.50 for update of old Epson Pack

ZAP3 - Direct read/write access to any TRSDOS 1.2 or 1.3 sector. Disable Passwords & access levels. Self prompting. Modify any sector in HEX or ASCII. Includes many patches to TRSDOS 1.2 & 1.3. Also COPYIT to allow backups of SCRIPSIT, VISICALC, etc. Just....$24.95

SDIR - Super directory manipulation for TRSDOS 1.2 or 1.3. Alpha 4 column directory & free space. Display a range of programs by extension. Change name and date. Generate report of location of any program on diskette. Just....$14.95

SPECIAL DEAL: Buy ZAP3 & SDIR together for $29.95

CASIO ELECTRONIC ORGANS have arrived!!!

The fantasic CASIO Electronic Organs are here in force. Fully equal to any $2000 traditional Organ with dozens of exciting NEW features not seen on other musical instruments:

CASITONE CT—403 (25 instruments,16 rythms,chord memory,etc.)..................$519
CASITONE CT-701 (programable, barcode reader,51 keys,etc.,etc.)..................$835

TEXAS COMPUTER SYSTEMS

Offers Lowest Prices on

TRS-80

Model II 64K



The best buy for small business needs and yet completely expandable as your business grows. Easy to use for the beginning operator. We have in STOCK all accessories and disk expansions as well as printers and software. **IMPORTANT**: We also have CP/M for the Model II plus a large amount of support software. All of these items at our fabulous DISCOUNT prices. We ship from DFW by air and fully insured for FAST safe delivery.

HARD DISK SUPPORT FOR THE MODEL II...NOW!

5, 10 or 20 Megabytes (up to 80 Megabytes) for the Model II. Full CP/M support. Also full support for TRSDOS and all TRSDOS software. Multiple computers (multi-user) can be connected to these hard disk systems and can share and access common data bases under both CP/M and TRSDOS. The same common data base can even be accessed simultaneously by several users. We use top of the line CORVUS Hard Disk Drives which have a proven track record and have outsold all of their competitors combined in the microcomputer market. Model I and III are also supported by these Hard Disk Systems. $Call for our LOW prices.

COLOR COMPUTERS

Orginal mfg.warranty on these items:

4K Level 1	$308
16K Level 1	$439
16K Extended Basic	$459
32K Extended Basic	$569
Color Disk 0...$499	Disk 1...$349

TCS 180 day Limited warranty on TCS items:

16K Level 1	$369
16K Extended Basic	$439
32K Extended Basic	$499
32K Upgrade Kit (TCS)	$79
EPSON/COLOR Int.& cable	$59

TRS80 MODEL III COMPUTER SYSTEMS

The following with Radio Shack Warranty:

Model III 16k	$825
Model III 32k	$979
Model III 48k	$1089
Model III 48k 2 Drives RS232	$2069

The following with quality TCS memory & our own 180 day limited warranty:

Model III 32K	$909
Model III 48K	$969

MODEL III DISK EXPANSION KITS

We use the highest quality fiberglass **CONTROLLER BOARDS** with double sided glass epoxy board and gold plated contacts in our TCS systems. The finest switching **POWER SUPPLY** available is also provided. The aluminum **MOUNTING HARDWARE** has slotted holes for easy installation of the drives and includes all the power and data cables necessary to install the controller, drives and power supply.

Our **DISK DRIVES** are made by Tandon the same company that makes the drives used by Radio Shack. These drives are 40 track, double density, 5 millisecond stepping rate and are fully burned in for 48 hours. These drives have the same specifications as the drives used by Radio Shack. No soldering or modifications to existing circuitry is necessary. The following kits are available:

KIT 1	**Controller, Power Supply & Mounting Hardware**	**$379**
KIT 2	**Controller, Power Supply, Hardware & 1 Disk Drive**	**$595**
KIT 3	**Controller, Power Supply, Hardware & 2 Disk Drives**	**$819**
KIT 4	**One Tandon Disk Drive (bare drive only)**	**$219**
KIT 5	**16K of High Quality TCS Memory chips**	**$49.95**
KIT 6	**32k of High Quality TCS Memory chips**	**$79.95**

MODEL III 48K 2 DISK DRIVES KIT....$1753

Yes, you read it right. A complete 48k 2 Disk Drive Model III computer system for just $1753. Here's what you get: one TRS80 Model III 16k Computer in factory carton, one CONTROLLER, POWER SUPPLY & HARDWARE kit (kit 1), two Tandon Disk Drives and 32K of TCS Memory. You also receive several important extras that make this a complete super kit. These extras include a complete illustrated instruction and trouble shooting manual, a TRSDOS 1.3 operating system and manual and a special diagnostic Diskette for testing the unit after you have put it together. The only tool necessary is a screwdriver. EVERYTHING is included in this kit and the price is right...$1753

MODEL III 48k 2 DISK DRIVES ... $1895

Above KIT fully assembled, with 48 hour burn-in test & 180 day TCS Limited Warranty!!

DEALER INQUIRIES ARE INVITED ON THE ABOVE TCS KITS

For fast, efficient service. **Heart of** we can air freight from Dallas

TEXAS COMPUTER SYSTEMS

P.O. Box 1327 Arlington, Texas 76004-1327

Toll Free Number 800 433-5184

Texas Residents 817 274-5625

Payment: Money order, cashiers or certified check. Prices above reflect3% cash Discount Call for Visa/MC card prices.

- Prices subject to change at any time
- No Tax out-of-state. Texans add 5%.
- Many items shipped FREE. Call for quote.

Circle 413 on inquiry card.

Source Code Modules

The source code listing has been structured to allow use of any one or a combination of the modules. For example, the video-line-print module (lines 1210 through 1580) can be keyed in as a stand-alone program. In doing so, appropriate starting and ending addresses must be added to the routine. Lines 130, 170, 180, 190, and 260 will provide the start and entry points. The following lines must be added to the "ZX" routine to complete a stand-alone listing:

```
1590 JP    0458H   ;GOTO
                    NORMAL
                    VIDEO IN
                    ROM
1600 END  START   ;EQUALS
                    TRANSFER
```

The key-beep routine has been included in the source-code listing for readers who wish to try it. To include the routine when keying in the code, the remark character (;) must be left out. Otherwise, it is not necessary to enter lines 760 through 1010.

The program starting address must be changed to a lower value if the key-beep routine is included. As the program byte count has not been calculated with key beep included, this must be done by picking an arbitrary starting address, assembling the program, and then calculating total byte count. Once the byte count is determined, the starting address can be changed accordingly.

MOD III BASIC Version

A BASIC language version of MOD III is provided in listing 2 for those who do not have an editor/assembler. The program listing is somewhat shorter than the assembly-language version because it does not include key beep.


As written, this program is self-checking for the correct response to RAM-size input (see lines 40 through 100). An INKEY$ routine (see lines 50, 60, and 90) is used for the input to prevent scrolling. If you enter two numbers in response to the RAM-size prompt, the program automatically branches to line 70 to check the input value. It is not necessary to press the ENTER key to conclude the input.

Line 70 checks the validity of the input value. If the A + B input is valid (i.e., 16, 32, or 48), program flow is directed to the corresponding lines. An invalid entry will erase the numbers that were typed after the RAM-size prompt and set up the INKEY$ routine for a new input cycle.

Listing 2: *The BASIC listing for MOD III. The disk BASIC commands have been disabled; remove the apostrophes to enable these lines.*

```
1 '       * MOD3 *  BASIC VERSION 8.1
2 '                  BY
3 '               J. ROCKE
4 '
10 CLS:PRINT:PRINT TAB(12)"BASIC PROGRAM TO POKE ";CHR$(34);"MOD III";CHR$(34)
20 PRINT:PRINT TAB(11)"INTO MEMORY USING DATA STATEMENTS"
30 PRINT:PRINT TAB(19)"BY:  JOE W. ROCKE":PRINT:PRINT
40 PRINT TAB(3)"<ENTER> THE SIZE OF RAM (16, 32, 48) THEN <RUN> ";CHR$(143);" ";
50 GOSUB90:A=VAL(A$):PRINT@565,A;:A=A*10
60 GOSUB90:B=VAL(A$):PRINT@565,A+B
70 IF (A+B)=16 THEN 110 ELSE IF (A+B)=32 THEN 120 ELSE IF (A+B)=48 THEN 130 ELSE
 PRINT@565,"      "
80 GOTO 50
90 A$=INKEY$:IFA$=""THEN 90
100 RETURN
110 RUN 170
120 TM=PEEK(16561)+PEEK(16562)*256:IFTM<48000 THEN 140 ELSE 350
130 TM=PEEK(16561)+PEEK(16562)*256:IFTM<60000 THEN 140 ELSE 560
140 PRINT@565,"      ":GOTO50
150 '************  16K - ROM III DATA  ************
160 '**      MEMORY SIZE?  32608
170 POKE 16526,77:POKE 16527,127:'NORMAL BASIC
180 'DEFUSR1=&H7F4D:'DISK BASIC
190 FOR Z8= 32589  TO 32767:READ Z9:POKE Z8,Z9:NEXT Z8
200 A=USR(0):'NORMAL BASIC
210 'PRINT USR1(0):'DISK BASIC
220 END
230 DATA 33,97,127,34,22,64,33,170,127,34,30,64,62,143,50
240 DATA 25,64,195,25,26,33,54,64,1,1,56,22,0,10,95,163,32
250 DATA 26,119,20,44,203,1,121,214,128,32,241,126,6,7,45
260 DATA 134,16,252,254,0,62,0,192,50,26,64,201,166,40,16
270 DATA 58,26,64,60,50,26,64,254,255,32,217,61,50,26,64
280 DATA 123,115,197,1,88,2,205,96,0,193,10,163,200,195,251
290 DATA 3,8,217,58,8,56,254,5,32,54,33,0,60,30,16,14,64
300 DATA 205,217,127,126,50,232,55,58,64,56,254,128,40,25
310 DATA 35,13,32,238,205,217,127,62,13,50,232,55,29,32
320 DATA 225,24,16,58,232,55,254,63,32,249,201,205,217,127
330 DATA 62,13,50,232,55,8,217,205,88,4,245,213,237,91,32
340 DATA 64,26,254,95,32,4,58,25,64,18,209,241,201
350 DELETE 10-350
```

Listing 2 continued on page 392



Our I/O boards are ready to plug in.

You already know you've got the hottest microcomputer on the market. IBM® made it. Now Quadram is setting the standards for hardware to help maximize the capabilities of your Personal Computer... for the very lowest price.

Add more byte to your IBM Personal Computer. Now!

Expanded memory. Until recently, if you wanted a floppy disk, an RS-232C board, and 256K bytes of memory — all five slots were filled. Thanks to Quadram, you can have 256K system memory by adding just one card, freeing up the other four slots for additional functions. Or, get the Quadram Deluxe board with up to 192K RAM, a clock/calendar, parallel interface and serial adapter. All on one board!

Full-line IBM add-ons with off-the-shelf availability. Expanded memory... additional capabilities... and unbeatable prices. Quadram's ready now to help your IBM bite off more. (We have been shipping off-the-shelf since late 1981.)

In-stock products	Retail price
Deluxe board (64K RAM installed)	$595
64K RAM card	$395
128K RAM card	$595
192K RAM card	$795
Serial RS-232C asynchronous adapter single port adapter dual port expansion kit	 $129 +60
Clock/calendar board (with diskette)	$159
Parallel interface card and cable	$159

Available soon: Non-Volatile RAM; Game I/O; Parallel/Game I/O Combination; 192K Memory/Clock Combination; ROM Board; Expansion Chassis; Disk-I/O Expansion Chassis; 5, 10, 20 meg Hard Disk.

For further information and the name of your nearest dealer, call (404) 923-6666 or fill in this coupon and mail to: Quadram Corporation, 4357 Park Drive, Norcross, Georgia 30093.

Name

Company Title

Address

City State Zip

Circle 344 on inquiry card.

Listing 2 continued:

```
360 '***********  32K - ROM III DATA  ***********
370 '**      MEMORY SIZE?  48991
380 POKE 16526,77:POKE 16527,191:'NORMAL BASIC
390 'DEFUSR1=&HBF4D:'DISK BASIC
400 FOR Z8=-16563  TO-16385:READ Z9:POKE Z8,Z9:NEXT Z8
410 A=USR(0):'NORMAL BASIC
420 'PRINT USR1(0):'DISK BASIC
430 END
440 DATA 33,97,191,34,22,64,33,170,191,34,30,64,62,143,50
450 DATA 25,64,195,25,26,33,54,64,1,1,56,22,0,10,95,163,32
460 DATA 26,119,20,44,203,1,121,214,128,32,241,126,6,7,45
470 DATA 134,16,252,254,0,62,0,192,50,26,64,201,166,40,16
480 DATA 58,26,64,60,50,26,64,254,255,32,217,61,50,26,64
490 DATA 123,115,197,1,88,2,205,96,0,193,10,163,200,195,251
500 DATA 3,8,217,58,8,56,254,5,32,54,33,0,60,30,16,14,64
510 DATA 205,217,191,126,50,232,55,58,64,56,254,128,40,25
520 DATA 35,13,32,238,205,217,191,62,13,50,232,55,29,32
530 DATA 225,24,16,58,232,55,254,63,32,249,201,205,217,191
540 DATA 62,13,50,232,55,8,217,205,88,4,245,213,237,91,32
550 DATA 64,26,254,95,32,4,58,25,64,18,209,241,201
560 DELETE 10-560
570 '***********  48K - ROM III DATA  ***********
580 '**      MEMORY SIZE?  65375
590 POKE 16526,77:POKE 16527,255:'NORMAL BASIC
600 'DEFUSR1=&HFF4D:'DISK BASIC
610 FOR Z8=-179  TO-1:READ Z9:POKE Z8,Z9:NEXT Z8
620 A=USR(0):'NORMAL BASIC
630 'PRINT USR1(0):'DISK BASIC
640 END
650 DATA 33,97,255,34,22,64,33,170,255,34,30,64,62,143,50
660 DATA 25,64,195,25,26,33,54,64,1,1,56,22,0,10,95,163,32
670 DATA 26,119,20,44,203,1,121,214,128,32,241,126,6,7,45
680 DATA 134,16,252,254,0,62,0,192,50,26,64,201,166,40,16
690 DATA 58,26,64,60,50,26,64,254,255,32,217,61,50,26,64
700 DATA 123,115,197,1,88,2,205,96,0,193,10,163,200,195,251
710 DATA 3,8,217,58,8,56,254,5,32,54,33,0,60,30,16,14,64
720 DATA 205,217,255,126,50,232,55,58,64,56,254,128,40,25
730 DATA 35,13,32,238,205,217,255,62,13,50,232,55,29,32
740 DATA 225,24,16,58,232,55,254,63,32,249,201,205,217,255
750 DATA 62,13,50,232,55,8,217,205,88,4,245,213,237,91,32
760 DATA 64,26,254,95,32,4,58,25,64,18,209,241,201
```

This safeguard prevents program execution until a correct RAM size has been input.

The check for RAM size is a vital feature of the BASIC program. The listing contains three data groups, and the computer will always read the first data group unless directed elsewhere. Without lines 40 through 70, the 16K-byte data would be POKEd to memory regardless of memory size. If this were the case in a 32K- or 48K-byte system, you would have only the equivalent of a 16K-byte system available for use.

Upon branching to a data group corresponding to the RAM size, the normal BASIC vectors are POKEd to memory (lines 170, 380, and 590). Data corresponding to the machine code equivalent values are then READ and POKEd to memory (e.g., lines 190, and 230 through 350). Upon completion of the data READ/POKE operation, unnecessary portions of the program are deleted to conserve memory (see lines 350 and 560). This returns the computer to READY status. Entering a RUN command will then activate the MOD III features.

Keying in the BASIC Program

If you shudder at the thought of keying in long, numerical data statements, take heart! The task is not as big as it may first appear if you are content with a program limited to one memory size only. In this case, the RAM-size input lines may be eliminated.

Only the desired memory-size data group need be typed in for an individualized RAM-size program. Using a 16K-byte RAM size as an example, only lines 150 through 340 need be keyed in. These lines will provide the major MOD III features for a 16K-byte system.

A word of caution is in order. If

THE QUASAR HHC TAKES COMPUTERS WHERE THEY'VE NEVER BEEN BEFORE.

Your Personal, Portable Database.

There were places you couldn't take a computer, or use one. Not any more. The Quasar HHC gives you the power of a computer anywhere you go. Planes, cars and boats, vacations, or wherever you may want to use it. The HHC can be your constant companion. So whatever data files or information you may need or want are always right at hand.

The Quasar HHC gives you the full power of a 6502 microprocessor. Programming in Microsoft Basic or the FORTH-like SNAP. And personal features like file creation, a calculator, and a real-time clock/secretary you can program to display reminder messages.

File data can be passed from one HHC to another or back and forth between an HHC and another computer. Just connect both computers through the HHC RS-232C interface, or transmit/receive over telephone lines with the HHC acoustic coupler.

There's never been a computer like the Quasar HHC. And never a better way to make you more effective.

For information on the Quasar HHC Hand-Held Computer, including how to become a dealer or distributor, write on your letterhead to Quasar Group Director HHC.

Circle 454 on inquiry card.





QUASAR COMPANY, Division of Matsushita Electric Corporation of America, 9401 West Grand Avenue, Franklin Park, Ill. 60131. (312) 451-1200

```
'MODIII'

* A SOFTWARE PROGRAM TO UPGRADE YOUR MODEL I *

BLOCK CURSOR - VIDEO SCREEN PRINT - AUTO KEY REPEAT

TRS-80 MODEL III FEATURES IN ONE PROGRAM
USING LESS THAN 300 BYTES OF MEMORY
```

Figure 1: *Sample output from the video-screen-print routine. If your printer can't handle graphics characters, the source code may have to be modified.*

you have never keyed in a machine code program via a BASIC READ/ POKE listing, note that the program should be saved prior to program execution. Therefore, be sure to save the BASIC program to cassette or disk after it is keyed in and before its execution. By doing so, you will have the source code (i.e., the BASIC program) in case the program bombs due to a typing error.

The BASIC program has been written to include both normal and disk BASIC USR(0) routines. To use the program with disk BASIC, it will be necessary to delete the remark (') character used to mask the disk BASIC statements (see lines 180, 210, 390, 420, 600, and 630). The corresponding normal BASIC lines (e.g., 170 and 200) may either be deleted or edited to become remark statements.

Using MOD III

Memory size must be set before running either version of MOD III. The memory protect values for the BASIC version are provided in lines 160, 370, and 580 of listing 2. The assembly-language (system-load) version will automatically execute upon your entering a slash (/) at the *? prompt after program loading is completed.

The MEMORY SIZE? prompt will be the first thing displayed on the video upon running the BASIC version. Upon your response to the prompt, the corresponding data are POKEd to memory. This is a very short run cycle that completes with a READY prompt. Entering RUN at this point results in program execution. Appearance of the block cursor provides the only visual evidence that the program has been POKEd to memory. From this point on, the video-line-print and key-repeat features are also available. Either version of MOD III is completely unobtrusive once it is loaded to protected memory.

Selectable Cursor

The program, as written, provides a block cursor (ASCII 160). The cursor may be changed by POKing in any ASCII (American Standard Code for Information Interchange) character of your choice. This is done by entering a POKE statement without a line number as follows:

POKE 16409,*nn*


where *nn* may be any ASCII number from 35 to 255. For example, POKing in an ASCII 42 will change the cursor to an asterisk (*).

Video Screen Print

Pressing the Z and X keys simultaneously will output to the line printer whatever is displayed on the screen. The printout can be stopped short of a full display print by pressing the space bar. Graphics characters on the video display will also be printed if the printer has graphics capability. The video-line-print feature has been tested with both the Epson and Okidata printers which have graphics capability. Figure 1 is an example of a video-display printout.

A nongraphics printer may print a period or other symbol in place of any graphics character displayed on

1-UPMANSHIP.



We opened our doors with two basic goals:

To distribute as many software packages to as many dealers as possible.

And to make money doing so.

Our success on both counts is the result of hard work, a positive business attitude and a recognition that you, as a retailer, have a right to be treated fairly and honestly by your distributor.

We're 1-up for three good reasons:

1. We always offer a wide selection of the latest and best microcomputer software packages available anywhere. (Why should you have to hunt for what you need?)
2. Our dealer discounts start with quantities of 1. (Remember all those times you just wanted one or two to see how they'd sell?)
3. We don't play The BackOrder Game. (If we can't ship your order within 48 hours we'll let you know, instead of hanging you out to dry.)

If there's anything else we can do for you, just let us know. Because we're 1-up and we intend to stay that way.

Software Distributors, 9929 Jefferson Blvd., Culver City, CA 90230. Telex 4990032 BVHL, ATT: SOFT

For our dealer info package, call (213) 559-9330.

SOFTWARE DISTRIBUTORS

We won't leave you holding the bag.

the video. The ZX routine may be modified to print a symbol of your choice with a minor change in the source-code listing. However, I haven't investigated this, and such a change must be left to your ingenuity. In attempting to do so, keep in mind that if the ASCII value displayed on the video is greater than 128, it is a graphics character. To modify the program, it would be necessary to load a substitute value less than 128 for a printer character output.

Key Repeat

Holding down any key results in an automatic key repeat. This feature has the advantage of providing a built-in key debounce via an approximate 25-millisecond time-delay loop. Holding down the space bar will automatically advance the cursor. This is convenient for spacing forward to a particular line location.

The key-repeat delay time may be increased if you prefer a slow repeat rate. To increase the time between keystrokes, the only change necessary is to increase the BC count in line 780 of listing 1. For example, changing the line to read:

```
0780 LD BC,1000 ;DELAY COUNT
```

will provide an approximate 50-millisecond delay.

The automatic key-repeat feature has the advantage of providing a built-in key debounce.

Applications

Applications of the MOD III utility features are many. From a cosmetic standpoint, the block cursor provides an aesthetic appearance in keeping with the image that the word "computer" conjures in the minds of many people. I've observed that people sitting at the keyboard for the first time appear to recognize the block cursor automatically as a silent prompt that expects them to do something. I prefer a block cursor simply because of its visibility.

The video-screen-print capability allows you to print out information that may not otherwise be available without altering the program in memory. It is particularly convenient in printing a graphics display, provided the printer has graphics capability.

Automatic key repeat is a nice feature to have, particularly because it costs so little in memory overhead, and I find it more convenient than counting characters when editing a program line. By holding down the space bar, you can quickly advance the cursor to the character to be edited.

Admittedly, MOD III does not emulate all the features of the Model III; but it truly upgrades the capabilities of the Model I at a minimum cost in memory overhead. ■





Give your computer the magic of speech with an ECHO™ Speech Synthesizer!

There are four new models to choose from: the ECHO 80 (TRS-80 models I & III), ECHO 100 (S-100), the ECHO GP (general-purpose, serial/parallel) and the ECHO SBC (single board computer). These join the popular ECHO][(Apple).

ECHO Speech Synthesizers use LPC synthesis pioneered by Texas Instruments, combined with a phoneme-based operating system to provide any vocabulary you desire while using a minimum of your computer's memory.

The TEXTALKER Speech Generator, standard with all ECHOs except the SBC, translates normal English text to speech automatically.

Simple commands allow you to select from:

- 63 different pitch levels
- Words spoken monotonically or with intonation
- Fast or slow speech output
- Entire words pronounced or spelled letter by letter
- Different volumes
- Spoken punctuation if desired

Speech applications are virtually unlimited, ranging from education to games to aiding the handicapped. The flexibility and low price of ECHO Speech Synthesizers make them the logical choice when adding speech to your system.

For more information see your dealer or contact:

SEC **STREET ELECTRONICS CORPORATION**
3152 E. La Palma Avenue, Suite D
Anaheim, CA 92806 Telephone: 714/632-9950

Circle 387 on inquiry card.

Binary-Coded Text

A Text-Compression Method

Trim text size by encoding common character strings.

Dr. Richard Tropper
Department of Psychology
Rhode Island College
Providence, RI 02908

The time is approaching when increasing quantities of textual information will be committed to computer storage. Newspapers, professional journals, and library materials in general all lend themselves to reduction to some form of binary coding. Binary coding, in turn, promises to facilitate storage, access, transmission, and searches of much of the material that traditionally has been reduced to the printed word.

At present, reduction of text to binary code is usually accomplished by translating each character of the text into a byte of data. Often, this is a wasteful strategy that fails to take advantage of redundancies and patterns within the English language as it is used. An alternative to character-byte storage of English-language text is the use of binary-coded text. Binary-coded text exploits the repetitive nature of typical written English to provide economies on the order of 60% of medium requirements over traditional character-byte storage. These savings are achieved without loss of information.

The inefficiency of character-byte storage is apparent when one considers the memory devoted to storing a typical six-letter word. Such a word requires 7 bytes of memory—the first 6 bytes store the six letters and the seventh byte stores the trailing blank. Those 7 bytes occupy 56 bits of memory and can take any one of 2^{56} possible states. If there were on the order of 2^{56} different six-letter words in the English language, then allocating 7 bytes to store one of them might be justifiable.

There are, in fact, considerably fewer than 2^{56} six-letter words in the language. One recent compilation analyzed the contents of 500 samples of English language text (*Computational Analysis of Present-Day American English*, H. Kucera and W. N. Francis. Brown University Press, 1967). Those 500 samples of text composed a body of text 1,014,232 words long, but, all together, there were only 50,406 unique words, of which only 6470 were six letters long. Even allowing for the obvious fact that Kucera and Francis did not conduct an exhaustive search of the totality of written English text, it seems apparent that the allocation of 56 bits is an extravagant expenditure of memory for the identification of a six-letter word.

Theoretically, the number of unique character strings that can appear in English-language text is infinte, but in practice it tends to be quite limited. A typical sample of text is composed of the repetitive use of a few common words and the occasional use of obscure ones. Kucera and Francis reported that within their million-word corpus of text the most frequently occurring word, "the," appeared 69,971 times. That word alone accounted for nearly 7% of the words in the text they examined. They further reported that the 100 most frequently used words accounted for some 47% of their corpus of text, and the 1000 most frequently used words accounted for a little more than two-thirds. Not only are a few common words heavily relied upon, but when a less common word is used, it tends to be reused within the same passage. The result is that the number of unique words that appear in any given sample of text tends to be relatively small. The data reported by Kucera and Francis suggest that a typical 2000-word passage would be

expected to contain fewer than 800 unique words.

Actually, English as it is used is even more limited than these data suggest. Kucera and Francis analyzed their work in terms of word types—unique concatinations of letters. Many of the word types that they counted are simply multiple derivatives of the same word root. A random sampling of their word lists indicates that 12% of the 50,406 words they cataloged can be formed by adding "s" or "es" to other entries within the list. Another 4% can be formed by adding "d" or "ed." Obviously, English as it is used relies on a rather small word base.

These properties of English-language usage suggest a strategy for the efficient storage, transmission, and search of English-language text. It is possible to construct a relatively brief dictionary of the character strings most frequently used in English and to assign a unique binary code to each. Then, for any given text to be encoded, a supplemental string list of those strings found to occur within the original text, but not within the dictionary, is put together. The original text is reduced to a series of pointers that indicate entries in either the dictionary or the string list. For such a text, all that needs to be stored is its string list and its pointer list. A decoding program that contains the dictionary within itself can reconstruct an accurate image of the original text from its string and pointer lists.

Experience with this technique has shown that the lists for such a text would require only about 40% as much medium for storage and correspondingly only about 40% as much time for transmission as the same text storage in traditional character-byte format. String searches of binary-coded text achieve even greater advantages over searches of character-byte text. If any of the elements of a target string are not found in the dictionary or in the string list of a given text, then there is no need to scan the pointer list of that text to see if the elements appear in the required order.

Beginning the Encoding Process

Encoding any given piece of text into binary-coded text is a matter of replacing each character string in the original text with a pointer code. Each pointer is a 2-byte code that identifies a string in either the dictionary or in the string list. (See figure 1.) Bits 0 through 6 and 8 through 10 of each pointer code are address bits. Bit 11 indicates whether the dictionary or the string list is being addressed. Bits 12 through 15 indicate one of the recognized word endings shown in table 1. When the pointer is decoded, it is printed as the string to which it points plus the word ending to which it points and an implied trailing blank.

Bit 7 of each pointer is reserved as a continuation code. When this bit is low, it indicates that the pointer has been abbreviated to a single byte and that bits 8 through 15 are implicitly 0. The effect of implying zeros in bits 8 through 15 is to allow the abbreviated, 1-byte pointers to address the first 128 entries in the dictionary while indicating the null string as the word ending. This permits these 128 entries to be represented by 1-byte, rather than 2-byte, pointers.

The first 24 entries of the dictionary are reserved for punctuation marks. (See table 2, page 404.) There are three general classes of punctuation marks: leading punctuation, trailing punctuation, and special codes. The pointers that indicate leading punctuation decode into the mark they represent but do not generate an implied trailing blank. The pointers for trailing punctuation do generate a trailing blank, but they suppress the trailing blank of the preceding character string. Capitalization of the first letter in a word is treated as a form of leading punctuation. During encoding, leading and trailing punctuation are stripped off each string to which they are found attached. The leading codes, if any, are added to the pointer list, followed by the code for the root string, then by the codes for trailing punctuation, if any. For example, if the English text contained the string:

"Hello!" b̸




Figure 1: *Diagram of a binary-coded text pointer. Of the 16 bits available, 10 are allocated to dictionary addressing, four define the word-ending code (given in table 1), one identifies the dictionary being addressed, and one is a continuation code. In a text stream, the less significant byte appears first. If bit 7 is a 0, this signals that the more significant byte is all zeros and that the next byte is the less significant byte of the next pointer.*

4-Bit Hexadecimal Code	Word Ending
0	(null string)
1	ments
2	ment
3	ings
4	ions
5	ely
6	ers
7	ion
8	ing
9	ly
A	ed
B	's
C	er
D	es
E	s
F	e

Table 1: *Hexadecimal codes assigned to recognized word endings.*

Solve the Energy Crisis with your own hands

Saving energy and money is as easy as switching light bulbs. This free slide rule calculator from Westinghouse shows you where to begin.

Saving energy is everyone's job. You can make it easier, however, if you take a close look at the lamps you're using now.

With the Westinghouse Energy-Saving Calculator, you can instantly analyze each lamp type's efficiency, and decide exactly which kind of bulb is more efficient in offices, plants, showrooms and display areas. You'll also learn how many watts you save and the annual energy cost savings per lamp.

As an example, if you have fluorescents, substituting our Econ-o-Watt® lamps for standard lamps will have an immediate effect—up to 6 watts per socket, with no appreciable change in light level.

For incandescents, the most efficient way to save, besides direct substitution, is by replacing your system with high pressure sodium lamps. These lamps can save up to 80% of the energy expended by incandescents, while producing an equivalent light level.

Call toll free 800-631-1259 to get your calculator.

Westinghouse lamp products and programs offer many other savings opportunities that can make the difference in your operating expenses. Call today and learn why the simplest, most straightforward solution to saving energy is taking matters into your own hands.



A-9703

the corresponding pointer list entry would be:

06 04 xx xx 0B 08

where xx xx is the pointer code for "hello."

The special-punctuation codes include 03 for "space," which is necessary whenever more than one ƀ separates two strings, and 00 for "end-of-line," which is effectively a linefeed/carriage return combination. Codes 01 and 02 are actually abbreviations of frequently occurring concatinations of punctuation codes. The 01 code replaces the sequence of hexadecimal numbers "0F 03 04" whenever that sequence is found in the pointer list. The sequence "0F 03 04" decodes as:

[period, with implied space] [space] [capitalize first letter of next string]

This is a common sequence that typically separates sentences of English-language text; it is efficiently abbreviated into a single byte, 01. Similarly, the special code 02 is the abbreviation for the sequence that begins each paragraph of English.

Pointer Code (Hexadecimal)	Interpretation
00	end-of-line
01	period-space-space-capitalize
02	space-space-space-space-space-capitalize
03	space
04	capitalize first letter of next string
05	leading single quote
06	leading double quote
07	leading left parenthesis
08	trailing double quote
09	trailing comma
0A	trailing right parenthesis
0B	trailing exclamation mark
0C	trailing question mark
0D	trailing colon
0E	trailing semicolon
0F	trailing period
10	trailing single quote
11–17	reserved (no present application assigned)

Table 2: *Pointer codes for punctuation and other common occurrences. The codes shown here are the first 24 words in the dictionary.*

The Dictionary

After the 24 punctuation codes, the remaining 1000 entries in the dictionary are character strings. Some representative entries in this dictionary (which is too long to be printed in its entirety) are given in table 3. The first string entry in the dictionary (the word "the"), therefore, appears at decimal address 24 and is assigned hexadecimal pointer code 18. The next 103 entries (decimal addresses 25 through 127) are assigned sequential hexadecimal pointer codes from 19 through 7F. These 104 entries are the 104 most frequently used words in the English language, according to Kucera and Francis. Together with the 24 punctuation codes, they occupy the lowest 128 addresses in the dictionary. These are the 128 addresses that can be identified with 1-byte pointers. Given that Kucera and Francis report that the 104 most frequently used words account for some 47% of written language and

BYTE'S Best Cellar List



Ciarcia's Circuit Cellar,
Volumes I, II, & III
by Steve Ciarcia

Collections of Steve Ciarcia's perennially popular columns from BYTE Magazine, these three volumes are sure to please home computer users and electronics hobbyists. **Volume I** includes power conversions, programming EPROMs, remote terminal interfacing, touch-input video display, and more. **Volume II,** focusing on projects which interface the personal computer with the home, features useful applications such as a computer-controlled home security system, computerized appliances, input-output expansion for the TRS-80, and even a computer-controlled wood stove. **Volume III** offers low-cost construction projects such as an ultrasonic rangefinder, handheld remote computer control, two speech synthesizers, and a remote-control motorized platform, to name just a few.

Build Your Own Z80 Computer
This complete guide to building a working computer offers engineers, students, and hobbyists an exciting alternative to buying a computer. With clear instructions, Steve Ciarcia fully explains how to build a basic single-board micro-computer based on the Zilog Z80 microprocessor. The finished product features a 1 K-byte operating system, serial and parallel ports, hexadecimal display, audio cassette mass storage, and easy expansion to include a video terminal.

Circle 65 on inquiry card.


McGraw Hill

Please send
_____ Ciarcia's Circuit Cellar, Vol. I $8.00
_____ Ciarcia's Circuit Cellar, Vol. II $12.95
_____ Ciarcia's Circuit Cellar, Vol. III $12.95
_____ Build Your Own Z80 Computer $15.95

Call Toll-Free 800/258-5420

Name ______________________ Check Enclosed ______________________
Address ______________________ Bill Visa/ MasterCard # ______________________
City ______ State ______ Zip ______ Expiration Date ______________________

Please add .75 per book to cover shipping cost.



70 Main Street Peterborough, N.H. 03458

B4

because punctuation is fairly common in English, this scheme provides that a bit more than half the pointers for a typical sample of English-language text can be only 1 byte in length.

The remaining 896 string entries in the dictionary are stored in truncated form. Each of these entries is the result of testing the trailing characters of an entry in Kucera and Francis's word list against each of the recognized word endings given in table 1 and lopping off the longest one from the right side of the word. The 105th entry in the dictionary, for example, is the word root "thos." This was generated by testing the 105th entry in Kucera and Francis's word list, "those," against the recognized word endings in table 1. The longest ending that matched was "e." Therefore, "e" was lopped off "those," leaving "thos." The rest of the dictionary was built up in the same manner except that those entries in the Kucera and Francis list that would have resulted in multiple identical entries in the dictionary were ignored. Consequently, words such as "seem," "seems," and "seemed" resulted in only a single dictionary entry, "seem." This scheme allows multiple derivative words to be represented by a single word root in the main dictionary.

Address (Decimal)	Code Pointer (Hexadecimal)	Dictionary Entry
24	0018	THE
25	0019	OF
26	001A	AND
27	001B	TO
28	001C	A
29	001D	IN
30	001E	THAT
31	001F	IS
32	0020	WAS
33	0021	HE
34	0022	FOR
35	0023	IT
36	0024	WITH
37	0025	AS
38	0026	HIS
39	0027	ON
40	0028	BE
.	.	.
.	.	.
.	.	.
1013	07F5	KITCHEN
1014	07F6	PRODUC
1015	07F7	CLOTH
1016	07F8	FAILUR
1017	07F9	FAMOU
1018	07FA	LONDON
1019	07FB	PUBLISH
1020	07FC	QUICK
1021	07FD	REGARD
1022	07FE	YOU'LL
1023	07FF	ACTIY

Table 3: *Entries from the beginning and end of the dictionary of 1024 words or word parts.*

String List

The string list is created sequentially as the encoding program steps through the original text. Each time the encoder encounters a string, it strips that string of leading and trailing punctuation. The remaining string is then tested against each of the elements of the dictionary and against as much of the string list as has already been made up. If no match is found, the string is truncated by lopping off its longest recognized word ending. The dictionary and string list are then searched again. This time, if no match is found, the remaining truncated string is added to the string list.

As the string list is being created, each entry is added to the preexisting list preceded by a single byte that indicates the length of the entry. For example, if the first three entries in the string list were "boy," "day," and "happy," the string list would initially

Information Encoded	3	b	o	y	3	d	a	y	5	h	a	p	p	y
Hexadecimal	03	02	0F	19	03	04	01	19	05	08	01	10	10	19

Table 4: *An example of a string list. This sample shows the encoding of the words "boy," "day," and "happy." A string list is a list of words and word pieces that belong in a coded passage of text but are not listed in the dictionary.*

New from GDC

THE ONLY BUSINESS-FEATURED MODEM UNDER $200

The GDC 103J-L

The only low-cost 300 bps dial modem
with the same features found in
modems which support business applications
...or your home computer.



Features:

- Operates over all telephone lines — even lines not usable by line powered units
- Data flow indication shows transmit and receive activity
- Carrier detect indication



- Answer/Originate mode is automatically selected — no need to manually switch
- Self diagnostics with Analoop® — loops data from terminal through modem to check operation
- Same high quality as our complete line of DataComm products.

For more information contact the experts at:


General DataComm Industries, Inc.
One Kennedy Avenue
Danbury, CT 06810
(203)797-0711



General DataComm Industries (Canada) Ltd.
104-1220 Innes Road
Ottawa, Ontario K1B 3V3
(613)745-9174

Local Distributors
Boston, MA (617)620-1800
Detroit, MI (313)963-6017
Great Neck, NY (516)482-3500
Los Alamitos, CA (213)431-4865
Los Angeles, CA (213)277-4562
Miami Lakes, FL (305)822-6750
Midland, TX (915)682-6806
Minneapolis, MN (612)535-5330
New York, NY (212)687-2455
Norwalk, CT (203)866-0533
Oklahoma City, OK (405)364-2222
Orlando, FL (305)859-7450
Philadelphia, PA (215)441-8600
Rochester, NY (716)546-5060
Tustin, CA (714)832-9920

Circle 184 on inquiry card.



Models 82A, 83A & 84A from ASAP

OKIDATA's new printer line represents a breakthrough in economical, quality printing. These new printers have more options and features than any previous OKIDATA printer. Faster print speed and throughput, full 96-character ASCII, and both Centronics and RS-232C interfaces standard, all at an affordable price. These models are ideal for home or business, personal or educational applications. And now, ASAP is offering these new printers at prices you won't want to miss. Compare the features below. Then call ASAP to order your OKIDATA printer today. Dealer inquiries invited.

Features	Okidata 82A 80 Column Printer	Okidata 83A 136 Column Printer	Okidata 84A 136 Column Printer
Print speed	120 characters per second	120 characters per second	200 characters per second
Throughput @80 Char./line	76 lines per minute	76 lines per minute	114 lines per minute
Print technique	Bidirectional	Bidirectional	Bidirectional
Dot matrix	9 x 9	9 x 9	9 x 9
Character set	Full 96-character ASCII	Full 96-character ASCII	Full 96-character ASCII
Graphics characters	64 block characters	64 block characters	64 block characters
Interface Centronics 8-bit parallel	Standard	Standard	OPTIONAL (Specify)
RS-232C (1200 bps)	Standard	Standard	—
Size (inches)	14.2W x 12.9D x 5.2H	20.2W x 12.9D x 5.2H	20.2W x 12.9D x 5.2H
Ribbon	Standard typewriter	Standard typewriter	Standard typewriter
Two New Features			
2K Serial Bufferboard (RS-232)	Optional	Optional	OPTIONAL (Specify)
Okigraph, HI-RES Graphics 60 vert. x 66 horiz. dots/inch	Optional	Optional	Standard

Printers

Epson MX-80
80 Column Dot Matrix Printer
Character set: full 96-character ASCII with descenders
Graphics characters: 64 block characters
Centronics-style 8-bit parallel interface standard: Apple, TRS-80. RS-232 interfaces optional.

MX-80 FT/Friction Feed

MX-100/132 Column

CALL FOR PRICE & DELIVERY

Apple Parallel Interface:
AEI-1 W/Cable $69.95

- Standard Interface
- Compatible with Epson & Okidata Printers
- On-board Firmware (2708)
  Optional Cables: $20.00
  AEC-2/Atari to Epson Printer
  TREC-2/TRS-80 to Epson/Okidata Printer
  RSC-1/RS-232 (male to male)

Serial Interface SEI-1 .... $55.00

- Asynchronous 300, 1200, 2400 or 9600 BPS
- Compatible with Epson Printers
- 75 to 9600 BPS

Manufacturer/Model #	Price
Anadex-9501 W/2K buffer	$1295.00
Diablo-630RO	$2095.00
C.Itoh Pro/Writer	Call for price
C.Itoh F-10 Printmaster	Call for price
Texas Instruments-810	$1650.00

Modems

Manufacturer	Model #	Price
Novation	CAT	S 149.00
Novation	d-CAT	S 160.00
Novation	Auto-Cat	S 229.00
DC Hayes	Smart Modem	S 245.00
DC Hayes	Micro Modem II (Apple)	S 320.00
DC Hayes	Micro Modem 100	S 335.00

Lexicon	Lex-11	S 139.00
Livermore	LIV-Star 20M	S 149.00
UDS	UDS 103 LP	S 185.00
UDS	UDS 202 LP	S 245.00

Monitors

Manufacturer	Model #	Price
Amdek	100/12" B&W	S 125.00
Amdek	100-80	S 169.00
Amdek	100G/12" Grn.	S 149.00
Amdek	Color-1 13"	S 375.00
Sanyo	DM 5109CX/9" Grn.	S 175.00
Sanyo	DM 5012/12" B&W	S 270.00
Sanyo	DM 5112ex/12" Grn.	S 290.00
Sanyo	DM C6013/13" Color	S 450.00
Zenith	ZVM-121/12" Grn.	S 115.00

Circle 461 on inquiry card.

Terminals

Manufacturer	Model #	Price
Ampex	Dialogue 80	$ 899.00
Lear Siegler	ADM-5	Call for price
Lear Siegler	ADM-3A	Call for price
Lear Siegler	ADM-3A+	Call for price
Lear Siegler	ADM-31	Call for price
Lear Siegler	ADM-32	Call for price
Lear Siegler	ADM-42	Call for price
Televideo	TVI 910	$ 625.00
Televideo	TVI 912C	$ 725.00
Televideo	TVI 925	$ 825.00
Televideo	TVI 950C	$ 925.00

Components

4116's (200 nS)/5290-3
Apple, TRS-80, Heath
1-15 ...... $1.85 each 50-99 ..... $1.60 each
16-49 ..... $1.70 each 100 up .... $1.40 each

2114 L-2/200 nS
Low-Power 1K x 4 Static RAM
1-16 ..... $2.80 each 50-99 .... $2.60 each
17-49 .... $2.70 each 100 up ... $2.45 each

2708/450 nS
1K x 8 EPROM .... $3.00 each or 8/$22.00

2716/5 Volt
2K x 8 EPROM .... $4.95 each

Support Chips
8080A-CPU ... $ 2.50 Z80A-SIO $22.00
Z80A-CPU ... $ 8.95 8255AC5 .... $ 6.95
Z80A-CTC ... $ 8.95 8257AC5 .... $15.00
Z80A-DART .. $13.95

Regulators
320T5 .... $.80 320T12 .... $.80
340T5 .... $.70 340T12 .... $.75

Connectors

	1-9	10-24	25 up
DB25P	$2.25	$2.15	$2.00
DB25S	$3.25	$3.10	$2.90
DB25C	$ .95	$ .85	$ .75

100 Pin IMSAI
Gold/S-100 Soldertail Connectors
$2.60 each or 10/$2.40 each

Capacitors
1 @ 12 Volt Ceramic ..... 8¢ each or 100/$7.00

DIP Sockets — Low Profile Tin Soldertail

Description	1-9	10-49	50-99	100 up
14 pin tin st	$ .15	$ .13	$ .12	$ .11
16 pin tin st	$ .16	$ .14	$ .13	$ .12
18 pin tin st	$ .19	$ .18	$ .16	$ .14
20 pin tin st	$ .25	$ .23	$ .21	$ .20
24 pin tin st	$ .26	$ .24	$ .22	$ .20
28 pin tin st	$ .32	$ .30	$ .29	$ .27
40 pin tin st	$ .42	$ .40	$ .38	$ .34

SYSTEMS WITH SPICE from CALIFORNIA COMPUTER SYSTEMS

FOR APPLE II™ USERS

Synchronous Serial Interface
Part Number 7712A .... Price: $149.00
Programmable Timer
Part Number 7440A .... Price: $ 95.00
Asynchronous Serial Interface
Part Number 7710A .... Price: $139.00
Calendar/Clock Module
Part Number 7424 .... Price: $ 99.00
3¾ Digit BCD A-to-D Converter
Part Number 7470A .... Price: $ 95.00
12K ROM/PROM Module
Part Number 7114A .... Price: $ 85.00
Parallel Interface
Part Number 7720A .... Price: $125.00
Arithmetic Processor
Part Number 7811A .... Price: $349.00
Centronics Printer Interface
Part Number 7728A .... Price: $125.00

FOR S-100 USERS

32K Static RAM Board
Part Number 2032C .... Price: $610.00
16K Static RAM Board
Part Number 2116C .... Price: $290.00
64K Dynamic RAM Board
Part Number 2065C .... Price: $550.00
Z80A CPU Board
Part Number 2810A .... Price: $265.00
Floppy Disk Controller
Part Number 2422A .... Price: $365.00
CP/M™ Version 2.2 Free With Purchase
S-100 Mainframe
Part Number 2200A .... Price: $475.00
2201A (220VAC) $475.00

S-100 Motherboard
Part Number 2501A .... Price: $150.00
4-Port Serial I/O Interface
Part Number 2710A .... Price: $245.00
2-Serial, 2-Parallel I/O Board
Part Number 2719A .... Price: $275.00
4-Port Parallel I/O Board
Part Number 2720A .... Price: $195.00

Cabinets*

CAB5V — Single cabinet for either Shugart or Qume 5¼", floppy disk drives (cabinet only) .... $ 75.00
CABBH — Dual cabinet for 8" floppy disk drives (horizontal mounting) .... $ 225.00
CABBV — Cabinet for 8" floppy disk drives (vertical mounting) .... $ 225.00
CAB8V/2F-9SMB — Desk top cabinet for (2) 8" Shugart or Qume floppy disk drives, 9-slot motherboard, card cage, fan, dust filter, power supply, and all power and drive cables ... Call for price

ASAP also provides a full line of high-reliability disk drive subsystems with either Shugart or Qume floppy disk drives. .... Call for price

*All cabinets come complete with power supply, fan and internal cables.

Microbyte Boards

Z80A/I-O CPU Board
- A complete single board Z80A CPU with serial/parallel interface (2) Ser. (3) Parallel
- Fully compatible with proposed IEEE S-100 Bus Standard
- Z80A CPU (4MHz version of the Z80)

$329.00 Assembled & Tested

Optional Monitor Program $40.00

64K Dynamic RAM Board
- Fully S-100 bus compatible (4 MHz)
- 64K x 8 bit dynamic RAM
- Low power:
  +8VDC @ 700 mA
  +16VDC @ 100 mA
  -16VDC @ 25 mA
- Built-in capacity with LED indicator and vector interrupt

$475.00 Assembled & Tested

Floppy Disk Controller
- DMA to within 16 Mbyte of memory
- State-of-the-art NEC765 LSI Controller
- IEEE S-100 compatible
- DMA arbitration allows use of multiple boards within a system

$329.00 Assembled & Tested

*CP/M $150.00 Available (Optional)

4-Port I/O Board
- Quad RS-232-C serial ports. One 20 mA current loop port
- Fully IEEE S-100 bus compatible
- Asynchronous communications with Z80A-DART™ or synchronous communications with Z80A-SIO/0™
- Full set of modem control signals, including RI (Ring Indicator)
- Easily configurable to any type of terminal interface

$265.00 Assembled & Tested
Cables Available (Optional)
***CP/M® Trade Mark of Digital Research**

ATARI COMPUTER PRODUCTS

ATARI 800
(16K) Personal Business Computer Features:
- Computer console
- Atari 8K basic
- 57 full stroke alpha-numeric keyboard with four function keys
- Operator's manual
- RF modulator
- Power supply

Call for price

ATARI 400 .... $349.00

Atari Optional Accessories

Model #	Description	Price
810	Disk Drive System	$ 455.00
820	40 Column Dot Matrix Printer	$ 279.00
822	40 Column Thermal Printer	$ 299.00
825	80 Column Dot Matrix Printer	$ 625.00
830	Acoustic Modem	$ 159.00
850	Interface Module	$ 169.00
410	Cassette Recorder	$ 80.00
CX30-04	Paddle Controls	$ 17.95
CX40-04	Joysticks (pair)	$ 17.95

INTRODUCING ASAP's
Atari 800 16K RAM Module: $55.00
1 year warranty parts & labor

Software

Description	Price
Atari	
Basketball	$ 30.00
Super Breakout	$ 30.00
Chess	$ 32.00
Video Easel	$ 25.00
3-D Tic Tac Toe	$ 25.00
Star Raiders	$ 36.00
Asteroids	$ 32.00
Music Composer	$ 42.00
Educational ROM	$ 19.95
Assembler/Editor	$ 45.00
Telelink I	$ 24.00
Space Invaders	$ 30.00
Kingdom	$ 12.95
Missile Command	$ 32.00
Biorhythm	$ 12.95
Graph It	$ 17.95
Energy Czar	$ 12.95
Mailing List	$ 19.95
Touch Typing	$ 19.95
Stock Charting	$ 19.95
Stock Analysis	$ 19.95
Bond Analysis	$ 19.95
Word Processor	$119.00
Personal Finance	$ 64.95
Microsoft BASIC	$ 75.00
Datasoft	
Atari Mailing List Disk	19.95
Atari Character Generator Disk	16.95
Text Wizard Disk	89.95
Micropainter Album 1 Disk	16.95
Micropainter Album 2 Disk	16.95
Le Stick Accessory	30.00
Innovative Design Software, Inc.	
Pool 1.5 HI-RES	$28.95
On-Line Systems	
HI-RES Adv #0 — Mission: Asteroid Disk	19.95
HI-RES Adv #2 — Wiz & Princess Disk	25.00
Roadwork Disk	29.95
Jawbreaker Disk	25.00
Softporn Adventure (X-rated) Disk	25.00
The Next Step Disk	29.95
Personal Software	
Visicalc Disk	169.00
FOR HOME ENTERTAINMENT SYSTEMS	
Activision	
Dragster Cartridge	19.95
Boxing Cartridge	19.95
Checkers Cartridge	19.95
Fishing Derby Cartridge	19.95
Skiing Cartridge	19.95
Bridge Cartridge	25.00
Tennis Cartridge	19.95
Laser Blast Cartridge	19.95
Freeway Cartridge	19.95
Kaboom! Cartridge	19.95
Stampede Cartridge	19.95
Ice Hockey Cartridge	25.00
Arcade Plus	
Ghost Hunter (Cassette)	$ 25.00
Ghost Hunter (Disk)	$ 30.00

DISKETTES from ASAP

Verbatim
5¼" Diskettes

Part #	Sector	Price
MD525-01	Soft	10/$27.50
MD525-10	Hard 10	10/$27.50
MD525-16	Hard 16	10/$27.50
8" Diskettes		
FD32-1000	Hard	10/$35.00
FD34-1000	Soft	10/$35.00

Memorex
5¼" Diskettes

Part #	Side/Dens	Sector	Price
MEM 3481	1/Dbl	Soft	10/$26.50
MEM 3483	1/Dbl	Hard 10	10/$2650
MEM 3485	1/Dbl	Hard 16	10/$26.50
8" Diskettes			
MEM 3060	1/Sgl	Soft	10/$35.00
MEM 3101	2/Sgl	Soft	10/$45.00
MEM 3090	1/Dbl	Soft	10/$45.00
MEM 3102	2/Dbl	Soft	10/$55.00

Scotch 3M
5¼" Diskettes

Part #	Side/Dens	Sector	Price
744-0	1/Sgl	Soft	10/$33.00
744-10	1/Sgl	Hard 10	10/$33.00
744-16	1/Sgl	Hard 16	10/$33.00
745-0	2/Dbl	Soft	10/$59.00
745-10	2/Dbl	Hard 10	10/$59.00
745-16	2/Dbl	Hard 16	10/$59.00

Maxell
5¼" Diskettes

Part #	Side/Dens	Sector	Price
MD1	1/Sgl	Soft	10/$35.00
MD2D	2/Dbl	Soft	10/$49.00
MH1	1/Sgl	Hard 16	10/$39.00
MH2D	2/Dbl	Hard 16	10/$55.00
8" Diskettes			
FD1-128	1/Sgl	Soft	10/$45.00
FH1-32	1/Sgl	Soft 32	10/$45.00
FD2-XD	2/Dbl	Soft	10/$55.00

Elephant Memory Systems

Part #	Side/Dens	Sector	Price
EMS-1	1/Sgl	Soft	$25.00
EMS 2	1/Dbl	Soft	10/$27.50
EMS 3	1/Dbl	Hard 10	10/$27.50
EMS 4	1/Dbl	Hard 16	10/$27.50
EMS 5	2/Dbl	Soft	10/$33.00
EMS 6	2/Dbl	Hard 10	10/$33.00
EMS 7	2/Dbl	Hard 16	10/$33.00

SRW
Media Storage Cases

Part #	Size	Price
SRW-5	5¼"	$2.50 ea.
SRW-8	8"	$3.25 ea.

All prices subject to change without notice. Call for best price.

ASAP offers a 30-day buyer protection policy: full money-back guarantee if not totally satisfied.

Ordering Information: name, address, phone, ship by: UPS or Mail. Shipping charge: add $2.50 up to 1 lb. for UPS blue; add $1.50 for U.S. Mail (U.S. only) ($25.00 minimum order). Call for larger shipments.

Terms: We accept cash, check, money orders, Visa & Master Charge (U.S. Funds only). Tax: 6% Calif. res. COD's and terms available on approval (school PO's accepted).



1198 E. Willow St., Signal Hill, CA 90806

Toll free outside California:
(800) 421-7701
Inside California:
(213) 595-6431
(714) 891-2663

Circle 461 on inquiry card.

read as shown in table 4. ASCII reserves the lower hexadecimal values for control codes, but those codes have no function in the string list. It turns out to be more efficient to give the 90 printable characters hexadecimal codes ranging from 01 to 5A and to reserve the 165 higher codes of 5B through FF for multiple character representations. No extensive or systematic research has been undertaken to identify the most efficient use of these 165 codes, but the following scheme was adopted and employed simply because it seemed reasonable.

Casual inspection of a typical sample of English-language text suggests that, within words, vowels are rarely separated by more than two consonants and that consonants are rarely separated by more than two vowels. This leads to the observation

Hexadecimal Code	Digraph	Hexadecimal Code	Digraph	Hexadecimal Code	Digraph
5B	BA	92	PE	C9	EH
5C	BE	93	PI	CA	EL
5D	BI	94	PO	CB	EI
5E	BO	95	PU	CC	EN
5F	BU	96	PY	CD	EP
60	BY	97	RA	CE	ER
61	CA	98	RE	CF	ES
62	CE	99	RI	D0	ET
63	CI	9A	RO	D1	EV
64	CO	9B	RU	D2	EW
65	CU	9C	RY	D3	IB
66	CY	9D	SA	D4	IC
67	DA	9E	SE	D5	ID
68	DE	9F	SI	D6	IF
69	DI	A0	SO	D7	IG
6A	DO	A1	SU	D8	SH
6B	DU	A2	SY	D9	IL
6C	DY	A3	TA	DA	IM
6D	FA	A4	TE	DB	IN
6E	FE	A5	TI	DC	IP
6F	FI	A6	TO	DD	IR
70	FO	A7	TU	DE	IS
71	FU	A8	TY	DF	IT
72	FY	A9	VA	E0	KV
73	GA	AA	VE	E1	IW
74	GE	AB	VI	E2	OB
75	GI	AC	VO	E3	OC
76	GO	AD	SH	E4	OD
77	GU	AE	VY	E5	OF
78	OY	AF	WA	E6	OG
79	HA	B0	WE	E7	OH
7A	KE	B1	WI	E8	OL
7B	HI	B2	WO	E9	OM
7C	HO	B3	QU	EA	ON
7D	HU	B4	WY	EB	OP
7E	HY	B5	AB	EC	OR
7F	LA	B6	AC	ED	OS
80	LE	B7	AD	EE	OT
81	LI	B8	AF	EF	OV
82	LO	B9	AG	F0	OW
83	LU	BA	AH	F1	UB
84	LY	BB	AL	F2	UC
85	MA	BC	AM	F3	UD
86	ME	BD	AN	F4	UB
87	MI	BE	AP	F5	UG
88	MO	BF	AR	F6	TH
89	MU	C0	AS	F7	UL
8A	MY	C1	AT	F8	UM
8B	NA	C2	AV	F9	UN
8C	NE	C3	AW	FA	UP
8D	NI	C4	EB	FB	UR
8E	NO	C5	EC	FC	US
8F	NU	C6	ED	FD	UT
90	NY	C7	EF	FE	EX
91	PA	C8	EG	FF	ST

Table 5: *A list of 165 common digraphs (two-letter combinations).*

"Without touching your program I can move it to and from Z80, LSI-11,™ 8086, 6502, 8080, 6809, 68000 and 9900-based computers."

JULIE ERWIN, Vice President, Marketing, SofTech Microsystems, Inc.

You can do it too, with SofTech Microsystems' unique software development and execution environment, the UCSD p-System™.

Our UCSD p-System is the only genuinely machine-independent operating system for 8-bit and 16-bit microcomputers. And to over 50,000 end-users and scores of applications developers it is the one proven, reliable answer to software obsolescence.

For software development, it allows you to work in any combination of UCSD Pascal™, FORTRAN-77, BASIC, and assembly language. It provides support for dynamic memory management and multitasking, with a full arsenal of powerful enhancements, such as a versatile Screen Editor, Native Code Generators, a Print Spooler, TURTLEGRAPHICS and XenoFile™, for easy access to CP/M® disks and files.

Users report that our UCSD p-System's friendly, fast and compact execution environment makes it their first choice in software. So whether you're buying or developing software for your IBM, Apple®, Tandy, Commodore, Texas Instruments, Philips or any other small computer, your best move is to our UCSD p-System. Nothing else touches it.

Our UCSD p-System is available for distribution licensing as well as single copy purchase. Visa and MasterCard orders are welcome, or you may write to us for more details.



9494 Black Mountain Road, San Diego, CA 92126. (714) 578-6105
TWX: 910-335-1594

UCSD p-System and UCSD Pascal are trademarks of the Regents of the University of California. LSI-11 is a trademark of Digital Equipment Corporation. XenoFile is a trademark of SofTech Microsystems, Inc. CP/M is a registered trademark of Digital Research, Inc. Apple is a registered trademark of Apple Computer, Inc.

Circle 466 on inquiry card.

Information	3	b	y	3	d	y	5	a	p
Encoded		o			a		h	p	y
Hexadecimal	03	5E	19	03	67	19	C9	BE	96

Table 6: *An example of a more compactly coded string list. This example uses the same words as table 4 but compresses all possible two-letter combinations into 1 byte as given by the entries of table 5. The encoding of the 2 bytes representing "5h" into the single byte, hexadecimal C9, is not a mistake; this will be interpreted correctly by the decoding algorithm.*

that words are largely composed of a series of consonant-vowel or vowel-consonant digraphs. Table 5 is a list of 165 such digraphs. Notice that within table 5 a few of the less likely consonant-vowel and vowel-consonant digraphs have been replaced by a few of the more likely consonant-consonant digraphs. Each digraph is assigned one of the hexadecimal codes from 5B through FF.

After the encoder has stepped through the entire original text and created the complete string list, it is possible to shorten the string list by scanning it for each of the digraphs coded in table 5 and, when a recognized digraph is found, abbreviating it to the appropriate single-byte hexadecimal code. The result is that the string list of "boy," "day," and "happy" is compressed into the string shown in table 6.

Notice that the hexadecimal code for the "5" preceding "happy" is 05. The hexadecimal code for the letter "e" is also 05. So far as the compressing routine is concerned, there is no difference between "5" and "e," so the "5" and the "h" in "happy" end up being compressed into the digraph "eh" and assigned the hexadecimal code C9. When the encoded text is being decoded and the logical inverse of the compressing routine is being performed, the "5" reappears to serve its indexing function. Compressing the string list in this manner reduces its length by about 30%.

An Application

To demonstrate the practical application of binary-coded text, I have reduced a copy of the Gettysburg Address from normally encoded text to binary-coded text. A copy of the original appears in table 7. The resulting binary-coded-text pointer list and string list appear in table 8. In normal character-byte format, the original text occupies 1474 bytes of memory. The pointer list and string occupy 486 and 136 bytes respectively, or a total of 42% of the length of the original text. Table 9 shows the reconstruction of the first line of the Gettysburg Address from the binary-coded text.

PUT YOUR APPLE TO WORK FOR YOU!
WITH THE THUNDERCLOCK PLUS™

As an APPLE user you already know all the things your APPLE can do. Now Thunderware expands that list with the THUNDERCLOCK PLUS, the complete clock/calendar system for your APPLE! Your programs can read the month, date, day-of-week, hour, minute, and second in any of APPLE'S languages. On-board batteries keep your THUNDERCLOCK running accurately when your APPLE is off - for up to 4 years before battery replacement. But that's just the beginning.

The THUNDERCLOCK PLUS is the most useful and versatile peripheral you can put in your APPLE. It can keep your disk files organized by time-and-date-stamping them, it enhances the usability of many of the new business/professional software packages for accounting, filing, and time management, and it can remotely control lights and appliances for security or display purposes in your business or home.

SOFTWARE PRODUCT COMPATIBILITY

Many of today's important software packages for data-base management, business applications, communications, and time management are designed to use the THUNDERCLOCK PLUS. If you have or plan to purchase any of these packages, a THUNDERCLOCK will greatly enhance their usefulness.

•VISIDEX* (Personal Software) •DB MASTER and MICRO-MEMO (Stoneware) •MICRO-COURIER and MICRO-TELEGRAM (Microcom) •THE CASHIER and THE STORE MANAGER (High Technology) •BUSINESS PLUS and NET-WORKS (Advanced Data Systems) ...and many others!

```
DISK VOLUME 254

*A 006 HELLO          07/07 16:37
*A 006 CLOCK          06/08 09:07
*A 004 FRAME          06/08 09:08
*A 004 DISK INFO      06/17 16:13
*B 003 BACKOFF        06/17 16:13
*B 005 SCREEN         07/24 17:32
*B 002 TCPUTIL        06/17 16:13
*B 004 SDTIME.O       06/17 16:13
*A 007 ADIGCLK        05/19 08:05
*A 011 SET TIME       06/08 09:08
*I 009 IDIGCLK        05/19 08:05
*A 007 TIME           06/08 09:08
*A 003 SLOTFINDER     07/07 16:56
*A 014 DEMO           06/17 16:14
```

THUNDERWARE'S DOS-DATER

Our new DOS-DATER software upgrades the regular DOS on your disks so that DOS will use the THUNDERCLOCK to time-and-date-stamp disk files. Every time a program is saved or a file is modified, the current date and time to the minute are stored in the CATALOG with the file's name. You can tell at a glance when a program was saved or when any file was last modified. And this time/date stamping feature is completely automatic. That means any program which uses DOS will time/date stamp its files!

REMOTE CONTROL

Add Thunderware's X-10 INTERFACE OPTION to your THUNDERCLOCK PLUS and your APPLE can control lights and appliances through your BSR X-10 Home Control System on your pre-defined schedules. Our powerful SCHEDULER software allows you to create and modify schedules easily and execute them in the 'background', while using your APPLE for other tasks in the 'foreground'. Use your APPLE for energy management, display and security lighting, or laboratory/process control.

Our PASCAL Software lets you use all the THUNDERCLOCK'S features in PASCAL and sets the F)iler date whenever you boot.

You get all this versatility in just one peripheral system. Backed by a full one year warranty. See your APPLE dealer for a demonstration, or contact us for more information. We'll give your APPLE the best time around!

Suggested retail prices:

THUNDERCLOCK PLUS $139
X-10 INTERFACE OPTION $49
PASCAL SOFTWARE DISK $29
DOS-DATER/DEMO DISK $29
MANUALS ONLY, each $5

Distributed by Apple Computer, Inc. and Computerland Corp.

THUNDERWARE, INC.
P.O. BOX 13322
Oakland, CA 94661
(415)-652-1737

*Requires software supplied on DOS-DATER/DEMO disk.

BSR X—10 is a trademark of BSR (USA) LTD.

APPLE II is a trademark of APPLE COMPUTER, INC

Four score and seven years ago, our fathers brought forth on this continent a new nation, conceived in liberty and dedicated to the proposition that all men are created equal.

Now we are engaged in a great civil war, testing whether that nation or any nation so conceived and so dedicated, can long endure. We are met on a great battlefield of that war. We have come to dedicate a portion of that field, as a final resting place for those who here gave their lives that that nation might live. It is altogether fitting and proper that we should do this.

But, in a larger sense, we can not dedicate—we can not consecrate—we can not hallow this ground. The brave men, living and dead who struggled here, have consecrated it, far above our poor power to add or detract. The world will little note, nor long remember, what we say here, but it can never forget what they did here. It is for us the living, rather, to be dedicated here to the unfinished work which they have thus far so nobly advanced. It is rather for us to be here dedicated to the great task remaining before us—that from these honored dead we take increased devotion to that cause for which they gave the last full measure of devotion—that we here highly resolve that these dead shall not have died in vain—that this nation, under God, shall have a new birth of freedom—and that government of the people, by the people, for the people shall not perish from the earth.

Table 7: *The Gettysburg Address prior to encoding in binary-coded-text form as in table 8.*

(8a)

04	13	64	98	70	12	F6	D4	EA	A5	8C	0E	14	07	64	0E
62	E0	07	81	50	12	A8	07	68	69	61	F6	10	9A	94	9F
A4	03	98	C1	05	CC	73	74	CC	6B	12	0B	5B	14	14	80
6F	CA	04	04	94	12	F6	BB	A6	74	F6	04	6F	14	A3	2D
D4	EA	9E	03	97	14	06	79	0C	82	17	04	02	97	16	07
FF	9B	07	07	0C	07	68	14	97	03	14	06	70	12	74	F6
F9	6F	8D	D8	03	8E	02	6D	04	A9	0E	03	04	A3	13	0B
C9	EA	EC	C6	D1	EE	06	98	A0	0C	16	02	69	04	A9	DB
C4	DD	F6	06	92	99	D8	00								

(8b)

02	92	02	80	F8	1A	BA	06	F5	E0	FB	02	09	66	84	64
F6	02	81	08	00	27	2C	82	08	1C	57	99	74	09	83	A8
1D	84	08	1A	00	85	A8	1B	18	86	78	1E	3B	8E	01	2F
87	A8	F4	07	0F	00	02	63	40	2F	88	A8	1D	1C	9F	01
E4	07	C9	01	09	93	86	CA	C2	00	1E	99	74	32	61	99
74	4B	83	A8	1A	4B	85	A8	09	54	00	90	01	89	F8	01
40	2F	C7	05	27	1C	9F	01	8A	08	19	1E	C9	01	0F	00
40	33	A2	F1	1B	85	F8	1C	8B	78	19	1E	DE	02	09	25
1C	F1	03	00	C5	84	B1	F1	22	80	F1	45	BA	F0	CB	F2
3F	EC	D3	1E	1E	00	99	74	9D	01	EC	F3	01	23	1F	8C
C8	8D	88	1A	CB	C7	1E	40	00	7C	5F	2C	0F	00	02	30
09	1D	1C	8F	C2	B6	F2	09	40	54	2E	85	F8	8E	08	40
54	2E	00	8F	F8	8E	08	40	54	2E	90	08	2C	FB	03	01
18	91	F8	8E	01	09	00	EC	83	1A	9B	04	09	45	92	A8
BA	F0	09	33	8F	A8	23	09	D8	01	00	C1	F2	66	B9	06
9C	C2	1B	A7	04	32	93	08	01	18	8A	01	46	85	F1	00
AE	F0	09	E9	03	90	01	A7	C5	09	4D	40	BA	01	BA	F0
09	30	23	54	96	C1	00	94	08	4D	35	6F	BA	F0	01	23
1F	22	A8	01	18	EC	83	09	81	C2	09	00	1B	28	85	A8
BA	F0	1B	18	95	A8	8F	01	36	35	33	00	B4	E2	D8	01
4B	96	98	97	A8	01	23	1F	81	C2	22	A8	01	1B	28	BA
F0	00	85	A8	1B	18	9F	01	98	08	F2	86	71	A8	01	BE
08	1E	31	00	5B	99	A8	9B	04	40	A9	F1	E8	A3	9A	78
1B	1E	CF	F5	00	22	36	35	CB	F2	18	9C	01	95	03	E9
F7	19	9A	78	8E	08	1E	00	40	BA	F0	BE	91	9B	F8	1E
5B	9B	04	E6	02	2E	33	9C	A8	1D	00	9D	08	8E	08	1E
2C	99	74	09	95	C1	AC	02	09	E6	02	33	1C	57	9E	08
19	00	DD	05	8E	00	1A	1E	DC	21	19	18	81	F1	09	2A
18	81	F1	09	22	00	18	81	F1	E6	02	2E	9F	08	31	18
F4	04	0F	00	FF	FF										

Table 8: *The Gettysburg Address in binary-coded-text form. Table 8a is the string list for the Address; table 8b is the pointer list. Table 9 shows how the first words of the Address are decoded.*

Limitations

While binary-coded text offers a significant potential for savings in media costs, it is not without its negative considerations. Encoding and decoding require time and memory. Also, the strategies that binary-coded text incorporates for the economic storage of traditional English text do not prove nearly so efficient when applied to irregular language or technical jargon.

The time and memory devoted to encoding and decoding are not as great as they might appear. Encoding is by far the lengthier of the two processes. The work that I did in developing the encoder was done on a Radio Shack TRS-80, which takes just under 30 seconds to encode the Gettysburg Address. Decoding the Gettysburg Address, on the other hand, takes only a few seconds. Inasmuch as any given piece of text needs to be encoded only once and thereafter can be stored for decoding an indefinite number of times, the time devoted to encoding is not necessarily a significant consideration. Decoding takes place at a rate far in excess of human reading speed, so the decoding time is irrelevant in any configuration in which it is being performed by a dedicated unit (such as an intelligent terminal or a microcomputer). The size of the encoder or decoder may or may not be a limiting factor: the encoder and decoder together, including the dictionary, occupy just under 10K bytes.

The fact that the string list is limited to 1024 entries does not really limit the size of the text that can be reduced to binary-coded text. A string list of 1024 entries is probably large enough to accommodate a text of approximately 10,000 words. The encoder can simply treat a text of 20,000 words as if it were two separate texts of 10,000 words each and create a separate string list for each "text." Regardless of the number of string lists the encoder has to generate, the ratio of storage requirements for character-byte text to storage requirements for binary-coded text should remain relatively constant at a ratio of around 5:2.

1. The first line of the Gettysburg Address (as it appears on a 64-character wide display):

ƀƀƀƀƀFourƀscoreƀandƀsevenƀyearsƀago,ƀourƀfathersƀbroughtƀforth(lf-cr)

2. The string list for the first line of text of the Gettysburg Address:

Information	4	s	c	r	f	r	t
Encoded			o	5	o		h
Hexadecimal Code	04	13	64	98	70	12	F6

3. The pointer list for the first line of the Gettysburg Address. (Note that the 2-byte pointers appear in less-significant-byte/more-significant-byte order. Each separate pointer code has been underscored to assist the reader in distinguishing 1- and 2-byte codes.)

02 92 02 80 F8 1A BA 06 F5 E0 FB 02 09 66 84 64 F6 02 81 08 00

Decoded:

02		indent and capitalize first letter next word	ƀƀƀƀƀ
92	02	dictionary address 274 plus null word ending	fourƀ
80	F8	string list address 0 plus "e" word ending	scor + eƀ
1A		dictionary address 26 plus null word ending	andƀ
BA	06	dictionary address 826 plus null word ending	sevenƀ
F5	E0	dictionary address 117 plus "s" word ending	year + sƀ
FB	02	dictionary address 379 plus null word ending	ago
09		trailing comma	,ƀ
66		dictionary address 102 plus null word ending	ourƀ
84	64	dictionary address 516 plus "ers" word ending	fath + ersƀ
F6	02	dictionary address 374 plus null word ending	broughtƀ
81	08	string list address 1 plus null word ending	forthƀ
00		linefeed/carriage return	

Table 9: *Reconstruction of the first line of the Gettysburg Address from the binary-coded text of table 8.*

Due to the fact that binary-coded text relies so heavily on its dictionary of frequently used words, its efficiency will necessarily suffer when it is confronted with atypical character strings. One tactic for coping with this problem is to use different dictionaries for different categories of texts. In fact, this enhances the efficiency of binary-coded text in general. A list of the 1000 most frequently used words to be found in a library of computer-science journals, for example, will be significantly different from a list of the 1000 most frequently used words in a collection of back issues of the *New York Times*. There is no logical obligation to encode all texts on the basis of the same dictionary. The only requirement of binary-coded text is that the decoding program have available the same dictionary as was used during encoding. ■

The complete encoded dictionary is available from the author for $10.

BYTELINES

News and Speculation About Personal Computing

Conducted by Sol Libes

Random Rumors: Word has it that IBM is developing its own floppy-disk drive for disks less than 5¼ inches in diameter. IBM is also said to be telling potential parts suppliers that it expects to ship approximately 1.2 million personal computers by 1984. And this coming summer the corporation is expected to introduce a larger brother for its Personal Computer. . . . Olivetti and Victor are expected to soon introduce systems that are software compatible with the IBM Personal Computer. . . . In a change of plans, Hitachi Ltd. is postponing introduction of its personal computer into the U.S. until late this year. Hitachi has been showing a prototype 6809-based system at trade shows. Reportedly, they feel that they do not yet have enough software support for it. . . . Mattel Electronics is said to be readying a portable terminal/computer. . . . Xerox may be seriously considering a low-cost portable terminal. . . you can expect similar introductions from Sinclair, Epson, Hitachi, and Alcatel-Electronique (France) at the National Computer Conference (NCC) show in June. All are expected to sell for less than $500. . . . Toshiba is expected to show a portable computer (T-100) using an optional flat-screen liquid-crystal display at the NCC. . . . Rumor has it that Apple will not have its new database/electronic-mailer/user-friendly 68000 system ready for introduction at the NCC. . . . Micropolis is reported to be readying 8-inch Winchester-technology disk drives with capacities of 60, 90, and 180 megabytes for introduction later this year.

Computer Flea Market: On Saturday and Sunday, April 17 and 18, several thousand computer hobbyists will flock to Trenton State College, New Jersey, for the Trenton Computer Festival, the world's largest personal-computer equipment flea market. This annual event is now in its seventh year. Many swap and seller tables, spread over more than eight acres, feature everything from complete computer systems to tiny electronic parts. There will be speakers, user-group meetings, an indoor exhibition area, and a banquet.

The Festival is sponsored by the Amateur Computer Group of New Jersey, the Philadelphia Area Computer Society, and the Trenton State Computer Society; the funds raised help support these nonprofit organizations. For information, call (609) 771-2487 or write to TCF-82, Trenton State College, Trenton, NJ 08625.

New Policies for Intertec: Intertec has been receiving negative press comments lately regarding its warranty policies and other matters. The company has made a series of announcements it feels will improve customer relations.

Intertec will now pay return freight on defective equipment, during the warranty period, and on equipment that arrives damaged to the dealers.

The company is instituting a money-back guarantee during the 90-day warranty. Customers may return their machines for any reason during that period and pay only a restocking charge of 5 percent for the first 15 days and higher percentages beyond that on a sliding scale.

A new user hot-line is available to solve customer problems. Any problem unresolved after 24 hours will be forwarded automatically to the product manager.

A series of across-the-board price reductions were announced last month. The Superbrain has dropped from $3495 to $2995; the Superbrain QD from $3995 to $3495; and the high-end Compustar from $4495 to $3995.

Several additional policy changes have been made to give Intertec dealers added flexibility in discount structures.

Intertec customers will now automatically become members of a company-sponsored user group, which will meet annually. The company is also sponsoring a new magazine for users.

More 68000 Systems: Systems based on Motorola's 68000 microprocessor are now available from Charles River Systems, Computhink, Codata Systems, Cromemco, and Dual Systems Control, as well as Empirical Research Group, Evans and Sutherland, Future Systems, Fortune Systems, Microdasys, Omnibyte, Q1, and Wicat Systems. This list will probably quadruple in size by year-end. And virtually all have or will have Unix-like operating systems. Most are designed to be multiuser systems, although they can be used by a single person. So far, most of the bus-oriented systems introduced use either the Multibus or the S-100 bus. Few, if any, are using the Versabus, specifically designed by Motorola for the 68000. The problem is that the Versabus requires very large and expensive boards and connectors.

Sinclair Flat-Screen: Sinclair Research Ltd. has disclosed an agreement with ICL (International Computers Ltd.), the largest computer maker in England, for ICL to produce a line of office work stations that will use Sinclair's flat video screen CRT and the Sinclair version of BASIC. Plans are for the units to be introduced in Europe and possibly the U.S. in early 1983. The ultra-compact work stations will function as stand-alone computers and also will communicate voice and data via private telephone systems.

Sinclair is also expected to show a prototype portable terminal using the flat screen at the NCC show. A flat-screen pocket television measuring 6 by 4 by 1 inches, retailing for about $100, is expected to be in production later this year.



"Our current recommendation for a big five accounting package is MBSI"

Computer Dealer magazine
January, 1982

At last, full feature general business software for micro-computers.

Officially authorized derivations from the popular MCBA® mini-computer packages, these packages have been eased down to micros and made even more user friendly.

The mini versions of these packages are distributed by over 900 OEMs and dealers, and are in use at over 9,000 end user sites worldwide.

And already these micro versions themselves are in use by thousands of end users.

Written in RM/COBOL™, these packages run under CP/M®, OASIS™, UNIX®, COS-990® and other operating systems.

They run on dozens of brands of micro-computers, including properly configured models from Radio Shack II, Apple III, Zenith, Hewlett Packard 125, Xerox 820, ALTOS, ONYX and many more.

Tens of man-years have gone into these packages, which comprise over 230 programs, 165,000 lines of structured source code, and 1,800 pages of user and technical documentation.

Our claim is simple:

THIS IS THE BEST MICRO-COMPUTER GENERAL BUSINESS SOFTWARE AVAILABLE.

And we stand behind that with a moneyback guarantee.

It's no accident that *Computer Dealer* magazine recently endorsed MBSI software.

So if you're a re-seller looking for first class micro-computer software, contact us today.



Micro Business Software, Inc.
Dover Rd., Dept. BY1
Chichester, NH 03263
Phone: (603) 798-5700

The unit, which will have a display three times brighter than conventional television sets and will use one quarter the power, will be made by Timex. According to Sinclair, a major U.S. retail chain has already agreed to buy 300,000 sets.

Sinclair has also disclosed that it is working on a short-distance electronic car that it hopes to have on the road before 1985.

More Flat-Panel Displays: Several manufacturers are already shipping flat-panel displays, suitable for use in video-style terminals, that are based on refinements of existing technologies: gas-discharge (GD), vacuum-fluorescent (VF), and liquid-crystal (LC). Low-cost DC-type GD displays, also known as plasma displays, are already available in sizes as large as 12 lines by 40 characters. AC-type GD displays offer inherent pixel memory, and therefore do not require refreshing and exhibit no flicker; however, they are more complex and consequently more expensive. Electro Plasma, in Millbury, Ohio, already offers an AC GD display that displays 66 lines by 80 characters; Interstate Electronic, in Anaheim, California, offers a 51-line by 85-character display (512 by 512 pixels); and Fujitsu America offers a 25-line by 80-character display (also 512 by 512 pixels).

Ise Electronics, Japan, holds the basic patents on VF technology and has licensed Nippon Electric Company (NEC) and Futuba, as well as its own Noritake Electronics division, to manufacture it. These companies are currently supplying VF displays with as many as 256 by 256 pixels. Color displays are also available on custom order.

LC displays are also increasing in size. For example, Seiko Instruments, Torrance, California, is currently shipping 4-line by 32-character displays. However, LC is the most expensive of the three, and all are still considerably more expensive than the old cathode ray tube (CRT) standby. But prices are dropping as the technology improves and production increases. At this time, the GD display shows the best promise of competing with the CRT.

Reasoning Computer: The Department of Energy's Argonne National Laboratory and Northern Illinois University have developed AURA (automated reasoning assistant), a general-purpose program that appears to mimic some reasoning skills of the human mind. It eliminates the need to understand complex programming when using a computer to solve a problem. The problem must be explained to AURA in terms it can understand, and suggestions must be made for AURA to investigate. AURA does not solve the problem; rather, it points out directions for further study.

IEEE Standards: The Binary Floating Point (P754) and Radix Free Floating Point (P854) standards are being voted on by the Institute of Electrical and Electronics Engineers (IEEE) standards committee members. Standards for Relocatable Object Code Format (P695) and High Level Language (P755) are in draft states. The IEEE Assembly Language Mnemonics Standard (P694) committee is extending the current standard (which most manufacturers seem to ignore) to include several of the newer 16- and 32-bit microprocessors. A committee is being formed to work on a standard for CP/M. A committee on Software Benchmark Standards has also been formed. For more information on IEEE Computer Standards in development contact: Michael Smolin, Chairman, IEEE Computer Standards Committee, c/o Synertek Inc., Box 552, MS#39, Santa Clara, CA 95052.

Research Cooperative: The Semiconductor Industry Association (SIA) is planning to fund basic reasearch projects at U.S. universities through a newly formed Semiconductor Research Cooperative (SRC). Dr. Robert Noyce, Intel Corporation vice-chairman and chairman of SIA, said SRC plans to raise $4 to 5 million from integrated-circuit makers this year. This is being done in response to the huge Japanese investments in research and training of engineers. Manufacturers are being asked to contribute an amount equal to 0.1 percent of their sales of semiconductor devices. Japanese firms would not be welcome to join because American firms are not presently allowed access to research being conducted in Japan's VLSI (very-large-scale integration) laboratories.

SRC would own patents produced by its efforts and would collect royalties from firms that use them. SRC will be staffed by 10 engineers, headed by a full-time director, and controlled by a technical advisory board. Companies so far participating in SRC are Intel, IBM, Digital Equipment Corporation, Motorola, Control Data, Advanced Micro Devices, National Semiconductor, and Fairchild Camera and Instrument. Notable for its absence is Texas Instruments.

Watching IBM: Sears has disclosed that, during its first two months of selling microcomputers via its five computer stores, IBM products have taken a "large lead in sales volume among products carried in the stores." IBM shares shelf space with the NEC PC-8001A, Vector Graphic Series 3, and a Wang word processor.

There are rumors that IBM will shortly announce an enlargement of its Personal Computer dealer base. Reportedly, a large number of independent retailers have applied for dealerships and are awaiting a decision. In the meantime, dealers have been encountering some availability problems because of the large demand for the Personal Computer.

IBM has disclosed that it will enter the industrial robot market shortly. Rumor has it that the robot will be designed for high-speed assembly or component insertion, selling in the $125,000 range.

Telephone Typesetting: For about two years now I have been sending many of the articles and books that I write (with Wordstar on my trusty old S-100-based personal computer) directly to a typesetter via modem (at 600 bits per second, during off hours, using the standard CP/M-modem protocol), to be typeset directly from my file. The turnaround time is terrific, and the prices are great because little labor is involved. The typesetter has his system operating automatically 24 hours a day so that I can dial in at any time

THE MICROCOMPUTER MAGAZINE THAT'S LIGHT YEARS AHEAD

FILL IN AND MAIL THIS CARD TODAY

BYTE® the small systems journal

Read your first copy of BYTE, the Small Systems Journal. If it is everything you expected, honor our invoice. If it isn't, just write "cancel" on the invoice and mail it back. You won't be billed, and the first issue is yours at no charge. Allow 6 to 8 weeks for processing your subscription.

MAIL CARD OR CALL TOLL FREE **800-258-5485**

Please print 4H42

Name

Address

City State/Province/Country Code

United States
☐ One year $19 (12 issues) ☐ Two years $34 ☐ Three years $49

Canada or Mexico
☐ One year $21 (12 issues) ☐ Two years $38 ☐ Three years $55

Foreign Rates (to expedite service, remit in U.S. funds drawn on a U.S. bank)
☐ Europe, one year, air delivered, $43
☐ All other countries, one year, surface delivered, $35
Air delivery available upon request

☐ **Check enclosed** (entitles me to **$13 issues for price of 12**, North America only)
☐ Bill VISA ☐ Bill Master Charge ☐ Bill me (North America only)

Card Number Expires


Signature

Allow 6 to 8 weeks for processing your subscription.


BYTE the small systems journal

McGraw-Hill

© BYTE Publications, Inc. 1981



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES




BUSINESS REPLY CARD
FIRST CLASS PERMIT NO. 39 MARTINSVILLE, NJ


POSTAGE WILL BE PAID BY ADDRESSEE

BYTE

Subscription Dept.
P.O. Box 590
Martinsville, NJ 08836



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES



BUSINESS REPLY CARD
FIRST CLASS PERMIT NO. 39 MARTINSVILLE, NJ

POSTAGE WILL BE PAID BY ADDRESSEE

BYTE

Subscription Dept.
P.O. Box 590
Martinsville, NJ 08836

and send the file. His system receives it automatically, whether he is there or not. He then adds the necessary typesetting control characters and processes the file directly through his machine. Two or three days later the typeset text is in my mailbox.

Typesetters across the country are recognizing the value of hooking up personal computers to their typesetting machines and the phone lines. Check your Yellow Pages for such services in your area.

EEPROM Update: Electrically erasable programmable read-only memories (EEPROMs) allowing erasure of bulk memory and Electrically alterable ROMs (EAROMs) allowing alteration of individual bytes are finally coming to the marketplace. They allow real-time program changes, have reasonable access speeds, and come in less expensive packages than standard EPROMs that are erased by ultraviolet light. At the present time they cost eight to ten times more than EPROMs. However, as production increases they are expected to drop to a competitive price and supersede EPROMs.

Already 16K-bit EEPROMs (2K by 8 bits) are available in limited quantities from Intel, National, General Instrument (GI), and Motorola. And even Hitachi has announced a 64K-bit (8K by 8 bit) EEPROM. In an interesting turn of events, Intel has gone to court and received a preliminary injunction against Seeq Technology prohibiting sharing of EEPROM technology with Zilog or any other company.

EAROMs are also available in limited quantities from GI, National Cash Register (NCR), Nitron, and Toshiba. NCR even makes a 2K by 8-bit EAROM. However, access times are measured in microseconds and dual power sources are required.

In the meantime, 64K-bit EPROMs are reaching full production status, and 128K-bit EPROMs are being sampled. Sixteen-bit-wide EPROMs are expected shortly.

ADAPSO Grant Program: The Association of Data Processing Service Organizations (ADAPSO), Arlington, Virginia, has established a grant and fellowship program for post-secondary students pursuing careers in the computer-services industry. Awards will be up to $1000 per recipient per academic year. The deadline for applying is April 20, 1982.

Unix Look-Alikes: Manufacturers are finally starting to ship the 16-bit Unix-like operating systems they've been advertising for the past year. Some even claim to have Unix-like systems for 8-bit computers. A few have been shipping these 8-bit systems for several months now. Bell Laboratories even has a Z80 version that it is using in-house. As reported last month, Western Electric, bowing to the Unix-like competition, has substantially lowered the price of Unix. It will be a few more months before we know how these new Unix-like systems for the 16-bit systems stack up. Below are some initial impressions.

Unix was designed by Bell Labs to run on the Digital Equipment Corp. PDP-11 models. Although it has been implemented on small PDP-11s, it runs best, with full-feature performance, on the larger PDP-11 machines that have a sophisticated memory-management hardware system. Therefore, to transport Unix to a microcomputer means that it too must have ample memory (at least 256K bytes) and a memory-management system, a good disk system, and a tape backup system for good measure.

Unix was written in C, a high-level systems-oriented language. Therefore, one would think that transporting Unix from one hardware system to another would be an easy job—somewhat on the level of transporting CP/M with its easily modified assembler-language BIOS (basic input/output system) module. However, because of Unix's orientation to the PDP-11 large-system architecture, this conversion takes a few programmer-years to accomplish. Hence the delay in releasing these implementations. In order to cope with this problem, Microsoft, operating under a Western Electric Unix license, has entered into agreements with some other software houses to convert Xenix, a Unix look-alike, to systems for which Microsoft has not yet implemented Xenix systems.

The result is that the microcomputer Unix look-alikes are not full Unix implementations. Many of the larger or less used utilities have been omitted (or, in some cases, they are available at an extra charge). In many cases the floating-point arithmetic or bit-fields have been omitted or restricted. Furthermore, many have adopted different conventions for function and system calls, library modules, and utilities. But even Bell Labs has not maintained compatibility between Unix implementations the way Digital Research has with CP/M.

It is still very early in the Unix versus Unix look-alikes competition. Some suppliers of Unix look-alikes have done a very good job. Others still have a long way to go, but there is no doubt that they will make improvements.

Japan Gaining on U.S: A recent report given by Commerce Undersecretary Lionel Olmer to the House Ways and Means Trade Subcommittee reported that Japan is moving along in a commitment to develop a world-scale computer industry. He reported that the Japanese government's policies, research programs, special tax incentives, direct financial assistance, and joint government-industry efforts were all aimed at "moving the Japanese computer industry to the technological forefront in every major area."

He also reported that they are now concentrating on improving their software capabilities and developing the computer of the future. "There has been a national consensus in Japan that their economic future depends upon a rapid evolution into a knowledge-intensive and technology-intensive economy." He went on to state: "I believe that the real challenge from Japan is just beginning."

Mr. Olmer concluded by stating that a change in "national attitudes" is required for the U.S. to retain its position as the world's premier industrial power. "We must work 'smarter' and save more. We must be willing to take risks. Only in this way can we restore our competitive edge, and 'made in America' will again be the unquestioned world standard for quality."

Random News Bits: Victor Business Products has introduced an 8088-based system, called Sirius I, that is rumored to be software-compatible with the IBM Personal Computer. The Sirius I was designed by Chuck Peddle, the wizard who created the 6502 microprocessor and the PET computer. Reportedly, Peddle is being sued by Commodore for alleged breach of contract, and he is in the process of countersuing. . . . Honeywell's Minneapolis credit union reports that it now issues about fifteen interest-free loans a week for the purchase of personal computers by Honeywell employees. . . . National Semiconductor is finally shipping samples of its new super 16-bit 16032 microprocessor, with production quantities expected by mid-year. . . . CBS-TV is experimenting with getting audience feedback via The Source (a timesharing information and telecommunications utility accessed via modem) so that viewers can immediately let show producers know what they like and do not like about prime-time shows. . . . Matsushita Electric, Hitachi, and Maxell have agreed to standardize on a new 3-inch compact floppy disk. . . . Atari has reduced the suggested list price of the Atari 800 from $1080 to $890; however, it has increased prices on some software. . . . Sinclair Research reports that by the end of 1981 it had sold over a quarter of a million ZX81 personal computers and that U.S. mail orders alone are 4000 a week. . . . Micropro and Digital Research have filed a joint copyright-infringement lawsuit against Data Equipment Inc., Sunnyvale, California, and its parent company, Dataforce International Inc., for selling "counterfeit copies" of their software.

Super/Duper News: Super/Duper Computers Ltd., Pieinthesky, Utah, has introduced a revolutionary new computer, the Super/Duper MAC-VIII. Based on a patented exclusive pipe-dream architecture, it boasts a speed faster than a bullet. The computer itself is so small that it seems lighter than air, and a new mass production technology is expected to result in a selling price as cheap as dirt. The MAC-VIII cannot be overloaded since it is made of solid steel. The computer will be marketed exclusively by Brooklyn Bridge Sales Inc. . . . Happy April!

MAIL: *I receive a large number of letters each month as a result of this column. If you write to me and wish a response, please include a self-addressed, stamped envelope.*

Sol Libes
POB 1192
Mountainside, NJ 07092 ■


BYTE's Bits

RCA to Service Epson MX Printers

RCA Service Company will provide nationwide warranty service for Epson America's MX series of microprocessor-based printers. RCA will also offer a wide variety of maintenance service packages to MX owners and users. Service will be performed by RCA technicians based in 180 locations throughout the U.S. ■

What's New?

PUBLICATIONS



Smart Ideas from Digital

The fourth edition of Ideas (Index and Description of Educational Application Software) lists more than 300 applications packages for Digital Equipment Corporation's computer systems using the VAX/VMS and RSTS/E operating software. Software packages are alphabetically listed by application under separate VAX/VMS and RSTS/E sections. For your free copy, request publication number EJ 19645-87 from Education Computer Systems Group, Media Response Manager, PK3-2/M94, 129 Parker St., Maynard, MA 01754.

Circle 550 on inquiry card.

Computerist's First Aid Manual

Perfect for those emergencies encountered by computer programmers, the Computerist's First Aid Manual gives detailed instructions for dealing with such maladies as "CRT Eye," "Asteroids Wrist," and "Missile Command Thumb." It also contains information for dealing with other common home computing emergencies. The manual is available for $19.95 from Medi-Comp Inc., 70 Main St., Petersborrow, NH 03458.

Circle R202 on inquiry card.

Computer Graphics Vendor Directory

The 1982 Directory of Computer Graphics Suppliers lists almost 300 vendors of hardware, software, systems, and services. The Directory contains key background information on each company's computer graphics products and services, complete with address, telephone number, and contact person. Among the subjects covered are computer-aided design and manufacturing, business graphics, animation, and image processing. Other features of the Directory include a computer-processed index that categorizes vendors by application and technological focus, technology studies and market reports, and a guide to computer-graphics seminars, conferences, and courses. For additional information, contact Stanley Klein, Computer Graphics Directory, Suite 27, 730 Boston Post Rd., Sudbury, MA 01776.

Circle 551 on inquiry card.

Journal Probes Computers in Education

The Journal of Computers in Mathematics and Science Teaching is a quarterly publication of the Association for Computers in Mathematics and Science Teaching (ACMST), a nonprofit professional organization. The journal explores such topics as "Computer-Based Methods in Chemistry," "A Microcomputer-Assisted Presentation of Atomic Orbits," and "Planning for Microcomputers in the Classroom." Other features of the journal include book reviews, a column on software resources, and a new products section.

Annual ACMST membership costs $7, which includes a subscription to the journal. For additional details, contact ACMST, POB 4455, Austin, TX 78765, (512) 836-4378.

Circle 552 on inquiry card.

CP/M Software Catalog

A catalog listing 50 volumes of low-cost, public-domain CP/M-based software is available from the Special Interest Group for Microcomputers (SIG/M). The complete 50-volume library, housed in single-density 8-inch disks, lists more than 900 programs. The catalog costs $1.50 in the U.S. and Canada and $2.50 elsewhere. Contact SIG/M, POB 97, Iselin, NJ 08830, or call Bill Chin, (201) 778-5140, or Henry Kee, (212) 539-3202.

Software Protection Report

The various resources available for software protection are explored in a 60-page manual from Communication Research Trade. The report explains the differences, advantages, and dangers of comparable security alternatives. Information on trade secret protection, trademarks, and patents is included, and a major portion of the report is devoted to copyright and infringement recourses. In addition, an example program demonstrating the proper display of a copyright notice is provided. The report on software protection is available for $75 from Communication Research Trade, POB 3151, Redwood City, CA 94064.

Circle 553 on inquiry card.

Information Age Papers

A compilation of papers presented in April 1981 at the "Communications in the 21st Century" symposium has been produced by John Wiley & Sons. In Communications in the 21st Century, 20 distinguished scientists, scholars, journalists, and business executives explore such issues as the development of a national communications policy, business strategies for managing the information explosion, and the effects of technology on individuals and institutions. Communications in the 21st Century costs $19.95

and is available from John Wiley & Sons Inc., One Wiley Dr., Somerset, NJ 08873, (201) 469-4400.
Circle 554 on inquiry card.



Test and Measurement Products Catalog

A 432-page directory of test and measurement products is available from Metermaster, a company that represents nearly 40 manufacturers of test and measurement instruments. The catalog contains design and performance specifications for meters, oscilloscopes, and other test and measurement instruments. Product and test equipment categories are organized alphabetically according to manufacturer. A glossary is also provided.

The 1981/1982 Metermaster Catalog is available free of charge to qualified engineers and buyers at Metermaster outlets, or you can write to Metermaster, 5646 Jillson St., Los Angeles, CA 90040, (213) 685-4340. Requests must be submitted on company letterhead.
Circle 555 on inquiry card.

10,000 Components in Free Catalog

Mouser Electronics' 128-page catalog of electronic components contains full product specifications, illustrations, and prices for more than 10,000 items, ranging from clips and coils to potentiometers and plugs. The catalog is available free of charge from Mouser Electronics, 11433 Woodside Ave., Santee, CA 92071, (714) 449-2220.
Circle 556 on inquiry card.

Catalog of Circuit Board Products


A new 16-page catalog that describes products for circuit boards is available free from Pace Inc. Some of the products listed in the catalog are rework and repair boards, desoldering and specialty systems, function accessories, and audio-visual training courses. Request catalog number 781 from Pace Inc., 9893 Brewers Court, Laurel, MD 20707, (301) 490-9860.
Circle 557 on inquiry card.

SYSTEMS

ADM-3 Upgrade Kit

The Interboard-3A Kit turns your Lear Siegler ADM-3 or -3A terminal into a microcomputer. The kit has a 4-MHz Z80 microprocessor with 64K bytes of memory and a floppy-disk controller that fits inside the terminal. A single RS-232C and a Centronics-type parallel port allow peripherals to be attached.

Options for the kit include dual Tandon disk drives with 500K bytes to 2 megabytes of storage, and the CP/M operating system. The Interboard-3A Kit costs $795 and is available from International Systems Marketing, 5161 River Rd., Building #2, Bethesda, MD 20816, (301) 986-0773.
Circle 558 on inquiry card.



Business Computers

BMC Computer's if800 computer series is designed for medium-sized businesses and as an alternative to multiuser, multitasking systems where a common database is unnecessary. The Z80-based if800 computers are completely integrated desktop work stations with a keyboard, a printer, and a 12-inch high-resolution red/green/blue color display. The if800 series features 20 user-programmable function keys, I/O slots supporting a multitude of interfaces, ROM cartridge, light pen, and a built-in printer with screen-print and list capabilities. The CP/M operating system and a color/graphics-enhanced BASIC are standard.

Original equipment manufacturers have four if800 models from which to choose, ranging in price from $4170 to $6570. Three models employ two built-in 5¼-inch disk drives for approximately 800K bytes of media storage; the fourth model has a single floppy-disk drive and a 5-megabyte Winchester hard-disk drive. Additionally, two models carry a direct-connect modem and a selection of supplied software. For details, contact BMC Computer Corp., 860 East Walnut St., Carson, CA 90746, (213) 323-2600.
Circle 559 on inquiry card.



Single-Board Computer

The SYM-2 single-board microcomputer incorporates most features of the SYM-1, plus onboard power supply, choice of three microprocessors (6502, 6809, or 6802), cassette-interface jacks, eight toggle switches for user input, and eight light-emitting diodes for user output. Intended for office and industrial applications, the SYM-2 is software-compatible with SYM-1 programs and firmware. The expansion and applications ports are also compatible with the SYM-1, so expansion devices, such as random-access read/write memory (RAM) or the FDC-1 floppy-disk controller are fully interchangeable between the two machines.

The SYM-2 costs $249. For further details, contact Synertek Inc., Mail Stop 61, POB 552, Santa Clara, CA 95052, (408) 988-5682.

Circle 560 on inquiry card.

Micromaster

The Micromaster computer is a self-contained desktop unit from Barreto and Associates that operates under a modified CP/M operating system. Designed for small- and intermediate-sized businesses, the IEEE S-100-based Micromaster has dual 8085 and 8088 processors and both a 5¼-inch, 5-megabyte Winchester hard-disk drive and 5¼-inch, 96-track-per-inch, 500K-byte floppy-disk drive (additional drives can be used). The Micromaster can operate in either single-user or multiuser environments and its 12-inch video display has an 80-character by 24-line format.

The Micromaster is supplied with 64K bytes of random-access read/write memory (RAM) that is expandable to 16 megabytes, one parallel and one serial port, and a high-level language (BASIC or FORTRAN). The Micromaster is available for $12,500 from Barreto and Associates Inc., 507 West 16, Sedalia, MO 65301.

Circle 561 on inquiry card.

SOFTWARE

TRS-80 Database Manager

Adventure International's Maxi Manager is a database manager for the TRS-80 Models I and III. It supports six different relational search techniques and up to 20 user-defined fields of 40 characters each. Records can be up to 800 characters in length, and Maxi Manager has calculated equation fields plus a report generator.

Maxi Manager requires 48K bytes of RAM (random-access read/write memory) and one disk drive. The software is supplied with more than 180 pages of instructions and examples. Maxi Manger is available for $99.95 from Adventure International, POB 3435, Longwood, FL 32750, (305) 862-6917.

Circle 562 on inquiry card.

Keeping a Stiff Upper LISP

A dialect of the LISP language, the Stiff Upper LISP has more than 120 built-in functions packed into 13K bytes. The user environment includes symbolic break, trace, and single-stepping packages, plus an interaction history with REDOing facilities. Also provided are an extensible editor and an extensible online help facility, both of which are usable from within the LISP environment. Upon initialization, the Stiff Upper LISP reads a file that enables the user to customize the environment to personal preferences. Other features include screen control, a program formatter, closures that maintain their own environments of procedures and data, both lexical and dynamic variable scoping, and tail recursion elimination by the interpreter where appropriate, which makes recursion as efficient as iteration.

Stiff Upper LISP is available, under the CP/M operating system, for $165 from Lifeboat Associates, 1651 Third Ave., New York, NY 10028, (212) 860-0300, or, under TRSDOS, from Tennant and Tennant Computing, 3537 Ridge-moor Dr., Garland, TX 75042, (214) 530-0575.

Circle 563 on inquiry card.

Circle 564 on inquiry card.

68000 Multiprocessor Operating System

MTOS-68K is a real-time, multitasking, multiprocessor operating system for the Motorola MC68000 microprocessor. A modular system deisgned for high throughput, MTOS-68K produces an assembly-language module that can be placed in ROM (read-only memory). It manages task coordination, memory pools, input/output, priority scheduling, interrupt processing, and multiple processors. The system runs on up to 16 separate processors that share a common memory. All processors are equivalent: there are no masters and no slaves. A single copy of MTOS-68K executes on all processors. Without changing application software, system performance can be improved by adding processors. Application software can be written in assembly language or in a high-level language such as Pascal or C.

MTOS-68K is distributed in assembly-language source-code form and is sold for a one-time license fee that permits the licensee to imbed the object program in his or her own products without further charge. For complete

details, contact Industrial Programming Inc., 100 Jericho Quadrangle, Jericho, NY 11753, (516) 938-6600.
Circle 565 on inquiry card.

Two Atari Games

Concom Enterprises has two new game programs for Atari 400/800 microcomputers. Both games are written in BASIC and machine language and feature fast action, sound effects, and high-resolution color graphics. Each requires 16K bytes of RAM (random-access read/write memory). In Close Encounters, two players compete in a space battle, each trying to destroy the other's flying saucer. The game requires two joysticks. The second game, High Voltage, pits you against two killer robots. You are trapped in a field that's surrounded by a high-voltage fence and littered with high-voltage obstacles. Strategy and speed are your keys to survival. High Voltage requires a single joystick.

Both games are available on cassette for $15.95 each. For details, contact Concom Enterprises, 2626 West Touhy, Chicago, IL 60645.

CP/M-Compatible Utility

Lifeboat Associates' Zap80 is a menu-driven 5¼- and 8-inch disk access utility for SB-80 and other CP/M-80-compatible 8080/Z80 operating systems. Zap80 automatically allows direct file viewing and patching by actual memory address. Zap80 is designed for experienced users and includes extensive file-utility servicing to access and patch file sectors, compare files, and so forth. For details, contact Lifeboat Associates, 1651 Third Ave., New York, NY 10028, (212) 860-0300.
Circle 566 on inquiry card.

New Hashing Method Speeds Database Manager

Micro Architect's IDM-X is a general-purpose interactive database manager for the TRS-80 Model II. The IDM-X features a built-in sort/merge package and a fast key-access method that uses a new hashing algorithm. IDM-X supports string, double-precision floating decimal, and integer variables. Other features include formatted numeric fields, using BASIC formats, and an extensive report writer.

The basic components of IDM-X are a database initialization program, a database manipulation program, the report writer, and a report generator. A dual-disk TRS-80 Model II with 64K bytes of memory is required. IDM-X costs $399; the user manual is available separately for $25. For additional information, request a product catalog from Micro Architect Inc., 96 Dothan St., Arlington, MA 02174, (617) 643-4713.
Circle 567 on inquiry card.

CP/M-86 for the IBM Personal Computer

Compuview's CP/M-86 (CP/M is a registered trademark of Digital Research) for the IBM Personal Computer includes an interactive line editor that permits cursor movement to the previous line and horizontal scrolling to a width of 162 characters, and emulation of terminals such as Televideo, the IBM 3101, and the Zenith Z-19. Other features are an increase in disk capacity from the 160K bytes supported by MS-DOS to 193K bytes; the ability to read and write many soft-sectored disk formats, including the Xerox 820's format; support for both serial and parallel printers; a disk formatter; a disk-copy program that makes a fast, "image" copy; the ability to set transmission rates for serial ports; and support of Tecmar's hard-disk drive and other peripherals.

For further information, contact Compuview, Suite 200, 1955 Pauline Blvd., Ann Arbor, MI 48103, (313) 996-1299.
Circle 568 on inquiry card.

Slide Rule Simulator

The Slide-Simulator transforms your TRS-80 Color Computer into a Mannehim-type slide rule. Using high-resolution graphics and controlled by the game paddles, the program simulates full log-log functions. A special expanded viewing option allows easy reading of the scales. The program is available on a 5¼-inch floppy disk. For price information and a catalog of other innovative software, contact Abstract Mathematical Concepts Inc., 70 Main St., Putterboro, NH 03458.


PERIPHERALS



Keyboard Eases Word Processing

A computer designed primarily to handle small-business applications is now available with a keyboard dedicated to word processing. The new keyboard is based on a Visual 200 computer terminal with electronic and mechanical adaptations for Micropro's Wordstar word-processing system. The keyboard allows the user to strike a single color-coded key for center line, release or set margins, clearing or setting tabs, underscore, or any one of 24 other commonly used word-processing commands and cursor movements.

The keyboard option is available on new Prodigy installations or as a field upgrade. For more details, contact Prodigy Systems Inc., 497 Lincoln Highway, Iselin, NJ 08830, (201) 283-2000.
Circle 569 on inquiry card.



Versatile Robot Arm

The Rhino XR-1 computer-controlled robot arm is a versatile, low-cost product for educational or light industrial use. The XR-1 can be run from a modem or any computer with an RS-232C port. Standing 32 inches high, the XR-1 contains six motors, one for each axis point. It can reach up to 32 inches from base to fingertips; radial reach is 22¼ inches from the center of rotation to fingertips. Waist resolution is 0.137 degrees; shoulder resolution is 0.076 degrees. The XR-1's lifting capability and gripping force are approximately 16 ounces.

The Rhino XR-1 computer-controlled robot arm costs $2400. Contact Sandhu Machine Design Inc., 308 South State, Champaign, IL 61820, (217) 352-8485, for further details.

Circle 570 on inquiry card.

Man-Machine Interface at Your Fingertips

The 1780A Infotouch Display screen is a 5- by 9-inch video-display screen with a touch-sensitive overlay. Messages, numbers, graphics, menus, switches, and special characters can be displayed through computer programming to guide an operator's response step by step. The Infotouch's screen displays 16 lines of 80 characters and features 60 definable touch-sense areas. The Infotouch can be used with almost any desktop, home, or large computer.

The 1780A Infotouch Display costs $1995. It's available from the John Fluke Manufacturing Co. Inc., POB C9090, Everett, WA 98206, (800) 426-0361; in Washington, (206) 354-5400.


Circle 571 on inquiry card.

Apple III Hard-Disk Storage

Corvus Systems has unveiled new mass-storage units for the Apple III computer based on high-capacity 5- to 20-megabyte Winchester hard-disk systems. The storage modules incorporate an intelligent controller, a proprietary controller, software, and an Apple III interface. Firmware for the intelligent controller supports features such as sector buffering, automatic retries, diagnostics, transparent formatting with cyclic redundancy check (CRC) error detection, and high-speed data transfer using direct memory access (DMA) to random-access read/write memory (RAM) within the controller.

The Apple III Winchester hard-disk mass-storage units range in price from $3750 to $6450. Contact Corvus Systems Inc., 2029 O'Toole Ave., San Jose, CA 95131, (408) 946-7700, for additional information.

Circle 572 on inquiry card.



No More Grappling with Graphics

The Grappler is a Centronics-compatible parallel interface board for the Apple II. It has on-board firmware to copy the Apple's high-resolution graphics screen to a wide variety of printers, such as Anadex, Integral Data Systems, Centronics, and Epson. In the Grappler's standard printing mode, each white dot on the Apple's screen is printed as a black dot on paper. The inverse graphics mode allows you to print the reverse graphics of white-on-black. The double-size option doubles the graphics screen horizontally and vertically. Other features of the Grappler include word wrap-around, variable line and page length, 90-degree text rotation, the ability to skip over perforation, and compatibility with the CP/M operating system and Apple Pascal.

The Grappler is available at Apple dealers and computer stores for $175, including manual and interface cable. For complete information, contact Orange Micro Inc., Suite

G, 3150 East La Palma, Anaheim, CA 92806, (800) 854-8275; in California, (714) 630-3322.

Circle 573 on inquiry card.

Apple II Button Pad

A naval-operated numeric keypad is available from Hindsight Engineering. Designed to plug directly into one of the Apple II's slots, the keypad leaves your hands free for computer operation. (To insure proper interface, operate in a lint-free environment.) The complete package includes the keypad, interface card, connecting cable, complete documentation, and instructions on developing naval dexterity. The package lists for $99.95. Hindsight Engineering, POB 107.5, Pizzaborough, NH 03458.

Circle 1007 on inquiry card.

Hard Disk for the ZX81

Responding to an obvious need of ZX81 owners for more data storage space, Hindsight Engineering has developed a 5-megabyte hard-disk system for the Sinclair ZX81. The system is available in either assembled or kit form. The kit includes instructions for building your own clean room for kit assembly. A DOS will soon be available. For pricing information and a catalog of other products, write to Hindsight Engineering, POB 107.5, Peanutbutter, NH 03458.



High-Quality Low-Cost Terminal

The WY-100 is an intelligent terminal offering an array of features normally found in more expensive products. The WY-100 exhibits ergonomic design with a detached keyboard and a tiltable/rotatable display console. It offers a data-validation ability that ensures accurate keyboard entry and editing capabilities such as character insert and delete. Other standard features include word wrap, display features for forms creation, a split screen for viewing more than one data group simultaneously, a separate I/O port for driving a printer, and an RS-232C port for host computer communications.

The WY-100 costs $995. For complete details, contact Wyse Technology, 2184 Bering Dr., San Jose, CA 95131, (408) 946-3075.

Circle 574 on inquiry card.

256K-byte Memory for IBM

Zobex's 256K-byte RAM (random-access read/write memory) board with parity is fully compatible with the IBM Personal Computer. The memory meets or exceeds IBM memory performance and requires only one expansion slot. The board contains a memory address-decoding scheme carried out by means of an onboard configuration switch that allows each 64K-byte segment on the board to be either disabled or based at any 64K-byte boundary from 0 to 1 megabyte. This allows the board to be used in conjunction with the IBM central processing unit board-mounted 64K-byte memory or mixed with IBM 64K-byte expansion boards.

The 256K-byte memory board costs $998; original equipment manufacturer's discounts are available. Contact Zobex, 7343 J. Ronson Rd., San Diego, CA 92111, (714) 571-6971.

Circle 575 on inquiry card.

Apple-Compatible Drives

A. M. Electronics' 5¼-inch add-on disk drives are designed for "plug-and-go" compatibility with the Apple computer. The drives are completely compatible with Apple disk operating systems and software, and offer 40 tracks of data storage and a 3-millisecond track-to-track access time.

The add-on disk drives for the Apple, complete with case and cable, are available for $345. Contact A. M. Electronics Inc., 3366 Washtenaw Ave., Ann Arbor, MI 48104, (313) 973-2312.

Circle 576 on inquiry card.



Hard Copy from Video Terminals

Axiom Corporation's Model EX-1650 printer can produce full-size hard-copy output directly from almost any video computer or graphics terminal, video monitor, or TV set. Entire pages of displayed data—even complex graphics, alphanumerics, foreign symbols, or hieroglyphics—are rapidly reproduced on the printer. Paper width is 8½ inches, which allows full-sized reproductions of forms, reports, and graphs.

The EX-1650 printer, with self-adjusting printhead, does not require external hardware or software. A single connection to a standard video jack is the printer's sole requirement. A smaller version of the printer, the EX-850, is available. The EX-850 accepts paper 5½ inches wide. The EX-1650 costs $3495. Contact Axiom Corp., 1014 Griswold Ave., San Fernando, CA 91340, (213) 245-9244.
Circle 577 on inquiry card.




Calendar/Clock for Small Computer

The Hayes Stack Chronograph is an RS-232C-compatible calendar/clock for small computers. The Chronograph reports time in hours, minutes, and seconds in 12- or 24-hour modes. The date is output in a year/month/day format with automatic adjustment for leap years. The Chronograph is independently powered, and has a battery backup to maintain time, date, and weekday for up to one year when the power fails or is disconnected.

Simple ASCII (American Standard Code for Information Interchange) character strings let the user set, read, and display calendar/clock data, control the computer alarm, and select various options.

A complete Chronograph system costs $249. Contact Hayes Microcomputer Products Inc., 5835 Peachtree Corners E., Norcross, GA 30092, (404) 449-8791.
Circle 579 on inquiry card.



5¼-Inch Fixed Disk Drives

The new S1 series of 5¼-inch fixed disk drives from Mitsubishi Electronics feature Winchester-design reliability. The S1 series has a high-speed seek time of 75 microseconds (μs) average, 160 μs maximum, which includes settling time. Available with large storage capacities of 3.33, 6.66 to 10 megabytes (unformatted), each disk surface employs one movable head to service 160 data tracks. Further details and specifications can be obtained from Mitsubishi Electronics America Inc., Computer Peripherals Div., 2200 West Artesia Blvd., Compton, CA 90220, (213) 979-6055.
Circle 578 on inquiry card.

S-100 Bus for Superbrain

The SBS-100A Interface Adaptor provides the necessary components for converting the Superbrain microcomputer to S-100 bus operations. The unit can be fitted within the Superbrain cabinet to control a single S-100 board or it can be mounted externally in an S-100 box for control over a number of S-100 boards.

The SBS-100A Interface Adaptor board costs $595, including postage but excluding duty fees. For further details, contact Icarus Computer Systems Ltd., Deane House, 27 Greenwood Pl., London NW5 1NN, England, 01-485 5574.
Circle 580 on inquiry card.

Tape Backup Fit for a Chieftain

If you own a Chieftain or Pathfinder system from Smoke Signal Broadcasting, you can now have a tape-streamer backup as an option for your 5¼- or 8-inch Winchester hard-disk system. The tape streamer can store up to 20 megabytes on ¼-inch cartridge tape. With a tape streamer, computer systems can transfer up to 20 megabytes of data in less than five minutes at 90 inches per second. The Chieftain and Pathfinder systems also incorporate two means of backup with the streaming-tape drive: file-by-file or a complete backup with a single command. Drive-to-tape and tape-to-drive data transfers are provided.

The tape streamer is available as a standard option to any Chieftain or Pathfinder Winchester disk-drive system for $1500. Also available are tape-streamer options for Smoke Signal Broadcasting models 98W10, 98W30, and 98W15T20. Contact your local Smoke Signal dealer or Deborah Conrad, Smoke Signal Broadcasting, 31336 Via Colinas, Westlake Village, CA 91362, (213) 889-9340.
Circle 581 on inquiry card.

New Winchester Disk Series

The Pyxis Series of 5¼-inch Winchester disk drives range from 4 to 16 megabytes of unformatted storage capacity. The series is available in four models: the Model 4, a single-disk device with 4 megabytes of storage; the Model 8, a two-disk device with 8 megabytes; the Model 12, a three-disk device with 12 megabytes; and the Model 16, a four-disk device with 16 megabytes of unformatted storage. The Pyxis series interface, form factor, mounting, and power requirements are all com-

patible with 5¼-inch Winchester-technology industry standards.

In original equipment manufacturer quantities, the Pyxis series ranges in price from $740 (Model 4) to $1290 (Model 16). For details, contact Ampex Corp., Memory Products Division, 200 North Nash St., El Segundo, CA 90245, (213) 640-0150.

Circle 582 on inquiry card.

MISCELLANEOUS



New Products Clean Circuit Boards

Two new products from Texwipe can help keep your printed-circuit boards clean. The first, Gold-Wipes, provides a convenient method to clean and protect the gold fingers and other metallic surfaces on printed-circuit boards. Gold-Wipes are individually foil-wrapped pads that are presaturated with cleaning and lubricating agents. Use of Gold-Wipes can cut down on adhesion, brittle fracture, and abrasion problems. The second product, D-Flux, is a cleaning solvent and brush for dislodging stubborn fluxes from printed-circuit boards. D-Flux's applicator dispenses a controlled amount of solvent, while the brush scrubs off flux. It is designed for use on board repairs, assembly operations, and other environments that require flux removal.


Both products are available directly from the manufacturer, Texwipe Co., Sales Office, POB 575, Upper Saddle River, NJ 07458, (201) 327-5577. Free samples and literature are available upon request.

Circle 583 on inquiry card.

Dynamic-Memory Board for S-100 Systems

Systems Group's new 128K-byte dynamic-memory board is fully compatible with most S-100-based microcomputer systems, including Alpha-Micro, North Star, and Dynabyte. The board has eight independent 16K-byte software-selectable memory banks, each addressable on any 16K-byte boundary. Other features include parity for single-bit error detection, 10 onboard diagnostic LEDs (light-emitting diodes), 4-MHz Z80 operation using transparent refresh, and full compliance with IEEE timing specifications with 20-megabyte extended addressing. The dynamic-memory board's power requirement is 8 watts maximum. Contact Systems Group, 1601 Orangewood Ave., Orange, CA 92668, (714) 633-4460.

Circle 584 on inquiry card.



Dual RAM Board for Apple II

RAMPlus+ is a new dual 16K-byte RAM (random-access read/write memory) card for the Apple II. Two banks of 16K-byte selectable RAM expand the Apple II to 80K bytes of available memory. The second bank of RAM is controlled by user-supplied software. Hardware and software selection of each 16K-byte bank of RAM is user-controlled. The card also supplies its own refresh circuitry.

RAMPlus+ can be installed in any slot on the Apple and does not require cables or the removal of integrated circuits from the Apple motherboard. When RAMPlus+ is in slot 0, it emulates the Apple Language Card. Multiple RAMPlus+ cards can be installed into the same Apple II.

RAMPlus+ is supplied with 16K bytes of installed RAM for $189. The additional 16K-byte plug-in RAM costs $24.95. RAM diagnostics on disk are included. For details, contact Mountain Computer Inc., 300 El Pueblo Rd., Scotts Valley, CA 95066, (408) 438-6650.


Circle 585 on inquiry card.

Erase-Only Memory

The Stanislowski Electronics 3131.3 is a 4K-byte, vigorous random-access erase-only memory (RAEOM) Imaginary Metal Oxide Semiconductor (IMOS) integrated circuit (IC). Packaged in a nonstandard 27-pin dual inline package (DIP), the 3131.3 RAEOMIMOSIC has six erasing modes for maximum versatility and is designed for all applications requiring an erase-only memory (EOM). Possible applications include disposing of obsolete data and programs, destroying incriminating evidence, and amusing computer hobbyists.

Due to the patented IMOS process, the 3131.3 remains fully functional even when power is removed, making it ideal for use during power blackouts.

The 3131.3 is priced at $0.59 (more or less) in OEM (optional ephemeral merchandise) quantities. Contact GIGO Enterprises, 70 Main St., St. Peter'sborough, NH 03458.



Adjustable Video Monitor Platform

Structural Concepts' new portable, swiveling, tilting, sliding video-monitor platform helps make any desk or tabletop ergonomically safe. The platform tilts 20 degrees up or down from a horizontal position for glare reduction and operator comfort and can swivel a full 360 degrees for shared or angled usage. Additionally, it can slide up to 8 inches frontwards or backwards, which can help reduce eye strain.

The video-monitor platform is available in a variety of sizes for most video monitors. Mounting hardware is not required. Contact Structural Concepts Corp., 17237 Van Wagoner Rd., Spring Lake, MI 49465, (800) 253-5102; in Michigan, (616) 846-3300.

Circle 586 on inquiry card.

Memory Management for the TRS-80 Model III

The Compactors I and IV are the first products in a series of add-on units for Radio Shack's TRS-80 Model III from Hurricane Laboratories. The Compactor I allows the TRS-80 to run CP/M applications and utility programs without altering the TRS-80's operating environment. When installed in the Model III, you can elect to use CP/M version 2.2, TRSDOS, TRS-BASIC, or Hurricane Laboratories' Z80 Diagnostic Monitor, which is a CP/M programming tool.

The Compactor IV gives the TRS-80 Model III an 80-character by 24-line video-display screen and provides an RS-232C serial interface. The Compactor IV lets you use the Model III as a stand-alone computer or as an intelligent terminal to a larger host computer system.

The Compactors I and IV cost $450 and $475, respectively. Contact Hurricane Laboratories Inc., POB 631, Cupertino, CA 95015, (408) 446-0777.

Circle 587 on inquiry card.

Cables Feature Both Male and Female Connectors

Computer System Associates' RS-232C cable sets have both male and female DB-25 connectors attached at each end. This approach eliminates the problem of having the wrong connector for a terminal, video-display device, or computer. Stocking one type of cable will satisfy all data cable requirements. Prices begin at $50. Contact Computer System Associates, 7562 Trade St., San Diego, CA 92121, (714) 566-3911.

Circle 588 on inquiry card.

High-Capacity Memory Board for IBM Personal Computer

Datamac Computer Systems' new high-capacity memory expansion board for the IBM Personal Computer lets you easily upgrade to 544K bytes of memory. The expansion board can be configured in a variety of sizes from 64K bytes to 256K bytes—all with parity.

The 64K-byte board is available for $499. For further details, contact Robert Lindgren, Datamac Computer Systems, 680 Almanor Ave., Sunnyvale, CA 94086 (408) 735-0323.


Circle 589 on inquiry card.

Radio Ratings Analysis

Recall is a software package that helps radio stations quickly organize and interpret data furnished by a major radio-station ratings service. Designed to be used with the Apple II microcomputer, Recall can analyze up to four radio stations or four rating books simultaneously. It displays full-color graphics and provides extensive printouts. Different sections of Recall can provide in-depth information on radio-audience flow dynamics, daypart recycling, and market positioning.

The Recall package costs $750, which includes a 100-page manual and support consultation. Contact Media Service Concepts, 1713 N. North Park Ave., Chicago, Il 60614, (312) 951-2680.

Circle 590 on inquiry card.




256K-Byte RAM for the S-100

The Superam 50 RAM (random-access read/write memory) board provides 256K bytes of RAM and is compatible with the IEEE-696 S-100 bus standard. The board can be configured for either bank-select or extended addressing. Bank-select offers 64K-byte banks for memory-protect applications, and each bank can be individually set to any 64K-byte block of the 256K-byte address space. Extended addressing allows memory placement at any 256K-byte boundary segment in a 16-megabyte address field. A parity bit feature that detects single-bit errors per byte is included with the Superam.

The Superam 50 is available in two speeds: the Superam 50-P with a 275-nanosecond maximum access time and the Superam 50-AP with a 225-nanosecond maximum access time. In original equipment manufacturer's quantities, the Superam 50-P costs $1300 and the 50-AP costs $1400. Contact Piiceon Inc., 2350 Bering Dr., San Jose, CA 95131, (408) 946-8030.

Circle 591 on inquiry card.

What's New?



Jon Swanson, staff drafting editor, irons out a few problems in his largest schematic.

Debugging Tool Irons Out Circuit Problems

The General Electric Model F340 Electric Iron serves as a handy debugging tool for crucial logic circuits that must exhibit planar topology or use especially thin-film substrates. Using the latest deionized-vapor-injection technology, the Model F340 can be used with circuits arrayed on fiber substrates up to 0.1 cm (approximately 1/8 inch) thick, assuming proper adjustments for duration of treatment.

Contact General Electric Company, Housewares and Audio Business Division, POB 5105Y, Hillside Station, Bridgeport, CT 06602.■

Where Do New Products Items Come From?

The information printed in the new products pages of BYTE is obtained from "new product" or "press release" copy sent by the promoters of new products. If in our judgment the information might be of interest to the personal computing experimenters and homebrewers who read BYTE, we print it in some form. We openly solicit releases and photos from manufacturers and suppliers to this marketplace. The information is printed more or less as a first-in first-out queue, subject to occasional priority modifications. While we would not knowingly print untrue or inaccurate data, or data from unreliable companies, our capacity to evaluate the products and companies appearing in the "What's New?" feature is necessarily limited. We therefore cannot be responsible for product quality or company performance.

Ask BYTE

Conducted by Steve Ciarcia

VIA Experiment Board

Dear Steve,

I need an I/O (input/output) experiment board that I can plug directly into an Apple II Plus I/O slot. For my purposes, the board must use a Rockwell 6522 VIA (versatile interface adapter). Do you have a schematic diagram of such a board, or do you know of a company or a person that has made one?

Everest McDade
Arden, NC

This interface has generated a lot of discussion, going back to the November 20, 1977, EDN *magazine article "EDN System Design Project." The biggest problem with the interface seems to be the "bogus" timing of the phase 2 signal on the Apple II bus. By running the phase 0 signal through two 4050 CMOS (complementary metal-oxide semiconductor) gates in series, the correct phase 0 timing can be achieved. (You can also try adding an 820-ohm resistor and a 56-picofarad capacitor because this will generate an additional 30-nanosecond delay, which should work as well.) The VIA's CS2 signal is then connected to the I/O select signal on the bus. This should solve your problem.*

You may also be interested in Kenneth Ciszewski's article "Add a Peripheral Interface Adapter to Your Apple II" (January 1982 BYTE, page 324). . . . **Steve**

Bus Standard Stops Here

Dear Steve,

For several months, some manufacturers were claiming that their product was "compatible with the proposed IEEE S-100 bus standard." Recently I noticed that the wording has changed to ". . . conforms to the IEEE-696 S-100 Standard." From this I infer that the "proposed standard" is now a bona fide standard. Where can I get a copy?

Paul Frost
Beaverton, OR

EDN *magazine recently featured an article on various bus standards, including the IEEE-696 S-100 bus standard. The article, "Compare μC-Bus Specs to Find the Bus You Need," by Carl Warren, (*EDN*, June 10, 1981, page 141), contained a complete definition of the S-100 bus.*

*For a copy of the standard, contact Howard Fullmer, Chairman IEEE-696 Committee, Parasitic Engineering, POB 6314, Albany, CA 94706, (415) 839-2636. . . .***Steve**

Totem Poles and TTL

Dear Steve,

I have a couple of questions about TTL (transistor-transistor logic). What is the difference between totem-pole and open-collector outputs? And what is an expandable gate? Many thanks!

M. A. M. Felt
Amsterdam, Netherlands

Totem-pole output on a TTL integrated circuit consists of two transistors essentially in series, one above the other (see figure 1). In the high output state, the top transistor conducts, so the output is greater than 2.4 volts (V). In the low output state, the bottom transistor conducts, so the output is less than 0.8 V.

During the transition between states, both transistors are conducting, and large current spikes are induced in the power supply. If not properly bypassed, these transient spikes may trigger other circuits. If a full 5 V are needed during the high state, a pull-up resistor can be used as shown in figure 2.

Open-collector output circuits replace the top transistor and diode of the totem pole with an external pull-up resistor (figure 3). These outputs can then be tied together as in a "wired-NOR" circuit or where an output high voltage greater than 5 V is desired. However, they are noisier and slower than totem-pole outputs.

Tying totem-pole outputs together usually means catastrophic results as each tries to pull the other high or low.

*Expanders and gate expanders are TTL devices that allow the expansion of some logic functions. For example, they would be used if a 32-input AND gate were needed. They are not very popular today. . . .***Steve**




Figure 1




Figure 2

Figure 3

V_{CC}
EXTERNAL PULL-UP RESISTOR
OUTPUT V_{CC}

Ask BYTE

Controlling Heat and Surges

Dear Steve,

I have two problems that I don't believe you have covered. First, in the Tampa/St. Petersburg area, which suffers from power-line noise due to lightning, BSR X-10 control units are often triggered by line surges. It is not really a good idea to leave the X-10 energized during an extended absence. To come home and find the TV, radio, or lights on when they should be off is not too good. This problem probably has an electronic solution.

Second, the TRS-80 Model I is not really designed for 24-hour continuous operation insofar as heat is concerned. To be sure, you can take the two power supplies out of the Expansion Interface, but even that is probably not enough. This problem requires a hardware solution, which may be easy once the necessary ventilation is determined.

R. M. Sanford
Largo, FL

According to reports, BSR X-10 control modules have been tripped by power-line transients. I have not had this problem in my area, so I'm unable to experiment with a fix. A metal-oxide varistor (MOV) across each module would help because they would clip the voltage surge at approximately 130 volts. These units are made by General Electric and are available from major industrial parts suppliers.

You didn't mention whether you were having problems with your TRS-80 because of heat or whether it simply gets hot. The easiest way to cure heat problems is to use a fan for some forced ventilation. This also avoids having to open the box. Placing larger heat sinks on the power transistors will draw off even more heat, but unless the heat can be carried away, nothing is to be gained by this approach.

Small fans are available from many sources, including Radio Shack. Remember to keep the fan motor away from any magnetic media such as disks or tapes. . . . **Steve**

You Get What You Pay For

Dear Steve,

I have a Commodore VIC-20 computer and I would like to get more characters per line. If it is possible, how do I go about doing it? Do I have to add or replace any hardware?

Itshak Mihaeli
Brooklyn, NY

For less than $300, the VIC-20 represents a good value. In designing a computer for that price range, however, some compromises had to be made. One such compromise, as you know, is the screen-display format of 23 lines of 22 characters. The display is memory-mapped (i.e., a certain portion of memory is set aside solely for the screen), so modifying this requires changing both the hardware and the software. Even the VIC's 176 by 176 high-resolution option will not allow any more characters, although different shapes are available under software control.

A comparison of the VIC-20 with four other low-cost microcomputers appeared in the May 1981 BYTE (see page 46). The article, "The Commodore VIC-20 Microcomputer, A Low-Cost, High-Performance Consumer Computer," by Gregg Williams, featured a chart that showed the VIC-20 to be quite comparable to its competition. . . . **Steve**

Sweet Talker Interface

Dear Steve,

I'm interested in interfacing the Sweet Talker speech synthesizer to my Commodore 4032N computer. (See "Build an Unlimited-Vocabulary Speech Synthesizer," September 1981 BYTE, page 38.) Commodore has made a bunch of machines, but virtually all of them have the parallel user's port, also called the VIA (versatile interface adapter) port. The lower 12 pins on the edge connector go to a MOS Technology 6522 VIA and consist of two grounds, eight data lines, a CA1 (an input) handshake line, and a CB2 line (described as "a very powerful connection that has most of the abilities of CA1 but can also act as the input of the VIA shift register").

I know how to program any byte onto the data lines I want, but Commodore is silent about using these "handshake" lines. Can I use one line to sense when it's time to deliver the next phoneme code, and the other to strobe the Sweet Talker once the phoneme is present? Since Apple Computer already has the interface on one model, I'm hoping that a PET/CBM interface will be very similar. Is a ready-made, interfaced PET/CBM version forthcoming? If not, I'd appreciate any help on doing it myself.

Larry Hatch
Menlo Park, CA

The 6522 VIA used in the PET computer is very powerful and versatile; however, a great deal of explanation is required to fully use its features. I strongly suggest that you get a copy of the 6522 Data Sheets *and a* 6500 Series Hardware Manual *for a complete explanation as well as some applications. Both are available from MOS Technology Inc., 950 Rittenhouse Rd., Norristown, PA 19403, (800) 345-6386; in Pennsylvania, (215) 666-7950, ask for marketing.*

*Handshaking lines CA1 and CB2 can control the Sweet Talker, but the proper control word must be written into address location hexadecimal E84C, the peripheral control register. My "Circuit Cellar" article described the necessary programming for the Sweet Talker. This should solve your interface problem. . . .***Steve**

Variable Errors

Dear Steve,

I own an Apple II complete with disk drives, Language card, Silentype printer, Videx 80-column video-display card, and Microsoft Softcard with a Z80 microprocessor. I've tried a couple of your machine-language programs, and although I didn't understand them, they work beautifully. I wrote this simple BASIC program:

```
10 a = 2
20 A = 3
30 Q = a * A
40 Print Q
```

but I got a syntax error in line 10. In my engineering program, I must use lowercase variables.

H. J. Baerwolf
Inglewood, CA

Applesoft BASIC does not recognize lowercase variables, which is why you got the syntax error. The May 1980 Micro, The 6502/6809 Journal *has an article that should solve your problem. (Contact Micro Ink Inc., 34 Chelmsford Ave., POB 6502, Chelmsford, MA 01824, (617) 256-5515.) The program not only handles lowercase variables but it takes care of punctuation, too. . . .***Steve**

Strain-Gage Data Collection

Dear Steve,

I recently read your BYTE articles on the Z8-BASIC microcomputer. (See "Build a Z8-Based Control Computer with BASIC, Part 1," July 1981 BYTE, page 38; "Part 2," August 1981 BYTE, page 50.) My company is interested in using the Z8 in the field of strain-gage data collection. For this application, we would also need an A/D (analog-to-digital) converter of the type used in your second article. Where can we obtain additional information on the ADC0808 A/D converter shown in figure 2 (August 1981 BYTE, page 66)?

G. F. Fornaro
United States Pipe and Foundry Co.
Birmingham, AL

*The Z8-BASIC microcomputer is an excellent choice for strain-gage applications. The ADC0808 is available from National Semiconductor Corp., 2900 Semiconductor Dr., Santa Clara, CA 95051, (408) 737-5000. . . .***Steve** ■

In "Ask BYTE," Steve Ciarcia answers questions on any area of microcomputing. The most representative questions received each month will be answered and published. Do you have a nagging problem? Send your inquiry to:
Ask BYTE
c/o Steve Ciarcia
POB 582
Glastonbury CT 06033

If you are a subscriber to The Source, send your questions by electronic mail or chat with Steve (TCE317) directly. Due to the high volume of inquiries, personal replies cannot be given. Be sure to include "Ask BYTE" in the address.

A BASIC Program for Home Cryptography

Ralph Roberts
POB 8549
Asheville, NC 28814

The study of codes and cryptograms has always fascinated me, and it takes little imagination to see the power of the personal computer applied to this field. I used cryptographic devices during Army service in the late sixties but now find that my Smoke Signal Chieftain is capable of encoding and decoding at a level much greater than the military devices I once used. That's "clear text" to me.

I devised the program shown in listing 1 as a first experiment in computerized encrypting. Much elaboration is possible, but this program may provide a starting point for you as well. The program is written in Computerware's version 6.0 BASIC but should run in most standard BASICs with minimal changes. If you don't have a disk drive, use data statements or read in the text one line at a time.

Listing 1: *An encoding and decoding program in Computerware's version 6.0 BASIC. The POKE statement at line 10 changes the BASIC's delimiter character from a comma to an end-of-line character to improve handling of commas in text.*

```
*
0001 REM :::. ENCODING, DECODING PROGRAM :::
0002 REM ::: by Ralph Roberts :::::::::::::
0010 POKE( 210,13)
0020 STRING= 124:LINE=100:PRINT:PRINT
0030 PRINT TAB(25),"ENCODING PROGRAM":PRINT:PRINT
0040 INPUT "Password",P$:GOSUB 240
0050 INPUT "Encoding or Decoding (1 or 2)",I
0060 PRINT :IF I=1 INPUT"Name of file to be ENCODED",A$
0070 IF I=2 INPUT"Name of File to be DECODED",A$
0080 IF I=2 LET A=A*(-1)
0090 INPUT "Name of file to receive 'doctored' output",C$
0100 OPEN #1,A$:OPEN #2,C$
0110 READ #1,B$
0120 IF B$="" THEN 230
0130 FOR X=1 TO LEN(B$)
0140 LET B=ASC(MID$(B$,X,1))
0150 IF I=1 LET B=B+A:IF B>123 LET B=(B-123)+32
0160 IF I=2 LET B=B+A:IF B<32 LET B=(B+123)-32
0170 LET D$=D$+CHR$(B)
0180 NEXT X:IF I=1 LET A=A+1:IF A=124 LET A=1
0190 IF I=2 LET A=A-1:IF A=-124 LET A=-1
0200 PRINT :PRINT B$:PRINT D$
0210 WRITE #2,D$:D$="":B$=""
0220 GOTO 110
0230 POKE( 210,44):CLOSE #1:CLOSE #2:END
0240 LET P=LEN(P$)
0250 FOR X=1 TO LEN(P$)
0260 LET P1=P1+ASC(MID$(P$,X,1)):NEXT X
0270 LET A=INT(P1/P):IF A>123 PRINT"Sorry, PASSWORD phrase too big":RUN
0280 RETURN
```

For those of you who need a practical use for this program before reading further, I'll offer this example. If you work with a multiuser system, say in a college or high school, you could store your deep, dark secrets in a format that no one else could decode. Those of us who don't have deep, dark secrets encode just for the fun of it (or so we'd like you to think).

Writing of secrets, I do have one little trick to make this encoding program work more conveniently. In line 10 of listing 1, the POKE statement changes the delimiter character in my BASIC from a comma to an end-of-line (EOL) character. This allows the program to process an entire line in a text file, including commas. If your manual conceals the location of the delimiter character (as mine did), it's easy to concoct a four- or five-line PEEK,POKE routine that will find the location for you. Just successively change each comma in memory (decimal 44) to the EOL character (decimal 13). After each change,

Listing 2: *An encoding run of the encoding-decoding program shown in listing 1.*

```
                         ENCODING PROGRAM


Password ? THE RAIN IN SPAIN FALLS MAINLY ON THE PLAIN
Encoding or Decoding (1 or 2) ? 1

Name of file to be ENCODED ? SECRET.MSG
Name of file to receive 'doctored' output ? SECRET.X9

TO: CIA HEADQUARTERS -- LANGLEY, VIRGINIA   FROM: SECRET AGENT X9 1/2.
<7"c+l)c0-),9=):<-:,cppc4)6/4-Aoc>l:/161)ccc.:75"c;-+:-<c)/-6<c@!ctruq

SUBJECT: CLANDESTINE ENTRY INTO REPUBLIC OF MOLDAVIA
<>+3.,=#d,5*7-.<=27.d.7=,Bd27=8d;.9>+52,d8/d685-*?2*

        TO OBTAIN PLANS ON SECRET 'BOOM-BOOM' MISSLE.
eeeeeeeee>9e9,>+38e:6+8=e98e=/-</>el,997r,9971e73==6/s

     Hi guys. Having wonderful time in Moldavia. Am sending you all
fffff3TfR°d©tf3LaTYRfbZYOP]Q°Wf_TXPfTYf8ZWOLaTLtf,Xf©PYOTYRfdZ°fLWW

this via courier bat. Hope she got through.
°TU_gbUMgO[a©UQ©gNM°ug4[®Qg_TQgS[°g°T©[aSTu

     Went by the secret research facility on the outscirts of Moldavia City
hhhhhDR[ahOfhaURh°RP_Rah_R°RN_PUhSNPVYVafh®[haURh®ba°PV_a°h®Sh:®YQNcVNh0Vaf

and had no trouble buying the blueprints for the dreaded 'boom-boom'
O®RiVORi®]ib°]cPZSiPcgW®UibVSiPZcS©°W®baiT]°ibVSiR°SORSRipP]][vP]][p

missile. They had a concession stand out front selling that and other
®XbbX[TxjCWThjWPSjPjR©]RTbbX©]jbcP]Sj©dcjUa©]cjbT[[X]VjcWPcjP]Sj©cWTa

plans. I'll bring them back in my bootheel. Need anything else? (sgnd) X9 1/2.
°®Q©cyk9r®®kRbY©WkdXU]kRQS[kY©k]ikR__dXUU®yk>UUTkQ©idXY©WkU©cU/kscW©TtkH)k!z"y
```

Listing 3: *A printout of the encoded file produced by the program run shown in listing 2.*

```
<7"c+l)c0-),9=):<-:;cppc4)6/4-Aoc>l:/161)ccc.:75"c;-+:-<c)/-6<c@!ctruq
<>+3.,=#d,5*7-.<=27.d.7=;Bd27=8d;.9>+52,d8/d685-*?2*
eeeeeeeee>9e9,>+38e:6+8=e98e=/-</>el,997r,9971e73==6/s
fffff3TfR°d©tf3LaTYRfbZYOP]Q°Wf_TXPfTYf8ZWOLaTLtf,Xf©PYOTYRfdZ°fLWW
°TU_gbUMgO[a©UQ©gNM°ug4[®Qg_TQgS[°g°T©[aSTu
hhhhhDR[ahOfhaURh°RP_Rah_R°RN_PUhSNPVYVafh®[haURh®ba°PV_a°h®Sh:®YQNcVNh0Vaf
O®RiVORi®]ib°]cPZSiPcgW®UibVSiPZcS©°W®baiT]°ibVSiR°SORSRipP]][vP]][p
®XbbX[TxjCWThjWPSjPjR©]RTbbX©]jbcP]Sj©dcjUa©]cjbT[[X]VjcWPcjP]Sj©cWTa
°®Q©cyk9r®®kRbY©WkdXU]kRQS[kY©k]ikR__dXUU®yk>UUTkQ©idXY©WkU®cU/kscW©TtkH)k!z"y
```

Listing 4: *A run of the encoding-decoding program, this time decoding the file shown in listing 3.*

```
                              ENCODING PROGRAM


Password ? THE RAIN IN SPAIN FALLS MAINLY ON THE PLAIN
Encoding or Decoding (1 or 2) ? 2

Name of File to be DECODED ? SECRET.X9
Name of file to receive 'doctored' output ? FRM.X9

<7"c+1)c0-),9=).<-:;cppc4)6/4-Aoc>1:/161)ccc.:75"c;-+:-<c)/-6<c@!ctruq
TO: CIA HEADQUARTERS -- LANGLEY, VIRGINIA   FROM: SECRET AGENT X9 1/2.

<>+3.,=#d,5*7-.<=27.d.7=,Bd27=8d;.9>+52,d8/d685-*?2*
SUBJECT: CLANDESTINE ENTRY INTO REPUBLIC OF MOLDAVIA

eeeeeeeee>9e9,>+38e:6+8=e98e=/-</>el,997r,9971e73==6/s
         TO OBTAIN PLANS ON SECRET 'BOOM-BOOM' MISSLE.

fffff3TfR°d©tf3LaTYRfbZYOP]Q°Wf_TXPfTYf8ZWOLaTLtf,Xf©PYCTYRfdZ°fLWW
     Hi guys. Having wonderful time in Moldavia. Am sending you all

°TU_gbUMgO[a©UQ©gNM°ug4[®Qg_TQgS[°g°T©[aSTu
this via courier bat. Hope she got through.

hhhhhDR[ahOfhaURh°RP_Rah_R°RN_PUhSNPVYVafh®[haURh®ba°PV_a°h®Sh:®YQNcVNh0Vaf
     Went by the secret research facility on the outscirts of Moldavia City

O©RiVORi®]ib°]cPZSiPcgW©UibVSiPZcS©°W®baiT]°ibVSiR°SORSRipP]][vP]][p
and had no trouble buying the blueprints for the dreaded 'boom-boom'

®XbbX[TxjCWThjWPSjPjR©]RTbbX©]jbcP]Sj©dcjUa©]cjbT[[X]VjcWPcjP]Sj©cWTa
missile. They had a concession stand out front selling that and other

°®Q©cyk9r®®kRbY©WkdXU]kRQS[kY©k]ikR__dXUU©yk>UUTkQ©idXY©WkU®cU/kscW©TtkH)k!z"y
plans. I'll bring them back in my bootheel. Need anything else? (sgnd) X9 1/2.
```

try to read into a string variable a DATA statement consisting of two words separated by a comma. When both words and the comma read in, you've found the location.

Another approach is to use more string variables, creating a new one each time a comma is encountered. Three or four variables would probably suffice, but occasionally you'll lose a space that falls at the front of the next string variable. It's better to find that delimiter character.

Aside from the way it handles commas, this program is really pretty simple—but the code it generates is not. The encryption begins as a simple offset. The program first reads your password (or passphrase) and sums the ASCII values of all the letters and spaces. To obtain the offset, the program divides the sum by the number of letters and spaces in the password. With an offset of 63, for example, every letter is printed 63 characters higher than it actually is (with a wrap-around feature to maintain the desired ASCII range of 32 to 123 and an upward shift of one so no space will be printed). In each succeeding line, the offset is increased by one. This prevents anyone from breaking your code by analyzing frequency of character appearance. Every single letter and space is represented by a *different* character in every line.

For spies, my encoding-decoding program comes in handy almost daily. Listing 2, for example, reveals how I ran the program to encode a message during my last CIA mission behind the Iron Curtain. Listing 3 is the printout of the encoded file I sent to Langley, and listing 4 shows a program run that decoded the same file. Decoding is merely the reverse of the encoding operation, but you must give the password.

With this program and a portable computer like the Osborne 1, you too can be a spy. Go forth, my fellow agents, and have secrets from one another! ■

Software Received

Apple

Adenoids, a medical adventure game for the Apple II. Floppy disk, $29.95. Lymphatic Software, 12 Sinus Way, Psychosomatic, NH 03458.

Amperdump, a high-resolution graphics dump utility program using the Epson MX-80 or -100 printer for the Apple II Plus. Floppy disk, $30. Madwest Software, POB 9822, Madison, WI 53715.

Ampergraph, a graphics utility package to generate plots and graphs for the Apple II. Floppy disk, $30. Madwest Software (see address above).

Antfarm, a language system for teaching programming to children for the Apple II. Floppy disk, $49.95. WIMS Computer Consulting, 6723 East 66th Pl., Tulsa, OK 74133.

Bug Attack, an arcade-type game for the Apple II. Floppy disk, $29.95. Cavalier Computer, POB 2032, Del Mar, CA 92014.

David's Midnight Magic, a high-resolution pinball game for the Apple II. Floppy disk, $34.95. Broderbund Software Inc., 1938 Fourth St., San Rafael, CA 94901.

Hi-Res Secrets, a graphics development package for the Apple II. Floppy disks, $125. Avant-Garde Creations, POB 30160, Eugene, OR 97403.

High-Res Mastertype, a typing instruction game for the Apple II. Floppy disk, $39.95. Lightning Software, POB 11725, Palo Alto, CA 94306.

The Manipulator, a text file utility system for the Apple II. Floppy disk, $34.95. Pear Software, 407 Terrace, Ashland, OR 97520.

Menu Generator, a menu-development software system for the Apple II Plus. Floppy disks, $39.95. Crane Software Inc., Suite 611, 16835 Algonquin, Huntington Beach, CA 92649.

Nutrichec 2.0, a diet and physical activity analysis program for the Apple II Plus. Floppy disk, $59.95. WIMS Computer Consulting (see address above).

Personal Tax Plan, an income tax planning package for the Apple II and the Western Digital Microengine. Floppy disk, $130. Aardvark Software Inc., 783 North Water St., Milwaukee, WI 53202.

Stone of Sisyphus, an adventure game for the Apple II Plus. Floppy disks, $29.95. Adventure International, POB 3435, Longwood, FL 32750.

Ultra Plot, a plotting utility program to create charts and graphs for the Apple II. Floppy disks, $70. Avant-Garde Creations (see address above).

Versaform, a business forms processing package in Pascal for the Apple II. Floppy disk, $389. Applied Software Technology, 15985 Greenwood Rd., Monte Sereno, CA 95030.

CP/M

Ddump 1.6, a sector-oriented disk dump utility program for CP/M. 8-inch floppy disk, $29.95. Elektrokonsult Inc., Konnerudgt. 3, N-3000 Drammen, Norway.

Dtest 1.7, a disk- and disk drive-testing program for CP/M. 8-inch floppy disk, $29.95. Elektrokonsult Inc. (see address above).

The Formula, a multifunctioned, business-oriented data-processing system for CP/M. 8-inch floppy disk, $595. Dynamic Microprocessor Associates, 545 Fifth Ave., New York, NY 10017.

PET

RPL Language, a compiled language system for the PET-2001. Cassette, $71.91; floppy disk $80.91. Samurai Software, POB 2902, Pompano Beach, FL 33062.

Vigil, an interactive graphics and game development system for the VIC-20. Cassette, $35. Abacus Software, POB 7211, Grand Rapids, MI 49510.

TRS-80

ColorFORTH, a FORTH language system for the TRS-80 Color Computer. Cassette, $49.95. Armadillo Software, POB 7661, Austin, TX 78712.

Do-It-Yourself Adventure Kit, an adventure game development program for the TRS-80 Models I and III. Floppy disk, $29.95. Suburban Software Co., R.D. #1, Box 74A, Spring Mills, PA 16875.

Hexspell 2, an extended spelling checker for the TRS-80 Models I and III. Floppy disk, $99. Hexagon Systems, POB 397, Station A, Vancouver, British Columbia V6C 2N2, Canada.

Imperial Arena, a Star Trek-type game for the TRS-80 Model I. Cassette or floppy disk, $15. Richard Bissonnette, POB 476, Amherst, MA 01004.

Linear Programming System, a system to solve linear programming problems for the TRS-80 Model I. Cassette, $9.89. Computer Heroes, 1961 Dunn Rd., East Liverpool, OH 43920.

Macro-Assembler 4004, an emulation of the 4004 microprocessor for the TRS-80 Models I, II, III, IV, etc. Hard disk, $1.95. MacaroonSoft, 45 The Way of All Flesh, Spittingboro, NH 03458.

Newtrieve, an indexing and data-retrieval program for the TRS-80 Models I and III. Floppy disk, $49.95. Unique Printing and Stationery Co., 11 Maiden Ln., New York, NY 10038.

Refware Thesaurus: Builder 1.0, a specialized thesaurus development program for the TRS-80 Model III. Floppy disk, $149.95. Refware, POB 451, Chappaqua, NY 10514.

Silly Syntax, a story creation game for the TRS-80 Color Computer. Cassette, $19.95. Sugar Software, 2153 Leah Ln., Reynoldsburg, OH 43068.

Stone of Sisyphus, an adventure game for the TRS-80 Models I and III. Floppy disks, $29.95. Adventure International, POB 3435, Longwood, FL 32750.

Other Computers

Fifth, a language system for the Atari 400/800. 25 ozs., $7.95. fig-Fork Software Inc., Frodo Alley, Fraternity, NH 03458.

Match/Bowl, two arcade-type games for the Bally Arcade. Cassette, $12.95. Edge, 12046 Flambeau Dr., Palos Heights, IL 60463. ■

This is a list of software packages that have been received by BYTE Publications during the past month. The list is correct to the best of our knowledge, but it is not meant to be a full description of the product or the forms in which the product is available. In particular, some packages may be sold for several machines or in both cassette and floppy-disk format; the product listed here is the version received by BYTE Publications.

This is an all-inclusive list that makes no comment on the quality or usefulness of the software listed. We regret that we cannot review every software package we receive. Instead, this list is meant to be a monthly acknowledgment of these packages and the companies that sent them. All software received is considered to be on loan to BYTE and is returned to the manufacturer after a set period of time. Companies sending software packages should be sure to include the list price of the packages and (where appropriate) the alternate forms in which they are available.

Programming Quickies

Base Conversion on the TRS-80 Pocket Computer

David M. Dolan
POB 632
South Pasadena, CA 91030

Base conversion, indispensable to the programmer, has been a favorite subject for programs since the earliest issues of microcomputer magazines. But because the need for converting numbers from one base to another usually arises while the computer is tied up developing a program, it is impractical to load and use a base-conversion program at the same time. Until Tandy began selling its TRS-80 Pocket Computer, the only other choice was the Texas Instruments Programmer calculator.

Base conversion at first appeared to be a natural for the Pocket Computer (PC). A second glance, however, revealed some obstacles. PC BASIC lacks two functions used extensively in previous base-conversion programs: string-manipulation and the ASC function, which returns the ASCII (American Standard Code for Information Interchange) code for string argument. Could I make a limited BASIC perform like an extended BASIC? It was a challenge I couldn't resist.

The program that met the challenge is shown in listing 1. It will convert any binary, octal, decimal, or hexadecimal number (up to decimal 65535) to its binary, octal, decimal, or hexadecimal equivalent. This represents an improvement over the TI Programmer calculator, which can't handle binary numbers.

The only concession I had to make to the limitations of PC BASIC is this: each digit of a number must be entered separately and followed by Enter. You designate the end of a number by entering a space (SPC), followed by Enter. The program then asks for the base of the number to be converted; you enter 2, 8, 10, or 16. In the same way, the program asks the base to which the number is to be converted. That's all there is to it.

Unfortunately, the Pocket Computer doesn't perform conversions as fast as a larger microcomputer or the TI Programmer. This PC BASIC program takes 15 seconds to change decimal 255 to hexadecimal FF, and 45 seconds to change binary 11111111 11111111 to hexadecimal FFFF. I tried various ways to make the program run faster. Some of them saved memory, but all ran slower. Perhaps you can do better.

Beware of trying to translate this program into other

dialects of BASIC. The program takes advantage of some of PC BASIC's peculiarities. Line 500, for instance, makes use of the fact that the string A$ is the same as A$(1), B$ is the same as A$(2), etc.

The sample run of the program is shown in listing 2 on page 438. To produce the printout, I translated the program to run on the TRS-80 Model II. The printout is similar to what you will find on the Pocket Computer. I produced the program listing itself (listing 1) by copying the debugged program by hand directly from the Pocket Computer to a Radio Shack Model II. Although not as reliable as a listing from a running program, this listing was the best one possible at the time. (Since then, Tandy has released a printer for the Pocket Computer.)

If, like me, you're a gadgeteer as well as a computer nut, you may have been looking for an excuse to buy one of the new pocket computers. This base-conversion program may give you that excuse. Depending on your needs, the base-conversion program might justify more than half the price of the new gadget.■

Listing 1: *A program for converting numbers from one base to another. Designed to run on the TRS-80 Pocket Computer, the program can convert a binary, octal, decimal, or hexadecimal number to its equivalent in the other three bases.*

```
10 PAUSE"BASE CONVERSION"
20 PAUSE"ENTER DIGITS SEPARATELY":PAUSE"PRESS ENTER AFTER EACH"
30 CLEAR:FORU=26TO41:INPUT"DIGIT (SPC TO EXIT):";A$(U)
40 IFA$(U)=" "LETU=U-1:GOTO60
50 NEXTU
60 INPUT"BASE OF #(2,8,10,16):";Q
70 INPUT"CONVERT TO(2,8,10,16):";R
80 V=0:W=0
90 FORT=UTO26STEP-1:GOSUBA$(T)
100 IFA(T)>QBEEP1:PAUSE"INVALID INPUT":GOTO30
120 V=V+INT(A(T)*Q^W+.5):W=W+1
130 NEXTT:GOTO300
140 "0":A(T)=0:RETURN
150 "1":A(T)=1:RETURN
160 "2":A(T)=2:RETURN
170 "3":A(T)=3:RETURN
180 "4":A(T)=4:RETURN
190 "5":A(T)=5:RETURN
200 "6":A(T)=6:RETURN
210 "7":A(T)=7:RETURN
220 "8":A(T)=8:RETURN
230 "9":A(T)=9:RETURN
240 "A":A(T)=10:RETURN
250 "B":A(T)=11:RETURN
260 "C":A(T)=12:RETURN
270 "D":A(T)=13:RETURN
280 "E":A(T)=14:RETURN
290 "F":A(T)=15:RETURN
300 A$(26)="0":A$(27)="1":A$(28)="2":A$(29)="3":A$(30)="4":A$(31)="5"
310 A$(32)="6":A$(33)="7":A$(34)="8":A$(35)="9":A$(36)="A"
320 A$(37)="B":A$(38)="C":A$(39)="D":A$(40)="E":A$(41)="F"
350 IFR=16GOSUB400:S$="HEX: ":GOSUB500:GOTO30
360 IFR=10GOSUB400:S$="DEC: ":GOSUB500:GOTO30
370 IFR=8GOSUB400:S$="OCTAL: ":GOSUB500:GOTO30
380 IFR=2GOSUB400:S$="BINARY:":GOSUB500:GOTO30
400 Y=V:W=INT(LOGV/LOGR+.000001):U=1
410 FORT=WTOOSTEP-1:X=INT(R^T+.5):Q=INT(Y/X)
420 A$(U)=A$(Q+26):U=U+1:Y=INT(Y-Q*X+.5)
430 NEXTT:RETURN
500 PRINTS$;" ";A$;B$;C$;D$;E$;F$;G$;H$;I$;J$;K$;L$;M$;N$;O$;P$:RETURN
```

Listing 2: *A sample run of the base-conversion program in listing 1. Note that after entering each digit of a number, the user must press Enter. The user marks a digit as the number's last by pressing SPC (space) and then Enter.*

```
Ready
>RUN
BASE CONVERSION

ENTER DIGITS SEPARATELY
DIGIT (SPC TC EXIT):? F
DIGIT (SPC TO EXIT):? C
DIGIT (SPC TO EXIT):? 7
DIGIT (SPC TC EXIT):? E
DIGIT (SPC TO EXIT):?
BASE OF # (2,8,10,16):? 16
CONVERT TO(2,8,10,16):? 2
BINARY  1111110001111110

ENTER DIGITS SEPARATELY
DIGIT (SPC TO EXIT):? 3
DIGIT (SPC TO EXIT):? 2
DIGIT (SPC TO EXIT) :? 7
DIGIT (SPC TO EXIT):? 2
DIGIT (SPC TO EXIT):? 5
DIGIT (SPC TO EXIT):?
BASE OF # (2,8,10,16):? 10
CONVERT TO(2,8,10,16):? 16
HEX  7FD5

ENTER DIGITS SEPARATELY
DIGIT (SPC TO EXIT) :? 3
DIGIT (SPC TC EXIT):? 5
DIGIT (SPC TO EXIT):? 7
DIGIT (SPC TO EXIT):?
BASE OF # (2,8,10,16):? 8
CONVERT TO(2,8,10,16):? 16
HEX  EF

ENTER DIGITS SEPARATELY
DIGIT (SPC TO EXIT):?
```

Career Opportunities in Computing

Jacqueline Johnston
1808 Pomona Dr.
Las Cruces, NM 88001

Rare is the computer hobbyist who has not considered entering the computer field professionally. Just entertaining the thought, however, raises several questions that are difficult to answer. Is there a demand for computer programmers? Is hobby experience of any value in landing a job?

The answer to both questions is "yes." Hobby-level interest in computers can lead to a rewarding and stimulating career as a computer professional. There is an urgent need for qualified programmers and analysts in all sectors of commerce and industry.

Granted, there are differences between home computing and the world of business and industry, but these differences should not deter you from seeking a career in a field you enjoy. In this article we will examine what the computer programmer does in the "real world," what the requirements are in terms of education and experience, where jobs can be found, and what to expect for the general pay scale. The emphasis will be on programmers, but the information is also applicable to related jobs.

Computer programming is a dynamic career field, and a semiannual survey of 500 companies by *Fortune* magazine shows that programming is virtually recession-proof. The demand for programmers is expected to increase more rapidly than the average demand in other fields, and the trend will continue through the mid-1980s as computer usage expands in business and research. Newspapers and magazines are filled with advertisements for programmers and analysts. In my job as a guidance counselor, I receive countless inquiries from companies searching for computer programmers.

Programming is an attractive field from the standpoint of both salary and working conditions. College placement offices report that computer-oriented graduates receive salary offers of approximately $1691 per month. In a recent poll I conducted of 150 companies hiring programmers, the average entry-level salary was $1665 per month. Experienced programmers can expect higher salaries, ranging up to $50,000 a year.

How to Choose

Programmer—mathematician—computer scientist—engineer. They all sound interesting, but which one is for you? Let's take a look at the work that each entails.

An *engineer* should have a bachelor's degree (often a master's is required) in one or more of the engineering fields: civil, electrical, mechanical, etc. Engineering positions generally involve design work—designing roads, machinery, buildings, or computers. These positions require a solid background in mathematics and some familiarity with computers and programming, as many solutions to engineering problems are arrived at through the use of preexisting or "canned" computer programs. If you are interested in design, an engineering career might be the thing for you. If you prefer programming and hands-on computer work, another field might be more to your liking.

The position of *computer scientist* evolved about ten years ago, so it is relatively new. A bachelor's degree in computer science is needed, and some positions require a master's degree. The educational background is broad in scope, and it includes the study of mathematics, computer hardware, computer operations, systems programming, compiler and assembler design, and high-level languages. Consequently, computer scientists

About the Author
Jacqueline Johnston, a former guidance counselor, is now a computer programmer with the Business Data Systems Office, White Sands Missile Range. The opinions expressed here are her own and not necessarily those of the White Sands Missile Range or the U.S. Government.

tend to have broad responsibilities in software design and computer-center management.

Mathematicians should have a minimum of a bachelor's degree in mathematics, and usually a minor or a second degree in physics or engineering. These positions involve the development of mathematical solutions to complex problems and the translation of the solutions into efficient computer programs. The work provides an excellent mix of mathematical and programming duties.

Computer programmer positions do not usually require a college degree, but applicable experience is required (and a degree in math, accounting, business administration, computer science, physics, or engineering is a definite asset). Computer programmers do a lot of what they like best—write programs. This may include systems and applications programs. On projects that require analytical solutions involving higher mathematics or engineering principles, an engineer or mathematician will usually perform that part of the job and then turn the project over to the programmer for completion.

Programming Jobs

Broadly speaking, programming can be divided into two principal areas: systems programming and applications programming. Although there is considerable crossover between the two, systems programming involves logical operations, while applications programming involves mathematical and process control operations.

Systems programmers frequently employ complex logical operations and concepts to develop executive control programs, monitors, assemblers, compilers, device utilities, and so forth. Most of their work is done in assembly or machine language and seldom requires the use of mathematics beyond algebra. Notable exceptions are certain system-design processes that require a knowledge of statistics.

Applications programming is a diverse field that can be broken into three broad subfields: scientific, busi-

ness, and process control. There are many types of jobs within each of the subdivisions; consequently, we will speak only in general terms. Applications programmers must have a strong background in mathematics. Especially important to scientific programmers are algebra, trigonometry, and calculus. The mathematics of finance is essential to business programmers.

Scientific programmers work on problems in all sectors of science and industry, from spaceflight planning to computer design, and from bridge building to chemical analysis. Most scientific programs are written in high-level languages, with FORTRAN and PL/I being the most common.

Business programmers work on financial applications, but there are many other projects such as inventory control and network analysis that fall within the business realm. Business programs are written in high-level languages, such as COBOL, RPG, and FORTRAN.

Process control refers to the use of a computer to monitor data from and transmit commands to external equipment in real time. Applications programmers in this area generally have some familiarity with the hardware of both the computer and the external equipment. Programs for these functions are usually written in assembly language or a high-level language such as FORTRAN, or a combination of the two.



Figure 1: *The plus signs on this map indicate locations of cities where programmer jobs were advertised during a recent one-week survey period. About 210 cities, representing more than 1100 programmer job openings, are illustrated.*

Geographic Distribution

Who has job openings for programmers? Manufacturers, banks, chemical companies, department stores, research firms, fast-food chains, petroleum companies, government agencies, and any scientific or commercial activity you can think of. Where are the jobs located? Everywhere.

Figure 1 is a computer-generated map that shows the locations of cities where job openings for programmers existed during a recent one-week survey period. (This, incidentally, is just one of several uses for the microcomputer in counseling job seekers.) A plus sign is drawn at the location of every city where there were one or more programmer jobs during the survey period.

Since only one plus sign is drawn for any city, regardless of the number of jobs available, there are many more jobs than plus signs. This particular map illustrates jobs in about 210 cities; the total number of jobs was more than 1100. The majority of jobs are concentrated in and around certain large population centers, as is readily apparent on the map. Note especially the concentration of plus signs near San Francisco, Los Angeles, Phoenix, Denver, Dallas, Houston, Chicago, New York City, Washington DC, and Miami.

Requirements

So computer programming sounds like an attractive career field? What are the requirements for entry? Most companies prefer that applicants have a bachelor's degree. Scientific and engineering organizations prefer degrees in computer science, mathematics, engineering, or the physical sciences. Organizations with business applications prefer applicants with coursework in computer science, accounting, and business administration. Of course, some workers with applicable experience in programming may be able to secure a position without a college degree. Good verbal and written-communications skills are always an asset. Normally companies prefer basic familiarity with one or more computer languages.

To keep track of the programming languages that are in demand, I perform a weekly survey of the languages required to qualify for jobs advertised during each survey week. In order to make the data available to my clients in a meaningful form, I use a microcomputer to generate a bar chart of the survey results. The chart created for a recent typical period is illustrated in figure 2. Survey figures are entered by means of the keyboard of a video terminal and the chart itself is printed on a line printer. For the sake of simplicity, the program is written in BASIC (see listing 1). It is brief and straightforward. The only change you might need to make is in the syntax of the PRINT #2 statements that send output to the line printer. (Not all versions of BASIC use this syntax.)

Returning to the bar chart, it's strikingly clear that during the particular survey period illustrated, knowledge of COBOL was required for more jobs than any other language, followed by FORTRAN,

```
                                    LANGUAGES REQUIRED FOR JOB OPENINGS
                                    ADVERTISED DURING WEEK OF 11 MAY 81


    ALGOL  ** 1.9 %

      APL  * .9 %

    BASIC  **** 3.8 %

    COBOL  ******************************************************************** 67.9 %

  FORTRAN  ************************* 25.2 %

   PASCAL  ******* 6.7 %

     PL/1  ************** 13.5 %

      RPG  ******************* 19.4 %

ALL OTHERS  *************** 14.5 %




ASSEMBLERS  ************************************* 36.8 %

           +----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+----+
           0         10        20        30        40        50        60        70        80        90        100
                                           PERCENTAGE OF JOB OPENINGS REQUIRING EACH LANGUAGE
```

Figure 2: *Bar chart showing which programming languages are required to qualify for jobs advertised. Totals exceed 100 percent because many jobs require knowledge of more than one language.*

Listing 1: *BASIC listing of the bar-chart program, which is useful for anyone who wants to keep tabs on programming-language requirements for jobs.*

```
1000 REM     THIS PROGRAM GENERATES A BAR CHART ILLUSTRATING THE PERCENTAGE
1020 REM     OF JOB OPENINGS REQUIRING KNOWLEDGE OF EACH OF THE VARIOUS
1040 REM     PROGRAMMING LANGUAGES.  THE CHART IS BASED ON STATISTICAL
1060 REM     DATA SOLICITED FROM THE USER.
1080 REM
1090 DIM L$(10),N(10)
1100 DATA "     ALGOL","       APL","     BASIC","     COBOL"
1200 DATA "   FORTRAN","    PASCAL","      PL/1","       RPG"
1300 DATA "ALL OTHERS","ASSEMBLERS"
1340 REM
1350 REM     FILE #2 IS THE LINE PRINTER.
1360 REM
1400 OPEN "LP:" FOR OUTPUT AS FILE #2
1500 FOR I=1 TO 10
1600 PRINT #2:
1700 NEXT I
1800 PRINT "SURVEY CONDUCTED FOR WEEK BEGINNING WHEN?"
1900 INPUT W$
1920 REM
1940 REM     FOR EACH OF THE TEN LANGUAGES, READ THE LANGUAGE NAME FROM
1950 REM     THE DATA STATEMENTS AND REQUEST THE NUMBER OF JOBS REQUIRING
1960 REM     THAT LANGUAGE.
1970 REM
2000 FOR I=1 TO 10
2100 READ L$(I)
2200 PRINT "NUMBER OF JOBS REQUIRING ";L$(I);"?"
2300 INPUT N(I)
2400 NEXT I
2500 PRINT "TOTAL NUMBER OF JOBS SURVEYED?"
2600 INPUT T
2640 REM
2650 REM     THE STATEMENTS FROM HERE THROUGH LINE 6000 PRINT OUT THE
2660 REM     CHART.
2670 REM
2700 PRINT #2:TAB(45);"LANGUAGES REQUIRED FOR JOB OPENINGS"
2800 PRINT #2:TAB(45);"ADVERTISED DURING WEEK OF ";W$
2900 PRINT #2:
3000 PRINT #2:
3100 PRINT #2:
3200 FOR I=1 TO 10
3400 IF I<>10 THEN 4000
3500 PRINT #2:
3600 PRINT #2:
3700 PRINT #2:
3800 PRINT #2:
```

Listing 1 continued on page 443

RPG, and PL/I. Additionally, about a third of all jobs required familiarity with assembly language (though not necessarily for a specific processor). The figures vary somewhat from week to week, but COBOL has been in demand by users of large computers for the past several years and it will probably remain in that position for some time. The rankings of FORTRAN, RPG, and PL/I as they appear on this chart are also fairly representative of their recent and projected demand. Not shown, but of special interest to many applicants, is the fact that almost 20 percent of the jobs surveyed during the period required knowledge of database-management systems. The totals exceed 100 percent because many jobs require knowledge of more than one language.

Civil Service Employment

In addition to openings in the private sector, the federal government offers opportunities to persons with college training or experience in computer programming. Due to the recent cutbacks in hiring, the outlook is not as bright as it is in the private sector, but good opportunities still

Listing 1 continued:

```
3900 PRINT #2:
3940 REM
3950 REM     COMPUTE THE PERCENTAGE AND ROUND IT OFF TO ONE DECIMAL PLACE.
3960 REM
4000 P=INT(1000*(N(I)/T))/10
4010 IF P<=100 THEN 4100
4020 P=100
4040 REM
4050 REM     COMPUTE THE NUMBER OF ASTERISKS TO BE PRINTED.
4060 REM
4100 J=INT(P+.5)
4200 PRINT #2:
4240 REM
4250 REM     PRINT OUT THE LANGUAGE NAME.
4260 REM
4300 PRINT #2:L$(I);"   ";
4400 IF J=0 THEN 4800
4430 REM
4440 REM     PRINT OUT A ROW OF ASTERISKS, THE NUMBER OF WHICH CORRESPONDS
4450 REM     TO THE PERCENTAGE OF JOBS REQUIRING THE LANGUAGE.
4460 REM
4500 FOR K=1 TO J
4600 PRINT #2:"*";
4700 NEXT K
4740 REM
4750 REM     PRINT OUT THE PERCENTAGE AT THE END OF THE LINE OF ASTERISKS.
4760 REM
4800 PRINT #2:P;"%"
4900 NEXT I
5000 PRINT #2:
5020 PRINT #2:
5040 REM
5050 REM     THE STATEMENTS FROM HERE THROUGH LINE 5500 PRINT OUT A
5060 REM     NUMERICAL SCALE AT THE BOTTOM OF THE CHART.
5070 REM
5110 PRINT #2:TAB(11);"+";
5120 FOR I=1 TO 20
5130 PRINT #2:"----+";
5140 NEXT I
5150 PRINT #2:
5300 FOR I=0 TO 100 STEP 10
5400 PRINT #2:TAB(I+10);I;
5500 NEXT I
5600 PRINT #2:
5700 PRINT #2:TAB(37);"PERCENTAGE OF JOB OPENINGS REQUIRING EACH LANGUAGE"
5800 FOR I=1 TO 10
5900 PRINT #2:
6000 NEXT I
6100 STOP
6200 END
```

exist, especially in Washington DC. Government employment is attractive from several standpoints and it offers good benefits in the areas of leave and retirement.

Persons doing computer programming work are usually hired as mathematicians, computer programmers, or computer scientists. Entry-level salaries for these positions range from $12,266 to $15,193 per year.

There are also various trainee positions, a number of which are filled through PACE (Professional and Administrative Career Examination), a written test. Veterans who served between August 5, 1964, and May 7, 1975, may be eligible for a VRA (Veterans Readjustment Appointment). These positions offer training programs, and the veteran need not participate in regular competitive procedures, although he or she must meet the position's minimum requirements.

For more information on jobs with the federal government, contact your local Federal Job Information Center, or call (800) 555-1212 to request a toll-free number.

Going to School

If you are interested in attending college to study computer programming, there are several publications that will help you locate schools offering suitable programs. Some of the most useful books are: *Lovejoy's College Guide, Chronicle Guide to Four-Year College Majors,* and *The College Blue Book* (four volumes). These are available at most public libraries, and they list colleges with programs in computer science and mathematics, offer brief descriptions of the colleges, and list tuition, admission requirements, etc.

College credits may also be earned through work experience and independent study. Credits for this

knowledge can be awarded through CLEP (College-Level Examination Program) and the ACT (American College Testing) Proficiency Examination Program. For information on costs and registration procedures, write to CLEP and ACT for their pamphlets (see the text box "Free Information," on page 446).

Those eligible for veterans' benefits can receive monthly payments from the VA (Veterans Administration) while attending school. A full-time student with no dependents receives $342 per month, tax free, for forty-five months ($15,390 total). Individuals with dependents receive correspondingly larger payments. A veteran with two dependents, for example, receives a total of $20,880. For more information on VA benefits, contact the VA Regional Office closest to you or the veterans' representative at the college you wish to attend, or call (800) 555-1212 to obtain a toll-free number. Remember, eligibility for veterans' benefits terminates ten years after separation from the service or on December 31, 1989, whichever comes first.

Getting the Job

If you are qualified for entry into the computer programming field, there are several steps that must be taken to secure a position. First, you must prepare an effective resume. Generally, an applicant can prepare a resume without paying a commercial resume writer. If you write it yourself, you will be better prepared to discuss your qualifications during the interview. The resume should be short—never more than two pages, and preferably not more than one. Most resumes are read in ten to fifteen seconds, so the information should be clear and easy to read. The purpose of the resume is to obtain an interview for the applicant. The applicant will usually have to fill out an application form if the firm is interested.

When the reSume is sent out, a cover letter should accompany it. The letter should be typed, never photocopied or mimeographed, and personalized to the firm receiving it. Addresses of firms hiring computer pro-

grammers can be obtained from *The College Placement Annual, Ad Search* (a weekly newspaper with employment ads from all over the country), *Career Opportunity Update*, local newspapers, and industry publications such as *ComputerWorld, Datamation, Electronics,* and *Electronic News.* A new publication, *Peterson's Annual Guide to Careers and Employment for Engineers, Computer Scientists, and Physical Scientists,* lists companies seeking graduates in these fields. (It is available for $13.25, postage paid, from Peterson's Guides Book Order Dept., POB 978, Edison, NJ 08817.)

Free employment counseling and placement services are available at state Job Service offices. There are more than 2400 local offices of the federal-state employment-service system, staffed with professionals who can help with career planning and finding a job. The Employment Service operates a computerized Job Bank system in virtually every state. These Job Banks comprise the largest, most comprehensive and up-to-date source of job openings in the nation. The listings are available on microfiche at your local state-employment service office.

A number of private employment agencies specialize in finding jobs for individuals with technical skills, and bill the client companies, rather than the job seeker, for their services. Although most of these firms are reputable, you should be cautious and read all the fine print before signing a contract.

One of the final steps in the job-hunting process is the job interview. There are many publications and books that offer advice on how to prepare for an efffective interview. It's important to learn as much as possible about the company before the interview, to make a presentable appearance, and to speak with confidence and enthusiasm.

It is a fact of life that choice jobs do not always go to the best-qualified applicant, but to the person who has the best job-hunting skills. The importance of resume preparation and interview technique cannot be overemphasized.

Summary

The transition from computer hobbyist to professional can be rewarding in terms of both personal satisfaction and salary. The employment outlook for computer-related jobs is excellent. In the *1981 College Placement Annual* more than 650 companies and government agencies advertised for computer programmers, and that number is expected to increase. A variety of corporations are represented, from banks to large-scale manufacturing companies. Jobs are available in most locations in the U.S., with the greatest demand in large metropolitan areas.

There are many jobs that involve programming—programmer, mathematician, computer scientist, and engineer. We have looked at the job duties and some of the entrance requirements for these positions. Some require a bachelor's degree and knowledge of one or more programming languages, particularly COBOL and FORTRAN. Those interested in attending college to become proficient in programming have many options to choose from, as an increasing number of schools offer suitable programs. Once you are qualified, it is imperative that you develop your job-hunting skills so that you can pursue the career of your choice. ■

Acknowledgments

I would like to thank White Sands Missile Range for providing the facilities to collect and develop some of the material presented in this article.

Free Information

1981 Computer Salary Survey and Career Planning Guide: *Source EDP, Suite 1100, 100 South Wacker Dr., Chicago, IL 60606 (or contact your local Source EDP Office).*

Mathematics and Related Positions *(Announcement Q1-1500),* Computer Specialists *(Announcement 420), and* other civil service job announcements: *United States of America, Office of Personnel Management, 1900 E St., NW, Washington, DC 20415 (or contact your local Job Information Center).*

CLEP May Be For You: *College Board Publication Orders, POB 2815, Princeton, NJ 08541.*

ACT Proficiency Examination Program: *ACT PEP Coordinator, Proficiency Examination Program, POB 168, Iowa City, IA 52240.*

Benefits for Veterans and Service Personnel with Service since January 31, 1955, and Their Dependents: *Veterans Administration, 941 North Capitol St., NE, Washington, DC 20421.*

Occupations in Demand at Job Service Offices: *Consumer Information Center, Pueblo, CO 81009.*

References

1. *Career Opportunity Update.* Career Research Systems Inc., Huntington Beach, CA, July 1980.
2. *College Placement Annual 1981.* The College Placement Council Inc., Bethlehem, PA, 1979.
3. *1981 Computer Salary Survey and Career Planning Guide.* Source EDP, Oak Brook, IL, 1981.
4. *Computer Specialists*, Announcement 420. US Office of Personnel Management, Washington, DC, February 1977.
5. *Dictionary of Occupational Titles*, Fourth Edition. US Department of Labor Employment and Training Administration, Washington, DC, 1977.
6. *Find Your Niche.* The Retired Officers Association, Washington, DC, January 1979.
7. *Mathematics and Related Positions*, Announcement Q1-1500. US Office of Personnel Management, Washington, DC, October 1978.
8. *Occupations in Demand at Job Service Offices*, Spring/Summer 1979. US Department of Labor, Employment and Training Administration, Washington, DC, 1979.
9. *Occupational Outlook Handbook*, 1980-81 Edition. US Department of Labor, Washington, DC, 1978.
10. *Out of the Service and Looking For a Job? Here's Help!* US Department of Labor, Employment and Training Administration, 1977.
11. *The US Army Career and Educational Guide.* US Army Recruiting Command, Fort Sheridan, IL.
12. *Veterans Employment Seminar Program Workbook*, Third Edition. National Alliance of Business, Washington, DC.
13. *Washington Counseletter.* Chronicle Guidance Publication Inc., Washington DC, March 1980.

Converting Apple DOS and Pascal Text Files

Now you can exchange information between DOS 3.3 and Pascal operating systems.

John B. Matthews, MD
6415 Tantamount Lane
Dayton, OH 45449

Wouldn't it be nice to use the Pascal editor on BASIC programs? Perhaps you would like to share Pascal programs with members of a user's group, but your newsletter editor or librarian prefers the text in DOS format. Maybe you can download FORTRAN programs via modem from the school computer. Unfortunately, Pascal doesn't recognize your modem.

Apple's implementation of UCSD Pascal is a real pleasure to use. At the same time, its disk operating system (DOS) is one of the more friendly and its BASIC is handy, if not especially efficient. Each system has its advantages and limitations and its own complement of editors and utilities to speed program development and text preparation. Still, there are occasions when you might want to move information from one environment to the other. Retype everything? No! Let the computer do the work.

To see how this might be accomplished, consider the organization of data on disks in the two systems. DOS 3.3 logically divides the disk into 560 sectors (35 tracks with 16 sectors each). Each sector contains 256 bytes of data. Pascal divides the disk into 280 blocks, each containing 512 bytes. A single DOS 3.3 sector and half of a Pascal block are physically (but not logically) identical. The solution to conversion revolves around this underlying similarity. All that is necessary is a map correlating DOS sector pairs and Pascal blocks.

Listing 1 is a Pascal program called GETDOS. It reads DOS-format text files and writes Pascal-format files. The array MAP contains the information needed to decide which half-block to use for a given sector. The procedure READSEC reads the indicated block and, based on the MAP, decides which half to move into the TEXT array. The procedure GETNAMES prompts the user for source and destination units, as well as a file name. If your system has more than two disk drives, you may want to modify the CASE statement to recognize the extra units. Note that output to the CONSOLE: or PRINTER: is also supported.

These methods may also apply to other operating systems, such as CP/M for the Z80 SoftCard.

Reading the source file is a matter of searching the DOS directory for the indicated file name, getting its track/sector list, and reading the data one sector at a time. Appendix C of the DOS 3.3 manual gives details of the directory and file organization. Files that are not text type or are too large to fit in the Pascal editor are rejected with an appropriate error message.

Since DOS stores text as negative ASCII (i.e., with the high-order bit in each character set to 1) and the Pascal editor expects to see positive ASCII (i.e., the high-order bit clear), the characters must be converted. Writing the destination file is handled two ways. If data are going to a disk file, the conversion is done once and the function BLOCKWRITE is used to speed up the transfer. If data are going to the CONSOLE: or PRINTER:, conversion and output proceed simultaneously one character at a time.

Files can be converted the other way, too. Listing 2 is an Applesoft BASIC program that reads Pascal files and writes DOS 3.3 text files. It bears the remarkably innovative title GETPAS. This program is organized along a line similar to its Pascal counterpart. The principal procedures are set off with REM statements. Since BASIC has no intrinsic procedure analogous to Pascal's UNITREAD, it calls the 6502

Text continued on page 457

Listing 1: *Program GETDOS is used to convert DOS 3.3 text files to Pascal format files. Reading the source file is a matter of searching the DOS directory for the indicated file name, getting its track/sector list, and reading the data one sector at a time. The array MAP contains the information needed to determine which half-block to use for each sector. The CASE statement can be modified if your system has more than two disk drives.*

```
PROGRAM GETDOS;

(*********************************************************************
 *                                                                   *
 * Program to convert DOS 3.3 text files to Pascal format files.     *
 *                                                                   *
 *********************************************************************)

CONST MAX=18432; (36 blocks of 512 bytes is maximum EDITOR can load.)
       PAGE=256; (DOS sectors are 256 bytes long.)
       CLEAREOL=29; CLEARSCREEN=12;

TYPE BYTE=0..255;
     UNITS=1..12;
     UNTYPED_FILE=FILE;
     SECTOR=RECORD
              BLOCK:0..7;
              HALF:(FIRST, SECOND)
            END;

VAR MAP: PACKED ARRAY[0..15] OF SECTOR;
    BUF. PACKED ARRAY[0..511] OF BYTE;
    TEXT: PACKED ARRAY[0..MAX] OF BYTE;
```

Listing 1 continued:

```
     SOURCEFILE, DESTFILE: STRING;
     SOURCEUNIT, DESTUNIT: UNITS;
     DRIVES: SET OF UNITS;
     BLOCK, TRAK, SEC, BLOCKCOUNT, I: INTEGER;
     PTR: INTEGER; {POINTER TO TEXT ARRAY}
     DONE, FOUND: BOOLEAN; CH: CHAR;
     F: FILE OF CHAR; {For use with CONSOLE: or PRINTER:}
     DISKFILE: UNTYPED_FILE; {For use with BLOCKWRITE}

PROCEDURE INITIALIZE;
   {For each of 16 sectors specify which block to read from}
   {a given track and which half to use as the sector.}
   BEGIN
     MAP[0].BLOCK:=0;   MAP[0].HALF:=FIRST;
     MAP[1].BLOCK:=7;   MAP[1].HALF:=FIRST;
     MAP[2].BLOCK:=6;   MAP[2].HALF:=SECOND;
     MAP[3].BLOCK:=6;   MAP[3].HALF:=FIRST;
     MAP[4].BLOCK:=5;   MAP[4].HALF:=SECOND;
     MAP[5].BLOCK:=5;   MAP[5].HALF:=FIRST;
     MAP[6].BLOCK:=4;   MAP[6].HALF:=SECOND;
     MAP[7].BLOCK:=4;   MAP[7].HALF:=FIRST;
     MAP[8].BLOCK:=3;   MAP[8].HALF:=SECOND;
     MAP[9].BLOCK:=3;   MAP[9].HALF:=FIRST;
     MAP[10].BLOCK:=2;  MAP[10].HALF:=SECOND;
     MAP[11].BLOCK:=2;  MAP[11].HALF:=FIRST;
     MAP[12].BLOCK:=1;  MAP[12].HALF:=SECOND;
     MAP[13].BLOCK:=1;  MAP[13].HALF:=FIRST;
     MAP[14].BLOCK:=0;  MAP[14].HALF:=SECOND;
```

Listing 1 continued on page 450

Listing 1 continued:

```
    MAP[15].BLOCK:=7; MAP[15].HALF:=SECOND;
  END; {INITIALIZE}

PROCEDURE PRINTAT(Y: INTEGER; S: STRING);
  BEGIN GOTOXY(0,Y); WRITE(CHR(CLEAREOL),S) END;
PROCEDURE GETNAMES;
VAR OK: BOOLEAN; DEST: STRING;
  BEGIN
    DRIVES:=[4,5];
    REPEAT
      WRITE(CHR(CLEARSCREEN));
      PRINTAT(2,'*** GETDOS ***  By John Matthews, M.D.');
      PRINTAT(5,'Units:  1. Console:   4. Drive #4');
      PRINTAT(6,'          5. Drive #5:  6. Printer:');
      PRINTAT(8,'Source Unit (4-5): '); READLN(SOURCEUNIT);
      PRINTAT(10,'Destination Unit (1-6): '); READLN(DESTUNIT);
      PRINTAT(12,'Source file name: '); READLN(SOURCEFILE);
      DESTFILE:=SOURCEFILE; STR(DESTUNIT,DEST);
      IF POS('.',SOURCEFILE)=0 THEN DESTFILE:=CONCAT(SOURCEFILE,'.TEXT');
      CASE DESTUNIT OF
        1: DESTFILE:='CONSOLE:';
        2: DESTFILE:='SYSTERM:';
        3: DESTFILE:='NOT AVAILABLE';
        4,5: DESTFILE:=CONCAT('#',DEST,':',DESTFILE);
        6: DESTFILE:='PRINTER:';
        7,8,9,10,11,12: DESTFILE:='NOT IMPLEMENTED';
      END; {CASES of DESTUNIT}
```

Listing 1 continued:

```
        PRINTAT(14,CONCAT('Destination file: ',DESTFILE));
        PRINTAT(16,'<cr> accepts, <e> exits, <sp> restarts ');
        READ(KEYBOARD,CH); OK:= EOLN(KEYBOARD);
        IF CH IN ['E','e',CHR(27)] THEN EXIT(PROGRAM);
      UNTIL OK;
    END; {GETNAMES}

PROCEDURE READSEC;
  BEGIN
    BLOCK:=(TRAK*8)+MAP[SEC].BLOCK;
    UNITREAD(SOURCEUNIT,BUF,512,BLOCK);
      CASE MAP[SEC].HALF OF
        FIRST:MOVELEFT(BUF[0],TEXT[PTR],PAGE);
        SECOND:MOVELEFT(BUF[PAGE],TEXT[PTR],PAGE);
      END; {CASES of MAP}
    PTR:=PTR+PAGE;
  END; {READSEC}

PROCEDURE READSOURCE;
CONST BYTES_PER_ENTRY=35; HEADER=11;
      BLANKS='                         '; {25 Blanks}
VAR NAME. STRING[30]; FILETYPE: BYTE;
    LIMIT, SECTORCOUNT, ENTRY: INTEGER;
    LIST: PACKED ARRAY[1..80,0..1] OF BYTE;
  BEGIN
    {Read catalog from track 17; sectors 15-1}
    PRINTAT(18,'Reading catalog...');
```

Listing 1 continued on page 452

Listing 1 continued:

```
TRAK:=17; PTR:=0; {Start at beginning of TEXT}
FOR SEC:=15 DOWNTO 1 DO READSEC;
{Find sourcefile entry}
LIMIT:=PTR-1; PTR:=HEADER; ENTRY:=0;
SOURCEFILE:=CONCAT(SOURCEFILE,' '); {Make name unique}
REPEAT
  NAME:=COPY(BLANKS,1,LENGTH(SOURCEFILE));
  ENTRY:=ENTRY+1;
  FOR I:= 1 TO LENGTH(SOURCEFILE) DO
    NAME[I]:=CHR(TEXT[PTR+I+2]-128);
  FOUND:= NAME=SOURCEFILE;
  IF NOT FOUND THEN {increment PTR}
    BEGIN IF (ENTRY MOD 7)=0 THEN PTR:=PTR+HEADER;
          PTR:=PTR+BYTES_PER_ENTRY END;
UNTIL FOUND OR (PTR>LIMIT);
IF {still} NOT FOUND THEN
  BEGIN PRINTAT(18,'File not found...'); EXIT(READSOURCE) END;
TRAK:=TEXT[PTR]; SEC:=TEXT[PTR+1]; {Location of track/sector list}
FILETYPE:=TEXT[PTR+2]; {0 if unlocked TEXT; 128 if locked TEXT}
SECTORCOUNT:=TEXT[PTR+33]-1; {Minus 1 for the track/sector list}
IF ((FILETYPE<>0) AND (FILETYPE<>128)) OR (SECTORCOUNT>72) THEN
  BEGIN FOUND:=FALSE; PRINTAT(18,'Not a TEXT file...');
        EXIT(READSOURCE) END;
{Read the track/sector list}
PTR:=0; READSEC; PTR:=12; {list starts at byte 12}
FOR I:= 1 TO SECTORCOUNT DO
  BEGIN LIST[I,0]:=TEXT[PTR]; PTR:=PTR+1;
```

Listing 1 continued:

```
          LIST[I,1]:=TEXT[PTR]; PTR:=PTR+1  END;
    {Finally, null the TEXT buffer and read the data}
    IF ODD(SECTORCOUNT) THEN BLOCKCOUNT:=(SECTORCOUNT+1) DIV 2
      ELSE BLOCKCOUNT:=SECTORCOUNT DIV 2;
    FILLCHAR(TEXT[0],BLOCKCOUNT*512,CHR(0));
    PRINTAT(18,'Reading file...'); PTR:=0;
    FOR I:= 1 TO SECTORCOUNT DO
      BEGIN TRAK:=LIST[I,0]; SEC:=LIST[I,1]; READSEC END;
  END; {READSOURCE}

PROCEDURE WRITEDEST;
VAR NEXTBYTE: BYTE;
  BEGIN
    PTR:=0;
    PRINTAT(18,CONCAT('Put ',DESTFILE,' on line; press <cr> '));
    READ(KEYBOARD,CH);
    IF DESTUNIT IN DRIVES THEN
      BEGIN
        PRINTAT(18,'One moment please...');
        FILLCHAR(BUF[0],512,CHR(0));
        FOR I:= 0 TO BLOCKCOUNT*512 DO {convert to positive ASCII}
          IF TEXT[I]>127 THEN TEXT[I]:=TEXT[I]-128;
        PRINTAT(18,CONCAT('Writing to ',DESTFILE,'...'));
        REWRITE(DISKFILE,DESTFILE);
        I:=BLOCKWRITE(DISKFILE,BUF,1,0); {Text file header}
        I:=BLOCKWRITE(DISKFILE,BUF,1,1); {Text file header}
        I:=BLOCKWRITE(DISKFILE,TEXT[0],BLOCKCOUNT,2);
```

Listing 1 continued on page 454

Listing 1 continued:

```
        CLOSE(DISKFILE,LOCK);
      END {THEN}
    ELSE
      BEGIN
        PRINTAT(18,CONCAT('Writing to ',DESTFILE,'...'));
        REWRITE(F,DESTFILE);
        WRITELN(F);
        REPEAT
          NEXTBYTE:=TEXT[PTR+1];
          CH:=CHR(TEXT[PTR]-128);
              WRITE(F,CH); PTR:=PTR+1;
            UNTIL NEXTBYTE=0;
            CLOSE(F,LOCK);
          END; {ELSE}
      END; {WRITEDEST}

    BEGIN {MAIN PROGRAM}
      INITIALIZE {sector/block map};
       REPEAT
        GETNAMES {and locations of files};
        READSOURCE {in DOS format};
        IF FOUND THEN WRITEDEST;
        WRITELN; WRITELN;
        WRITE('Another file? (Y/N) ');
        READ(KEYBOARD,CH);
        DONE:= CH IN ['N','n'];
      UNTIL DONE
    END  {MAIN}
```

Listing 2: *The Applesoft BASIC program GETPAS is used to convert Pascal text (.TEXT) files to DOS 3.3 text files. The Pascal volume directory is read from blocks 2 through 5 to find the indicated file name. Since BASIC does not have an intrinsic procedure analogous to Pascal's UNITREAD, GETPAS calls the machine-language routine shown in listing 3.*

```
   1  REM GETPAS: PASCAL TO TEXTFILE CONVERSION
   2  REM By J. Matthews, MD   7/6/81
   3  GOTO 200: REM START OF MAIN PROGRAM

   4  REM *** SUBROUTINES ***

100  REM  WRITE FILE (SKIP NULLS)
105 CH =  PEEK (I)
110  IF CH = 16 THEN I = I + 1:CH = 0: IF PEEK(I) > 32 THEN
       FOR J = 33 TO PEEK(I): PRINT " ";: NEXT J:I = I + 1: GOTO 105
115  IF CH = 0 AND I > EN THEN  RETURN
120  IF CH = 0 THEN I = I + 1: GOTO 105
125 I = I + 1: PRINT  CHR$ (CH);: GOTO 105

130  REM  READ A BLOCK
135 SL% = SS:DR% = SD
140 TR% =  INT (BLOCK / 8)
145 PT% =  INT ((BLOCK / 8 - TR%) * 8)
150 SE% = M%(PT%,0): CALL RWTS
155  GOSUB 190:BU% = BU% + PAGE
160 SE% = M%(PT%,1): CALL RWTS
165  GOSUB 190:BU% = BU% + PAGE
170  RETURN

175  REM  CENTER TITLE
180  HTAB 20 -  LEN (T$) / 2: PRINT T$: RETURN

185  REM  ERR TRAP
190  IF ER% <  > 0 THEN  VTAB 20: CALL  - 868:
       PRINT "DOS ERROR...": POP : POP : GOTO 290
195  RETURN

200  REM *** INITIALIZE ***

205 RWTS = 16384: HIMEM: RWTS
210 PRINT  CHR$ (4),"BLOAD RWTS.OBJO"
215 PAGE = 256
220 BU% = RWTS + PAGE:CM% = 1
225 BEG = BU%:EN = BU% + PAGE
230 M%(0,0) = 0:M%(0,1) = 14
235 M%(1,0) = 13:M%(1,1) = 12
240 M%(2,0) = 11:M%(2,1) = 10
245 M%(3,0) = 9:M%(3,1) = 8
250 M%(4,0) = 7:M%(4,1) = 6
255 M%(5,0) = 5:M%(5,1) = 4
260 M%(6,0) = 3:M%(6,1) = 2
265 M%(7,0) = 1:M%(7,1) = 15

270  REM *** GET FILE NAMES ***

275  HOME : VTAB 3
280 T$ = "*** CONVERT: PASCAL TO TEXT ***": GOSUB 180: PRINT
285 T$ = "BY JOHN MATTHEWS, M.D.": GOSUB 180
290  VTAB 8: HTAB 1
295  PRINT "SOURCE SLOT:  6";
300  HTAB  PEEK (36): GET IN$
```

Listing 2 continued on page 456

Listing 2 continued:

```
305 SS =  VAL (IN$)
310  IF SS = 0 THEN SS = 6
315  IF SS < 0 OR SS > 7 THEN 290
320  PRINT SS
325  VTAB 10: HTAB 1
330  PRINT "SOURCE DRIVE: 1";
335  HTAB  PEEK (36): GET IN$
340 SD =  VAL (IN$)
345  IF SD = 0 THEN SD = 1
350  IF SD < 1 OR SD > 2 THEN 325
355  PRINT SD
360  VTAB 12: HTAB 1
365  PRINT "DESTINATION SLOT:  6";
370  HTAB  PEEK (36): GET IN$
375 DS =  VAL (IN$)
380  IF DS = 0 THEN DS = 6
385  IF DS < 1 OR DS > 7 THEN 360
390  PRINT DS
395  VTAB 14: HTAB 1
400  PRINT "DESTINATION DRIVE: 2";
405  HTAB  PEEK (36): GET IN$
410 DD =  VAL (IN$)
415  IF DD = 0 THEN DD = 2
420  IF DD < 1 OR DD > 2 THEN 395
425  PRINT DD
430  VTAB 16: HTAB 1
435  INPUT "SOURCE FILE: ";SF$: IF LEN(SF$)=0 THEN 430
440  VTAB 18: HTAB 1
445  INPUT "DESTINATION FILE: ";DF$
450  IF  LEN (DF$) = 0 THEN DF$ = SF$: VTAB 18:
       PRINT "DESTINATION FILE: ";DF$
455 L2 =  LEN (SF$)
460  VTAB 20: CALL  - 868: PRINT "PRESS <RET> TO PROCEED;
       <ESC> TO END ";: GET IN$: IF IN$ =  CHR$ (27) THEN 605
465  PRINT : IF IN$ <  >  CHR$ (13) THEN 290
470  IF SD = DD THEN  VTAB 20: PRINT "INSERT THE SOURCE DISK;
       PRESS <RET> ";: INPUT "";IN$

475  REM *** GET DIRECTORY ***

480  VTAB 20: CALL  - 868: PRINT "READING DIRECTORY..."
485 BU% = RWTS + PAGE: FOR BLOCK = 2 TO 5: GOSUB 135: NEXT BLOCK
490 EN = BU%

495  REM *** FIND FILE NAME ***

500  FOR I = BEG TO EN STEP 26:NA$ = ""
505 SB = PEEK (I) + 256 * PEEK (I+1): NB = PEEK (I+2) + 256 * PEEK (I+3):
      L1 =  PEEK (I + 6)
510  IF L1 <  > L2 THEN 525
515  FOR J = I + 7 TO I + L1 + 6:NA$ = NA$ +  CHR$ ( PEEK (J)): NEXT J
520  IF NA$ = SF$ THEN 540
525  NEXT I
530  IF NA$ = "" THEN  VTAB 20: CALL  - 868:
       PRINT "FILE NOT FOUND: PRESS <RET> ";: INPUT "";IN$: GOTO 290

535  REM *** READ SOURCE ***

540  VTAB 20: CALL  - 868: PRINT "READING FILE..."
545 SB = SB + 2:EB = NB - 1:BU% = RWTS + PAGE
```

Listing 2 continued:

```
550  FOR BLOCK = SB TO EB: GOSUB 135: NEXT BLOCK
555  IF SD = DD THEN  VTAB 20: CALL  - 868:
       PRINT "INSERT DESTINATION DISK; PRESS <RET> ";: INPUT "";IN$

560  REM *** WRITE DEST ***

565  VTAB 20: CALL  - 868: PRINT "WRITING..."
570  PRINT  CHR$ (4);"OPEN ";DF$;",D";DD
575  PRINT  CHR$ (4);"DELETE ";DF$
580  PRINT  CHR$ (4);"OPEN ";DF$;",D";DD
585  PRINT  CHR$ (4);"WRITE ";DF$
590 I = BEG:EN = BU% - PAGE: GOSUB 105
595  PRINT  CHR$ (4);"CLOSE ";DF$
600  VTAB 20: CALL  - 868: PRINT "ANOTHER FILE (Y/N) ";:
       GET IN$: IF IN$ = "Y" THEN 270
605  PRINT : END
```

Listing 3 begins on page 458

Text continued from page 447:

machine-language program found in listing 3, that in turn calls the read/write track and sector (RWTS) routines from DOS. (See the DOS 3.3 manual, page 94.) The Applesoft PTRGET routine is used to allow passing variables by name rather than by location using the traditional PEEK and POKE.

The Pascal volume directory is read from blocks 2 through 5 of the disk. It is organized as 26-byte records, the first of which is the volume name:

```
Directory record
   Starting block: integer;
   Next available block: integer;
   File type: integer;
   File name: string[15];
   I/O designation: 0..255;
   Date: packed array occupying 2
      bytes;
   end;
```

Deleted files are marked by setting the length byte of the name string to 0. In reading the file itself, note that text files have a two-block header that ordinarily contains editor settings like environment and markers. The header can be skipped.

Writing the file requires, once again, that the high-order bit of each character be reset. This is done with the standard Applesoft function CHR$. This method is rather slow, but trying to implement a "BLOCK-WRITE" function in BASIC would require writing to both the disk directory and the volume table of contents. This is more safely left to DOS. To mark the end of file, DOS uses the null (ASCII 0) character. Pascal uses these to fill in the unused portions of blocks. Intervening nulls are simply bypassed as the file is written. One further conversion is helpful here. Pascal source lines that are indented are preceded by the data link escape (DLE, ASCII 16) character followed by a single byte specifying the number of spaces to indent plus 32. Without converting these to spaces, the indentation of Pascal text would be lost.

These methods may also apply to other operating systems, such as CP/M for the Z80 Softcard from Microsoft. If the directory and sector organization can be found, the conversion is possible.

These are the tools. Now you have one less excuse to keep your favorite Pascal programs tucked away in the back of a box. ■

Listing 3: *A 6502 machine-language routine to interface the BASIC program of listing 2 with the read/write track and sector routine of DOS 3.3 for direct control of disk access. More information on the RWTS routine can be found in the DOS 3.3 manual.*

```
0000:        * RWTS INTERFACE FOR APPLESOFT BASIC
0000:        * J. Matthews, M.D., 7/6/1981
0000:        *
0000:        * Variables passed by name:
0000:        *
0000:        * SL%= SLOT NUMBER
0000:        * DR%= DRIVE 1 OR 2
0000:        * TR%= TRACK 0 TO 34
0000:        * SE%= SECTOR 0 TO 15
0000:        * CM%= 0 (NULL: NO ACTION)
0000:        *    = 1 (READ A SECTOR)
0000:        *    = 2 (WRITE A SECTOR)
0000:        *    = 4 (FORMAT THE DISK)
0000:        * BU%= ADD. OF 256 BYTE BUFFER
0000:        *
0000:        * Returned:
0000:        *
0000:        * ER%= DOS ERROR CODE (0=NONE)
0000:        *
----- NEXT OBJECT FILE NAME IS RWTS.OBJ0
4000:                  ORG   $4000
4000:                  MSB   OFF
4000:        *
4000:        * I/O Block offsets: DOS 3.3 manual p94-98.
4000:        *
0001:        IBSLOT   EQU   $01          ;SLOT
```

Listing 3 continued:

```
0002:              IBDRVN   EQU   $02          ;DRIVE
0003:              IBVOL    EQU   $03          ;VOLUME
0004:              IBTRK    EQU   $04          ;TRACK
0005:              IBSECT   EQU   $05          ;SECTOR
0008:              IBBUFP   EQU   $08          ;BUFFER POINTER
000C:              IBCMD    EQU   $0C          ;COMMAND
000D:              IBSTAT   EQU   $0D          ;ERROR #
000F:              IOBPSN   EQU   $0F          ;PREVIOUS SLOT
0010:              IOBPDN   EQU   $10          ;PREVIOUS DRIVE
4000:              *
4000:              * Page zero locations:
4000:              *
001E:              TPSAV    EQU   $1E
0048:              IOB      EQU   $48
0083:              VARPNT   EQU   $83
00B8:              TXTPTR   EQU   $B8
4000:              *
4000:              * DOS hooks:
4000:              *
03D9:              RWTS     EQU   $3D9
03E3:              GETIOB   EQU   $3E3
4000:              *
4000:              * Applesoft PTRGET routine:
4000:              *
DFE3:              PTRGET   EQU   $DFE3
4000:              *
4000:20 E3 03      ENTRY    JSR   GETIOB       ;GET I/O BLOCK ADDRESS
```

Listing 3 continued on page 460

Listing 3 continued:

```
4003:84 48        STY  IOB        ;SAVE IT
4005:85 49        STA  IOB+1
4007:A5 B8        LDA  TXTPTR     ;SAVE TXTPTR
4009:85 1E        STA  TPSAV
400B:A5 B9        LDA  TXTPTR+1
400D:85 1F        STA  TPSAV+1
400F:20 79 40     JSR  GETSL%     ;GET SL% (SLOT)
4012:0A           ASL  A          ;TIMES 16
4013:0A           ASL  A
4014:0A           ASL  A
4015:0A           ASL  A
4016:A0 01        LDY  #IBSLOT
4018:91 48        STA  (IOB),Y
401A:20 7F 40     JSR  GETDR%     ;GET DR% (DRIVE)
401D:A0 02        LDY  #IBDRVN
401F:91 48        STA  (IOB),Y
4021:A9 00        LDA  #$00       ;VOLUME=0
4023:A0 03        LDY  #IBVOL
4025:91 48        STA  (IOB),Y
4027:20 85 40     JSR  GETTR%     ;GET TR% (TRACK)
402A:A0 04        LDY  #IBTRK
402C:91 48        STA  (IOB),Y
402E:20 8B 40     JSR  GETSE%     ;GET SE% (SECTOR)
4031:A0 05        LDY  #IBSECT
4033:91 48        STA  (IOB),Y
4035:20 91 40     JSR  GETBU%     ;GET BU% (BUFFER)
```

Listing 3 continued:

```
4038:A0 08            LDY  #IBBUFP
403A:91 48            STA  (IOB),Y        ;LOW BYTE
403C.A0 00            LDY  #$00
403E:B1 83            LDA  (VARPNT),Y
4040:A0 09            LDY  #IBBUFP+1
4042:91 48            STA  (IOB),Y        ;HIGH BYTE
4044:20 97 40         JSR  GETCM%         ;GET CM% (COMMAND)
4047:F0 27            BEQ  RETURN         ;NULL COMMAND
4049:A0 0C            LDY  #IBCMD
404B:91 48            STA  (IOB),Y
404D:20 9D 40         JSR  GETER%         ;GET ER% POINTER
4050:20 E3 03         JSR  GETIOB
4053:20 D9 03         JSR  RWTS
4056:A0 0D            LDY  #IBSTAT
4058:B1 48            LDA  (IOB),Y        ;ERROR CODE
405A:B0 02            BCS  ERROR          ;RWTS SETS C BIT ON ERR
405C:A9 00            LDA  #$00           ;ER%=0 IF C BIT CLEAR
405E:A0 01      ERROR LDY  #$01
4060:91 83            STA  (VARPNT),Y     ;RETURN IBSTSAT IN ER%
4062:B1 48            LDA  (IOB),Y        ;Y=IBSLOT
4064:A0 0F            LDY  #IOBPSN
4066:91 48            STA  (IOB),Y        ;UPDATE SLOT
4068:A0 02            LDY  #IBDRVN
406A:B1 48            LDA  (IOB),Y
406C:A0 10            LDY  #IOBPDN
406E:91 48            STA  (IOB),Y        ;UPDATE DRIVE
```

Listing 3 continued on page 462

Listing 3 continued:

```
4070:A5 1E          RETURN   LDA   TPSAV          ;RESTORE TXTPTR
4072:85 B8                   STA   TXTPTR
4074:A5 1F                   LDA   TPSAV+1
4076:85 B9                   STA   TXTPTR+1
4078:60                      RTS                  ;TO APPLESOFT
4079:               *
4079:               * Find Applesoft variables:
4079:               *
4079:20 A3 40       GETSL%   JSR   VARGET
407C:53 4C 25                ASC   'SL%'
407F:20 A3 40       GETDR%   JSR   VARGET
4082:44 52 25                ASC   'DR%'
4085:20 A3 40       GETTR%   JSR   VARGET
4088:54 52 25                ASC   'TR%'
408B:20 A3 40       GETSE%   JSR   VARGET
408E:53 45 25                ASC   'SE%'
4091:20 A3 40       GETBU%   JSR   VARGET
4094:42 55 25                ASC   'BU%'
4097:20 A3 40       GETCM%   JSR   VARGET
409A:43 4D 25                ASC   'CM%'
409D:20 A3 40       GETER%   JSR   VARGET
40A0:45 52 25                ASC   'ER%'
```

Listing 3 continued:

```
40A3:            *
40A3:            * VARGET: On entry to PTRGET, TXTPTR points to first
40A3:            * character of the variable name. On exit, the address
40A3:            * of the variable's value is in VARPNT and Y,A.
40A3:            *
40A3:            * Pop return stack and store variable pointer in TXTPTR.
40A3:            *
40A3:68          VARGET  PLA
40A4:85 B8               STA   TXTPTR
40A6:68                  PLA
40A7:85 B9               STA   TXTPTR+1
40A9:            * Increment pointer to first character in ASC string.
40A9:E6 B8               INC   TXTPTR
40AB:D0 02               BNE   VAR1
40AD:E6 B9               INC   TXTPTR+1
40AF:20 E3 DF    VAR1    JSR   PTRGET
40B2:A0 01               LDY   #$01
40B4:B1 83               LDA   (VARPNT),Y
40B6:            * Note return is to second most recent caller
40B6:60                  RTS

*** SUCCESSFUL ASSEMBLY: NO ERRORS
```




A Simple Multiprocessor Implementation

A simple connection can be the start of a multiprocessing, multitasking system.

John Harrington
3840 West Clarendon
Phoenix, AZ 85019

Have you been looking for an easy way to simultaneously operate more than one computer? If you have, your search is at an end. In this article, I describe a method to control two or more computers connected by serial data lines. Even if the computers are performing completely unrelated tasks, they can still be controlled from a single terminal.

For example, one machine might run a BASIC program, while the other controls your home-security system. Or one could print a data file on a hard-copy device, while the operator updates the same file on the other machine.

Another possibility is the job performed by some very large computers—splitting a single task into segments and processing the segments separately but simultaneously. This provides good news and bad news. The good news is an impressive reduction in the time needed to complete the overall task. The bad news is the complexity of the software required to accomplish this!

For several years, some friends and I kicked around the idea of interconnecting computers. Many gallons of coffee and plenty of discussion yielded many possibilities. We wrote some extensive software to allow the exchanging of programs and data via modems and telephone lines, and played around with multiple-processor printer spoolers, but never did implement multiprocessing.

However, I was given an excellent opportunity to experiment when I upgraded my SwTPC 6800-based dual-disk-drive machine with a Motorola 6809 processor. This was accomplished by making some minor hardware changes and plugging in a new 6809 processor card. The old 6800 card was plugged into another motherboard, with a homemade power supply. A friend had built a wooden cabinet for his SwTPC computer; his original cabinet soon held my second computer. Since my bankroll was limited, extra memory and input/output hardware were added sparingly. Some swapping got me a Shugart Associates SA-400 5¼-inch floppy-disk drive. Before long, I was the proud owner of two almost identical disk-based microsystems, one running a 6800, the other, a 6809.

In certain situations, assigning more than one task to a single processor noticeably increases overall execution time.

Both machines run FLEX, Technical Systems Consultants' (POB 2570, West Lafayette, IN 47906) excellent DOS (disk operating system). FLEX contains a built-in interrupt-driven background (i.e., invisible to, and not interactive with, the user) *printer spooler*, allowing low-priority disk-file printing while the main user task is running in foreground. This is called "limited multitasking." But if two things are happening at once on one computer, isn't that just as good as having two computers? No, not quite.

Spooling is a beautiful feature I use often, but it has a few drawbacks. First, only two tasks are permitted, one of which must be the printing of the contents of a disk file. Second, because the two tasks are swapped under interrupt control, background printing slows or stops while disk accesses, or any operations that mask interrupts, are being performed. This is particularly noticeable when you are using fast printers.

In fact, any single-processor multitasking scheme has an inherent limitation. The available processor time is split between the tasks. As a result, no task can run as fast as it would alone. On I/O- (input/output) intensive tasks, where much time is spent waiting on I/O devices or oper-

ator input, the effects of this time division may be unnoticeable. On the other hand, if the tasks rarely have to wait on I/O, execution time may slow down in almost inverse proportion to the number of tasks.

These problems can be avoided by multiprocessing. Since I now had two nearly identical machines, all excuses for not developing a multiprocessing system were gone. Several approaches to putting the system together were considered. The easiest one is to designate one machine as the primary unit, and let it control the other as a secondary machine. All control for the secondary machine has to pass through the primary. Little extra hardware is required, and the software is simple.

Another scheme is to use multiport memory, a special block of memory set up so that either machine may address it. To pass data or instructions between machines, the data are written by one processor to this memory and read by the other. Although very fast, this approach requires special hardware and some complex software. Similar drawbacks would occur if we used DMA (direct memory access—the transmission of data directly between the memory of a computer and a peripheral device, which might be the other processor) to pass data.

Shared-memory, direct-memory-access, and shared-bus multiprocessing systems involve both complex hardware and software.

Another approach is to design a small dedicated controller, such as a single-chip microprocessor with a program in ROM (read-only memory), to control the larger machines. The terminal connects to the controller, which in turn controls the other machines via serial data ports. Several other possibilities exist, including using a shared bus, where two or more processors communicate directly with memory and I/O via read and write instructions, as with the Intel 8086, Zilog Z8000, and Motorola 68000 16-bit microprocessors.

The method chosen for my first try was the simplest—the primary/secondary concept. The machines do not have to be identical, or even similar. Both only need serial ports that can be interconnected, as in figure 1. The ones shown here are serial RS-232C ports. A serial port on the primary machine (designated machine 1) is plugged into the control port of the secondary machine (designated machine 2) where a user terminal would be connected in a single-user system. Any data or commands output from machine 1 through this port are obeyed by machine 2 as though they came directly from the control ter-




Figure 1: *A simple RS-232C serial connection between two computers can provide the necessary communications interface to create a multiprocessing system.*

minal; it doesn't know the difference. The only hardware change is to cross-connect pins 2 (BA) and 3 (BB) on the RS-232C cable connecting the two machines. This can be done either by making a special cable or by installing a DPDT (double-pole, double-throw) toggle switch on either machine. This is necessary so the transmitted-data line from one machine is connected to the data-receiving line on the other.

Incidentally, the reversing switch is also handy for connecting an external modem to one of your serial ports. It is necessary to reverse pins 2 and 3 in that case, and the switch saves making special cables. See figure 2 for details. Your ports or terminal may have special handshaking requirements, and you may have to tie pin 5 high or perform some other modification to get proper operation. Your hardware instruction book might note the serial interface requirements. (Or see "Build a Null Modem," by Robert Haar, BYTE, February 1981, page 198.)

Be sure the ports connecting the two machines are set for identical data rates, no faster than your control-terminal rate. I suggest running everything at 9600 bps (bits per second), if your control terminal is capable of it.

Software

The program in listing 1, called MACH2 and written in 6809 assembly language, runs in machine 1, but is called only when you "talk" to machine 2. When it is running, all characters typed on the user terminal are routed through machine 1 over the RS-232C line to machine 2, and all responses from machine 2 are routed by the software through machine 1, back to the terminal. It has the effect of the terminal being connected directly to machine 2. After you have started machine 2 on a particular task, typing a Control-X instantly puts you back in control of machine 1. You can now start it on an entirely different job from the one machine 2 is working on. Later, you may wish to talk to machine 2 again, to check on the progress of a job. With the described setup, just type

the name of the program, MACH2, and you are again communicating with your second machine. As before, typing a Control-X gets you back to machine 1.

The software necessary to do this is simple. However, I couldn't resist complicating it a bit, using the enhanced instruction set available on the 6809. For instance, moving a program to execute in a different area of memory is painless. Unlike other 8-bit microprocessors, 6809 machine-language programs are easily written to be position-independent. They are not relocatable, as with a linking loader, but truly position-independent. A program doesn't care what its physical address in memory is—put it anywhere, and it runs.

MACH2 is disk-resident. When called, it is loaded into FLEX's "utility-command area" of memory and run. First, the program initializes the serial port used to control the second machine. This has to be done after power-up with any of the software-programmed serial ports before use. Next, the program moves part of itself (the permanent part) to the top of user memory. This does two good things. First, it frees the utility-command area for use by other utility programs. Second, the program is now memory-resident; it doesn't have to be loaded from disk each time you use it.

FLEX has already determined where the top of memory is, and has stored that address in an area reserved for pointers and other parameters. The program gets that address, and moves itself just under it. The system's end-of-memory pointer is changed to a location just below the

Text continued on page 470




Figure 2: *When connecting two computers' RS-232C ports, it may be necessary to swap the connections to pins 2 (TD, transmit data) and 3 (RD, receive data) in the cable, as in figure 2a, or install a toggle switch, as in figure 2b. Other installation-specific modifications may be necessary to make the serial ports compatible.*

Listing 1: *A 6809 machine-language program, MACH2, that permits a user to control two interconnecting machines from one terminal, allowing the execution of two different tasks by separate processors.*

```
                                 NAM    MACH2
                                 OPT    PAG

                        * THIS PROGRAM ALLOWS CONTROL OF A SECOND
                        * MACHINE VIA A SERIAL PORT.

                        * ONCE CALLED, THIS PROGRAM IS MEMORY-RESIDENT
                        * AND REQUIRES NO SUBSEQUENT DISK LOADS.
                        * "MEMEND" IN FLEX ($CC2B) IS SET JUST BELOW
                        * THIS PROGRAM SO THAT IT WILL NOT BE WRITTEN
                        * OVER.

                        * OPERATING SYSTEM: 6809 FLEX (TM) T.S.C.
                        * HARDWARE: MACHINE 1- SWTPCO 6809
                        *           MACHINE 2- SWTPCO 6800

                        * WRITTEN 2-5-80   JOHN R. HARRINGTON
                        * EQUATES

                  CD03  WARMS   EQU    $CD03      FLEX9 WARMSTART
                  E004  PORT1   EQU    $E004      CONTROL PORT ADDRESS
                  E008  PORT2   EQU    $E008      PORT TALKING TO SECOND MACHINE
                  CD18  PUTCHR  EQU    $CD18      OUTPUT CHARACTER TO CONTROL PORT
                  CC2B  MEMEND  EQU    $CC2B      "END OF MEMORY" STORAGE
                  CD24  PCRLF   EQU    $CD24      <CRLF> TO CONTROL PORT
                  CD1E  PSTRNG  EQU    $CD1E      <CRLF> AND STRING TO CONTROL PORT
                  CC12  UCTADD  EQU    $CC12      USER COMMAND TABLE ADDRESS

C100                            ORG    $C100

C100 20   01            START   BRA    MACH2      BRANCH OVER VERSION

C102 01                         FCB    1          VERSION 1

C103 BD   CD24          MACH2   JSR    PCRLF
C106 86   03                    LDA    #3         MASTER RESET FOR ACIA PORT
C108 B7   E008                  STA    PORT2
C10B 86   11                    LDA    #$11       8 BITS, NO PARITY, 2 STOP BITS
C10D B7   E008                  STA    PORT2      PORT IS NOW INITIALIZED
C110 FC   CC2B                  LDD    MEMEND     PRESENT END OF MEMORY
C113 FD   C13D                  STD    ORIGME     SAVE IT FOR LATER
C116 83   00D5                  SUBD   #ENDPGM-MACH20 SUBTRACT LENGTH OF PART TO BE MOVED
C119 FD   CC2B                  STD    MEMEND     SET MEMORY END JUST BELOW OUR PROGRAM
C11C 1F   01                    TFR    D,X        MEMEND GOES INTO X
C11E 30   01                    LEAX   1,X        NOW X HAS NEW STARTING ADDRESS
C120 34   10                    PSHS   X          SAVE IT
C122 108E C210                  LDY    #ENDPGM    LAST BYTE TO BE MOVED
C126 34   20                    PSHS   Y          SAVE ITS  ADDRESS
C128 108E C13B                  LDY    #MACH20    FIRST BYTE TO BE MOVED
C12C A6   A0            MOVE    LDA    ,Y+        GET A BYTE OF THIS PROGRAM
C12E A7   80                    STA    ,X+        AND MOVE IT
C130 10AC E4                    CMPY   ,S         FINISHED?
C133 26   F7                    BNE    MOVE       NOT YET
C135 32   62                    LEAS   2,S        FIX STACK
C137 35   10                    PULS   X          GET NEW STARTING ADDRESS
C139 6E   84                    JMP    ,X         AND GO THERE

                        * THE REST OF THIS PROGRAM GETS RELOCATED TO A
                        * NEW SPOT JUST UNDER TOP OF USER MEMORY SPACE.
                        * THE CODE IS POSITION-INDEPENDENT AND WILL RUN
                        * ANYWHERE. PART OF THE CODE MOVED IS AN EXTENSION
                        * TO THE FLEX COMMAND TABLE (COMTBL).
```

Listing 1 continued:

```
C13B 20    02        MACH20  BRA    MACH21      BRANCH AROUND TEMP STORAGE

C13D 0000            ORIGME  FDB    0           ORIGINAL TOP OF MEMORY ADDRESS

C13F 30    8D 0013   MACH21  LEAX   MACH22,PCR GET NEW ADDRESSES FOR ROUTINES
C143 AF    8D 00BC           STX    ADDR1,PCR AND PUT IN COMMAND TABLE
C147 30    8D 0050           LEAX   RESTORE,PCR
C14B AF    8D 00BE           STX    ADDR2,PCR
C14F 30    8D 00AA           LEAX   COMTBL,PCR POINT TO COMMAND TABLE
C153 BF    CC12              STX    UCTADD      TELL FLEX WHERE IT IS NOW
C156 30    8D 004F   MACH22  LEAX   MSG,PCR     "YOU ARE NOW CONTROLLING MACHINE TWO"
C15A BD    CD1E              JSR    PSTRNG
C15D BD    CD24              JSR    PCRLF
C160 8E    E004      MACH23  LDX    #PORT1      POINT TO CONTROL PORT
C163 8D    22                BSR    CHECK       ANY KEYBOARD INPUT?
C165 24    12                BCC    MACH25      NOPE
C167 8D    22                BSR    INPORT      YES- GET THE CHARACTER
C169 81    18                CMPA   #$18        CONTROL-X?
C16B 26    0A                BNE    MACH24      NOPE
C16D 30    8D 005F           LEAX   MSG2,PCR    "YOU ARE NOW CONTROLLING MACHINE ONE (6809)"
C171 BD    CD1E              JSR    PSTRNG
C174 7E    CD03      JWARMS  JMP    WARMS       BACK TO FLEX

C177 8D    17        MACH24  BSR    OPORT2      SEND TO SECOND MACHINE
C179 8E    E008      MACH25  LDX    #PORT2      POINT TO SECOND MACHINE
C17C 8D    09                BSR    CHECK       IS IT TALKING TO US?
C17E 24    E0                BCC    MACH23      NO, LOOP
C180 8D    09                BSR    INPORT      YES, GET THE CHARACTER
C182 BD    CD18              JSR    PUTCHR      PRINT ON CRT
C185 20    D9                BRA    MACH23      AND LOOP FOR MORE

                     * CHECK PORT FOR INPUT- ENTER WITH PORT ADDRESS
                     * IN X REGISTER

C187 A6    84        CHECK   LDA    ,X          GET STATUS BYTE
C189 47                      ASRA               SHIFT STATUS BIT INTO CARRY
C18A 39                      RTS                CARRY SET INDICATES CHARACTER WAITING

                     * INPUT CHARACTER FROM A PORT (ENTER WITH PORT ADDRESS IN X)

C18B A6    01        INPORT  LDA    1,X         GET THE CHARACTER
C18D 84    7F                ANDA   #$7F        STRIP PARITY BIT, IF ANY
C18F 39                      RTS

                     * SEND CHARACTER TO PORT TWO (SECOND MACHINE)

C190 F6    E008      OPORT2  LDB    PORT2       GET STATUS BYTE
C193 57                      ASRB               SHIFT READY BIT INTO CARRY
C194 57                      ASRB
C195 24    F9                BCC    OPORT2      LOOP UNTIL READY
C197 B7    E009              STA    PORT2+1     SEND THE CHARACTER
C19A 39                      RTS

                     * RESTORE MACHINE TO ORIGINAL CONDITION

C19B 8E    0000      RESTORE LDX    #0
C19E BF    CC12              STX    UCTADD      CLEAR EXTENSION TO COMMAND TABLE
C1A1 AE    8C 99             LDX    ORIGME,PCR GET ORIGINAL MEMORY END ADDRESS
C1A4 BF    CC2B              STX    MEMEND      PLUG IT BACK IN
C1A7 20    CB                BRA    JWARMS      AND EXIT

                     * STRINGS

C1A9 20 2D 59 4F     MSG     FCC    / -YOU ARE NOW CONTROLLING MACHINE TWO-/,4
C1D0 20 2D 59 4F     MSG2    FCC    / -YOU ARE NOW CONTROLLING MACHINE ONE (6809)/,4

                     * COMMAND TABLE

C1FD 4D 41 43 48     COMTBL  FCC    /MACH2/,0
C203 C156            ADDR1   FDB    MACH22
C205 52 45 53 54             FCC    /RESTORE/,0
```

Listing 1 continued:

```
C20D C19B        ADDR2   FDB    RESTORE
C20F 00                  FCB    0
C210 00          ENDPGM  FCB    0

                         END    START

0 ERROR(S) DETECTED

SYMBOL TABLE:

ADDR1  C203   ADDR2  C20D   CHECK  C187   COMTBL C1FD   ENDPGM C210
INPORT C18B   JWARMS C174   MACH2  C103   MACH20 C13B   MACH21 C13F
MACH22 C156   MACH23 C160   MACH24 C177   MACH25 C179   MEMEND CC2B
MOVE   C12C   MSG    C1A9   MSG2   C1D0   OPORT2 C190   ORIGME C13D
PCRLF  CD24   PORT1  E004   PORT2  E008   PSTRNG CD1E   PUTCHR CD18
RESTOR C19B   START  C100   UCTADD CC12   WARMS  CD03
```

Text continued from page 467:

program, to protect it. This address is checked by most software, which will not use memory above it, making the program fairly safe from being clobbered. Now that the program is in a safe place, you transfer control to it, and it executes. The flowchart (figure 3) shows how it works. All communication with machine 2 is routed through the program until a Control-X is entered from the keyboard, at which time it jumps to the DOS, putting you back in control of machine 1. Executing the program again sends your communication to machine 2, and so on.

Now comes the tricky part. FLEX allows its command table, the look-up table of memory-resident programs and routines that appear as DOS commands to the user, to be extended to include any number of new commands. The advantage of memory-resident programs is that they don't have to be loaded from disk each time they are used—just type in the name of the program and it's running. FLEX does the difficult part. You just have to create the new command-table extension and tell FLEX where it is. This is done by stuffing the address of the table in a special memory location. Then, whenever you type in a command, FLEX looks at its table, then your table, before looking on the disk for the command.

This is the way it works: after power-up, the first time you type "MACH2" the program is loaded from disk and run. Subsequent calls to MACH2 are instantaneous, since the program is already in memory and the addition to the command table points to it. This feature saves much time and disk wear in a long session. The added command table is physically located at the end of the program. Remember, this is a protected area of memory, not likely to get written over. Two commands are in the table: "MACH2", which connects the terminal to machine 2, as described earlier, and "RESTORE", which turns off the multiprocessing. That is, it restores machine 1 to its original configuration by disabling the new command table and putting the top-of-memory pointer back to its original value.

RESTORE was used mainly during program development and debugging. It is not particularly useful now. No provisions were made in the program for passing data files between

BEGIN

PRINT "YOU ARE NOW CONTROLLING MACHINE TWO" ON TERMINAL

CHARACTER READY AT KEYBOARD PORT

?

YES

NO

IS IT A CONTROL-X ?

YES

NO

SEND CHARACTER TO SECOND MACHINE

CHARACTER READY FROM MACHINE TWO

?

NO

YES

PRINT THE CHARACTER ON THE TERMINAL

PRINT "YOU ARE NOW CONTROLLING MACHINE ONE" ON TERMINAL

RETURN TO OPERATING SYSTEM

Figure 3: *Flowchart of the algorithm used in the communications and control program given in listing 1.*

machines, just commands. Presently, I move text or data files between machines by swapping disks between drives.

If you are running FLEX on a 6809-based computer, you can use this software as is. If not, the algorithm represented by the flowchart of figure 3 can easily be written in almost any language on any computer. It could even be written in BASIC, if you have latent masochistic tendencies. The extra command table and the self-relocation features are not required, but are handy.

You might even extend the algorithm to control a dozen or more machines. That'll keep you out of trouble for a year or two—trying to dream up a dozen things you need to do simultaneously.

Presently, data transfer is limited to a rate of 9600 bps, the maximum speed available on the serial ports without modification. This just isn't fast enough for some things I have in mind, so my next major project will be dual-port memory for very fast transfer of data between machines. But I think if you try the present scheme, you'll like the results.■

An Introduction to NSC Tiny BASIC

The Language of the INS8073

Jim Handy
National Semiconductor
2900 Semiconductor Dr.
Santa Clara CA 95051
408-737-4613

National Semiconductor's new INS8073 Microinterpreter is the first single IC (integrated circuit) that can be programmed in a high-level language. Since a description of the hardware in INS8073-based systems has already appeared elsewhere (see "On-Chip Tiny BASIC Dumps Development Systems," *Electronic Design*, November 22, 1980, page 235), this article will focus on the language of the new chip. Called NSC Tiny BASIC, it resembles other Tiny BASIC interpreters but has certain enhancements, which I'll describe in detail. (See table 1 for a summary of NSC Tiny BASIC features.) Especially noteworthy are NSC Tiny BASIC features that make interrupts and input/output (I/O) routines easy to handle and others that make provisions for multiprocessing.

NSC Tiny BASIC offers advantages to both the inexperienced and the experienced programmer. Using NSC Tiny BASIC, the inexperienced programmer can write comprehensive programs in much less time than equivalent assembly-language programs would require. And since NSC Tiny BASIC lets you jump back and forth between machine code and BASIC, the experienced programmer can write less important routines in BASIC while still using assembly-language for critical routines.

About the Author

At the time he wrote this article, Jim Handy was product marketing engineer for single-chip microcomputers at National Semiconductor Corporation. He is now employed by Digital Research.

Language Expressions

NSC Tiny BASIC permits the use of 26 variable names: the letters A through Z. The values assigned to these variables are 16-bit signed integers. Fractions or floating-point numbers are not allowed.

All numeric constants are decimal numbers except when preceded by a number sign (#), which indicates a hexadecimal number. For example, "55" would be treated as a decimal number, while "#55" would be treated as hexadecimal (equal to 85 decimal). Decimal constants must be in the range of −32767 to +32767. Relational operators are the standard BASIC symbols (= equal to; > greater than; < less than; < = less than or equal to; > = greater than or equal to; < > not equal to). The relational operators return either a 0 (FALSE) or −1 (TRUE) as a result. Note that > < is an illegal operator.

Standard arithmetic operators are provided for the four basic arithmetic functions (+ addition; − subtraction; / division; * multiplication). The arithmetic is standard 16-bit two's-complement arithmetic. Fractional quotients are truncated at the right, not rounded, and remainders are dropped; therefore, both 16/3 and 17/3

give 5 as a result. As usual, division by zero is not permitted; it will result in an error break.

NSC Tiny BASIC follows the usual algebraic rules for order in evaluating expressions. Parentheses control the order of evaluation, and you should use them liberally. They insure clarity in complicated expressions.

NSC Tiny BASIC provides logical operators AND, OR, and NOT. These perform bitwise logical operations on their 16-bit arguments and produce 16-bit results. The AND and OR operators are called binary operators because they perform an operation on two arguments (or operands). Here's an example of the use of AND, with the binary interpretation shown at right:

```
>LIST
 10 A = 75          A = 0000  0000  0100  1011
 20 B = 99          B = 0000  0000  0110  0011
 30 C = A AND B     C = 0000  0000  0100  0011
 40 PRINT C
>RUN
67
```

The following program shows how the logical AND can be used with other relational operators:

```
>LIST
10 INPUT A
20 INPUT B
30 IF (A>50) AND (B>50) THEN GO TO 60
40 PRINT "ONE OR BOTH ARE SMALL"
50 GO TO 10
60 PRINT "BOTH ARE BIG"
70 GO TO 10
```

If we run the program, console output will look like this:

```
>RUN
? 51
? 52
BOTH ARE BIG
? 51
```

Expressions

Variable Names A—Z
Decimal constants in the range −32767 to +32767
Hexadecimal numbers (preceded by a "#")

Operators

Relational Operators
=
>
<
>=
<>

Arithmetic Operators
+
−
/
*

Logical Operators
AND
OR
NOT

The Indirect Operator

@	Accesses absolute memory locations one byte at a time; e.g., LET X = @6800 assigns value at address 6800 to X.

Functions

MOD (a,b)	Yields absolute value of remainder from division of a by b
RND (a,b)	Generates pseudorandom integer in range from a through b, inclusive
STAT	Represents 8-bit value of the status register
TOP	Yields address of first byte above the program in the current page of RAM
INC	Increments a memory location
DEC	Decrements a memory location

Statements

Input/Output Statements

INPUT	Inputs one or more expressions or numbers, separated by commas (or spaces)
INPUT $ A	Inputs a string to successive memory locations starting at location A
PRINT	Outputs information from program; gives decimal numbers and quoted strings
PRINT $ B	Prints string beginning at address B up to next carriage rturn

Assignment Statements

LET	Sets a variable, memory location, string variable or the status register to value entered

Program-Control Statements

GO TO	Branches to line number
GOSUB	Calls subroutine at line number
RETURN	Returns control from subroutine to line following GOSUB statement
IF/THEN	Shifts program control based on result of logical test
DO/UNTIL	Causes repetition of enclosed statements until specified condition is met
FOR/NEXT	Causes repetition for specified number of times
STEP	Sets size of increment in iterations of FOR/NEXT statements
LINK	Transfers control to a machine-language routine at a specified address
ON	Helps process interrupts; "ON interrupt-#1, 200" transfers control to GOSUB statement at line 200 when specified interrupt occurs.
STOP	Causes program to stop and prints current line number, then returns to edit mode
CONT	Resumes execution of program stopped by STOP
DELAY	Delays execution for specified number of time units up to maximum of 1040 milliseconds
CLEAR	Initializes all variables to 0, disables interrupts, enables BREAK capability, resets all stacks

Commands

NEW	Establishes a new start-of-program address
RUN	Runs the current program
LIST	Lists the current program

Table 1: *A summary of NSC Tiny BASIC features.*

```
? 49
ONE OR BOTH ARE SMALL
? 49
? 49
ONE OR BOTH ARE SMALL
? ^C
STOP AT 10
>
```

The following similar program shows the use of a logical OR with other relational operators:

```
>LIST
10 INPUT A
20 INPUT B
30 IF (A>50) OR (B>50) THEN GO TO 60
40 PRINT "BOTH ARE SMALL"
50 GO TO 10
60 PRINT "ONE OR BOTH ARE BIG"
70 GO TO 10
```

Here's a sample run:

```
>RUN
? 51
? 52
ONE OR BOTH ARE BIG
? 51
? 49
ONE OR BOTH ARE BIG
? 49
? 49
BOTH ARE SMALL
? ^C
STOP AT 10
>
```

The third logical operator (NOT) is unary; i.e., it performs an operation on only one argument. An example follows, again showing the binary interpretation at right:

```
>LIST
  10 A = 11          A = 0000 0000 0000 1011 = 11
                                                 10
  20 B = NOT A
  30 PRINT B         B = 1111 1111 1111 0100 = -12
>RUN                                             10
-12
```

Tiny BASIC Functions

NSC Tiny BASIC offers several functions for use in arithmetic expressions. For example, the MOD (or modulo) function returns the absolute value of the remainder from the division a/b, where a and b are arbitrary expressions. If the value of b is zero, an error break will occur as in any division operation. Here's an example of the use of MOD:

```
>LIST
  10 A = 95                     2
  20 B = 44                 44 /95
  30 PRINT MOD (A,B)            88
>RUN                             7 MOD (95,44)
  7
```

The NSC Tiny BASIC random-number generator is called RND, and it returns a pseudo-random integer in the range from a through b, inclusive. For the RND function to perform correctly, a should be less than b, and b−a must be less than or equal to 32767 (decimal). A typical example is:

```
>10 PRINT RND (1,100)
>RUN
  27
```

The STAT function returns the 8-bit value of the INS8073 status register. STAT may appear on either side of an assignment statement, enabling you to modify the status register as well as read it. The carry and overflow flags of the status register are usually meaningless, because the NSC Tiny BASIC interpreter itself is continually modifying these flags. The interrupt-enable flag may be altered by an assignment to STAT (e.g., STAT = #FF). Locations of individual flags in the status register are shown in

table 2. The function of each bit in the status register is shown in table 3. Here is an example of the use of the STAT function:

```
>LIST
  10 LET A = STAT
  20 PRINT A
>RUN
  176 The decimal number, 176, translates to
  1 0 1 1 0 0 0 0 binary.
```

Other Functions

The TOP function returns the address of the first byte of RAM (random-access read/write memory) above the NSC Tiny BASIC program that is available to the user. This will be the address of the highest byte in the NSC Tiny BASIC program, plus 1. A program can use all the memory in the RAM above and including TOP as scratchpad storage. As an example:

```
>10 PRINT TOP
>RUN
4400     4400 is the first address of unused RAM
```

The INC and DEC functions increment or decrement a memory location X. Here are some examples:

```
10 LET X=1032
20 A=INC(X)
  .
  .
  .
50 B=DEC(X)
60 X=INC(6000)
70 Y=DEC(6000)
```

These instructions are used for multiprocessing and are noninterruptible. This means that if two 8073s are used on the same bus, whenever one processor executes an INC (X) or DEC (X) instruction, the other processor must remain idle. These instructions are generally used for communications between processors in a multiprocessor system.

Statements

The INPUT statement is used to input data to an NSC Tiny BASIC program. One or more items (variables, expressions, etc.), separated by commas, may be entered according to the following formats:

Most Significant Bit	7	6	5	4	3	2	1	0	Least Significant Bit
	CY/L	OV	SB	SA	F3	F2	F1	IE	

Table 2: *A representation of the INS8073 status register. Bits 5 through 0 can be either read or set from NSC Tiny BASIC.*

```
10 INPUT A
20 INPUT B,C
```

When the statement at line 10 is executed, NSC Tiny BASIC prompts you with a question mark. You type in a number, which is assigned to the variable A after you press the RETURN key. NSC Tiny BASIC then prompts

BIT	DESCRIPTION
7	CARRY/LINK (CY/L): This bit is set to 1 if a carry occurs from the most significant bit during an add, a subtract, or any instruction that alters the status register. This bit may also be set by the operations performed by the SHIFT RIGHT WITH LINK (SRL) and the ROTATE RIGHT WITH LINK (RRL) machine-language instructions.
6	OVERFLOW (OV): This bit is set if an arithmetic overflow occurs during a machine-language add or subtract instruction.
	NOTE: Bit 7 and bit 6 may be of little or no use in an NSC Tiny BASIC program.
5	SENSE BIT B (SB): Tied to an external connector pin, this bit can be used to sense external conditions. This is a "read-only" bit; it is not affected when the contents of the accumulator are copied into the status register by a STAT instruction. Sense bit B is also the second interrupt input and may be examined by use of the "ON" command.
4	SENSE BIT A (SA): Like sense bit B, this bit is tied to an external connector pin and serves to sense external conditions. In addition, sense bit A acts as the interrupt input when the INTERRUPT ENABLE (see bit 3 of status register below) is set. This bit is also a "read-only" bit and can be examined with the "ON" command. NSC Tiny BASIC uses this bit as the serial input bit from the TTY or CRT.
3	USER FLAG 3 (F3): This bit can be set or reset as a control function for external events or for software status. It is available as an external output from the INS8073.
2	USER FLAG 2 (F2): Similar to F3. This flag is used by NSC Tiny BASIC to control the paper-tape reader relay.
1	USER FLAG 1 (F1): Similar to F3. This flag is used by NSC Tiny BASIC as the serial-output bit (with inverted data) to the TTY or CRT.
	NOTE: The outputs of flags 1, 2, and 3 of the status register serve as latched flags. These flags are set to the specified state when the contents of the status register are modified by an assignment to STAT, and remain in that state until the contents of the status register are modified under program control.
0	INTERRUPT-ENABLE FLAG (IE): The processor recognizes the interrupt inputs if this flag is set. This bit can be set and reset under program control. When the interrupt-enable flag is set, NSC Tiny BASIC recognizes external interrupt requests received via the SENSE A or B inputs. When reset, this interrupt-enable flag prevents the INS8073 from recognizing interrupt requests.

Table 3: *A summary of the function of each bit in the INS8073 status register.*

you with another question mark, and you type in two numbers, separated by commas. These numbers will be assigned to B and C in that order. A sample run follows:

```
RUN
? 45
? 237, 4455
```

NSC Tiny BASIC would now continue execution of the program.

NSC Tiny BASIC accepts expressions as well as numbers in response to an INPUT request. For example:

```
>LIST
  10 A=10
  20 INPUT B,C
  30 PRINT B,C
>RUN
?A+1,A*2
 11   20
```

The comma between the entered expressions is not mandatory and can be replaced by spaces if the second expression does not start with a plus or minus sign. There must be at least as many expressions in the input list as variables in the INPUT statement. If an error occurs when NSC Tiny BASIC tries to evaluate the typed-in expression, the message

```
RETYPE
```

is printed along with the error message, and the question mark prompt will appear again so that you can type the expressions correctly.

NSC Tiny BASIC allows string input, as described in the section on string handling, found later in this article. INPUT may not be used in the command mode.

The PRINT statement is used to output information from the program. Quoted strings are displayed exactly as they appear, with the quotes removed. Numbers are printed in decimal format. A space precedes positive numbers, and a minus sign precedes negative numbers. All numbers have a trailing space. A semicolon at the end of a PRINT statement suppresses the usual carriage return and line feed with which NSC Tiny BASIC terminates the output.

Strings stored in memory (such as those generated by a string input statement) may also be printed. A typical example:

```
>LIST
  PRINT "THIS IS A STRING"
  20 A=10
  30 B=20
  40 PRINT "10 PLUS 20=", A+B
  RUN
THIS IS A STRING
10 PLUS 20= 30
```

The word LET may be used or omitted in an assignment statement, but the execution of an assignment statement is faster if the word LET is used. The left portion of an assignment statement may be a simple variable (A through Z), STAT, or a memory location, which is indicated by an @ followed by a variable, a number, or an expression in parentheses. Here are some sample assignments:

```
LET X=7
X=7
LET E=I*R
E=I*R
STAT=#70
LET @A=255
@(T+36)=#FF
```

Conditional assignments may be made without using an IF statement. The method hinges on the fact that all predicates are actually evaluated to yield −1 if true and 0 if false. Thus, if a predicate is enclosed in parentheses, it may be used as a multiplier in a statement as shown here:

```
LET X= -A*(A> =0)+A*(A<0)
```

This statement would assign the absolute value of A to X.

Program Control

NSC Tiny BASIC provides an assortment of program-control statements. The GO TO statement permits program branches to a specific line number or a line number called by an arbitrary expression. For example,

```
10 GO TO 50
```

would cause the program to jump from line 10 directly to line 50, but

```
10 GO TO X+5
```

would cause the program to jump from line 10 to line X+5. The value of X is variable, allowing dynamic control of program execution at this point.

The GOSUB and RETURN statements are useful when a computation or operation must be performed at more than one place in a program. Rather than write the routine over again each time it is needed, you employ a GOSUB instruction to "call" the computation or operation (referred to as a subroutine). After the subroutine has been executed, a RETURN instruction (the last instruction of the subroutine) causes the program to resume execution at the next line number following the original GOSUB instruction. An example is shown in figure 1. GOSUBs may be nested up to eight levels deep (including interrupt levels).

The IF. . .THEN statement allows program control to be modified by a logical test condition. The test condition follows the IF clause of the statement. When the test condition is true (nonzero), the THEN portion of the statement will be executed. When the test condition is false (zero), the THEN portion will be ignored and execution will continue at the next numbered line of the program. For example:

```
50 IF X>J THEN GO TO 140
```

NSC Tiny BASIC allows the omission of the word THEN from an IF. . .THEN statement. This omission, also allowed on some larger BASICs, enhances the clarity of the program. The previous example would become:

```
50 IF X>J GO TO 140
```

The DO. . .UNTIL statement is unique to NSC Tiny BASIC. Borrowed from Pascal, this statement is used to program loops, thus keeping GO TO statements to a minimum. The DO. . .UNTIL statement makes NSC Tiny BASIC programs clear in structure and easy to read. The following example shows the use of DO. . .UNTIL statements to print numbers less than 100:

```
10 PRINT 1: PRINT
20 PRINT 2
30 I=3              :REM I IS NUMBER TESTED
40 DO
50 J=1/2            :REM J IS THE LIMIT
60 N=1              :REM N IS THE FACTOR
70 DO               :REM SEEKS A DIVISIBLE
                    FACTOR OF I
80 N=N+2
90 UNTIL (MOD(I,N)=0 OR (N>J))
100 IF N>J PRINT I  :REM NO DIVISIBLE FACTOR
110 I=I+2
120 UNTIL (I>100)   :REM ENDS THE SEARCH
```

By enclosing a 0 or more statements between the DO and the UNTIL <condition> statement (where the <condition> is any arbitrary expression), you cause repetition of the enclosed statements as a group until the <condition> evaluates to a nonzero number (a true condition). DO. . .UNTIL loops can be nested, and NSC Tiny BASIC will report an error if the nesting level becomes too deep (more than eight levels).

The FOR. . .NEXT statement in NSC Tiny BASIC is identical to the FOR. . .NEXT statement in standard




Figure 1: *The effects of the GOSUB and RETURN statements in NSC Tiny BASIC. On the first GOSUB call (line 50), the order of execution follows the solid arrows. On the second GOSUB call (line 100), the order of execution follows the dashed arrows.*

BASICs. A STEP function in the FOR statement may be used to specify the size of the increment in each iteration of the statement. In the absence of a specified STEP, NSC Tiny BASIC assumes a STEP value of +1. The value of the STEP may be either positive or negative. Starting and ending values of the FOR. . .NEXT loop are included in the FOR statement. The loop is repeated when the NEXT statement has been executed, provided the upper limit of the FOR statement has not been reached. When the upper limit is reached, the program will exit from the FOR. . .NEXT loop. NSC Tiny BASIC causes an error break if the variable in the NEXT statement is not the same variable as that used in the FOR statement.

FOR. . .NEXT loops may be nested, and NSC Tiny BASIC will report an error if the nesting level becomes too deep; a depth of four levels of FOR loop nesting is allowed. A FOR loop will be executed at least once, even if the initial value of the control variable already exceeds its bounds before starting. The following program would print the odd integers less than 100:

```
10 N=100                :REM UPPER LIMIT
20 FOR I=1 TO N STEP 2  :REM START AT 1 WITH
                         STEP OF 2
30 PRINT I              :REM PRINT A NUMBER
40 NEXT I               :REM REPEAT (at line 20)
                         20)
```

When increased execution speed is needed, you can use a LINK statement to transfer control from an NSC Tiny BASIC program to an INS8073 machine-language routine. A statement of the form LINK <address> will cause transfer of control to the INS8073 machine-language routine, starting at the specified address. Control is transferred by execution of a JSR (Jump to Subroutine) instruction.

The INS8073 has two address pointers, P2 and P3, in addition to the program counter and the stack pointer. When a LINK statement transfers control to a machine-language routine, the routine can modify the pointers P2 and P3. The value of pointer P3 is unpredictable; P2 points at the starting location of the storage of A through Z variables. These variables are stored in ascending alphabetical order, two bytes each, low-order byte first. Here is an example:

```
  10 LINK #1800              NSC Tiny BASIC trans-
  20 IF A=0 THEN PR            fers to address #1800
     "SENSE A IS LOW"          to read sensor.
  30 IF A=1 THEN PR
     "SENSE A IS HIGH"
  99 STOP                    Program transfers back
>RUN                           to NSC Tiny BASIC
SENSE A IS HIGH
STOP AT 99
>RUN
SENSE A IS LOW
STOP AT 99
```

The program above requires the machine-language program described below to be loaded into address 1800 hexadecimal.

```
              .TITLE SENSE    ;THIS PROGRAM
                              READS SENSE A PIN
0000          .=01800
1800 06       LD    A,S       ;TINY BASIC JUMPS
                              HERE
1801 D410     AND   A,=16
1803 6C02     BZ    LOW
1805 C401     LD    A,=1
1807 CA00     ST    A,0,P2    ;STORES AC-
                              CUMULATOR INTO
                              LOCATION OF
                              VARIABLE A
1809 5C       RET             ;RETURN TO TINY
                              BASIC
     0000     .END
```

The ON statement helps process interrupts. The format of the statement is:

ON interrupt−#, line-number

When the numbered interrupt (interrupt−#) occurs, NSC Tiny BASIC executes a GOSUB statement beginning at the line number given. If the line-number given is zero, the corresponding interrupt is disabled at the software level. Interrupt numbers may be 1 or 2. Use of the ON statement disables console interrupts (BREAK function). Interrupts must also be enabled at the hardware level by setting the interrupt-enable bit in the status register (e.g., using STAT=1).

Although the last line of a program does not have to be a STOP statement, use of a STOP in this way does help in debugging. The STOP statement may be inserted as a breakpoint in an NSC Tiny BASIC program. On encountering a STOP statement, NSC Tiny BASIC prints a stop message and the current line number, then returns to the edit mode. Thus, you can see whether your program has reached the desired point. Any number of STOP statements may appear in the program. By removing the STOP statements one by one, you can test the program in parts until debugging is completed. Execution of a stopped program may be continued after the STOP by a CONT (continue) command.

Other Useful Features

The DELAY statement delays NSC Tiny BASIC for "expr" time units (nominally milliseconds, 1 through 1040). Delay 0 gives the maximum delay of 1040 ms. The format is:

DELAY expr

For example:

```
>10 DELAY 100      Delay 100 ms.
```

The CLEAR statement initializes all variables to 0, disables interrupts, enables BREAK capability from the console, and resets all stacks (GOSUB, FOR. . .NEXT, and DO. . .UNTIL). For example:

```
10 ON (2,250)   Break is disabled, Interrupt 2 is
                enabled.
                      .
                      .
                      .
300 CLEAR       Break is reenabled, Interrupt 2
                is disabled.
```

The indirect operator is an NSC Tiny BASIC exclusive, at least in the realm of BASIC. This operator performs the functions of PEEK and POKE with a less cumbersome syntax. The indirect operator can access absolute memory locations and can service input/output devices as well. Its utility is especially significant for microprocessors like the INS8073, for which interfacing is commonly performed through memory addressing.

When an "at" sign (@) precedes a constant, a variable, or an expression in parentheses, that constant, variable, or expression is taken as an unsigned 16-bit address at which a value is to be obtained or stored. Thus, if an input device has an address of #6800 (hexadecimal), the statement

```
LET X=@#6800
```

would input from that device and assign the value of the input to the variable X. If the address of an output device was #6801, the statement

```
@#6801=Y
```

would output the least significant byte of Y to the device. The indirect operator accesses memory locations only one byte at a time. An assignment such as @A=248 changes the memory location pointed to by A to 248 binary (1111 1000), since 248 can be expressed as one byte. However, an assignment such as @A=258 changes the memory location pointed to by A to 2, because expressing the value 258 causes a carry to a ninth bit, which is lost, as shown below:

```
258₁₀ = 1       0000  0010
      extra     one byte (stored into location to
       bit      which A would point)
```

Only the least significant byte of 258 (which is 2) is stored at the location to which A would point.

In any place where a variable, such as B, would be legal, the construct "@B" (which means the byte located at the memory location whose address is the value of B) would also be legal. Here are some other examples:

```
40 LET B=6000          Assigns 6000 to B.
50 LET @B=100          Stores decimal 100 in
                       memory location 6000.
60 LET C=@B            Sets C equal to 100.
70 PRINT @6000         Prints 100.
80 LET D=@(A+10*D)     Sets D equal to the value
                       stored in memory location
                       (A+10*D).
```

Parentheses are required when @ is applied to an expression.

More than one statement can be placed on one program line by placing a colon between the statements. This technique can improve readability of the program and can save memory space. Here is an example of the use of multiple statements:

```
200 PRINT "MY GUESS IS",Y:PRINT "INPUT A
     POSITIVE NUMBER";: INPUT X:
     IF X <=0 GO TO 200
```

If X is negative or zero, you will be instructed to enter a positive number, and the program will return to line 200 for a new guess. If you had entered a positive number correctly, the program would have proceeded to the next numbered line after line 200.

You must use multiple statements per line with care. The above example shows that if the condition of the IF

statement is false, control passes to the next program line. Anything else on the line containing multiple statements will be ignored.

String Handling

To input string data, a statement of the form

INPUT $ F

where F is a starting address, is used. When the program reaches this statement during program execution, NSC Tiny BASIC prompts you with a question mark (?). All line-editing characters may be used (back space, line delete, etc.). If a control-U is typed to delete an entered line, NSC Tiny BASIC will continue to prompt for a line until a line is terminated by a carriage return. The line is stored in consecutive locations, starting at the address pointed to by F, up to and including the carriage return. For example,

20 INPUT $ A

may also be written

20 INPUT $A

and inputs a string to successive memory locations starting at A.

An item in a PRINT statement can include a string variable in the form of $B. When the print statement is encountered during program execution, the string will be printed beginning at the address B up to, but not including, a carriage return. A keyboard interrupt will also terminate the printing of the string if the interrupt is detected before the carriage return. For example,

50 PRINT $B

prints the string beginning at the location pointed to by "B".

Characters in quotes can be assigned to string variables just as numerical values are assigned to other variables. A statement of the form

$C="THIS STRING IS A STRING"

when encountered during program execution, would cause the characters in quotes to be stored in memory starting at the address indicated by C and going up to and including the carriage return at the end of the line. For example:

70 $D="THIS IS A STRING WITH NO
INPUT STATEMENT."
A T is stored at location "D", an H at location "D+1", etc.

Strings can be moved from one memory block to another. A statement of the form

$A=$B

(where A and B are addresses) will transfer the characters in memory beginning with address B to memory beginning with address A. The last character, normally a carriage return, is also copied. Note that a statement such as

$(A+1)=$A

would be disastrous, because it fills all of RAM with the first character of $A. Here is an example of moving one memory block to another location:

```
10 A=TOP          :REM A POINTS TO EMPTY
                   RAM ABOVE TOP OF
                   PROGRAM
20 C=TOP+100      :REM C POINTS TO RAM 100
                   BYTES ABOVE A
30 D=TOP+200      :REM D POINTS TO RAM 100
                   BYTES ABOVE C
40 INPUT $A       :REM STORES CHARACTERS
                   WHERE A POINTS
50 PRINT $A
60 LET $C="IS THE STRING INPUT AT LINE 10"
70 $D=$C          :REM STORES CHARACTERS
                   WHERE D POINTS
80 PRINT $D
```

Commands

The NEW command establishes a new start-of-program address equal to the value of "expr". NSC Tiny BASIC then executes its initialization sequence, which clears all variables, resets all hardware/software stacks, disables interrupts, enables BREAK capability from the console, and performs a nondestructive search of RAM. If the value of "expr" points to a ROM (read-only memory) address, the NSC Tiny BASIC program that begins at that address will be automatically executed. The NEW command does not alter memory (including the end-of-program pointer used by the editor). For example:

>NEW 1000

NEW used without an argument sets the end-of-program pointer equal to the start-of-program pointer, so that a new program may be entered. If a program already exists at the start-of-program address, it will be lost. For example:

>NEW 1000	Sets program pointer to 1000
>NEW	Sets end-of-program pointer to 1000

The RUN command runs the current program. For example:

>RUN	Execution begins at lowest line number

The CONT (continue) command continues execution of the current program from the point where execution was suspended (via a STOP, console interrupt, or reset). An NSC Tiny BASIC program that is executing can be interrupted by pressing the BREAK or RESET keys on the keyboard. Execution can be resumed by entering the CONT command. For example:

```
>RUN
  THIS IS THE STRING INPUT AT LINE 10
  THIS IS THE STRING INPUT AT LINE 10
  THIS IS THE STRING INPUT AT LINE 10
  THIS IS THE STRING INPUT AT LINE 10 Press
    BREAK or RESET.
 ^C
>CONT
  THIS IS THE STRING INPUT AT LINE 10
  THIS IS THE STRING INPUT AT LINE 10
  And so on...
```

The LIST(expr) command lists the current program (optionally starting at the line number specified by "expr"). For example:

```
>LIST 10
10 INPUT $A
20 PRINT $A
30 LET $C="IS THE STRING INPUT AT LINE 10"
40 $D=$C
50 PRINT $D
```

Conclusion

NSC Tiny BASIC and the INS8073 Microinterpreter Chip offer many advantages to the programmer. NSC Tiny BASIC's indirect operator represents a substantial improvement over the usual PEEK and POKE statements. The DO . . . UNTIL statement brings the advantages of structured programming into the realm of Tiny BASICs for the first time. These and other advanced features of NSC Tiny BASIC offer you the convenience of a high-level language as well as new possibilities for elegance and efficiency in process-control and other applications often reserved for assembly language.

Furthermore, with NSC Tiny BASIC and the INS8073, transferring programs from RAM to ROM is remarkably simple. Because the INS8073 executes ASCII (American Standard Code for Information Interchange) data, if the program will run in RAM, it will run in ROM. You don't have to put anything in ROM except what you put on paper.

Programmers have already used the INS8073 and NSC Tiny BASIC for a wide variety of applications, including precision measurement of conditions in oil wells and testing the feasibility of the digital design of an FM tuner. In the coming years, the INS8073 and NSC Tiny BASIC will simplify many other complex tasks.■

Easy Entry Program for Radio Shack's Color Computer

Tim Field
1021 Shenandoah Drive
Lafayette, IN 47905

Radio Shack's versatile new TRS-80 Color Computer packs a big bang for a small cost. The power of its 6809 microprocessor is the computer's biggest attraction.

To take full advantage of the 6809, you must develop machine-language programs. The Easy Entry program is a short BASIC program that will greatly help you enter machine-language programs for the Color Computer. By no means does it replace an assembler, but Easy Entry will save you many hours of arduous and error-prone work until you get one. (For more information, see "A Closer Look at the TRS-80 Color Computer," October 1981 BYTE, page 334.)

The Color Computer's BASIC provides the necessary keywords (PEEK, POKE, and USR) to permit entry of machine-language programs. However, using these commands to enter a short program is soon cumbersome and tedious. You must develop, code, and hand-assemble the program, enter it into memory, and test and debug it. And the entry is not that simple.

All values must be converted into decimal values between 0 and 255 before they can be POKEd into the Color Computer. Op codes must be individually converted to decimal from their hexadecimal format in the 6809 data sheets. Negative values must be converted to the form understood by the computer. Decimal addresses greater than 255 must be broken down into two-byte values. Then, after completing all these conversions, each value must be individually POKEd into memory. The Easy Entry program (see listing 1) handles all conversions and POKEs each converted value into its proper memory locations.

Plug-in Programming

If you're serious about assembly-language programming for the Color Computer, you'll need an assembler/editor, which allows much more efficient programming.

The Color Computer's unique design makes it possible to purchase plug-in ROM cartridges containing editor/assembler programs. Two examples are the Radio Shack Editor/Assembler Program Pack (part number 263250, $39.95) and the Micro Works Software Development System (SDS80C, $89.95). With these utility programs in ROM, the constant problem of loading and relocating programs is eliminated and almost the entire RAM space is available to your program. . . SJW.

Conversions

Normal Decimal Entries. A single byte value (0 to 255 or −127 to 127) may be specified simply by responding with the desired value on a prompt from the program. For example, to POKE value 98 decimal into the next memory location, input 98 at the next prompt.

Hexadecimal to Decimal Conversions. PEEK and POKE accept and return decimal values for specified memory locations. This is terrific because we live in a decimal-reliant society and are uncomfortable working directly with hexadecimal values. Unfortunately, computers "think" in binary (0s and 1s), which is not easily converted to decimal (and vice versa). However, binary to hexadecimal to binary conversions are relatively straightforward, and the resulting hexadecimal values occupy considerably less room (two characters per byte for hexadecimal versus eight characters for binary).

Listing 1: *The Easy Entry program, written in BASIC for the Color Computer. A complete description of the program is given in table 1.*

```
10  CLS:CLEAR(40):INPUT"START:";A$:A=275:GOSUB200
20  A=VAL(A$)
30  PRINTA;:INPUT"NEXT:";C$:IFC$="*"THENEND
40  A$=RIGHT$(C$,LEN(C$)-1):D$=LEFT$(C$,1)
50  IFD$=","THENGOSUB200ELSEIFD$=";"THENGOSUB300ELSEA$=C$:GOSUB100
60  A=A+1:GOTO30
100 U=VAL(A$):IFLEFT$(A$,1)="-"THENU=256+U
110 POKEA,U:RETURN
200 U=VAL(A$):B=ABS(U):V=-1
210 IFU<0THENU=B:K=1ELSEK=0
220 IFU>=0THENU=U-256:V=V+1:GOTO220
230 U=B-V*256:IFK=1THENU=256-U:V=255-V
240 POKEA,V:A=A+1:POKEA,U:RETURN
300 C=LEN(A$):GOSUB400:J=E:C=C-1:GOSUB400
310 POKEA,16*E+J:RETURN
400 IFC<1THENE=0ELSEE=ASC(MID$(A$,C,1))-48
410 IFE>9THENE=E-7
420 RETURN
500 G$="O":GOSUB700:INPUT"START:";X:INPUT"END:";Y
510 PRINT#-1,X:PRINT#-1,Y
520 FORZ=X TO Y:A=PEEK(Z):PRINT#-1,A:NEXTZ:CLOSE-1:END
600 G$="I":GOSUB700:INPUT#-1,X:INPUT#-1,Y
610 PRINTX,Y:A=275:B=X:U=X:V=-1:GOSUB210
620 FORZ=X TO Y:INPUT#-1,A:POKEZ,A:NEXTZ:CLOSE-1:END
700 INPUT"FILE NAME:";F$:OPENG$,-1,F$:RETURN
```

Since op codes are often specified in hexadecimal and must be converted to decimal before being POKEd into memory, the program handles the conversion for you. To indicate that the current entry is a hexadecimal value, merely precede it with a ";". The acceptable values must be in the 00 to FF range. For example, ;7F tells the program to convert hexadecimal value 7F to decimal 127 before being POKEd into memory.

Decimal to Decimal Conversions. You might question the necessity of converting a decimal value to decimal. POKE will accept values between 0 and 255; if a value exceeds 255, it must be broken down into multiple bytes, which are then POKEd into memory in order, from the most significant to the least significant byte. For example, the decimal value 3500 is broken down into a most-significant-byte value of 13 (decimal) and least-significant-byte value of 172.

This process usually involves manually converting the original value into its hexadecimal equivalent (3500 decimal to 0DAC hexadecimal), breaking the hexadecimal value into two bytes (0D and AC), and then reconverting these two bytes to decimal (0D to 13 and AC to 172). The program will accept any input value which is preceded by a ".", convert that into two bytes of decimal, and POKE both into memory. This gives a value range of 0 to 65535.

Negative Decimal to Positive Decimal. As previously mentioned, the POKE function takes values between 0 and 255. If you wish to POKE a negative number into memory (e.g., a negative branch offset), you must convert the negative value to its positive equivalent. To understand how a negative value has an equivalent positive value, we must look at how the computer "knows" if a value is positive or negative.

When seeking a data value, the computer expects to use the most significant value bit as the sign bit. If the value is 8 bits long, bits 0 to 6 are the value bits and bit 7 (the eighth bit) specifies whether the value is positive or negative. If the sign bit indicates a negative value, the

Listing 2: *This sample program paints the screen purple and then returns to BASIC control. Memory locations 1024 to 1536 are used for video memory in the Color Computer. Value 191 paints one block on the screen purple.*

```
LDB     191      ; C6  191
LDY     1024     ; 10 8E  1024
STB     ,Y+      ; E7 A0
CMPY    1536     ; 10 8C  1536
BLT     -8       ; 2D  -8
RTS              ; 39
```

Listing 3: *This listing shows an Easy Entry program sample run. The machine-language program in listing 2 has been entered.*

```
RUN
START:? 3000               (Start POKEing at address 3000)
 3000 NEXT:? ;C6           (At address 3000 poke hex value C6)
 3001 NEXT:? 191           (Poke single byte decimal 191)
 3002 NEXT:? ;10
 3003 NEXT:? ;8E
 3004 NEXT:? ,1024         (Poke double byte decimal 191...takes two bytes)
 3006 NEXT:? ;E7
 3007 NEXT:? ;A0
 3008 NEXT:? ;10
 3009 NEXT:? ;8C
 3010 NEXT:? ,1536
 3012 NEXT:? ;2D
 3013 NEXT:? -8            (Poke negative single byte decimal -8)
 3014 NEXT:? ;39
 3015 NEXT:? *             (Done with entering program)
OK                         (Computer response)
Y=USR(1)                   (Execute program)
```

value bits specify the two's complement of the absolute value. This provides an effective value range for 8 bits between −127 and +127. Thus, 255 decimal indicates a negative value and, taking the two's complement of the value bits, we find that we have specified a −1.

The program automatically converts negative decimal values into their positive equivalents. The value may be either 8 or 16 bits.

Operation

The program is simple to operate. On initiation, the program prompts you for the starting address for the first byte of the machine-language program. The address is stored in memory locations 275 and 276, so a simple USR command after entry of the machine-language program executes that program. You are then prompted for each value in sequence, starting at the beginning address. The current address is displayed with each prompt, and this entry loop continues until you enter an asterisk (*) to signify termination of the program-entry session. The program then returns control of the computer to you. (See listings 2 and 3 for examples of an Easy Entry program sample run.)

Saving and Loading Machine-Language Programs

Once you enter and debug a machine-language program, you can save it on tape. Since the Color Computer's BASIC does not allow you to directly save machine-language programs, I have included two routines (lines 500 through 700) that save and load the programs for you. If you have a 4 K-byte machine and are developing a large machine-language program, you can separate these two routines from the main program and load them only when ready to save your program. Lines 210 through 240 and 500 through 700 must be used.

If you wish to leave the program conveniently intact, there are still more than 1700 bytes available for the 4K-byte computer. (If you have 16K bytes of memory, you naturally have lots of space.) You should limit machine-language programs to address 2500 decimal and up.

Type "RUN 500" to save a machine-language program. You will be prompted for the desired file name for program storage and the starting and ending address of the machine-language program. All bytes between the starting and ending addresses are saved on tape. For example, you might have a program with a main loop at address 2500 through 3000, subroutines at 3100 through 3150 and 3400 through 3450, and a data table at 3475 through 3500. You would want to save your program from ad-

Lines	Purpose
Main Routine	
10	Initialize program. Prompt user for starting address and place into 275-276.
20-30	Prompt input from user . . . if "*" then end program.
40-50	Determine type of input. Jump to appropriate subroutine for conversion and POKEing of value.
60	Move to next address and repeat.
Subroutines	
100-110	Value is between −255 and +255. If negative, negate input. POKE value.
200-240	Input (A$) is a decimal value to be converted into two eight-bit values. Line 220 loops, subtracting 256 from U per loop until U is less than zero. Then, the most significant byte is V; least significant byte is U. POKE both bytes and increments POKE pointer A.
300-310	Input is hexadecimal (00-FF). The value is calculated by finding the decimal equivalent of each ASCII value and then adjusting these values to give appropriate results. The final value is then calculated by adding the least significant value (corresponding to least significant hexadecimal entry) to 16 times the most significant entry.
400-420	Input single hexadecimal character (character C in string A$) and return the equivalent decimal value in variable E. If C<1 then return E=0.
Save/Load Routines (execute with "RUN 500" or "RUN 600" commands)	
500-520	Input file name, starting and ending addresses, and save specified memory block to cassette tape.
600-620	Input file name. Load file from cassette into memory address found at start of data file. Poke starting address into 275-276 to allow the USR command to execute loaded program.
700	Routine used by 500 and 600. Used to fetch file name of desired file to be saved or loaded.

Table 1: *The Easy Entry program routines and their functions.*

dress 2500 to 3500. All unused addresses between the routines and the tables are also saved.

To load a previously saved machine-language program, type "RUN 600". You will be prompted for the file name of the program to be loaded. The program then reads from the tape the starting and ending addresses used when the program was stored,sorting the program in those memory locations. The starting address of the program being loaded is automatically converted into two bytes and POKEd into memory locations 275 and 276. Thus, if you have a complete program loaded, you can immediately execute it by typing Y=USR(1).

Since Easy Entry loads machine-language programs into specific memory locations, you can save parts of programs, load them all separately, and execute a program. For instance, you might be developing several programs, each using a large subroutine. If the subroutine is subject to changes, or if you store the subroutine with each separate program, it is easy to lose track of revisions. However, if you want that routine at a permanent location (say address 3700 through 4100), you can save it separately from other programs. Then, wishing to execute one program, you load the subroutine, load the program's main body, and execute. Be certain that the proper address is loaded into memory locations 275 and 276 so that the computer knows where to look when you execute the USR command.

How the Routines Work

The save and load routines treat each machine-language program byte as data. To save a program, each byte is consecutively PEEKed at and then sent to the tape using the PRINT#-1 command. The first two pieces of data stored in the data file are the starting and ending addresses of the machine-language program being stored. When the load routine is executed, it reads these two addresses, reads all data from the tape, and POKEs it into the specified memory block.

You might think that saving a large machine-language program to tape and writing each individual byte to tape separately would be time consuming. Thanks to the PRINT#-1 statement's design, this isn't so. Apparently, the Color Computer's BASIC sets aside a buffer used to store the PRINT#-1 data values. When this buffer is full, data is sent to the tape and the buffer is refilled, allowing you to save a machine-language program of 2 K bytes in about 30 seconds. The time required to load a program is similar.

The Easy Entry program requires only about 450 bytes of memory. For a 4 K-byte Color Computer, this leaves almost 2000 bytes of available memory to store machine-language programs. A lot can be accomplished in 2000 bytes of machine language.

Your machine-language programs may be entered starting at address 2200. Little error checking is included in the program to keep it as small as possible. After entering a few values, you should become adept at using the program and save yourself many hours. ■

STATISTICAL SOFTWARE

ELF — Stepwise regression, factor analysis, correlation coefficients, crosstabs, simple statistics, t-tests, ANOVA, stepwise discriminant analysis, all BASIC transformations and more. $200.00

TWG/ARIMA — Box-Jenkins for seasonal and non-seasonal models, identification, estimation and forecasting. Price: $300.00.

Each includes a database manager, numeric software keypad, and is menu-driven. Each requires an Apple II with Applesoft, 48K, and DOS 3.3.

For further information, write

The Winchendon Group
3907 Lakota Road
P.O. Box 10114
Alexandria, VA 22310

*Apple II and Applesoft are trademarks of the Apple Computer Company

Circle 437 on Inquiry card.

ELIZA IS HERE!

AT LAST! A FULL IMPLEMENTATION of the original ELIZA program is now available to run on your microcomputer!

Created at MIT in 1966, ELIZA has become the world's most celebrated artificial intelligence demonstration program. ELIZA is a non-directive psychotherapist who analyzes each statement as you type it and then responds with her own comment or question — and her remarks are often startlingly appropriate!

Designed to run on a large mainframe, ELIZA has hitherto been unavailable to personal computer users except in greatly stripped down versions lacking the sophistication which made the original program so fascinating.

Now, our new microcomputer version possessing the **FULL** power and range of expression of the original is being offered at the introductory price of only $25. And if you want to find out how she does it (or teach her to do more) we will include the complete **Source Program** for only $20 additional.

Order your copy of ELIZA today and you'll never again wonder how to respond when you hear someone say "Okay, let's see what this computer of yours can actually do!"

ELIZA IS AVAILABLE IN THE FOLLOWING DISK FORMATS:

1. Standard 8 inch single density for all CP/M based computers
   $25 for ELIZA.COM — add $20 for Microsoft BASIC-80 Source
2. 5¼ inch CP/M for Apple II equipped with Z-80 SoftCard
   $25 for ELIZA.COM — add $20 for Microsoft BASIC-80 Source
3. 5¼ inch for 48K Apple II with Applesoft ROM and DOS 3.3
   $25 for Protected File — add $20 for Unprotected Source

ARTIFICIAL INTELLIGENCE RESEARCH GROUP

VISA

921 NORTH LA JOLLA AVENUE
LOS ANGELES, CALIFORNIA 90046
(213) 656-7368 (213) 654-2214
MC, VISA and CHECKS ACCEPTED



Circle 40 on Inquiry card.



Scotch® DISKETTES

SAVE 40% Write for our complete list.

		Price/10
5¼'' Specify soft, 10 or 16 sector		
#744	1 side/sgl dens	$26.70
#744D	1 side/dbl dens	31.20
#745	2 sides/dbl dens	38.40
8'' Specify soft or 32 sector		
#740	1 side/sgl dens	27.30
#741	1 side/dbl dens	35.80
#743	2 sides/dbl dens	43.60

CHECKS — VISA — MC — C.O.D.
(313) 777-7780 ADD $2 SHIPPING

LYBEN COMPUTER SYSTEMS
27204 Harper Ave.
St. Clair Shores, MI 48081

Authorized Distributor
Information Processing Products **3M**

Circle 241 on Inquiry card.

DISKETTES CASSETTES


Error-Free 5¼-inch Diskettes (MD-5) single-sided, soft sector, single or double density, reinforced hub.

Item	Qty 10	Qty 50
MD-5	$25.00	$110.00
C-10	$ 7.50	$ 32.50
C-20	9.00	39.00
C-60	11.50	50.00
C-90	15.00	70.00

UPS SHIPPING INCLUDED in Continental USA
CA Customers add taxes

MICROSETTE
475 Ellis St., Mt. View,
CA 94043 (415) 968-1604

Circle 274 on Inquiry card.



RAM: 64K-200ns (128 refresh) — **8/$79**

Color R.F. Modulator Kit: — $13.79

14A S-100 Power Supply Kit—$29.95
(for line cord and circuit breaker, add $8.95)
47-63 Hz, 95-250 VAC with RFI filter included. ±16V @2A

Disk Power Kit—24V/5A — $19.95

New! RGB Displays
Now Higher-Resolution!

- High Contrast Black-Stripe Tube
- Ultra Stable Convergence
- 90 Day Warranty
- 15.7 KHz

Microangelo
CAT-100, IBM

13"- $349.00
525 x 420 lines, 32 lbs

19"- $379.00
525 x 620 lines, 48 lbs.
(Displays 80 characters on IBM)
Active 12' Cable to IBM with "Intensity" input—$75.00

Add shipping, and insurance. We are philosophically against VISA & M.C. (for 5% who wouldn't be?)

Dealin' Electronics
735 Loma Verde, Palo Alto, CA 94303 • 415-493-5930

Circle 141 on Inquiry card.

TYPESETTING from your own COMPUTER

Type your manuscripts, catalogs, or other text into your word processing computer.

Send it to us on a diskette or via a modem transmission and we'll send you camera ready film copy.

Computer typesetting provides high quality, easy to read copy at a fraction of the cost of conventional typesetting.

Call or write for instructional brochure that includes typestyle selections, formatting instructions, and examples.

Dream Electronics
131 N.W. 2 nd. St. 1-503-7524833
Corvallis, Oregon 97330

Circle 152 on Inquiry card.

FOR YOUR



HARDWARE AND SOFTWARE
FREE CATALOG
OVER 350 PRODUCTS
SPECIAL OFFER
wabash® DISKETTES
Unique SR-3000 Formulation - 100% Certified
Error Free - Hub Rings Installed on 5¼"
5¼"SS/SD $21.95/BX DS/DD $29.95/BX
8" SS/SD $23.75/BX DS/DD $36.75/BX
ONE TIME ONLY - ONE BOX/CUSTOMER
Ask For Our S-100 and Related Products Catalog

2.4MB NEC 8" FLOPPY DISKS SUBSYSTEM $1675

FETCH COMPUTER PRODUCTS DIVISION OF:
ALMALY TRADING CORPORATION
8135 S.W. 17 STREET, MIAMI, FL 33155
TELEX: 51-9602 "ALMALY MIA"

800-327-2251

Apple is a Registered Trademark of Apple Computers

Circle 16 on Inquiry card.

ANALOG⟺DIGITAL DIGITAL⟺ANALOG
CONVERSION MODULES

SOFTWARE GAIN CONTROL

high accuracy — programmable gain instrumentation amplifier — custom board test — S-100 — 2 to 15 khz conversion time — mixable high and low inputs — gain from 1 to 1024 — 12-bit — sample and hold amplifier 8-channel differential — 16-channel — analog to digital high accuracy — programmable gain instrumentation amplifier — custom board test — S-100 — 2 to 15 khz conversion time — mixable high and low inputs — gain from 1 to 1024 — 12-bit — sample and hold amplifier 8-channel differential — 16-channel — analog to digital high accuracy — programmable gain instrumentation amplifier — custom board test — S-100 — 2 to 15 khz

For additional details about the AD-100-4 and other fine California Data Corporation 100% individually tested, high reliability products, circle the reader service card number below or for faster response write or call us.

CALIFORNIA DATA CORPORATION
3475 Old Conejo Road, Suite C-10
Newbury Park, CA 91320
(805) 498-3651

Circle 72 on Inquiry card.

WANTED:
APPLE, IBM, TRS-80, CP/M
SOFTWARE

Westico is a publisher and distributor of professional software for microcomputers. If you have a new program ready for distribution or want your existing programs to reach a larger market, contact:

Phillip Woellhof, V.P. Mktg.
Westico, Inc.
25 Van Zant Street
Norwalk, CT 06855
(203) 853-6880

To increase your profits, take advantage of Westico's worldwide promotion and distribution.

WESTICO
The Software Express Service

Atari Club in Virginia

The recently formed Virginia Atari Club meets at 5 p.m. on the second Thursday of the month in the NASA Langley Research Activities Building (1222) in Hampton, Virginia. For more information, contact Olaf O. Storaasli, 109 Five Forks Ln., Hampton, VA 23669, (804) 851-4936.

DATAmerica

A newsletter packed with games, reviews, articles, software exchange, and programs is available from DATAmerica Computer User's Group. The group's interests embrace most popular computers, including the Apple II, TRS-80, Sinclair, Atari, PET, and VIC-20. Membership fees are $10 per year. A sample issue of the newsletter is available for $1. Contact DATAmerica, 312 East 84 St. #1A, New York, NY 10028, or through the Micronet RUN MLOM. XBA[70265,742].

International Service Association Formed

The International Association of Service Companies (IASCO) has been formed to provide specialized support services to independent service companies supporting mini- and microcomputer systems. To aid the independent service organization, IASCO has established a Board of Governors to coordinate the activities of several specialized industry committees. The Board's goals hinge around the development of service standards of performance for its membership, the implementation of centralized information centers to aid members, and to prepare and coordinate both technical and managerial educational programs for members. IASCO is currently preparing a support profile listing the various locations throughout the United States and Canada serviced by its membership. This information will be made available to interested parties.

Service companies seeking IASCO membership will be required to meet minimum standards of service performance, service times, test equipment availability, and technical capability. For more information, contact S. Michael Smith, 1409 Centre Circle Dr., Downers Grove, IL 60515, (312) 620-8750.

Color Computer Club Started

Rohit Gupta has started a new computer club for TRS-80 Color Computer owners and users. Annual dues are $4, which includes a monthly newsletter on Color Computer developments. Contact Rohit Gupta, 28 Friars Ln., Springfield, IL 62704.

New Zealand Computer Hobbyists

Micro, the official publication of the New Zealand Microcomputer Club, overflows with news of club projects and activities, classified advertisements, software library happenings, and notes from user groups. The club is investigating the chances of setting up a computerized bulletin-board service and is trying to stock its magazine library. The club would like to discuss the possibility of exchanging publications with groups from overseas. Contact the New Zealand Microcomputer Club Inc., POB 6210, Auckland, New Zealand.

Apple Club Open to Hobbyists

Membership in the Big Red Apple Club is open to anyone who, for geographical reasons, is unable to belong to a local club. All club business is conducted through the monthly newsletter, *The Scarlett Letter*, which also contains programs, utilities, technical tips, and educational applications. A free software library is maintained. Annual fees are $12. The club is a member of the International Apple Corp. Contact John Wrenholt, Big Red Apple Club, 1301 North 19th, Norfolk, NE 68701, (402) 379-3531.

Apples Thrive Down Under

The Apple Users Group (Sydney) has formalized its objectives in a constitution and has elected an executive committee to direct the activities of its large membership. The club meets at the Sydney Grammar School, Science Auditorium, on the second Monday of the month at 6:30 p.m. The group maintains a software library and produces a monthly newsletter, *Applecations*. Contact the Apple Users Group (Sydney), POB 505, Bankstown, New South Wales 2200, Australia, or call Colin Rutherford, (02) 520 0926.■

Books Received

Apple Pascal Games, Douglas Hergert and Joseph T. Kalash. Berkeley, CA: Sybex, 1981; 371 pages, 17.2 by 22.3 cm, softcover, ISBN 0-89588-074-1, $14.95.

The Apple II Blue Book, A Complete "Where to Find It" Book of Software, Hardware, and Accessories for the Apple II, WIDL Staff. Chicago, IL: WIDL (5245 West Diversey Ave.), 1981; 131 pages, 21 by 26.5 cm, softcover, ISBN none, $19.95.

Computer-Assisted Data Base Design, George U. Hubbard. New York: Van Nostrand Reinhold, 1981; 285 pages, 14.5 by 22.3 cm, hardcover, ISBN 0-442-23205-5, $24.95.

The Captain 80 Book of BASIC Adventures, Robert Liddil. Tacoma, WA: 80-Northwest Publishing, 1981; 252 pages, 20.5 by 27 cm, softcover, ISBN none, $19.95.

Computing Using BASIC, An Interactive Approach, Tonia Cope. New York: Halsted Press, 1981; 351 pages, 14.5 by 22.3 cm, softcover, ISBN 0-470-27280-5, $19.95.

Data Models, Dionysios C. Tsichritzis and Frederick H. Lochovsky. Englewood Cliffs, NJ: Prentice-Hall, 1982; 381 pages, 17.5 by 23.6 cm, hardcover, ISBN 0-13-196428-3, $24.95.

A Dictionary of Minicomputing and Microcomputing, Philip E. Burton. New York: Garland STPM Press, 1982; 347 pages, 14.5 by 22.3 cm, hardcover, ISBN 0-8240-7263-4, $42.50.

Directory of Online Databases, Volume 3, Number 1 (Fall 1981), compiled and edited by Ruth N. Cuadra, David M. Abels, and Judith Wanger. Santa Monica, CA: Cuadra Associates, 1981; 186 pages, 21 by 27.5 cm, softcover, ISSN 0193-6840, $29.95.

Electronic Circuits and Applications, Bernard Grob. New York: McGraw-Hill, 1981; 468 pages, 18.5 by 23.5 cm, hardcover, ISBN 0-07-024931-8, $20.95.

55 Color Computer Programs for the Home, School and Office, Ron Clark. Woodsboro, MD: Arcsoft Publishers, 1981; 127 pages, 13.5 by 21 cm, softcover, ISBN 0-86668-005-5, $9.95.

The Index, The Ultimate Index for All Personal Computer Users, W. H. Wallace. St. Ann, MO: Missouri Indexing (POB 301), 1981; 489 pages, 13 by 20.5 cm, softcover, ISBN none, $14.95.

Instant Freeze-Dried Computer Programming in BASIC, Jerald R. Brown. Beaverton, OR: Dilithium Press, 1982; 193 pages, 20.7 by 27.5 cm, softcover, ISBN 0-918398-57-6, $12.95.

Introduction to Computers and Computer Science, 3rd edition, Richard C. Dorf. San Francisco, CA: Boyd & Fraser Publishing Company, 1981; 617 pages, 16.4 by 23.8 cm, hardcover, ISBN 0-87835-113-2, $18.95.

Introduction to Word Processing, Hal Glatzer. Berkeley, CA: Sybex, 1981; 205 pages, 14.5 by 22.3 cm, softcover, ISBN 0-89588-076-8, $12.95.

JCL in a System 370 Environment, Barry L. Bateman and Gerald N. Pitts. Boston, MA: CBI Publishing, 1982; 182 pages, 18.5 by 23 cm, softcover, ISBN 0-8436-1606-7, $16.95.

Knowledge-Based Systems in Artificial Intelligence, R. Davis and D. B. Lenat. New York: McGraw-Hill, 1982; 490 pages, 23.5 by 16.5 cm, hardcover, ISBN 0-07-001557-7, $39.50.

Pascal: An Introduction to Methodical Programming, 2nd edition, W. Findlay and D. A. Watt. London, England: Pittman Books Ltd., 1981; 404 pages, 14.5 by 22.5 cm, softcover, ISBN 0-273-01714-4, £5.95.

Programming in BASIC-Plus, Jasper J. Sawatzky and Shu-Jen Chen. New York: John Wiley & Sons, 1981; 273 pages, 20.8 by 27.4 cm, softcover, ISBN 0-471-07729-1, $14.95.

The UCSD Pascal Handbook, Randy Clark and Stephen Koehler. Englewood Cliffs, NJ: Prentice-Hall, 1982; 356 pages, 15 by 23 cm, hardcover, ISBN 0-13-935544-8, $19.95.

The Word Processing Handbook, Russell Allen Stultz. Englewood Cliffs, NJ: Prentice-Hall, 1982; 237 pages, 17.5 by 23.5 cm, hardcover, ISBN 0-13-963454-1, $17.95. ■

This is a list of books received at BYTE Publications during this past month. Although the list is not meant to be exhaustive, its purpose is to acquaint BYTE readers with recently published titles in computer science and related fields. We regret that we cannot review or comment on all the books we receive; instead, this list is meant to be a monthly acknowledgment of these books and the publishers who sent them.

Event Queue

April 1982

April

Courses from George Washington University, Hampton, VA; Salem, NH; Washington, DC; London, England; and Berlin, West Germany. Among the courses scheduled are "Voice Input/Output," "Microwave Systems Planning," "Writing Professional and Technical Communications," and "Computer Graphics Systems: Design and Applications." For further information, contact Continuing Engineering Education, School of Engineering and Applied Science, George Washington University, Washington, DC 20052, (800) 424-9773; in the District of Columbia, (202) 676-6106.

April

Courses in Structured Systems, various sites throughout the U.S. Courses in "Structured Systems Design," "Structured Requirements Definition," and "Management Overview of Data Structured Systems Development" are being offered by Ken Orr and Associates. For information on meeting times, places, and fees, contact Ken Orr and Associates Inc., 715 East 8th, Topeka, KS 66607, (800) 255-2459; in Kansas, (913) 233-2349.

April

Fundamentals of Data Processing for Administrative Assistants and Office Support Staff, various sites throughout the U.S. The American Management Associations (AMA) has designed this three-day course for secretaries, assistants, supervisors, and other personnel desiring to learn the fundamentals of data processing and its use in offices. Computer hardware, software, programming languages, and technology will all be covered. The team fee for AMA members is $470 per individual and $550 for nonmembers. Individual fees are $550 for AMA members and $630 for nonmembers. For a schedule of dates and locations, contact the AMA, 135 West 50th St., New York, NY 10020, (212) 586-8100. To register by phone, call (212) 246-0800.

April


Knowledge Engineering in the 1980s, Boston, MA. Expert Systems are computer programs that reason in tasks that require considerable human expertise, such as locating computer malfunctions, monitoring intensive care patients, analyzing noisy signal data, and diagnosing medical problems. This one-day executive briefing provides an introduction to the potential benefits and costs of Expert Systems. For further information, contact Dina Barr, Teknowledge, 151 University Ave., Palo Alto, CA 94301, (415) 326-6827.

April-May

Courses from Boeing Computer Services, various sites throughout the U.S. Boeing Computer Services is offering a wide variety of computer-related courses at its regional service centers. Course topics range from "Introduction to Data Processing" to "Structured Program Development in FORTRAN." For a complete schedule of times, locations, and fees, contact Boeing Computer Services Co., Education and Training Division, POB 24346, Seattle, WA 98124, (206) 575-7700.

April-May

Seminars and Conferences from Datapro Research, various sites throughout the U.S. Among the topics to be pre-



sented are "IBM's Systems Network Architecture," "Data Dictionary/Directory Systems," and "Data Processing: Fundamental Concepts." Enrollment fees are $640 for Datapro subscribers and $690 for nonsubscribers. For a complete catalog with descriptions, dates, and locations, contact Datapro Research Corp., 1805 Underwood Blvd., Delran, NJ 08075, (800) 257-9406; in New Jersey, (609) 764-0100.

April-June
Courses and Seminars from Sira Institute, various sites throughout England. Sira Institute is sponsoring seminars on a wide variety of subjects, ranging from microprocessor familiarization to design and development of microprocessor-based equipment. For details, contact Conferences & Courses Unit, Sira Institute Ltd., South Hill, Chislehurst, Kent BR7 5EH, England.

April-June
Datamation Institute Seminars on Information Management, various sites throughout the U.S. Databases and communications, systems performance, data-processing management, word processing, office automation, computer graphics, and topics of general interest are among the areas to be covered by these two-day seminars. Fees range from $495 to $595. For schedules of times and places, contact Karen Smolens, the Center for Management Research, Datamation Institute Seminar Coordination Office, 850 Boylston St., Chestnut Hill, MA 02167, (617) 738-5020.

April-June
Intensive Two-day Seminars for Professional Development, various sites throughout New England. Among the seminars to be offered by Worcester Polytechnic Institute are "Fundamentals of Data Processing," "Distributed Systems: The Architecture and Utilization of this Revolutionary Technology," and "Microprocessors: Hardware, Software, and Applications." Registration fees range from $445 for a two-day program to $990 for a 7-day executive institute. For complete details, contact Ms. Ginny Bazarian, Office of Continuing Education, Worcester Polytechnic Institute, Worcester, MA 01609, (617) 793-5517.

April-June
The Master Method of Selling Small-Business Systems, Westlake Village, CA. This one-day seminar is designed for mini- and microcomputer manufacturers and software vendors who sell small-business systems. The seminar fee is $150. For details, contact Seminar Information, M. W. L. Inc., 32038 Watergate Court, Westlake Village, CA 91361, (213) 889-2607.

April-June
National Computer Graphics Association Winter/Spring 1982 Seminar Program, various sites throughout the U.S. Topics covered include "Computer Graphics: Technology and Applications," "Successful Business Graphics," and "Applications of Computer Graphics to Transportation Problems." Seminar fees are $395 for association members and $425 for nonmembers. For complete details, contact Eloise Wenker, NCGA Seminar, 2033 M St. NW, #300, Washington, DC 20036, (202) 466-4102.

April-June
One- and Two-day Professional Development Seminars, various sites in the greater Boston area. Among the courses being offered by Boston University are "Business Writing for Results," Improving Customer Service,"

and "Assertive Management." Registration fees range from $295 for a one-day program to $445 for a two-day program. These seminars can be conducted within your company. For details, contact Ms. Joan Merrick, Center for Management Research, 850 Boylston St., Chestnut Hill, MA 02167, (617) 738-5020. For information on the in-company seminars, contact Ms. Elaine Dee at the same address.

April-June

Productivity '82, various sites throughout the U.S. and Canada. This two-day show features hands-on demonstrations of Hewlett-Packard's newest computer and application solutions ranging from personal and small-business computers to the top-of-the-line computer systems for office computing, distributed data processing, and factory automation. Sixteen different seminars are held each day, on such topics as using personal computers, choosing financial and applications software, and preparing easy-to-read graphics. Additional information can be obtained from local Hewlett-Packard sales offices or from Rudanne Clark, Hewlett-Packard, 3000 Hanover St., Palo Alto, CA 94304, (415) 857-7247.

April-July

Computerized Robots, various sites throughout the U.S. This four-day course is tailored for managers concerned with the planning and design of advanced manufacturing methods and for those who will be involved with the development and integration of high-technology robot systems. Course topics include the extent of robot automation in the U.S., Japan, and Europe; technical capabilities and limitations of robots; robot sensory mechanisms, vision, touch, proximity; and programming techniques for robot control. The course fee is $845. For details, contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

April-July

Computer Network Design and Protocols, various sites throughout the U.S. This four-day course will focus on the practical aspects of network design, interfacing, protocols, and packet switching. Among the topics to be covered are how to determine system requirements and perform design trade-offs, how to carry out network communication and control protocols, and how to evaluate available network hardware and software components. The course fee is $845. For complete details, contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

April-July

Structured Design and Programming, various sites throughout the U.S. This four-day course emphasizes the development of skills that facilitate the efficient production of reliable, well-documented, and maintainable programs, on time and within budget. Some of the topics to be addressed are structured software design methods, how to write structured programs for mini- and microcomputers, and how to improve program readability and reliability. The course fee is $795. Contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

Event Queue

April-July

Technical Classes from Zilog, Campbell, CA. Zilog is offering a series of one- to five-day technical classes at its California-based training facility. Topics range from "Microprocessors: A General Introduction" to "Zeus/System 8000 User." Contact Zilog, Training and Education Dept., 1315 Dell Ave., Campbell, CA 95008, (408) 446-4666.

April 13-14

The Sixth Annual Computer/Terminal Fair, University of Dayton Arena, Dayton, OH. This show is sponsored by the University of Dayton. The latest in word processors and mini- and microcomputers will be featured. Contact Dan Schumacher, University of Dayton, 300 College Park Ave., Dayton, OH 45469, (513) 229-3511, for details.

April 13-16

Digital Filters and Spectral Analysis, Los Angeles, CA. This course is intended for project and design engineers responsible for the implementation of advanced digital signal-processing systems. Among the topics to be addressed are digital signal-processing fundamentals, fast Fourier transform algorithms, and finite impulse and recursive filters. Computer programs that implement many of the design techniques discussed in the course are provided in the course materials. The fee is $795. For further information, contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

April 13-16

Digital Image Processing and Analysis, Boston, MA. Integrated Computer Systems' course in digital image processing is designed for engineers, scientists, technical managers, and other professionals responsible for the specification, design, implementation, or application of digital image processing systems. Among the topics to be covered are image acquisition, image-processing software and database structures, interactive two- and three-dimensional image processing and display, and real-time arrays. Some of the applications examples to be presented are quality assurance and robot vision. The course fee is $795; on-site courses can be arranged. Contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

April 14-18

Electronic Home Entertainment Show, Arlington Park Race Track Exposition Hall, Arlington Heights, IL. This show will feature audio and video equipment, video games, home computers, and citizen-band radio systems. It will run concurrently with the Fourth Annual Energy & Home Improvement Fair. Contact Expo Management Inc., Suite S2-132 Arcade, The Apparel Center, Chicago, IL 60654, (312) 329-1191.

April 15-16

Software Quality Assurance Technology, San Francisco, CA. This seminar explores how, when, how much, and with what effect programs should be tested to assure their quality. The seminar fee is $450, which includes notes, textbooks, and reference materials. Additional information is available from Ms. Gloria Kulbe, Software Research Associates, POB 2432, San Francisco, CA 94126, (415) 957-1441.

April 15-17
The 1982 Computer Showcase Expo, St. Louis, MO. The Computer Showcase is designed for small-business owners, independent professionals, and corporate managers. Admission is $7.50. For further details, contact the Interface Group, 160 Speen St., POB 927, Framingham, MA 01701, (800) 225-4620; in Massachusetts, (617) 879-4502.

April 15-18
The Second Southwest Computer Show and Office Equipment Exposition, Market Hall, Dallas Market Center, Dallas, TX. This show features mini- and microcomputers for business, education, government, industry, home, and personal use. Data- and word-processing equipment, office machines, computer peripherals, and office supplies will be displayed. General admission is $5. Contact National Computer Shows, 824 Boylston St., Chestnut Hill, MA 02167, (617) 739-2000.

April 16-17
The Twelfth Annual Virginia Computer Users Conference, Marriott Hotel, Blacksburg, VA. This conference is sponsored in cooperation with the ACM (Association for Computing Machinery). Topics include artificial intelligence, office automation, and database management. Contact Deidre Maskaleris or Wesley Braudaway, 562 McBryde Hall, Virginia Polytechnic Institute & State University, Blacksburg, VA 24061, (703) 961-6931.

April 17-18
The Seventh Annual Trenton Computer Festival (TCF-82), Trenton State College, Trenton, NJ. TCF-82 is devoted exclusively to the needs of personal-computing hobbyists and fans. At TCF-82, manufacturers, stores, and dealers will be exhibiting computer-related products and services. Forums, speakers, a giant outdoor flea market, and a banquet on Saturday night highlight this event. General admission is $5; students pay $3. A space in the flea market costs $10. For further information, contact Dr. Allen Katz, Dept. of Engineering Technology, Trenton Computer Festival, Trenton State College, Hillwood Lakes CN550, Trenton, NJ 08625, (609) 771-2666.

April 19-21
Open Systems Interconnection with X.25 and Other Related Protocols, Denver Marriott Hotel-City Center, Denver, CO. Sponsored by *Data Communications*, a McGraw-Hill publication, this seminar will present a thorough treatment of the basic OSI (Ohio Scientific) Reference Model, describing the seven-layer structure, service definitions, and emerging protocols. Detailed presentations of the X.25 packet protocol will be included. The seminar fee is $690. For further details, contact the McGraw-Hill Conference & Exposition Center, Rm. 3677, 1221 Avenue of the Americas, New York, NY 10020, (212) 997-4930.

April 19-23
The Eighth Annual Reliability Testing Institute, Ramada Inn, Tucson, AZ. This institute is presented by the University of Arizona College of Engineering and the Hughes Aircraft Company, Tucson, Arizona. It seeks to provide engineers, managers, and teachers with a working knowledge of analyzing component, equipment, and system performance and failure data to determine the distributions of their times to failure, failure rates, reliability, and confidence limits. Planning small sample size, short duration, and low-cost tests and analyzing the results will be covered as well as

other testing methods. The fee is $675. Contact Dr. Dimitri Kececioglu, Institute Director, Aerospace and Mechanical Engineering Dept., Building 16, University of Arizona, Tucson, AZ 85721, (602) 626-2495.

April 20-22
D-COM, Hynes Auditorium, Boston, MA. D-COM will bring DEC (Digital Equipment Corporation) vendors together with DEC users. For information, contact Ron Davies, D-COM Inc., 7312 Burdette Court, Bethesda, MD 20817, (301) 469-7650.

April 20-23
The Fourth International Conference on Video and Data Recording, University of Southampton, Southampton, England. This conference is designed for engineers and physicists. Papers, group sessions, and a trade exhibition will be featured. Among the topics to be addressed are "Magnetic and Other Recording Media," "Theory of Recording Processes," and "Coding, Modulation, and Signal Processing." Highlighting this conference will be a forum on digital standards. For further information, contact the Conference Registrar, Institution of Electronic and Radio Engineers, 99 Gower St., London, WC1E 6AZ, England, Tel: 01-388-3071.

April 20-23
VIO-Voice Input/Output for Computers, Boston, MA. This four-day course is designed for product development and design engineers, systems analysts, programmers, and technical managers involved in the planning, design, and implementation of voice input/output systems. The topics to be covered include voice-processing algorithms and software, evaluating VIO hardware components and systems, utilizing speech-synthesis techniques, and designing voice-recognition techniques. Participants will have the opportunity to work with devices that permit online generation of computer voice output, data entry by means of voice input, and voice input for system control. The course fee is $795; on-site courses can be arranged. For information, contact Ruth Dordick, Integrated Computer Systems, 3304 Pico Blvd., POB 5339, Santa Monica, CA 90405, (800) 421-8166; in California, (800) 352-8251.

April 21-28
Hanover Fair '82, Hanover, West Germany. The annual Hanover Fair is one of the world's largest industrial trade exhibitions. More than 330 American firms are expected to exhibit products, services, and technology at the Fair. Contact M. A. Delia, Hanover Fairs Information Center, POB 338, Whitehouse, NJ 08888, (800) 526-5978; in New Jersey, (201) 534-9044.

April 22
California Computer Show, Hyatt Hotel, Palo Alto, CA. This show is for original equipment manufacturers, knowledgeable users, distributors, and dealers. More than 60 computer manufacturers will be exhibiting mainframes, mini- and microcomputers, and peripherals. Contact Carol Reimer, Norm De Nardi Enterprises, 289 South San Antonio Rd. #204, Los Altos, CA 94022, (415) 941-8440.

April 22-25
New York Computer Show and Office Equipment Exposition, Nassau Coliseum, Uniondale, NY. For details, see April 15-18.

April 23-25
The 1982 Computer Showcase Expo, Miami, FL. For details, see April 15-17.

April 24
Computer Swap America, Santa Clara County Fair Grounds, San Jose, CA. This high-technology flea market features everything from floppy disks to home satellite-receiving stations. Admission is $3. Contact Computer Swap America, POB 52, Palo Alto, CA 94302, (415) 494-6862.

April 25-30
DP Training Managers' Workshop, Washington, DC. This workshop is intended for individuals with less than 18 months' experience in coordinating data-processing training programs. Participants will learn to establish in-house education programs that will meet management objectives and ensure a high return on their organizations' investment in training. The registration fee is $850. Contact Linda Hubacek, Deltak Inc., 1220 Kensington Rd., Oak Brook, IL 60521, (312) 920-0700.

April 27-30
Digital Filters and Spectral Analysis, Washington, DC. For details, see April 13-16.


April 27-28
The Eighth Annual National Computer Security and Privacy Symposium: Top Secret '82, Washington, DC. Sponsored by Honeywell, approximately 22 national authorities on computer security and privacy will speak on a variety of topics. Training workshops in security planning and risk analysis, disaster recovery and contingency planning, and computer fraud investigation will be held. The fee for the symposium is $525; discounts on multiple registrations are available. Contact the Security Symposium Registrar, Honeywell Inc., M/S T-99-4, POB 6000, Phoenix, AZ 85005; or call Jerome Lobel, (602) 249-5370.

April 28-May 1
The Third Annual Conference of the Educational Computing Organization of Ontario, Ontario Institute for Studies in Education (OISE), Toronto, Ontario, Canada. This conference is designed for educators at all levels. Exhibits will be featured. Contact OISE, 252 Bloor St. W, Toronto, Ontario M5S 1V6, (416) 923-6641, for additional details.

April 29-30
An Assessment and Forecast of Computer Graphics, Rye Town Hilton, Port Chester, NY. This conference will assess the present state of computer graphics and will evaluate hardware, software, systems services, and applications. The role of graphics in today's business environment will be considered and factors affecting market growth will be analyzed. Leaders in the industry will present and exchange views with attendees. For further information, contact Carol Sapchin, Frost & Sullivan Inc., 106 Fulton St., New York, NY 10038, (212) 233-1080.

May 1982

May-June
Sensors & Systems '82, various sites throughout the central and western regions of the U.S. This series of three-day conferences will cover all aspects of sensor technology from temperature sensors through to displacement, velocity, acceleration, magnetic field, and moisture. Other topics to be covered include signal conditioning, digital interfaces, and system interfaces. Contact Network Exhibitions, 785 Harriet Ave., Campbell, CA 95008, (408) 370-1661.



Event Queue

May 2-7
DP Training Managers' Workshop, Chicago, IL. For details, see April 25-30.

May 6-9
The Southern California Computer Show & Office Equipment Exposition, Los Angeles Convention Center, Los Angeles, CA. For details, see April 15-18.

May 7-9
The 1982 Computer Showcase Expo, Anaheim, CA. For details, see April 15-17.

May 10-12
Dexpo 82, Marriott Hotel, Atlanta, GA. This exposition features DEC- (Digital Equipment Corporation) compatible hardware, software, and services. Contact Expoconsul International Inc., 19 Yeger Rd., Cranbury, NJ 08512, (609) 799-1661.

May 10-13
The Annual Meeting and Technical Conference of the IEEE Industrial Power Systems Department, Marriott Hotel, Philadelphia, PA. For details, contact Dr. Paul Reece, General Electric Co., 6901 Elmwood Ave., Mail Drop 06302, Philadelphia, PA 19142, (215) 726-2800.

May 10-14
The Twentieth Annual Convention of the Association for Educational Data Systems (AEDS), Sheraton Twin Towers, Orlando, FL. This convention includes presentations on the state of the art in educational computing. Administrative and instructional computing applications will be presented, and new ways of improving educational processes will be explored. Contact AEDS, 1201 Sixteenth St. NW, Washington, DC 20036, (202) 833-4100.

May 12-14
The 1982 Carnahan Conference on Security Technology, Carnahan House Conference Center, Lexington, KY. Among the topics to be addressed at this conference are "Federal Standards for Telecommunications Privacy and Security," "Secure Voice-Bandwidth Modem," and "Multistatic, Airborn Intruder Detection Radar." The registration fee is $325, which includes buffets, a banquet, and a copy of the proceedings. Contact Susan McWain, Office of Continuing Education, College of Engineering, 223 Transportation Research Building, University of Kentucky, Lexington, KY 40506, (606) 257-3971.

May 14-15
The Second Annual Southern California Computers-in-Education Conference, University High Scool, Irvine, CA. This conference covers the application of computers in education from kindergarten through two-year college. All areas of curriculum will be covered, including reading, mathematics, science, language, and special education. Hands-on workshops and field trips are planned. Contact Craig Walker, Arrowview Intermediate School, 2299 North G St., San Bernardino, CA 92405, (714) 886-9118.

May 14-16
Applefest/Boston, Hynes Auditorium, Boston, MA. This show will feature more than 200 displays and booths of Apple-compatible products and accessories. Seminars and panel discussions will be held. Ticket prices are $6 per day or $15 for a three-day pass. Contact National Computer Shows, 824 Boylston St., Chestnut Hill, MA 02167, (617) 739-2000.

May 15-16
The North American Computer Othello Championship, Learning Resources Center, Andersen Hall, Northwestern University, Evanston, IL. This two-day tournament is sponsored by the United States Othello Association. Champions will be determined in three categories: microcomputer systems (located on site), mainframe systems (telephone hookup), and special-purpose Othello machines. For complete tournament details, write to Professor Peter W. Frey, Dept. of Psychology, Northwestern University, Evanston, IL 60201.

May 16-21
Advanced DP Training Management Workshop, Los Angeles, CA. This workshop is intended for training managers directly responsible for planning, monitoring, and evaluating data-processing training and reporting to upper-level management. The prerequisite for this workshop is completion of Deltak's Training Managers' Workshop (see April 25-30) and a minimum of one year's experience since completion, or the equivalent on-the-job experience. The registration fee is $850. Contact Linda Hubacek, Deltak Inc., 1220 Kensington Rd., Oak Brook, IL 60521, (312) 920-0700.

May 16-19
The First Annual Convention & Exposition of the Electronic Funds Transfer Association—EFT Expo, Fairmont Hotel, Dallas, TX. This convention will feature addresses on a wide range of electronic funds transfer issues, including automated teller interchange, changes in corporate network services, home financial services alternatives, and security. A special forum on the role of electronic funds transfer in the future of financial services deregulation will highlight the convention. An equipment exhibit will be featured. For complete details, contact the Electronic Funds Transfer Association, Suite 800, 1029 Vermont Ave. NW, Washington, DC 20005, (202) 783-3555.

May 18-20
Microcomputers—A New Tool for Foresters, Purdue University, West Lafayette, IN. Sponsored by Purdue University's Department of Forestry and Natural Resources and by the Inventory and Systems Analysis Working Groups of the Society of American Foresters, this conference seeks to advance the professional forester's knowledge of microcomputers and their applications in forestry. Session themes include hardware and software considerations as well as information processing and forest-inventory systems. Contact John W. Moser Jr., Dept. of Forestry and Natural Resources, Purdue University, West Lafayette, IN 47907, (317) 494-3596.

May 19-21
Computer Hong Kong 82, Regent Hotel, Hong Kong. This three-day program, which embraces the Fifth Hong Kong Computer Conference, will focus on the electronic data-processing market. For further details, contact Kallman Associates, 5 Maple Court, Ridgewood, NJ 07450, (201) 652-7070.

May 21-23
The 1982 Computer Showcase Expo, Boston, MA. For details, see April 15-17.

May 22
The Third Annual New Jersey Microcomputer Show & Flea Market, Holiday Inn (North), Newark International Airport, Newark, NJ. This event will feature more than 50 commercial exhibitors and 150

Circle 8 on inquiry card.

Event Queue

flea market sellers. Hardware, software, and accessories for all popular systems will be featured. Contact Kengore Corp., 3001 Rte. 27, Franklin Park, NJ 08823, (201) 297-2526, for additional information.

May 23-28
DP Training Managers' Workshop, Dallas, TX. For details, see April 25-30.

June 1982

June 6-11
Advanced DP Training Management Workshop, Calgary, Alberta, Canada. For details, see May 16-21.

June 6-11 and June 20-25
DP Training Managers' Workshop, Philadelphia, PA, and Chicago, IL. For details, see April 25-30.

June 13-16
The Fifteenth Annual Conference of the Association of Small Computer Users in Education, Chatham College, Pittsburgh, PA. This conference will include papers and demonstrations on the educational and administrative uses of computers. Other topics of interest are robotics, Pascal programming, computer literacy, and the use of packaged software in computer courses. For more information, contact Jan Carver, Computer Center, Chatham College, Pittsburgh, PA 15232, (412) 441-8200.

June 15-17
The 1982 IEEE MTT-S International Microwave Symposium, Hyatt Regency Hotel,

A Message to our Subscribers

From time to time we make the BYTE subscriber list available to other companies who wish to send our subscribers promotional material about their products. We take great care to screen these companies, choosing only those who are reputable, and whose products, services, or information we feel would be of interest to you. Direct mail is an efficient medium for presenting the latest personal computer goods and services to our subscribers.

Many BYTE subscribers appreciate this controlled use of our mailing list, and look forward to finding information of interest to them in the mail. Used are our subscribers' names and addresses only (no other information we may have is ever given).

While we believe the distribution of this information is of benefit to our subscribers, we firmly respect the wishes of any subscriber who does not want to receive such promotional literature. Should you wish to restrict the use of your name, simply send your request to BYTE Publications Inc, Attn: Circulation Department, 70 Main St, Peterborough NH 03458. Thank you.

INCREDIBLE? BELIEVE IT! IT!

Washington Computer Services

an affiliate of WASHINGTON ELECTRIC COMPANY INCORPORATED est. 1912

CUSTOM COMPUTER ROOM WIRING SINCE 1960

97 Spring Street, New York, New York 10012

TO ORDER: CALL OUR TOLL-FREE NUMBER: (800) 221-5416 In N.Y. State and for technical information: (212) 226-2121

HOURS: 9 AM-5:30 PM (EST) Monday-Friday TELEX: 12-5606 CABLE: WASHCOMP NYK

PRINTERS



150 cps bidirectional - 9x9 dot matrix, quietized case, 136 col, vertical form control and many other functions *NOW* $950

We feel this printer offers the best price/performance ratio available.

RS-232 serial to 19,200 baud x-on, x-off add $25

Teletype 40, 300 LPM-typewriter quality, RS-232 interface. This quality printer is available in many configurations including forms access, quietized case, etc. from **Only $3200**

Teletype 43	from $995
Teletype AP-200, 340 cps dot matrix (similar to Data Prod. M-200)	$2799
NEC Spinwriter-55 cps, bidirectional, letter quality	
R.O. 7710 $2560 KSR 7720	$2799
DIABLO 630-40 cps, bidirectional, daisy wheel, plot/graph	$2349
QUME Sprint 9/45 cps, daisy wheel	$2228
C. ITOH Starwriter, 25 cps, daisy wheel, parallel	$1500
C. ITOH Starwriter, 45 cps, daisy wheel, serial	$1680
EPSON MX-80, 100, 80 cps, 9x9 dot matrix	$CALL
ANADEX 9500/9501, up to 200 cps, high resolution dot	$1325
OKIDATA Microline 80, 80 cps, 9x7 dot matrix	$399
Microline 82A, bidirectional, friction/pin feed	$525
Microline 83A, bidirectional, 120 cps, uses 15" paper	$799
TI—810, 150 cps, Basic	$1449
Package-Compressed print, vertical form control	$1630
MANNESMANN MT 1705 200 cps, 7x9, 132 col	$CALL
TALLY **MT 1805** 200 cps, 7x9 + NLQ 40x18 matrix	$CALL
CENTRONICS	$CALL
739 100 cps, nx9 dot matrix, **Full Graphics**	$567
DEC LA-34	$1085
IDS PRISM, 132 col., color	$1785

S-100 SPECIALTIES

DUAL 68000 16 bit multi-user UNIX V.7	$CALL
SEATTLE COMPUTER 8086 16 bit, 128K RAM, Syst. #2	$3499

Systems Group Call us for best prices on these high quality 2nd generation boards and systems.

California Computer Systems These high quality, reliable products have made CCS defacto industry standard for S-100 products

Assembled and tested:		list	only
2200	H.D. Mainframe, 20a. P.S., 12 slot MB	$434	$359
2065C	64K dynamic RAM/Bank Select	$720	$580
2810A	Z-80 CPU, serial port, ROM monitor	$310	$259
2422A	Floppy Cont, CP/M 2.2, ROM monitor	$425	$345

IMS INTERNATIONAL **8000 SX**, multi-user, multi-processor, turbo DOS CPM 2.2. FULL 2 YEAR WARRANTY! $CALL

GODBOUT ELECTRONICS We offer generous discounts on the Compupro line of fast, quality 8 and 16 bit boards

NorthStar **ADVANTAGE & HORIZON** $CALL

NEC Low prices on PC-8000 series $CALL

Similar savings on the full lines of **CCS, SSM, NNC, MORROW, DELTA, NORTHSTAR, ITHACA INTERSYSTEMS, GODBOUT, NEC, TELEVIDEO, IMS ZENITH, ADDS, DEC, DATA GEN., ATARI, DYNABYTE, TECMAR, DUAL**

8" DISK DRIVE SALE

8" SHUGART SA801R	$450	**8" SHUGART SA 851R**	$669	2 for $1289
QUME DATATRACK 8			$589	2 for $1110

VISTA Industrial grade enclosure for 2 drives with P.S.	$420
MORROW Discus 2D + CP/M®, **MICROSOFT BASIC, CONT.**	$950
Discus 2 + 2 + CP/M®, **MICROSOFT BASIC, CONT.**	$1195
Enclosure, power supply for 2 8" drives A & T	$350

HARD DISK SPECIALS

	List	only
CORVUS 10MB and controller	$5358	$CALL
20MB and controller	$6450	$CALL
Constellation Network Multiplexer and Mirror Video Tape Disk Backup		
MORROW 26MB + controller + CP/M 2.2®, M basic	$4495	$3821
CAMEO **controller**, CDC Hawk Drive (5 fix, 5 rem)	$7995	$6795
controller, Western Dynex (5 fix, 5 rem)	$5995	$5099

XCOMP Winchester 5¼ drives complete with case, cable, software, S-100 controller. Adapter avail. for use with any Z-80 system. Cartridge drive controllers avail.

				List
5MB	*APPLE*		*Z-89*	$2898
10MB	*XEROX*	OEM discounts available!	*R.S. MOD. II*	$3398
	ALTOS		*S-100*	

ADES PRIAM 8" and 14" Winchester/tape subsystems avail.

ACCOUNTING PLUS			$CALL
WORDSTAR	$300	**DBASE II**	$525
MBASIC 80	$235	**SUPERCALC**	$221

FULLY CONFIGURED BUSINESS SYSTEMS

The following are some examples of the fully assembled and tested business and scientific computer systems which we offer. All include 64K bytes RAM, Z-80A, 4mh CPU. We offer a full line of quality, tested software.

Inter-Systems fine computers	$CALL
Delta S-4500 10 User, Multi-Processor, 40 MB hard 17 MB tape	$CALL
CC 2210A w/floppy controller, 1 serial port	$1849
CCS 300-1A w/1.2 MB floppy drives, 2 serial, 2 parallel ports	$4849
CCS 400-1A w/10 MB hard disc, 2 serial, 2 parallel ports	$6999
NNC 80W w/5MB floppy, 8.4 MB hard disc, (OASIS optional)	$6693
ALTOS single and multi-user systems	$CALL
MORROW DESIGNS **Decision 1**, CP/M Microsoft Basic, UNIX	$CALL

XEROX. 820 Desktop computer-64K, 2 floppys. (CP/M avail.) List **$2995** **$CALL**

We offer multi-user *networks* by **DELTA PRODUCTS, DISCOVERY, TELEVIDEO, MUSYS, IMS, DIGITAL MICROSYSTEMS**

TERMINALS

PMMI MODEM	$359
AMPEX DIALOGUE 30, 80, 81	$CALL
TELEVIDEO 910 C (multi-terminal)	$610
925C	$795
950C	$950
SOROC IQ 120	$729
HAZELTINE ESPRIT	$669
DEC VT-100	$1575

Similar savings for our **HAZELTINE** and **LEAR SIEGLER** lines

LOOK HERE!

AMPEX Dialogue 80™



Call us for **ALL** your softwear needs

Systems Houses, Educational Institutions, & Government Agencies Given Special Consideration

ALL OF OUR PERIPHERALS CAN BE CONFIGURED FOR RADIO SHACK® MODEL II

DEALER and INTERNATIONAL INQUIRIES WELCOME

For fast delivery, send certified check, money order or call to arrange direct bank wire transfer. Personal or company checks require two to three weeks to clear. All prices are mail order only. Prices subject to change without notice; call for latest prices. Prices include 3% cash discount. N.Y. residents add sales tax. Qantex is a trademark of North Atlantic Industries, Inc. Radio Shack® is a trademark of the Tandy Corp. CP/M® is a trademark of Digital Research. All sales subject to our standard sale conditions (available on request).

VISA MasterCard

Circle 430 on Inquiry card.

Dallas, TX. The theme of this symposium is "Thirty Years of Microwaves." Papers and tutorials on a wide range of topics, including computer-aided design and measurement techniques, microwave field and network theory, as well as satellite communications/microwave systems, will be presented. Contact J. R. Griffin, Texas Instruments Inc., Mail Stop 3432, POB 405, Lewisville, TX 75067, (214) 462-5693.

June 15-17
The Office Automation Show/Conference, Barbican Centre, London, England. For details on this show and conference, contact Clapp & Poliak International, 7315 Wisconsin Ave., Washington, DC 20014, (301) 657-3090.

June 16-18
The Twentieth Annual Meeting of the Association for Computational Linguistics, University of Toronto, Toronto, Ontario, Canada. This meeting features papers on syntax, computational semantics, discourse analysis and speech acts, machine translation, as well as the mathematical and theoretical foundations of computational linguistics. For additional information, contact Don Walker, Artificial Intelligence Center, SRI International, Menlo Park, CA 94025, (415) 859-3071.

June 28-30
National Educational Computing Conference (NECC-82), Radisson-Muehlebach Hotel, Kansas City, MO. This conference features papers, sessions, panel discussions, and exhibits of educational computing products. Among the topics to be addressed are "Computer Use in the Physical Sciences," "Computer Education for Teachers," and "Computer Science, Engineering, and Information Systems Education." For more information, contact E. Michael Staman, NECC-82 General Chairman, Computer Services, 305 Jesse Hall, University of Missouri-Columbia, Columbia, MO 65211. ■

In order to gain optimal coverage of your organization's computer conferences, seminars, workshops, courses, etc, notice should reach our office at least three months in advance of the date of the event. Entries should be sent to: Event Queue, BYTE Publications, POB 372, Hancock NH 03449. Each month we publish the current contents of the queue for the month of the cover date and the two following calendar months. Thus a given event may appear as many as three times in this section if it is sent to us far enough in advance.

FLOPPY DISK DRIVES

SPECIAL!!!!!!!! QUME DATATRAK 8

Virtually the industry standard. High quality/reliability. Full featured, double sided, double density.

Tandon TM 848 .... $545

$525 quantity 1, $499 quantity 2 up.

TANDON DOUBLE SIDED, DOUBLE DENSITY MINIS

TM100-2 .... 48 TPI (500 KBYTES) $325
Compatible with Northstar, Cromemco, TRS-80

TM100-4 .... 96 TPI (1000 KBYTES) $425
Compatible with Zenith, Heath, etc.

TANDON 5¼" HARD DISKS

TM 602 (5MB) $1195
TM 603 (10MB) $1295

CPU

CCS 2810 .... $ 275
Godbout Z-80A .... $ 275
Godbout 8085A .... $ 295

MEMORY

CCS 2065 64K dynamic .... $ 595
CCS 2116 32K static .... $ 625
Godbout RAM 17 64K .... $ 675

I/O

CCS 2710 4 SIO .... $ 325
Godbout Interfacer 1 .... $ 225
Godbout Interfacer 2 .... $ 225

CONTROLLERS



Tarbell single density kit $195
Tarbell single density A & T $310
Tarbell double density A & T $425
CCS 2422 w/CPM 2.2 .... $350
Godbout Disk 1 .... $450
MDA MXV-21 LSI-11 controller (RX-01, RX-02 compatible) $1050

MISCELLANEOUS

2 Disk drive enclosure ..... $ 95
(fits Siemens, Shugart, Qume)
CP-206 power supply $110
(powers two floppies)

Cable Kits 2 drives ...... $ 35
3 drives ...... $ 40
4 drives ...... $ 45
Diskettes ss $39/10 – ds $59/10

Mini-Enclosure with power supply
1 drive ...... $ 85
2 drives...... $120


NEW !!!!
Qume Sprint 9
DAISY WHEEL PRINTER .. $2395
45 CPS, RO. Available in KSR version.
Call for further particulars.
Ribbons: $125/case
Bidirectional tractor feed $225

NEW !!!!
ABM 85 Video Terminal .. $ 895
– Detachable keyboard
– Televideo 920, ADM 3A compatible
– High resolution green phosphor (23 MHZ)
– Extra multi-bus or S-100 slot for stand-alone capability


Electrolabs
POB 1608, Palo Alto, CA 94302 (415) 965-7040

Terms of sale: cash or checks, MC/VISA. Min. order $25. CA residents add 6% tax. Prices subject to change without notice. All goods subject to prior sale.


SUNNY LOW LOW COST
POWER SUPPLIES
FOR S-100, FLOPPY DISKS.



KIT 1, 2 & 3 For S–100



R3 For Three 8" or 5¼" Disk Drives



S3 2 in 1 Unit for S–100 and two 8" or 5¼" Disk Drives. It fits most Disk System Mainframes.

S-100 POWER SUPPLY KITS (OPEN FRAME WITH BASE PLATE, 3 HRS. ASSY. TIME)

ITEM	USED FOR	@ + 8 Vdc	@ – 9 Vdc	@ + 16 Vdc	@ – 16 Vdc	@ + 28 Vdc	SIZE W × D × H	PRICE
KIT 1	15 CARDS SOURCE	15A	______	2.5A	2.5A	______	12" × 5" × 4⅞"	54.95
KIT 2	SYSTEM SOURCE	25A	______	3A	3A	______	12" × 5" × 4⅞"	61.95
KIT 3	DISK SYSTEM	15A	1A	2A	2A	4A	14" × 6" × 4⅞"	69.95

DISK DRIVE POWER SUPPLY "R3" REGULATED, OPEN FRAME, ASSY. & TESTED **69.95**
SPECS: + 5V @ 5A OVP, –5V @ 1A + 24V@ 5A, SHORTS PROTECT. 2 SIZES AVAIL., 1.) 9" (W) × 6¼" (D) × 4⅜" (H), 2) 9" (W) × 4⅞" (D) × 5¼" (H)
OPTION: 1.) REPLACE + 24V BY + 12V, 2.) FOR SIZE 1 ONLY, ADD ± 12V @ 1A, AT AN ADDITIONAL $12.00.
IDEAL FOR THREE 8" or 5¼ FLOPPY DISK DRIVES, SUCH AS SHUGART 801/851, SIEMANS FDD 100-8/200–8 OR 100–5 ETC

DISK SYSTEM PWR SUPPLY "S3" OPEN FRAME, ASSY. & TESTED. COMPACT SIZE: 10"(W) × 6" (D) × 5" (H) **99.95**
REGULATED OUTPUTS FOR DISK DRIVES: +5V @ 4A, –5V @ 1A, +24V @ 4A (OR + 12V @ 4A), SHORTS PROTECT
UNREGULATED OUTPUTS FOR S–100: +8V @ 14A, ± 16V @ 3A. (OPTION: ADD OVP FOR +5V, ADD $5.00)
A COMPLETE UNIT FOR DISK SYSTEM WITH THE MAINFRAME CONTAINING 12 SLOTS & TWO 8" or 5¼" DISK DRIVES

POWER TRANSFORMERS (WITH MOUNTING BRACKETS)

ITEM	PRIMARY	SECONDARY #1	SECONDARY #2	SECONDARY #3	SIZE W × D × H	PRICE
T_1	110/120	2 × 8 Vac, 15A	28 Vac, CT, 2.5A	______	3¾" × 3⅝" × 3⅛"	22.95
T_2	110/120	2 × 8 Vac, 25A	28 Vac, CT, 3.5A	______	3¾" × 4⅜" × 3⅛"	28.95
T_3	110/120	2 × 8 Vac, 15A	28 Vac, CT, 2.5A	48 Vac, CT, 2A	3¾" × 4⅜" × 3⅛"	30.95
T_4	110/120	2 × 8 Vac, 6A	28 Vac, CT, 1.5A	48 Vac, CT, 3A	3¾" × 3⅝" × 3⅛"	23.95
T_5	110/120	2 × 8 Vac, 6A	28 Vac, CT, 2A	______	3" × 3" × 2½"	15.95

SHIPPING For each power supply $5.50 in Calif., $8.00 in other states, $18.00 in Canada. For each Transformer $5.00 in all States, $12.00 in Canada. Calif. Residents add 6% Sales Tax.



MAILING ADDRESS:
P.O. BOX 4296
TORRANCE, CA 90510
TELEX: 830-5010
ANSWER BACK FOR TELEX SUNYCO TRUC

SUNNY INTERNATIONAL
(TRANSFORMERS MANUFACTURER)
(213) 328-2425 MON-SAT 9-6


SHIPPING ADDRESS:
22129½ S. VERMONT AVE
TORRANCE, CA 90502



APPLE, TRS80, TI, IBM, PET...

TRY! OUR $99 SELECTOR SWITCH

Available for RS232, IEEE 488, BNC...



Our $99(– S8AB) switch will save you money and aggravation. Share your printer, modem etc. The selection is made by turning the front panel knob. Eliminate the aggravation of connecting and disconnecting cables. Our –S8AB two position unit can connect one printer to two CPU's. It can also be used to connect one CPU to either a printer or a modem. We also have 3, 4, 5, & 6 position units. In fact we have about 30 models to satisfy all the common applications. Our products are the most popular units on the market. We sold over 10,000 units. We offer a **5 YEAR WARRANTY. OUR UNITS HAVE AN EXCLUSIVE MONITORING OPTION.** We have distributors and dealers in most cities. If your favorite computer dealer does not carry a Giltronix Switch please have him call us. We offer the greatest discounts as well as evaluation samples. Call us for a FREE colorful catalog.



GILTRONIX, INC
UNIVERSAL INTERFACE PRODUCTS

970 San Antonio Ave., Palo Alto, CA 94306
DEALER INQUIRIES INVITED!
Call (415) 493-1300

Circle 187 on inquiry card.

TRS 80 USER

GILTRONIX SOLVED YOUR SWITCHING PROBLEM





A. OUR $169.00 "GTRS-2AB-AP2" SWITCHING UNIT, WILL CONNECT THE OUTPUT OF YOUR TRS 80 TO TWO (2) DEVICES (LINE PRINTERS, DAISY WHEEL PRINTERS ETC). TO SELECT DEVICE 1 OR 2, SIMPLY TURN THE KNOB TO THE DESIRED POSITION. NO MORE MESSING **WITH CABLES! EASY TO INSTALL EASY TO OPERATE! 5 YEAR WARRANTY!**

B. SAME UNIT FOR THREE (3) DEVICES, REQUEST PART NO. GTRS-2ABC-AP4 ($199.00).

C. TO SHARE ONE PRINTER BETWEEN TWO (2) TRS 80's, REQUEST PART NO. GTRS-2AB-AP1 ($169.00).

D. TO SHARE ONE PRINTER BETWEEN THREE (3) TRS 80's, REQUEST PART NO. GTRS-2ABC-AP3 ($199.00).

ALL FOUR UNITS ARE AVAILABLE FROM STOCK.

OTHER SWITCHING PRODUCTS ARE ALSO AVAILABLE. WE HAVE OVER 30 MODELS OF MANUAL, REMOTE AND AUTOMATIC UNITS. SEE NEXT COLUMN FOR ADDITIONAL INFORMATION.

CONTACT GILTRONIX OR OUR LOCAL DISTRIBUTORS.


DEALER INQUIRIES INVITED!
Call (415) 493-1300

GILTRONIX, INC
UNIVERSAL INTERFACE PRODUCTS

450 San Antonio Ave., Palo Alto, CA 94306

Circle 188 on inquiry card.

T-BAR* COMPATIBLE SWITCHING UNITS



GILTRONIX is now offering a line of T-BAR* compatible switching units. These units called GDnS24 are dual switching modules that mount in a T-BAR 19" RACK (5700 series). If you need to expand your present system you can add GILTRONIX GDn units which offer several distinct advantages.

1. P.C. board technology instead of individual wiring.
2. All connectors are mounted on a rear panal in a vertical position instead of a 45° angle.
3. Optional 3rd. position (OFF) available.
4. Totally sealed P.C. board mountable swich.
5. Price per channel $139.00
6. Optional monitoring LED's. For TxDATA and RxDATA.

GILTRONIX is also offering it's own version of the 19" RACK. The GILTRONIX version is 60% more efficient since it offers up to 16 channels (eight dual channels) instead of ten channels (max. capacity for T-BAR RACK)

See next column for additional information.

GD2S24 Dual Pack — $275.00 Quantity Discounts Available.
(*T-BAR is a registered trademark of T-Bar Corp.)

DEALER INQUIRIES INVITED!
Call (415) 493-1300

GILTRONIX, INC
UNIVERSAL INTERFACE PRODUCTS

970 San Antonio Ave., Palo Alto, CA 94306

Circle 189 on inquiry card.

SOFTWARE AUTHORS



Cash in on your creative energies, join InfoSoft Computer Systems' SOFTWARE DEVELOPMENT PROGRAM. Get all of your R&D hardware at our distributior cost plus

20% Royalty!

We give you personalized service, offer a non-exclusive marketing agreement, plus other specialized services. We seek: high level language compilers, cross-assemblers, utilities, DMBS, new OS, educ. and business applications, and any other marketable program. We offer full development and documentation. Don't hesitate, contact us immediately.

Michael L. Dean, V.P. R&D
InfoSoft Computer Systems

2699 Clayton Rd.
Concord, CA 94519
(415) 680-0202

Single Source Solution

Circle 205 on Inquiry card.

RS-232 PROBLEMS?

We have a large assortment of problem solvers at **B & B ELECTRONICS**, send for our new Catalog.

RS-232 TESTER. Seven LED'S display the status of RS-232 lines: **$39.95**

RS-232 DATA TAP. Lets you tap data off a RS-232 line: **$34.95**

RS-232 NULL MODEM. Replaces a set of modems for testing: **$19.95**

RS-232 GENDER REVERSERS. Convert a male connector to female or a female to male. Either one: **$19.95**
Set of both Reversers: **$34.95**

B & B ELECTRONICS
BOX 475 / MENDOTA, IL 61342
IL Residents add 5% Tax

Circle 178 on inquiry card.



special OF THE MONTH

HP-85's	$2540.00
HP-83's	$1450.00
HP-9895 Dual 8" Drives	$5300.00
HP-8292 Dual 5" Drives	$1960.00
HP-7225B Plotter	$1720.00
LOBO Disc Drives	$ 395.00
IDS 445G Printers	$ 699.00
NEC Spinwriters with Tractors	$2560.00
IDS 460G Printers	$1099.00
IDS 560G Printers	$1330.00
C ITOH Starwriter 25's	$1300.00
CCS 300 Dual 8" Drive computer with 64K RAM, OASIS, CP/M 2.4MB Disc memory, 2 serial ports, 1 parallel port and a Televideo 910 CRT	Call for price
CDC Lark Subsystems	Call for price

219/836-5350


Meade's DATA SYSTEMS
"THE COMPLETE SYSTEMS AND SUPPORT TEAM"
MARKET SQUARE SHOPPING CENTER, RIDGE RD. & CALUMET AVE., MUNSTER, IN 46321

Circle 250 on inquiry card.



Verbatim flexible disks

Call Free **(800) 235-4137** for prices and information. Dealer inquiries invited. C.O.D. and charge cards accepted.



VISA

PACIFIC EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA 93401. In Cal. call (800) 592-5935 or (805) 543-1037.

Circle 319 on inquiry card

LABELS



2.99 perM

15/16"x3½" 1 up - pin feed
white pressure sensitive

PRICE INCLUDES SHIPPING
Packed 5M per box - Min. order 1 box - $14.95
Check with order - Mass Residents add 5% Sales Tax

CHECK-MATE™
P.O. Box 103, Randolph, MA 02368
Telephone: 617-963-7694

Circle 81 on inquiry card.



NEW! for the '89 from

MAGNOLIA MICROSYSTEMS

DOUBLE DENSITY DISK CONTROLLER


for both 5¼" & 8" drives
only **$595** complete
including CP/M™ 2.2

MAGNOLIA MICROSYSTEMS, INC.
2812 Thorndyke W., Seattle 98199
(206) 285-7266 (800) 426-2841

CP/M is a trademark of Digital Research.

Circle 246 on inquiry card.

64K STATIC RAM BOARD FOR S-100 BUS
$470



FEATURES

- Conforms to IEEE 696 standard.
- 8 or 16 bit data transfers.
- 24 bit addressing.
- Bank select in 32K-32K or 48K-16K.
- Banks selectable/deselectable on DMA.
- Responds to phantom pin 67 or 16.
- 2K x 8 static rams with 2716 pin out.
- Power consumption is typically 600 ma.
- Banks on or off on power up.
- Bank addressable to any of 256 possible ports.
- 8MHz with 150ns parts standard, faster speeds available on request.
- Available partially loaded as a 32K board.
- Multiple bank residence.

OMNIRAM

OMNIRAM INTRODUCTION:

The Fulcrum Computer Products OMNIRAM for the IEEE 696 (S100) bus provides 64 kilobytes of fast static random access memory. Provision is made for 8 or 16 bit transfers, extended 24 bit addressing, and for control via the bus phantom line. In addition, a number of features are included to make the OMNIRAM compatible with systems designed before the IEEE 696 standard was developed. These include bank selection and provision for operation with IMSAI-type front panels. When the bank select option is activated, the board is divided into two parts which can reside in separate banks. The division of the board may be into two 32K sections or into one 16K section and one 48K section. Provision is made for DMA overide of bank select if needed. The board is also compatible with IEEE 696 or IMSAI-type extended addressing.



Omniram 64	64K	32K
With 200ns. Rams	.... $470	.... $325
With 150ns. Rams	.... $490	.... $340
With 120ns. Rams	.... $550	.... $395

Distributed by:
WW COMPONENT SUPPLY INC. 1771 JUNCTION AVENUE • SAN JOSE, CA 95112 • (408) 295-7171

Circle 441 on inquiry card.

FULL LINE ALL PARTS & COMPUTER PRODUCTS

Quest ELECTRONICS

P.O. Box 4430X
Santa Clara, CA 95054
Will calls: 2322 Walsh Ave.
(408) 988-1640

Same day shipment. First line parts only. Factory tested. Guaranteed money back. Quality IC's and other components at factory prices.

INTEGRATED CIRCUITS

Phone orders only (800) 538-8196

7400TTL
7400N .19
7402N .19
7404N .22
7409N .19
7410N .19
7414N .55
7420N .19
7430N .19
7442N .49
7445N .69
7447N .69
7448N .69
7474N .35
7475N .49
7485N .65
7489N 1.70
7490N .35
7495N .55
74100N 1.00
74107N .30
74123N .55
74125N .45
74145N .60
74150N 1.20
74151N .65
74154N 1.25
74157N .55
74161N .70
74162N .85
74163N .85
74174N .89
74175N .85
74190N 1.15
74192N .79
74193N .79
74221N 1.25
74298N .85
74365N .65
74366N .65
74367N .65

74LS00 TTL
74LS00N .25
74LS02N .25
74LS04N .25
74LS05N .25
74LS08N .35
74LS10N .25
74LS13N .45
74LS14N .99
74LS20N .25
74LS22N .25
74LS28N .35
74LS30N .25
74LS33N .55
74LS38N .35
74LS74N .45
74LS75N .50
74LS90N .60
74LS93N .65
74LS95N .85
74LS107N .40
74LS112N .45
74LS113N .45
74LS132N .75
74LS136N .49
74LS151N .75
74LS155N .79
74LS157N .75
74LS162N .95
74LS163N .95
74LS174N .95
74LS190N 1.00
74LS221N 1.19
74LS258N .69
74LS367N .69

LINEAR
CA3045 .90
CA3046 1.10
CA3081 1.80
CA3082 1.90
CA3089 3.40
LM301AN/AH .34
LM305H .87
LM307N .35
LM308N .98
LM309K 1.25
LM311H/N .64
LM317T 1.65
LM317K 3.75
LM318 1.49
LM320K-5 1.35
LM320K-12 1.35
LM320K-15 1.35
LM320T-5 .85
LM320T-8 .85
LM320T-12 .85
LM320T-15 .85
LM323K-5 4.95
LM324N .59
LM339N .99
LM340K-5 1.35
LM340K-8 1.35
LM340K-12 1.35
LM340K-15 1.35
LM340K-24 1.35
LM340T-5 .75
LM340T-8 .75
LM340T-12 .75
LM340T-15 .75
LM340T-18 .75
LM340T-24 .75
LM350 5.50
LM377 2.29
LM380N 1.00
LM381 1.60
LM382 1.60
LM709H .59
LM723H/N .49
LM733N .85
LM741CH .35
LM741N .35
LM747H/N .75
LM748N .50
LM1303N 1.75
LM1304 1.10
LM1305 1.27
LM1307 1.10
LM1310 2.75
LM1458 .55
LM1812 8.25
LM1889 2.49
LM2111 1.75
LM2902 2.25
LM3900N .59
LM3905 1.25
LM3909N .95
MC1458V .55
NE550N 1.30
NE555V .39
NE556A .65
NE565A 1.00
NE566V 1.50
NE567V 1.00
NE5708 4.75
78L05 .60
78L08 .60
78M05 .85
75108 1.49
75491CN .50
75492CN .55
75494CN .89

A to D CONVERTER
80388 4.50
8700CJ 13.95
8701CN 22.00
8750CJ 13.95
LD130 9.95
9400CJV/F 7.40
ICL7103 9.50
ICL7107 14.25

CMOS
CD4000 .25
CD4001 .35
CD4002 .35
CD4006 .95
CD4007 .25
CD4008 .95
CD4009 .45
CD4010 .45
CD4011 .35
CD4012 .25
CD4013 .45
CD4014 .95
CD4015 .95
CD4016 .45
CD4017 1.05
CD4018 .94
CD4019 .45
CD4020 .95
CD4021 .95
CD4022 1.10
CD4023 .28
CD4024 .75
CD4025 .23
CD4026 1.65
CD4027 .65
CD4028 .80
CD4029 .95
CD4030 .45
CD4035 .85
CD4040 .95
CD4042 .75
CD4043 .85
CD4044 .85
CD4046 .95
CD4049 .45
CD4050 .55
CD4051 .95
CD4060 1.42
CD4066 .71
CD4068 .39
CD4069 .35
CD4070 .35
CD4071 .30
CD4072 .30
CD4073 .35
CD4075 .30
CD4076 .95
CD4078 .30
CD4081 .30
CD4082 .30
CD4116 .47
CD4490 5.50
CD4507 .99
CD4508 1.95
CD4510 .95
CD4511 .94
CD4515 2.25
CD4516 1.10
CD4518 1.25
CD4520 1.02
CD4527 1.51
CD4528 1.25
CD4553 3.50
CD4566 2.45
CD4583 2.35
CD4585 .95
CD40192 3.00
74C00 .35
74C04 .35
74C10 .35
74C14 .75
74C20 .35
74C30 .35
74C48 1.95
74C74 .85
74C76 .80
74C90 1.25
74C93 1.25
74C154 3.25
74C160 1.69
74C175 1.19
74C192 1.65
74C221 1.90
74C905 6.00
74C906 .75
74C914 1.95
74C922 5.00
74C923 5.50
74C925 6.75
74C926 6.95
74C927 6.95

INTERFACE
8095 .65
8096 .65
8097 .65
8098 .65
8T09 1.25
8T10 1.75
8T13 1.40
8T20 4.95
8T23 1.75
8T24 1.75
8T25 3.20
8T26 1.69
8T28 1.95
8T97 .99
8T98 .99

MOS/MEMORY RAM
2101-1 1.95
2102-1 .65
2102AL-4 1.25
2102AN-2L 1.65
2104A-4 4.95
2107B-4 3.75
2111-1 2.99
2112-2 2.99
2114 2.24
2114L 300ns 2.50
2114L 450ns 2.37
4116 200ns 2.50
8/4116 200ns 15.40
MM5280 3.00
MM5321 9.95
MM5330 5.94
P5101L 8.95
4200A 11.50
9368 3.50
410D 10.00
416 2.50
TMM2016 16.95
HM6116 16.50

CLOCKS
MM5311 4.95
MM5312 3.90
MM5314 3.90
MM5369 1.95
MM5841 14.45
MM5865 7.95
CT7010 8.95
CT7015 8.95
MM5375AA/N 3.90
MM5375AG/N 4.90
7205 16.50
7207 7.50
7208 15.95
7209 4.95

MICROPROCESSOR
6502 6.95
6502A 9.50
6504 6.95
6522 8.75
6530 9.50
6532 14.95
6551 11.85
6800 5.70
6802 11.95
6820 4.95
6850 3.50
8080A 3.95
8085A 8.50
Z80A 6.00
Z80B 18.95
Z80P10 6.50
Z80A P10 5.95
Z80 CTC 5.95
Z80ACTC 8.65
Z80 DART 15.25
Z80A DART 18.75
Z80DMA 17.50
Z80A DMA 27.50
Z80 S10/0 23.95
Z80A S10/0 28.95
Z80 S10/1 15.00
Z80A S10/1 23.90
Z80 S10/2 23.95
Z80AS10/2 28.95
Z80BCTC 17.95
Z80B P10 17.95
8212 1.85
8214 3.75
8216 1.80
8224 2.50
8228 4.95
8251 4.75
8253 8.95
8255 4.75
8257 8.75
8259 6.90
1802CE plas. 13.95
1802E plas. 17.95
1861P 5.95

UART/FIFO
AY5-1013 3.95
AY5-1014 6.95
3341 6.95

PROM
1702A 4.50
2532 17.50
2708 2.95
2716T1 8.50
2716 5 Volt 5.50
8/2716 5 Volt 39.00
2732 16.50
2758 7.49
8741A 39.95
8748 39.95
8748-8 34.95
8755A 49.95
N82S23 2.95
N82S123 3.95
N82S126 5.75
N82S129 4.75
N82S131 4.95
N82S136 8.75
N82S137 8.75
DM8577 2.90
8223 3.50

CONNECTORS
30 pin edge 2.50
44 pin edge 2.75
86 pin edge 4.00
100 pin edge 3.95
100 pin edge w/w 4.95

IC SOCKETS

Solder Tin Low Profile

PIN	1UP	PIN	1UP
8	.13	22	.30
14	.14	24	.30
16	.16	28	.40
18	.20	36	.58
20	.29	40	.49

WIRE WRAP LEVEL3

PIN		PIN	
14	.55	24	.93
16	.57	28	1.00
18	.67	40	1.59

2 level 14 pin w/w .20

CRYSTALS
1 MHz 4.50
2 MHz 3.95
4 MHz 3.95
5 MHz 3.95
10 MHz 3.95
18 MHz 3.90
20 MHz 3.90
32 MHz 3.90
32768 Hz 4.00
1.8432 MHz 4.50
3.5795 MHz 1.20
2.0100 MHz 1.95
2.097152 MHz 3.95
2.4576 MHz 3.95
3.2768 MHz 3.95
5.0688 MHz 3.95
5.185 MHz 3.95
5.7143 MHz 3.95
6.5536 MHz 3.95
14.31818 MHz 3.95
18.432 MHz 3.95
22.1184 MHz 3.95

KEYBOARD ENCODERS
AY5-2376 11.95
AY5-3600PRO 17.95
74C922 5.49
74C923 5.50
HD0165-5 7.95

D Connectors RS232
DB25P 2.95
DB25S 3.50
Cover 1.25

DE9S 1.95
DA15P 2.10
DA15S 3.10
Complete Set 9.50

Stopwatch Kit 26.95
Auto Clock Kit 17.95
Digital Clock Kit 19.75

RESISTORS ¼ watt 5%
10 per type .05
100 per type .015
1000 per type .012
5000 per type .0085
350 piece pack, 5 per type 8.95
½ watt 5% per type .05

1981 IC MASTER CLOSEOUT $59.95

DIP SWITCHES
4-position .85
5-position .90
6-position .90
7-position .95
8-position .95

KEYBOARDS
56 key ASCII keyboard kit $74.95
Fully assembled 84.50
Enclosure Plastic 19.95
Metal Enclosure 69.95

LEDS
Red T018 .15
Green, Yellow T018 .20
Jumbo Red .25
Green, Orange, Yellow Jumbo .25
Clipilte LED Mounting Clips 4/.80
(spec: red, amber, green, yellow, clear)

CONTINENTAL SPECIALTIES in stock
Complete line of breadboard test equip.

OK WIRE WRAP TOOLS in stock
Complete line of AP Products in stock.

SPECIAL PRODUCTS
2.5 MHz Freq. Counter Kit 37.50
30 MHz Freq. Counter Kit 47.75

AC TRANSFORMERS

FRAME		WALL PLUG	
6V 500ma	$4.00	10V 2 amp	$7.95
6.3V CT 600ma	4.60	12V 250ma	2.95
12V 250ma	1.95	12V CT 250ma	3.75
12.6V CT 600 ma	4.95	12V 500ma	4.50
12.6V CT 2 amps	5.95	12V 1 amp	5.95
12.6V CT 4 amp	8.60	12V 2 amp	7.95
12.6V CT 8 amp	10.80	6, 9, 12 VDC	
24V CT 100 ma	3.95	300ma	8.95
24V CT 600ma	4.95	9 VDC 500 ma	3.75


Constant Voltage Transformers 12V, 11 amp; 5V, 23 amp; 24V, 11 amp 15.00

DISPLAY LEDS

MAN72/74	CA/CA	.300	.75
DL704	CC	.300	1.25
DL707/DL707R	CA	.300	1.00
DL727/728	CA/CC	.500	1.90
DL747/750	CA/CC	.600	1.49
FND359	CC	.357	.70
FND500/507	CC/CA	.500	.99
FND503/510	CC/CA	.500	.90
FND800/807	CC/CA	.800	2.20
10 digit display			1.25
7520 Clairex photocells			.39
TIL311 Hex			9.50
MAN4610	CA	.40	.99
MAN4640	CC	.40	1.20
MAN4710	CA	.40	.95
MAN4740	CC	.40	1.20
MAN6640	CC	.56	.99
MAN6710	CA	.60	.99
MAN6740	CC	.60	.99

TELEVIDEO TERMINAL
Model 950 $980.00

4116 200ns Dynamic RAM 8/$15.40



RCA Cosmac 1802 Super Elf Computer $106.95

The Super Elf is a small single board computer that does many **big** things. It's an excellent computer for training and for learning programming with its machine language and yet it's easily **expanded with additional memory, Full Basic, ASCII Keyboards, video character generation, etc.**

ROM monitor; State and Mode displays; Single step; Optional address displays; Power Supply; Audio Amplifier and Speaker; Fully socketed for all IC's; Full documentation.

The **Super Elf** includes a **ROM** monitor for program loading, editing and execution with **SINGLE STEP for program debugging** which is not included in others at the same price. With **SINGLE STEP** you can see the microprocessor chip operating with the **unique Quest** address and data bus displays **before, during** and **after** executing instructions. Also, CPU mode and instruction cycle are decoded and displayed on 8 LED indicators.

An RCA 1861 **video graphics** chip allows you to connect to your own TV with an inexpensive video modulator to do graphics and games. There is a **speaker system** included for writing your own music or using many music programs already written. The speaker amplifier may also be used to drive relays for control purposes.

A 24 key **HEX keyboard** includes 16 HEX keys plus **load, reset, run, wait, input, memory protect, monitor select** and **single step**. Large, on board displays provide output and optional **high and low address**. There is a 44 pin standard connector slot for PC cards and a 50 pin connector slot for the Quest Super Expansion Board. Power supply and sockets for **all** IC's are included plus a detailed 127 pg. instruction manual which now includes over 40 pgs. of software info. including a series of lessons to help get you started and a music program and graphics target game. Many schools and universities are using the Super Elf as a course of study. OEM's use it for training and R&D.

Remember, other computers only offer Super Elf features at additional cost or not at all. **Compare before you buy. Super Elf Kit $106.95, High address option $8.95, Low address option $9.95. Custom Cabinet** with drilled and labelled plexiglass front panel **$24.95.** All metal Expansion Cabinet, painted and silk screened, with room for 5S-100 boards and power supply **$57.00. NiCad Battery Memory Saver Kit $6.95.** All kits and options also completely assembled and tested.

Questdata, a software publication for 1802 computer users is available by subscription for $12.00 per 12 issues. Single issues $1.50. Issues 1-12 bound $16.50.

Moews Video Graphics **$3.50**, Games and Music **$3.00**, Chip 8 Interpreter **$5.50**, Starship 4K cassette **$14.95**. Exciting and challenging space game. Complete manual included.

Free 14 page brochure of complete Super Elf system.

Quest Super Basic V5.0

A new enhanced version of **Super Basic** now available. Quest was the first company worldwide to ship a full size Basic for 1802 Systems. A complete function **Super Basic** by **Ron Cenker** including floating point capability with scientific notation (number range $\pm.17E^{38}$), 32 bit integer ±2 billion; multi dim arrays, string arrays; string manipulation; cassette I/O; save and load, basic, data and machine language programs; and over 75 statements, functions and operations.

New improved faster version including **renumber** and essentially **unlimited variables.** Also, an exclusive user expandable command library.

Serial and Parallel I/O routines included.

Super Basic on Cassette $55.00.

Super Expansion Board with Cassette Interface $89.95

This is truly an astounding value! This board has been designed to allow **you** to decide how you want it optioned. **The Super Expansion Board comes with 4K of low power RAM** fully addressable anywhere in 64K with built-in memory protect and a **cassette interface.** Provisions have been made for all other options on the same board and it fits neatly into the hardwood cabinet alongside the **Super Elf.** The board includes slots for up to 6K of **EPROM** (2708, 2758, 2716 or TI 2716) and is **fully socketed.** EPROM can be used for the monitor and Tiny Basic or other purposes.

A 1K Super ROM Monitor $19.95 is available as an on board option in 2708 EPROM which has been preprogrammed with a program loader/editor and error checking multi file cassette read/write software, (relocatable cassette file) another exclusive from Quest. It includes register save and readout, block move capability and video graphics driver with blinking cursor. Break points can be used with the register save feature to isolate program bugs quickly, then follow with single step. If you have the **Super Expansion Board** and **Super Monitor** the monitor is up and running at the push of a button.

Other on board options include **Parallel Input and Output Ports with full handshake.** They allow easy connection of an ASCII keyboard to the input port. **RS 232 and 20 ma Current Loop** for teletype or other device are on board and if you need more memory there are two **S-100** slots for static RAM or video boards. Also a 1K Super Monitor version 2 with video driver for full capability display with Tiny Basic and a video interface board. **Parallel I/O Ports $9.85, RS 232 $4.50, TTY 20 ma I/F $1.95, S-100 $4.50.** A **50 pin connector set** with ribbon cable is available at **$18.95** for easy connection between the **Super Elf** and the **Super Expansion Board.**

Power Supply Kit for the complete system (see Multi-volt Power Supply below).

ELECTRONIC SYSTEMS KITS

Apple Peripheral Kits

SERIAL I/O INTERFACE 0 to 30,000 baud, D.T.R., Input & output from monitor or basic, or use Apple as intelligent terminal, Bd only (P/N 2) **$14.95,** Kit (P/N 2A) **$51.25,** Assembled (P/N 2C) **$62.95.**

PROTOTYPING BOARD (P/N 7907) **$21.95.**

PARALLEL TRIAC OUTPUT BOARD 8 triacs, each can switch 110V, 6A loads, Bd only (P/N 210) **$19.20,** Kit (P/N 210A) **$119.55.**

OPTO-ISOLATED INPUT BOARD 8 inputs, can be driven from TTL logic, Bd only (P/N 120) **$15.65,** Kit (P/N 120A) **$69.95.**

Interface Kits

SERIAL/PARALLEL INTERFACE Bidirectional, Baud rates from 110 to 19.2K, sw selectable polarity of input and output strobe, 5 to 8 data bits, 1 or 2 stop bits, parity odd or even or none, all characters contain a start bit, +5 & −12V required. Bd only (P/N 101) **$11.95,** Kit (P/N 101A) **$42.89.**

RS-232/TTL INTERFACE Bidirectional, requires ±12V, Kit (P/N 232A) **$9.95.**

RS-232/20mA INTERFACE Bidirectional, 2 passive opto-isolated circuits, Kit (P/N 7901A) **$14.95.**

PROM Eraser

Will erase 25 PROMs in 15 minutes. Ultraviolet, assembled. 25 PROM capacity **$37.50** (with **timer $69.50**). 6 PROM capacity OSHA/UL version **$78.50** (with timer **$108.50**).

NiCad Battery Fixer/Charger Kit

Opens shorted cells that won't hold a charge and then charges them up, all in one kit w/full parts and instructions. No PC board. **$8.95**

Z80 Microcomputer

16 bit I/O, 2 MHz clock, 2K RAM, ROM Breadboard space. Excellent for control. Bare Board **$28.50.** Full Kit **$99.00.** Monitor **$20.00.** Power Supply Kit **$35.00.** Tiny Basic **$30.00.**

Modem Kit $60.00

State of the art, orig., answer. No tuning necessary. 103 compatible 300 baud. Inexpensive acoustic coupler plans included. Bd. only $17.00. Article in June *Radio Electronics.*

60 Hz Crystal Time Base Kit $4.40

Converts digital clocks from AC line frequency to crystal time base. Outstanding accuracy.

Video Modulator Kit $9.95

Convert TV set into a high quality monitor w/o affecting usage. Comp. kit w/full instruc.

Multi-volt Computer Power Supply

8v 5 amp, ±18v .5 amp, 5v 1.5 amp, −5v .5 amp, 12v .5 amp, −12v option. ±5v, ±12v are regulated. Basic Kit **$35.95.** Kit with chassis and all hardware **$51.95.** Add $5.00 shipping. Kit of hardware **$16.00.** Woodgrain case **$10.00.** $1.50 shipping.

Type-N-Talk by Votrax


Text to speech synthesizer with unlimited vocabulary, built-in text to speech algorithm, 70 to 100 bits per second speech synthesizer, RS232C interface $359.00. Speech IC **$79.95.**

1802 16K Dynamic RAM Kit $149.00

Expandable to 64K. Hidden refresh w/clocks up to 4 MHz w/no wait states. Addl. 16K RAM **$25.00.**

S-100 4-slot expansion $ 9.95
Super Monitor VI.I Source Listing $15.00

Rockwell AIM 65 Computer



6502 based single board with full ASCII keyboard and 20 column thermal printer. 20 char. alphanumeric display ROM monitor; fully expandable. **$419.00.** 4K version **$449.00.** 4K Assembler **$35.00.** 8K Basic Interpreter **$65.00.**

Special small power supply 5V 2A 24V .5A assem. in frame **$59.00.** Molded plastic enclosure to fit both AIM 65 and power supply **$52.50.** AIM 65 1K in cabinet with power supply, switch, fuse, cord assem. **$559.00.** 4K **$579.00.** A65/40-5000 AIM 65/40 w/16K RAM and monitor **$1295.00.** RAM Board Kit (16K, **$195**) (32K, **$215**). VD640 Video Interface Kit **$119.00.** A&T **$149.00.** Complete AIM 65 in thin briefcase with power supply **$518.00.** Special Package Price: 4K AIM, 8K Basic, power supply, cabinet **$629.00**

AIM 65/KIM/SYM/Super Elf 44 pin expansion board; board with 3 connectors $22.95.

Elf II Adapter Kit $24.95

Plugs into Elf II providing Super Elf 44 and 50 pin plus S-100 bus expansion. (With Super Expansion). High and low address displays, state and mode LED's optional **$18.00.**

Super Color S-100 Video Kit $129.95


Expandable to 256 x 192 high resolution color graphics. 6847 with all display modes computer controlled. Memory mapped. 1K RAM expandable to 6K. S-100 bus 1802, 8080, 8085, Z80, etc. **Dealers: Send for excellent pricing/margin program.**

TERMS: $5.00 min. order U.S. Funds. Calif. residents add 6% tax. $10.00 min. VISA and MasterCard accepted. $1.00 insurance optional. Shipping: Add 5%; orders under $25.00—10%.


Prices subject to change

FREE: Send for your copy of our NEW 1982 QUEST CATALOG. Include 88¢ stamp.


Circle 349 on inquiry card.



Circle 170 on inquiry card.



Circle 429 on inquiry card.



Circle 319 on inquiry card.



The Last Disassembler You Will Ever Need!

Mnemonics Externally Defined

Zilog, Intel, PASM Supplied

ASCII/HEX Preconditioner

Can Externally Def. Equates

Optional Address Listing


ASM/PASM/M80 Compatible

DB statements forcible over user specified range

$150. complete/$25. manual only
for further information contact

COMPUTER TOOLBOX, INC.
1325 East Main St.
Waterbury, Ct. 06705
Phone (203) 754-4197

Circle 112 on inquiry card.



Circle 58 on inquiry card.



Circle 428 on inquiry card.



$239.00 FACTORY SALE PRICE

You get the NEW APF-IM-1 Full Size Powerful Computer: Includes 14K ROM with Level II BASIC built in, 9K User RAM, Color, Sound, Professional 53 keyboard, Two controllers, Two 10 key numeric pads, High speed cassette, A.C. adapter, RF modulator, T.V. switchbox. Accepts TAPE-DISK-PLUG IN CARTRIDGES. It is PLUG IN EXPANDABLE at low cost. 90 day parts and labor warranty, owners guide, BASIC language manual. All this in a beautiful black and white console case for only $239.00.

15 DAY FREE TRIAL Return within 15 days complete and undamaged for refund of purchase price.

PROTECTO ENTERPRIZES
BOX 550, BARRINGTON, IL 60010
TO ORDER PHONE 312/382-2192

Circle 339 on inquiry card.





THE BEST VALUE ON THE MARKET

- Z80 4MHZ
- 64K RAM
- DUAL 8" DRIVES
- 1.2 MB STORAGE
- 2 SERIAL I/O
- 2 PARALLEL I/O
- OPERATING SYSTEM AND UTILITIES

MICRO BUSINESS ASSOCIATES, INC.
500 SECOND STREET
SAN FRANCISCO, CA 94107
415-957-1343

Circle 258 on inquiry card.

QUARTZ CRYSTALS

1.000A	5.1585B	8.14160B	12.000B	23.884 B	38.288B	41.937 B
1.8432A	5.185 B	8.330 B	12.218B	24.000 B	38.312 B	42.000 B
2.000A	5.3248 B	8.387 B	12.440B	24.578B	38.383B	42.627 B
2.0971 A	5.588 B	8.448B	12.477 B	25.000 B	38.812 B	42.700 B
2.4578A	5.585B	8.499 B	12.838 B	28.500B	37.982 B	42.753 B
2.5000A	5.587 B	8.578 B	12.858 B	28.875 B	38.064 B	42.815 B
2.8650A	5.7143 B	8.805 B	13.1072 B	27.000 B	38.444 B	42.851 B
2.8670A	5.760B	8.990B	13.478B	28.357 B	38.825B	42.876 B
3.000 A	5.982 B	9.544 B	13.5168 B	28.400B	38.878 B	42.926 B
3.087 A	5.9904B	9.830 B	14.3182B	28.827 B	38.925B	42.963 B
3.2768 A	6.000 B	9.8304 B	14.391 B	29.937 B	38.937 B	43.000 B
3.330A	6.144 B	9.933B	15.000 B	30.064 B	39.503 B	43.037 B
3.5790B	6.236B	9.950 B	15.180B	31.437 B	39.688 B	43.074 B
3.800B	8.250 B	9.984 B	15.444 B	32.000 B	39.753 B	43.111 B
3.8884 B	6.280B	9.989 B	15.506 B	32.378B	39.876 B	43.127 B
4.000 B	6.2977 B	10.000 B	16.000 B	32.937B	39.963 B	43.148 B
4.1934 B	6.300 B	10.240B	17.224 B	33.200 B	40.375B	43.185 B
4.3425 B	8.400 B	10.496 B	17.508 B	33.878B	40.444 B	43.259B
4.434 B	8.5536 B	10.499 B	17.625B	34.375B	40.592 B	43.296B
4.440 B	6.667 B	10.884 B	18.000 B	34.437 B	40.777 B	43.333B
4.550 B	6.7584 B	10.8250 B	18.1958 B	34.555 B	40.8125 B	43.370B
4.738B	6.912B	10.838B	18.432 B	34.977B	40.833 B	43.407 B
4.750 B	7.0918B	10.850B	19.750B	35.768 B	40.875 B	43.444 B
4.9152 B	7.15909 B	11.000 B	20.000 B	35.873 B	40.888 B	43.518 B
4.9562 B	7.183 B	11.136 B	20.480 B	35.875B	40.926B	43.550B
5.000 B	7.925 B	11.218 B	20.890 B	35.925 B	41.000 B	43.592 B
5.0176 B	8.000 B	11.289 B	21.400 B	35.937 B	41.168 B	43.630B
5.0688 B	8.055 B	11.656 B	22.1184 B	38.000 B	41.377B	48.000 B
5.1200 B	8.077 B	11.681 B	23.400 B	36.062 B	41.626 B	32.768KHZA

ALL 'A' — 3.49 ALL 'B' — 2.49 10 OR MORE-DEDUCT 5%


ADD $1.00 SHIPPING
CAL. RES. ADD 6% SALES TAX
FREE OSCILLATOR SCHEMATICS WITH ANY ORDER

QUALITY COMPUTER PARTS
P.O. BOX 743 / CHATSWORTH, CA 91311

Circle 346 on inquiry card.

PrintersPlus

...computers, peripherals, accessories and supplies!



APPLE ACCESSORIES

Apple II & 48K	CALL
Disk II w/controller DOS 3.3	CALL
Disk II Add-On	CALL
Microsoft Z80 Softcard	299.
16K Ram Card	159.
CCS Parallel Card	109.
Async Serial Card	139.
Clock/Calendar Card	99.
IEEE Card	239.
A-D Card	99.
Mountain Comp. Romplus	130.
KB Filter ROM	49.
CPS Multifunction Card	199.
Supertalker	259.
Paymar L/C Adapter - New	39.
— Old	49.
M&R Super Mod	25.
Superterm	319.
Videx Video Term	299.

APPLE SOFTWARE

Personal S/W Desktop Plan II	$159.
CCA Data Mgmt	85.
Visicalc	159.
Visiplot	159.
Visitrend/Visiplot	219.
Visidex	169.
Visiterm	129.
Micropro Wordstar	259.
Super-Sort	145.
Mail-Merge	90.
Data Star	215.
Spell Star	169.
Muse Super Text II	129.
Address Book	44.
Form Letter Module	79.
Stoneware-DB Master II	199.
Microcom-MicroCourier	239.
Infotory	199.

RIBBONS

NEC	$77.00/Doz.
Qume	45.00/Doz.
Diablo	66.00/Doz.
Anadex	135.00/6 ea.
Tritel	95.00/Doz.
TI/DEC/TTY	45.00/Doz.
Epson	13.95/ea.
MPI/Axiom/Base 2	10.00 ea.

MAGNETIC MEDIA

Premium Quality At Bargain Prices
5¼" Diskettes, all Formats
100% Certified with hub rings, box of 10


Single sided, single density	26.95
Single sided, double density	29.95
Double side, double density	38.95

8" Diskettes, All Formats, 100% Certified

Single sided, single density	29.95
SSSD Error Free	32.95
Single sided, double density	39.95
Double sided, double density	49.95

EPSONS

Complete Stock of MX-80, MX-80 F/T MX-100 Printers, Graphics Chip Sets Cards and Cables



NEC-8023 A, 100 cps Matrix Printer

Hi-Res dot graphics, proportional spacing, correspondent quality printing, bi-directional tractor and friction feed. 80, 132 col. Greek & Math symbols. Everything you need in a small printer.

List $840 .... $599.





MODEMS

UDS 103 LP, *direct*	$169.
103 JLP *Auto Answer*	209.
202 LP *1200 BAUD*	259.
NOVATION CAT, acoustic	145.
D-CAT, *direct*	155.
Auto Cat	219.
Apple Cat	339.
HAYES S100 Micromodem	$349.
Apple Micromodem	299.
Smart Modem	249.

VIDEO MONITORS

Zenith 12" Green	$119.
NEC 12" Green	$185.
Amdex 12" B/W (Leedex)	$139.
Amdek 13" Color Lo-Res	$439.

VIDEO TERMINALS

Ampex Dialog 80	$995.
Ampex Dialog 30	795.
Televideo 920C	845.
Televideo 950	995.




NEC
PC-8000 Series Microcomputer System.

INTRO PRICING $ 1099.00

- Z-80A CPU 4 MHz
- 5 user programmable function keys • 82 Keys with numeric keypad • 160 x 100 resolution • 80 character screen


PC-8001A Microcomputer w/32K RAM	899.
PC-8012A I/O Unit w/32K RAM Expansion slots	599.
PC-8031A Dual Mini-Disk Drive Unit	899.
PC-8032A Add-On Dual Mini Disk Drive Unit	799.



MPI 88G / 99G MATRIX


High resolution dot-addressable graphics for Apple. Enhanced "correspondence quality" printing. Tractor and friction feed. Serial and Parallel Input. 100 cps Bidirectional printing. 80, 96 and 132 column widths!

88 G List $749	$589.
99 G List $849	$660.
Apple Parallel I/O Card/Cable/Disk	$110.
with Graphics Prom (Ap-Pak)	$145.
IEEE I/O Card	$55.
Single Sheet Feeder	$25.
QT Cover	$35.



NEC SPINWRITERS

7710/7730 RO w/tractor	$2,595.
7720 KSR w/tractor	$2,895.
3510/3530 RO	$1,895.
Bi-directional tractor	$225.
Pusher tractor	$350.



OLYMPIA

Letter quality. Daisy wheel printer/typewriter interfaces to Apple, Atari, NEC, TRS80 and RS232 Serial ports. A truly cost effective letter quality printer that functions as a typewriter.

ES100 RO Computer printer List $1690	CALL
ES100 Typewriter only	CALL
Interface Card Only (specify serial or parallel)	$295.
I/O Cable (specify serial or parallel)	$35.
Apple Serial Card	$139.
Print Wheels & Ribbons	CALL

TO PLACE YOUR ORDER CALL:

TELEPHONE (714) 744-7314


TELEX 697120

or write to:

PALOMAR
Computer Products
910-105 W. San Marcos Blvd., San Marcos, CA 92069

TERMS OF SALE: Cash, check, money order, bank wire transfer, credit card or purchase orders from qualified firms and institutions. Please include telephone number with order and expiration date on credit card orders. California residents add 6% sales tax. Advertised prices are for prepaid orders F.O.B. shipping point. Add 3% for shipping in U.S. Pricing and availability subject to change without notice.

Circle 324 on inquiry card.



Circle 373 on inquiry card.

IEEE-488 TO TRS-80* INTERFACE

Everything needed to add *powerful* BASIC GPIB-488 controller capability to TRS-80 Model 1 or 3, Level 2 or DOS with a minimum of 16K.

488-80C *For Model 3 Operation*

488-80B *For Model 1 Operation*

Model 488-80B or 488-80C Price: $375.
+ shipping, insurance & tax
WHEN ORDERING SPECIFY DISK OR TAPE

SCIENTIFIC ENGINEERING LABORATORIES
11 Neil Drive • Old Bethpage, NY 11804
Telephone: (516) 694-3370

**Trademark of Tandy Corp.*
There is no affiliation between Scientific Engineering Laboratories and Tandy Corp. or Radio Shack.

Circle 362 on inquiry card.

S-100 VOICE


The ARTICULATOR board allows you to record, store, and playback any vocabulary on your S-100 computer. Input speech is digitized by the ARTICULATOR and send to the computer via an on-board port for storage at 1K to 2K bytes/sec. This data is then sent back from the computer to the ARTICULATOR for very high quality playback. On-board VOX switching minimizes memory storage requirements.

PRICE — $350 A&T
AVAILABLE NOW

Quintrex, Inc.
4461 Indian Creek Parkway
PO Box 7384
Overland Park, KS 66207

Circle 350 on Inquiry card.

Like-new products



For free catalog,
phone toll-free (800) 225-1008
In Massachusetts (617) 938-0900

GENSTAR REI SALES COMPANY
19527 Business Center Dr., Northridge, CA 91324

Circle 186 on inquiry card.

Convert your TRS-80 into a
DEVELOPMENT SYSTEM

Z-80 In-Circuit emulation and EPROM/EEPROM programming in a single compact unit.



Debug stand-alone systems with program in TRS-80 RAM, then copy working program into PROM.

Only $329 including personality module for 2716, 2516, 2758, 2508, 2532, 2816, 2808, 48016.

ORION INSTRUMENTS
172 Otis Ave, Woodside, CA 94062
(415) 851-1172

Circle 312 on inquiry card.

UV EPROM ERASER



$49.95

- ERASES ALL UV ERASABLE EPROMS (2708, 2716, 2564, etc.)
- QUICK FIFTEEN MINUTES ERASE TIME
- ERASES OVER FIFTEEN EPROMS AT A TIME
- LAMP LIFE, 7700 HOURS
- INDUSTRIAL MODEL $88.50.
- INDUSTRIAL MODEL WITH TIMER & SAFETY INTERLOCK SWITCH $97.50. *(Rugged steel enclosure with bottom drawer)*

THE BEST 6809 SINGLE BOARD COMPUTER AVAILABLE

- *Floppy Controller*
- *Printer Port*
- *RS-232 Port*
- *SWTPC compatible*
- *Runs TSC Flex*
- *Full Documentation*

PRICE: **$389.00**

FOR THE SS-50 AND S-100 BUS
ASSEMBLED, TESTED, 48 HOUR BURN-IN, 90 DAY WARRANTY

2716 EPROMS 250 ns $4.95 *DIRECT FROM FACTORY*
SS-50 6809 CPU CARD: 1MHZ $149.00 2MHZ $189.00
RS-232 INTELLIGENT EPROM PROGRAMMER . . . $489.00
Programs: 2716, 2516, 2532, 2732, 8748, 8749
ANTISTATIC FOAM 4" x 8" $3.95

WE ACCEPT VISA, MASTERCARD, C.O.D., CHECKS
PHONE ORDERS (305) 776-5870
TWX: 510-955-9496 • Engineering Hot-Line: (305) 974-0967

LOGICAL DEVICES INC.
781 W. OAKLAND PARK BLVD. • FT. LAUDERDALE, FLORIDA 33311
ADD: $3.00 SHIPPING, $2.00 C.O.D. CHARGES

Circle 43 on inquiry card.

BASF Flexy-Disks®

SAVE 40% Write for our complete list.

5¼" Specify soft, 10 or 16 sector	Price/10
1 side/single density	$26.70
1 side/double density	31.90
2 sides/double density	37.10

8" Specify soft or 32 sector	
1 side/single density	26.70
1 side/double density	31.90
2 sides/double density	41.60

CHECKS — VISA — MC — C.O.D.
(313) 777-7780 ADD $2 SHIPPING

LYBEN COMPUTER SYSTEMS
27204 Harper Ave.
St. Clair Shores, MI 48081

Circle 243 on inquiry card.

IPEX NEW!

"ELF" Interface Converts Your Typewriter into Printer

- Finest print quality
- Low cost
- Easy installation
- Quick delivery
- Fits IBM Selectric® and Electronic Typewriters
- Models for all popular computers
- Call or write for more information, today!

\- We export to all countries -

IPEX INTERNATIONAL INC.
5115 Douglas Fir Rd.
Calabasas, CA 91302 U.S.A.
Tel: (213) 710-1444 TLX/TWX: 910 494 2100

Circle 216 on inquiry card.

8086/8087/8088
CROSS SOFTWARE PACKAGES


1 C cross compiler for the 8086. All facilities of the complete C language, including floating point for the 8087, are supported. Optionally, memory can be allocated for use with the 8088. Output is symbolic assembly language. The compiler is suitable for use in porting UNIX to the 8086.

2 Cross assembler/linker/librarian/downline loader for the 8086. Assembler input is an extension to that used by Intel. Loader output is a file in standard Intel hex format.

3 Simulator/debugger for the 8086. Capabilities include display, breakpoints, interpretive execution, as well as many others.

Host System: PDP-11 running RT-11, RSX-11M, UNIX/V6, UNIX/V7; or VAX-11 running VMS, UNIX/32V.

For additional information:



1701 21st Ave. S., Suite 222 • Nashville, TN 37212
Phone (615) 383-7520

Intel is a trademark of Intel Corporation; UNIX and UNIX/32V are trademarks of Bell Laboratories; RT-11, RSX-11M, PDP-11, VMS, and VAX-11 are trademarks of Digital Equipment Corporation.

Circle 11 on Inquiry card.

cc6502

C cross compiler for the 6502. With the exception of three minor features, all facilities of the complete C language are supported. Output is symbolic assembly language and is easily customized to existing assemblers. This cross compiler has been in use for over one year.

Host System: PDP-11 running RT-11, RSX-11M, UNIX/V6, UNIX/V7; or VAX-11 running VMS, UNIX/32V.

For additional information, contact



1701 21st Ave. S., Suite 222 • Nashville, TN 37212
Phone (615) 383-7520

UNIX and UNIX/32V are trademarks of Bell Laboratories; RT-11, RSX-11M, PDP-11, VMS, and VAX-11 are trademarks of Digital Equipment Corporation.

Circle 12 on inquiry card.

SCR SUPER-BUYS

$10.00 MIN. ORDER HANDLING/SHIPPING...$2.50
UPS ANYWHERE IN CONTINENTAL U.S.

1982 BUYERS GUIDE NOT JUST ANOTHER CATALOGUE BUT A BUYERS GUIDE "OF THE FUTURE" FREE

1. **UHF-VHF CONVERSION KIT.** Complete with PC board, all required components; jumper wire; cabinet with speaker, and comprehensive brochure incl. schematic, board layout, mounting and hook-up diagrams, parts list, and assembly and set-up instructions. All parts are industrial prime quality. $119.95 ea.

2. **NEW ZENITH ZVM-121 HIGH-LEGIBILITY CRT MONITOR.** Features 12" green phosphor CRT, with 15 Mhz Bandwidth. 40 or 80 character widths are operator switch-selectable. Fully compatible with 80-column Apple cards, etc. $117.95 ea.

OUTSIDE CAL. 800-854-8660
INSIDE CAL. (714) 527-2554

SCR ELECTRONICS INC.
VISIT OUR NEW SUPER CENTER
5303 Lincoln Ave., Cypress, CA 90630
Pay by CHECK, M.O., VISA, M/C

Circle 365 on inquiry card.

68KFORTH

New SYSTEMS LANGUAGE for ERG 68-696 CPU and Motorola's KDM board. O/S, Compiler, Monitor, MACRO Assembler, Interpreter, Virtual Memory, Screen Editor, DBL Precision Arithmetic and more. Enhanced FIG-FORTH Vocabulary. Environment: stand alone, Bell Lab's UNIX, or Whitesmiths' IDRIS, etc.

$795

EMPIRICAL RESEARCH GROUP, INC.
PO Box 1176
Milton, WA 98354
206-631-4855

Circle 169 on inquiry card.

APPLEWARE INC.




Offering an extensive software library of:
- Packed disks/60 programs each
- 3.3 DOS
- Both sides used
- Demuffined easily for 3.2.1. use
- Hubring reinforcer for long life

- Data Base
- Utilities
- Educational
- Entertainment
- Graphics
- Finance
- Music
- Domestic

INTRODUCTORY OFFER !!
Order all 3 disks and get a bonus disk FREE!! Call now: 1-800-327-8664
Fla. residents: 305-584-7004
Disks are $59.95 @ + $3 handling.
6400 HAYES ST.,
HOLLYWOOD, FL. 33024

Circle 34 on inquiry card.

6800 Micro Modules



FOR INTERFACING TO: sensors, transducers, analog signals, solenoids, relays, lamps, pumps, AC motors, DC motors, stepper motors, keyboards, displays, 488 GPIB.


ADDITIONAL FEATURES: 6800 MPU, counter/timer, fail safe battery back up

WINTEK
Wintek Corp.
1801 South Street
Lafayette, IN 47904
317-742-8428

Circle 439 on inquiry card.

Dysan CORPORATION

Solve your disc problems, buy 100% surface tested Dysan diskettes. All orders shipped from stock, within 24 hours. Call toll FREE (800) 235-4137 for prices and information. Visa and Master Card accepted.



PACIFIC EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA 93401. (In Cal. call (805) 543-1037.)

Circle 319 on inquiry card.

ISIS ⟷ CP/M®

Full bi-directional file transfer capabilities are provided in the ISIS-CP/M utilities package. Written in machine language and running under CP/M, these utilities permit the CP/M user to read or write files direct to/from an ISIS Diskette. They will run under any version of CP/M without regard to diskette density. The complete package is $250.00 including user's manual. Write for free brochure on other CP/M software.

CP/M is a registered trademark of Digital Research
ISIS is a trademark of Intel Corporation



SOUTHERN COMPUTER SYSTEMS, INC.
P.O. Box 3373A
Birmingham, AL 35255
(205) 933-1659

Circle 379 on inquiry card.

North Star BASIC UTILITY SET

- EDITOR — Create & edit a Basic program using 26 commands, including GLOBAL locate & change.
- BPRT — Print & cross reference a Basic program.
- BPAK — Pack a Basic program.
- RE — Rename a disk file.

$69 plus $1.50 shipping, Calif. Res. add 6%.
Check, VISA, M/C

SZ Software Systems
1269 Rubio Vista Road, Altadena, Calif. 91001
(213) 791-3202

Circle 401 on inquiry card.

Breakthrough BASIC For Mod II's

Now Easier To Write, Easier To Read With Basic IDEAS™

Stop kidding yourself. BASIC is hard to write, harder to read, and a pain to modify. But if you're good with BASIC, you'll be great with Basic IDEAS™.

Just insert the Basic IDEAS™ diskette into your TRS-80* Mod II, and immediately begin to benefit from these new capabilities:

EASIER TO WRITE-EASIER TO READ-EASIER TO MODIFY

- ☐ **Full Screen Edit Facility.** Includes Global Search & Replace, Multi-Line Insert & Delete, Scrolling, and much more.
- ☐ **Meaningful Variable Names.** Up to 255 characters. You're no longer limited to 2-character symbols!
- ☐ **User-Defined Labels for GOTOs.** Say goodbye to line numbers, hello to self-explanatory programs.
- ☐ **Copy Facility and Call Structure.** Now make it easy to include subroutines from external files.
- ☐ **Nested IF/THEN/ELSE/ENDIF Statements.** Can now span multiple lines. A great boon to readable programs, especially when combined with meaningful variable names & labels with callable subroutines.

All these new, advanced programming capabilities without sacrificing any existing features of Mod II BASIC. A snap to learn, Basic IDEAS™ comes fully documented. Works with either 1 or 2-drive Mod II Systems.

Only $299. Write now for FREE brochure.

Computer IDEAS Corporation
4229 Hall St. • Dallas, Texas 75219

*Registered Trademark of Tandy Corporation

Circle 106 on inquiry card.



LEO ELECTRONICS, INC.
8921 S. Sepulveda #208
Los Angeles, CA 90045
(213) 641-3101 (800) 421-2418

WHY PAY MORE? SAVE MONEY!
LOWEST PRICES ON PARTS!

EPROMS	
2708	2.60
2716	4.00
2716-1(350ns)	6.50
TMS 2716	6.00
2732	10.00
2532	12.00

REGULATORS	
7805	.75
7812	.75
7815	.75
7905	.85
7912	.85
7915	.85

RAMS	
4116(200ns)	8/13.00
4116(150ns)	8/16.00
2114(200ns)	8/18.00


MICROPROCESSORS	
Z-80A-CPU	5.50
8080A	2.25
8085A	7.00

TERMS: Check, Visa, Mastercard. Call for C.O.D.
U.S. Funds only. California Residents add 6% Sales Tax.
SHIPPING: Add $2.00 for Ground $5.00 for Air.
ALL MAJOR MANUFACTURERS
ALL PARTS 100% GUARANTEED

Circle 235 on inquiry card.

HAYES SMARTMODEM

$239.88
DELIVERED



High performance data communications system for small computers. SMARTMODEM is a stand-alone 300 baud modem system including the SMARTMODEM unit, power pack, and modular telephone cable. Completely programmable, the SMARTMODEM can be controlled using any programming language.

- ☐ FCC approved direct-connect
- ☐ Auto-answer/Auto-dial
- ☐ Touch-tone/Pulse-dialing
- ☐ Full/Half duplex
- ☐ Audio monitor
- ☐ 7 status LED lights

HIGH TECHNOLOGY AT AFFORDABLE PRICES

THE BOTTOM LINE

Orders & Information
(603)-673-8857
Orders Only
(800)-343-0726

12 Johnson Street, Milford NH 03055

Circle 57 on inquiry card.



Such A Deal!


Have You Ever Considered USED EQUIPMENT?

Want To Save Lots?
We Carry All Brands of
Used Minis and Micros*
(DEC - DG - APPLE - TRS-80, ETC.)

Call or Write for **FREE** List of Bargains:
Compuchange
Box 4151
Anaheim, Ca. 92803
(714) 535-1990

*No Cost or Obligation
To List with Us!!
Call for More Info!

Circle 95 on inquiry card.



Circle 162 on inquiry card.

WANT HELP?

COBOL PROGRAMMER'S AIDE (CPA)

Provides extensive assistance in **CODING, DEBUGGING, MAINTAINING** and **DOCUMENTING** your Cobol programs - Improve your efficiency and productivity - **EASY TO USE - MENU DRIVEN - A PRACTICAL SET** of **TOOLS** - An **INVALUABLE AIDE.**

CPA features:

- **SOURCE ANALYZER & CROSS REFERENCE**
- **SOURCE EDITOR & REFORMATTER**
- **SOURCE OVERVIEWER**
- **DOCUMENTATION PRINTER**
- **PARAMETER FETCHER SUB-PROGRAM**
- **COMPREHENSIVE MANUAL** and more

Available for CP/M[2], CDOS[3] or CROMIX[3] users utilizing COBOL-80[1] or Cromemco Cobol.

Satisfaction guaranteed or full refund!

For Program Samples and information call or write:

APM *Automated Programming Methods, Inc.*
2212 Dupont Dr.,
Irvine, CA 92715
(714) 851-8686

Trademarks: [1]MicroSoft. [2]Digital Research. [3]Cromemco

Circle 45 on inquiry card.



SPEECH SYNTHESIZER

$70 Each
(5 or more, $55 each)

Order in Ones or Thousands

The SC-01A Speech Synthesizer is a completely self-contained solid state device. This single chip phonetically synthesizes continuous speech of unlimited vocabulary.

The SC-01A contains 64 different phonemes which are accessed by a 6-bit code. Computer interfaces and text-to-speech algorithms also available for product development.

Votrax is a trademark of Federal Screw Works

Call 1-800-645-3479, in N.Y. 1-516-374-6793

MICROMINT INC.
917 Midway
Woodmere, N.Y. 11598





Call for quantity pricing.

Circle 471 on inquiry card.

S100 Intelligent

Color Graphics

- 8085 6K Prom 8K Ram
- SubLogic Graphics software in onboard Prom
- 32 Graphics commands including shaded polygons, circles, boxes
- Horizontal and vertical text

256 × 192 Hires 128 × 192 4 color
$395

Limited quantity SMS 64K S-100 stat ram ass. & tested $395

California Computer Graphics
25 Avenida Dr.
Berkeley CA 94708
(415) 540-5698

Circle 75 on inquiry card.



Circle 109 on inquiry card.

5¼" Floppy Disk Drives
(single side-single or double density)

TANDON Model TM 100-1 } **$209.95** ea.
CDC Model 9409

2 or more — $204.95 ea.*

Floppy Drive Power Connector Kit $2.00*
5¼" Memorex Floppy Disks - single side soft sector, single or double density - Box of 10 .... $28.00*

CALL NOW - TOLL FREE

800-824-7888 all states except CA.
800-852-7777 for CA residents.
Ask for Operator #99.

MC/VISA or C.O.D. with certified check or money order. Kansas residents add 3% sales tax.

*Plus shipping.
For info call: 316-683-9225
316-685-9445



923 Longfellow Street
Wichita, KS 67207

Circle 183 on inquiry card.

NEW LOWER PRICES


"THE BIG BOARD"

OEM - INDUSTRIAL - BUSINESS - SCIENTIFIC

SINGLE BOARD COMPUTER KIT!

Z-80 CPU! 64K RAM!





PARTIALLY ASSEMBLED KITS
For All Sockets Installed
And Soldered Add $50.

WANT MORE INFO?
Full Documentation and
Schematics — $5.

U.K. AND EUROPE: CONTACT VINCELORD LTD. 47 GOLDHURST TERRACE LONDON NW6

THE FERGUSON PROJECT: Three years in the works, and maybe too good to be true. A tribute to hard headed, no compromise, high performance, American engineering! The Big Board gives you all the most needed computing features on one board at a very reasonable cost. The Big Board was designed from scratch to run the latest version of CP/M*. Just imagine all the off-the-shelf software that can be run on the Big Board without any modifications needed! Take a Big Board, add a couple of 8 inch disc drives, power supply, an enclosure, C.R.T., and you have a total Business System for about 1/3 the cost you might expect to pay.

$499.00 ** (64K KIT BASIC I/O)

SIZE: 8½ x 13¾ IN.
SAME AS AN 8 IN. DRIVE.
REQUIRES: +5V @ 3 AMPS
+ - 12V @ .5 AMPS.

FULLY SOCKETED!

FEATURES: (Remember, all this on one board!)

64K RAM

Uses industry standard 4116 RAM'S. All 64K is available to the user, our VIDEO and EPROM sections do not make holes in system RAM. Also, very special care was taken in the RAM array PC layout to eliminate potential noise and glitches.

Z-80 CPU

Running at 2.5 MHZ. Handles all 4116 RAM refresh and supports Mode 2 INTERUPTS. Fully buffered and runs 8080 software.

SERIAL I/O (OPTIONAL)

Full 2 channels using the Z80 SIO and the SMC 8116 Baud Rate Generator. FULL RS232! For synchronous or asynchronous communication. In synchronous mode, the clocks can be transmitted or received by a modem. Both channels can be set up for either data-communication or data-terminals. Supports mode 2 Int. Price for all parts and connectors: $65.

BASIC I/O

Consists of a separate parallel port (Z80 PIO) for use with an ASCII encoded keyboard for input. Output would be on the 80 x 24 Video Display.

24 x 80 CHARACTER VIDEO

With a crisp, flicker-free display that looks extremely sharp even on small monitors. Hardware scroll and full cursor control. Composite video or split video and sync. Character set is supplied on a 2716 style ROM, making customized fonts easy. Sync pulses can be any desired length or polarity. Video may be inverted or true. 5 x 7 Matrix - Upper & Lower Case

FLOPPY DISC CONTROLLER

Uses WD1771 controller chip with a TTL Data Separator for enhanced reliability. IBM 3740 compatible. Supports up to four 8 inch disc drives. Directly compatible with standard Shugart drives such as the SA800 or SA801. Drives can be configured for remote AC off-on. Runs CP/M* 2.2.

TWO PORT PARALLEL I/O (OPTIONAL)

Uses Z-80 PIO. Full 16 bits, fully buffered, bi-directional. User selectable hand shake polarity. Set of all parts and connectors for parallel I/O: $19.95

REAL TIME CLOCK (OPTIONAL)

Uses Z-80 CTC. Can be configured as a Counter on Real Time Clock. Set of all parts: $9.95

BLANK PC BOARD — $175

The blank Big Board PC Board comes complete with full documentation (including schematics), the character ROM, the PFM 3.3 MONITOR ROM, and a diskette with the source of our BIOS, BOOT, and PFM 3.3 MONITOR.

CP/M* 2.2 FOR BIG BOARD

The popular CP/M* D.O.S. to run on Big Board is available for $159.00.

PRICE CUT!

PFM 3.3 2K SYSTEM MONITOR

The real power of the Big Board lies in its PFM 3.0 on board monitor. PFM commands include: Dump Memory, Boot CP/M*, Copy, Examine, Fill Memory, Test Memory, Go To, Read and Write I/O Ports, Disc Read (Drive, Track, Sector), and Search. PFM occupies one of the four 2716 EPROM locations provided.
Z-80 is a Trademark of Zilog.

Digital Research Computers
(OF TEXAS)
P.O. BOX 401565 • GARLAND, TEXAS 75040 • (214) 271-3538

TERMS: Shipments will be made approximately 3 to 6 weeks after we receive your order, VISA, MC, cash accepted. We will accept COD's (for the Big Board only) with a $75 deposit. Balance UPS COD. Add $4.00 shipping.
USA AND CANADA ONLY

*TRADEMARK OF DIGITAL RESEARCH. NOT ASSOCIATED WITH DIGITAL RESEARCH OF CALIFORNIA, THE ORIGINATORS OF CPM SOFTWARE
**1 TO 4 PIECE DOMESTIC USA PRICE.

Circle 148 on inquiry card.

Circle 319 on inquiry card.

Circle 221 on inquiry card.

Circle 337 on inquiry card.

Circle 78 on inquiry card.

Circle 102 on Inquiry card.

Circle 180 on inquiry card.

Circle 383 on inquiry card.

Circle 79 on Inquiry card.

Circle 374 on Inquiry card.

WE WILL NOT BE UNDERSOLD

CP/M® Software	Software/Manual only
Computer Pathways	
Pearl (level 1)	$ 99/$25
Pearl (level 2)	$299/$40
Pearl (level 3)	$549/$50
Digital Research	
PL/I-80	$459/$35
BT-80	$179/$30
Mac	$ 85/$15
Sid	$ 65/$15
Z-Sid	$ 90/$15
Tex	$ 90/$15
DeSpool	$ 50/$10
Micropro	
WordStar	$319/$60
Customization Notes	$ 89/$na
Mail-Merge	$109/$25
WordStar/Mail-Merge	$419/$85
DataStar	$249/$60
WordMaster	$119/$40
SuperSort I	$199/$40
Spell Star	$175/$40
Microsoft	
Basic-80	$289/$na
Basic Compiler	$329/$na
Fortran-80	$349/$na
Cobol-80	$574/$na
M-Sort	$124/$na
Macro-80	$144/$na
Edit-80	$ 84/$na
MuSimp/MuMath	$224/$na
MuLisp-80	$174/$na
Organic Software	
Milestone	$269/$30
Supersoft	
Diagnostic I	$ 49/$20
Diagnostic II	$ 84/$20
Disk Doctor	$ 84/$20
Forth (8080 or Z80)	$149/$30
Fortran	$219/$30
Fortran w/Ratfor	$289/$35
Unicorn	
Mince	$149/$25
Scribble	$149/$25
Both	$249/$50
Data Base	
FMS-80	$649/$45
dBASE II	$595/$50
Access/80	$699/$50
Pascal	
Pascal/MT+	$429/$30
Pascal/M	$189/$20
Miscellaneous	
SpellGuard	$299/$25
The Last One	$549/$na
SuperCalc	$269/$50
CBASIC-2	$ 98/$20
MicroStat	$224/$25
StatPak	$449/$40
Micro B+	$229/$20

Apple Software (Business)	
Micropro	
Wordstar	$269
MailMerge	$ 99
Wordstar/MailMerge	$349
SuperSort I	$159
Spellstar	$129
Personal Software	
Visicalc 3.3	$229
CCA Data Mgr	$ 84
Desktop/Plan II	$229
Visiterm	$139
Visidex	$229
Visiplot	$185

Personal Software (cont.)	
Visitrend/Visiplot	$ 275
Zork	$ 34
Miscellaneous	
Micro Courier	$ 219
Super-Text II	$ 127
ASCII Express	$ 59
Apple Software (Entertainment)	
Wizard & Princess	$ 28
Mystery House	$ 24
Flight Simulator	$ 29
Raster Blaster	$ 26
Space Eggs	$ 26
Sargon II	$ 29
ABM	$ 22
Micropainter	$ 29
Apple Panic	$ 28
Pool 1.5	$ 26
Apple Accessories	
Z-80 Softcard by Microsoft	$ 299
Keyboard Enhancer	$ 119
Apple Joystick	$ 49
Sup-r Mod	$ 25
CPS Multifunction Card	$ 199
Videoterm by Videx	$ 249
16K Card by Microsoft	$ 159
Sup-r Fan	$ 39
ALF9 Voice Board	$ 149
CCS Cards	$Call
CCS Parallel Model 7720	$Call
CCS Serial Model 7710D	$Call
CCS Centronics Model 7728	$Call
Disk Drives For TRS-80* Model 1	
CCI-100 5¼", 40 Track	$ 299
Add-ons for Zenith Z-89	
CCI-189 5¼", 40 Track	$ 389
Z-87 Dual 5¼" system	$ 995
Drives for Z-90	$Call

External card edge and power supply included. 90 day warranty/one year on power supply.

Corvus 5M	**$ 3089**
Corvus 10M	**$ 4489**
Corvus 20M	**$ 5429**
Corvus Mirror	**$ 699**
Shugart 8" 801R Raw Drive	$ 399
TANDON 5¼" Raw Drive	$ Call
Power Supplies	$ Call
Diskettes—Box of 10	
Maxell 5¼"	$ 40
Maxell 8"	$ 45
BASF/Verbatim 5¼"	$26.95
BASF/Verbatim 8"	$ 36
Plastic File Box—Holds 50 5¼" dskts.	$ 19
Plastic Library Case 5¼"	$ 3
Plastic Library Case 8"	$ 4
Head Cleaning Diskette	$ 25
Floppy Saver	$10.95
Floppy Saver Rings	$ 6.95
16K RAM Kits	
One Kit	$19.00
Two Kits	$37.00
200ns for TRS-80*, Apple II, (specify): Jumpers	$ 2.50
Computer Systems	
Atari 400	$ 359
Atari 800	$ 699
Call for other Atari products	
Zenith Z89, 48K	$ Call
Zenith Z90, 64K	$ Call
Call for other Zenith products	

For fast delivery, send certified checks, money orders or call to arrange direct bank wire transfers. Personal or company checks require one to three weeks to clear. All prices are **mail order only** and are subject to change without notice. **Call for shipping charges.**

Terminals	
ADDS Viewpoint	$ Call
Zenith Z-19	$ 719
Televideo 910	$ 559
Televideo 920C	$ 729
Televideo 950	$ 969
S-100 California Computer Systems	
Mainframe	$ 349
Z80 CPU	$ 239
64K RAM	$ 569
Floppy Disc Cntrl	$ 339
Integrated Sys. w/int. cables, tstd.	$1975
2P + 2S I/O	$ 269
4 Port Serial I/O	$ 249
4 Port Parallel I/O	$ 179

Casio Calculators		
Pocket Comp.	FX702	$185.00
Desk Printr/Calc.	FR100	$ 79.95
Scientific Calc.	FX8100	$ 49.95
Game Watch	CA90 Plastic	$ 49.95
Game Watch	CA901 Steel	$ 69.95
Calendar Watch	AX210	$ 59.95

Printers — NEC Spinwriter	
7710 R.O. Ser	$2395
7710 Ser w/tr.	$2595
7720 KSR w/tr.	$2795
7730 R.O. Par	$2395
7730 R.O. Par w/tr.	$2595
NEW 3500 Series	**$ Call**
Epson MX-70	**$ Call**
Epson MX-80	**$ Call**
Epson MX-80FT	**$ Call**
Epson MX-100	**$ Call**
Epson Graftrax	**$ Call**
PaperTiger 560 Gr. & 2K	$ Call
IDS Prism 80	$ Call
IDS Prism 132	$ Call
PaperTiger Access.	$ Call
Olivetti DY 211 Daisy Wheel	**$ Call**
Anadex DP-8000	$ 849
Anadex DP-9500/01	$1389
Okidata Microline 80 Fric. & pin feed	$ Call
Okidata Microline 82A Fric. & pin feed	$ Call
Okidata Microline 83A 120 cps	$ Call
Okidata 84 200 cps	$ Call
Centronics 739	$ 739
Data South 180 cps	$ Call
Monitors	
Leedex 12" B&W	$ 119
Leedex 12" Green Screen	$ 129
Leedex 13" Color	$ 329
Sanyo 9" B&W	$ 149
Sanyo 9" Green Screen	$ 189
Sanyo 12" Green Screen	$ 249
Sanyo 12" B&W	$ 239
Sanyo 13" Color	$ 449
Zenith 13" Color	$ 349

****** **Special of the Month** ******
Zenith 12" Green Screen
$129

Telecommunications	
Prentice Star Modem 1-yr. guar.	$ 125
Univ. Data System UDS103LP	$ 149
Univ. Data System UDS103JP	$ 185
Novation Cat	$ 139
Novation D-Cat	$ 149
Novation Auto-Cat	$ 199
Novation Apple Cat II	$ 299
Hayes Smart Modem™	$ 249
Hayes Micro-Modem II™	$ 295
Hayes Chronograph™	$ 225
CCI Telnet Com. Package	$ 135

DEALER (NATIONAL/INTERNATIONAL) INQUIRIES INVITED **Send for FREE Catalogue**



TO ORDER CALL TOLL FREE 1-800-343-6522
TWX: 710-348-1796 Massachusetts Residents call 617/242-3361

420-438 Rutherford Ave., Dept. B04M
Charlestown, Massachusetts 02129
Hours 9 AM-8 PM (EST) Mon.-Fri. (Sat. till 5)

Technical Information call 617/242-3361
Massachusetts Residents add 5% Sales Tax
Tandy Corporation Trademark/* Digital Research





Circle 130 on inquiry card.

FORTH

Complete FORTH program development systems for the IBM® Personal Computer. Packages include interpreter/compiler with virtual memory management, line editor, custom screen editor, assembler, decompiler, utilities, file and record access modules, and many demonstration programs. 100 page user manual. Optional floating point arithmetic extensions and cross compiler available.

Ready to run under PC-DOS or CP/M-86®. Standalone version available soon. 64 kbytes RAM and two disk drives recommended. (IBM is a registered trademark of International Business Machines Corp. CP/M is a registered trademark of Digital Research, Inc.)

Laboratory Microsystems
4147 Beethoven Street
Los Angeles, CA 90066
(213) 306-7412

Circle 231 on inquiry card.

SOFTWARE PROFESSIONALS

CONSIDER CALIFORNIA!

SYSTEMS DEVELOPMENT
MICROCOMPUTER/BAY AREA.....TO $40K

DIAGNOSTICS/SOFTWARE DEVELOPMENT
SAN DIEGO....................TO $32K

SOFTWARE ENGINEER
SIGNAL PROCESSING/BAY AREA...TO $42K

LOCAL NETWORKING ANALYST
ORANGE COUNTY...............TO $40K

SOFTWARE ENGINEER/UNIX, C
BAY AREA....................TO $45K

FOR MORE INFORMATION ABOUT THESE AND OTHER OPPORTUNITIES, CALL:

(714) 565-4331 PLEASE SEND RESUME

WESTBROOKE SEARCH, INC.
9320 CHESAPEAKE DRIVE, SUITE 202
SAN DIEGO, CALIFORNIA 92123

C P N I X

CP/M -- UNIX
COMMUNICATION PROGRAM

-FEATURES-
TERMINAL MODE : FILE TRANSFERS TO/FROM LOCAL DISK : AUTOMATIC LOGIN/LOGOFF : USER OPTIONS : SOURCE CODE

MANUAL $5.00 : COMPLETE $49.90

ANSCO
BOX 24069
Minneapolis, MN 55424
612-927-9018

CP/M is a trademark of Digital Research
UNIX is a trademark of Western Electric

Circle 31 on inquiry card.


```
S-100 18-SLOT                 $    590
S-100 MAINFRAME 6-SLOT WITH
      TWO DT-8s               $  1,690
DISK  SUB-SYSTEM WITH
      TWO DT-8s               $  1,390
ANGEL-I TEXT AND DATA
      PROCESSOR               $  7,990
ALTOS ACS 8000-2              $  2,990
      ACS 8000-10             $  6,990
TELEVIDEO TVI-910             $    590
          TVI-950             $    990
OKIDATA 82A                   $    490
        83A/TRACT.            $    790
QUME    9-45                  $  2,190
DIABLO  630                   $  2,290
OTHER PRODUCTS AND SOFTWARE
  AT SIMILAR LOW PRICES
```

(213) 820-4231

ANGEL COMPUTER PRODUCTS
A DIVISON OF
E & U ENGEL CONSULTING
1719 So. CARMELINA AVE
LOS ANGELES, CA. 90025

Circle 171 on inquiry card.

Daisywheel from $649!



ELECTRONIC LETTER-QUALITY TYPEWRITER AND KSR-TERMINAL!

USE YOUR COMPUTER AS A CONTROLLER AND SAVE WITH THE BASIC INTERFACE MODELS...SOFTWARE DRIVERS PROVIDED FOR APPLE, RADIO SHACK AND Z-ASSEMBLERS.

INTELLIGENT CONTROLLER MODELS FROM $789 FEATURING: PARALLEL CENTRONICS COMPATABILITY WITH 1K BUFFERS, PROGRAMMABLE FOR LINE OR BLOCK MODE, JUSTIFICATION, AND CENTERING. RS-232 SERIAL MODELS FROM $829.

ALL MODELS SUPPORT ALL THREE PITCHES, 100 CHARACTERS, 24 TYPE STYLES, COMES WITH CASE AND 90 DAY WARRANTY.

BASED ON PRAXIS 30 AND 35. DEALER/OEM INQUIRY INVITED.

SYSTEMED CORP.
JCMH, Hospital Dr., Mountain City, TN 37683
POB 18
(615) 727-6000

Circle 395 on inquiry card.

C compilers and Cross compilers

Available for:

PDP-11	RT-11/RSX-11
6809	SDOS/FLEX
8080	CP/M
8085	CP/M
Z80	CP/M
8086	
8088	

OTHERS PENDING

The full C language, as described in "The C Programming Language" by Kernighan and Ritchie.

UNIX version 7 compatible.

UNIX is a trademark of Bell Labs
RT11/RSX11 are trademarks of Digital Equipment Corp.
SDOS is a trademark of Software Dynamics
CP/M is a trademark of Digital Research
FLEX is a trademark of Technical Systems Consultants

TELECON SYSTEMS
90 E. Gish Road, Suite 25
San Jose, California 95112
408-275-1659

Circle 408 on Inquiry card.

FORTH 6800

YOU'VE HEARD ALL THE BENEFITS OF FORTH. NOW YOU CAN HAVE THEM ON YOUR 6800 WITH G-FORTH

- TRUE FIG-FORTH COMPILER
- FASTER THAN BASIC
- MORE EFFICIENT THAN ASSEMBLY
- CUTS PROGRAM DEVELOPMENT
- HIGHLY STRUCTURED

G-FORTH COMES WITH A COMPLETE EDITOR, VIRTUAL STRING ARRAYS, 6800 ASSEMBLER, SET OF UTILITIES, AND TUTORIAL ON DISKETTE. G-FORTH RUNS ON THE SWTPC COMPUTER, A SINGLE PERCOM LFD-400 DISK WITH MINIDOS, AND 16K.

$69.95
Check or M.O.

GREENE SOFTWARE
P.O. BOX 23
VICTOR, N.Y. 14564
Overseas Add $10.00
N.Y. Add 7% Tax.

30 Day Money Back Guarantee.

Circle 473 on inquiry card.

S-100

INDUSTRY STANDARD THROUGHOUT (IEEE 696)
• Z-80 processor-4Mz • 10 slot motherboard • Enhanced CP/M* • On board monitor • Complete manuals • Line filters • 2-8" Shugart-801R-drives • 64K RAM-expandable to 256 • 2 serial/parallel ports • EPROM programmer, 6K EPROM • 2 Filtered receptacles • Heavy duty power supply.

COMPARE

WE SUPPORT OUR PRODUCTS
Assembled, burned-in, 1 FULL YEAR warranty Technical hotline, newsletter, upgrades. ALSO - Discount software, Zenith, Epson.

$2995 PLUS SHIPPING

COMPUTERIZED MANAGEMENT SYSTEMS
310 1st Ave. S., Seattle, WA 98104
Phone (206) 624-9499/598-4274

*CP/M is a trademark of Digital Research

Circle 115 on inquiry card.

ADVANCED PRODUCTIVITY SYSTEM FOR TRS-80 * MODEL II

Finally a general purpose, high performance productivity system. APS is functionally comparable to the widely acclaimed SPF productivity system used on most large-scale computers. It is fully menu driven and provides Browse, Edit, Utility and Word Processing subsystems as well as split screen support. It is a powerful tool for quickly and efficiently creating, manipulating and revising programs, text files and data files of any size.

The full-screen, general purpose Edit Subsystem supports function keys as well as primary and line commands. A unique dataset isolation feature guarantees dataset integrity while editing.

The Utility Subsystem allows dataset allocation, record format conversion, dataset recovery and more.

Registered users receive full maintenance support. For more information contact:

Arrix Logic Systems Inc.
P.O. Box 142
Don Mills, Ontario
Canada M3C 2R6

* Registered Trademark of Tandy Corporation

Circle 472 on inquiry card.

CRT CONTROLLER



This Intelligent CRT Controller uses an 8085A CPU & an 8275 integrated CRT Controller. It features:

- 25 lines (80 char./line)
- 5x7 dot matrix
- Upper & lower case
- Two 2716's (controller & char. generator)
- Serial interface RS232 & TTL
- Baud rates of 110, 150, 300, 600, 1200, 2400, 4800 and 9600
- Keyboard scanning system
- Unencoded keyboard required
- Uses +5V & ± 12V Power Supplies
- Does not have graphic capabilities.

Documentation includes program listing and composite video circuit.

Bare Board only (withdoc)	$39.95
2716 Char. Gen. A7	$19.95
2716 Program A12	$19.95

A-D CONVERTER

JBEs 16 channel A-D Converter plugs in to your Apple II computer. It uses an ADC0817 which incorporates a 16 channel multiplexer and an 8 bit A-D Converter. The 16 inputs are high impedance and the voltage range is 0 to 5.12volts. Conversion time is <100μsec. The resolution is 8 bits or 256 steps, linearity is ± 1/2 step. Two 16 pin DIP sockets are used for input, GND & reference voltage connections. There are 3 single bit TTL inputs. Doc. Includes sample program.

81-132A Assm.	$89.95
81-132K Kit	$69.95
81-132B Bare Board	$29.95

EPROM PROGRAMMER

JBE's EPROM Programmer is designed to program 5V 2516's, 2532's & 2716's. It interfaces to the JBE Parallel I/O card using four ribbon cables. An LED indicates when the EPROM is being programmed. A textool zero insertion force socket is used for the EPROM. Comes with complete documentation for writing and reading EPROM's in the Apple II or Apple II Plus. Cables available separately.

80-244A Assm.	$49.95
80-244K Kit	$39.95
80-244B Bare Board	$24.95

PARTS

6502 MPU	$9.95
6522 VIA	$9.95
Z-80 MPU	$9.95
Z-80 PIO	$9.95
TWO 2114 RAM	$9.95
2716	$14.95
50 pin conn.	$5.95
Dip Jumper 2 ft.	$4.95

6522 APPLE II INTERFACE

The JBE 6522 Parallel Interface for the Apple II Computer, plugs directly into any slot 1 through 7 in the Apple. This card has 2 6522 VIA's that provide:

- Four 8 bit bi-directional I/O ports
- Four 16 bit programmable timer/counters
- Serial shift registers
- Handshaking

A 74LS05 is for timing. Four 16 pin sockets provide easy connections to other peripheral devices. (Dip jumpers with ribbon cables are also available from JBE) The 6522 Parallel I/O card interfaces to the JBE EPROM programmer. Understanding of machine language required to use this board. Inputs and outputs are TTL compatible.

79-295A	$69.95	Assembled
79-295K	$59.95	Kit
79-295B	$19.95	Bareboard

SPEECH SYNTHESIZERS





JBEs Speech Synthesizers use the Votrax SC-01 Phoneme Synthesizer chip. The SC-01 phonetically synthesizes continuous speech of unlimited vocabulary. The SC-01 contains 64 different phonemes and 4 levels of inflection accessed by an 8 bit code. It requires 10 Bytes per second for continuous speech. Both boards have an audio amp for direct connection to an 8 ohm speaker.

Documentation includes basic user programs, a phoneme chart and listing of coded words to help you get started. Documentation for the Apple II® Speech Synthesizer includes a disk with many user programs.

81-088 Apple II Speech Synthesizer	$139.95
81-120 Parallel Input Speech Synthesizer	$149.95

Prices include the SC-01 Chip
SC-01 sold separately for $ 75.95

EPROM EXPANSION CARD



JBE EPROM Expander for the Apple II holds six 5V 2716s for a total of 12K bytes of EPROM. This board takes the place of the on board ROM in the Apple. It is software switchable by the same technique used by the Apple II firmware card. Solder jumpers are for reset to the Apple ROM or EPROM Expansion Card. Use JBE EPROM Programmer and Parallel I/O to program your EPROMs. EPROMs sold separately.

81-085A Assm.	$59.95
81-085K Kit	$49.95
81-085B Bare Board	$39.95

81-260 "SLIM"

Single board large scale Integration Microcomputer. This 4.5 x 6.5 board uses the 6502 Microprocessor, two 6522 VIA's, four 2114 RAM's, 2516, 2716 or 2532 EPROM. The fully buffered 22/44 pin bus is similar to the KIM®, SYM®, and AIM® expansion connector. The four 8 bit I/O ports connect through 16 pin dip sockets. This board was designed for control and is ideal for Personal and OEM use.

- 6502 MPU
- Two 6522 VIA's
- Four 2114 RAM's (2K bytes)
- One EPROM 2516 or 2532
- Crystal clock 1 Mhz
- Requires 5V 1AMP Power
- 4.5 x 6.5 card
- Power on reset
- Fully buffered-expandable
- Solder mask-both sides

Use your Apple II Computer, JBE 6522 Parallel Interface card and EPROM Programmer as a development system for SLIM.

Prices:

81-260A	$199.95	Assembled
81-260K	$149.95	Kit
81-260B	$ 39.95	Bare Board

6502 MICROCOMPUTER





6502 MPU, 6522 VIA, 2716 EPROM, 2114 RAM single board computer. Single 5 volt power supply at 400 Ma. Two independent 8 bit I/O ports with handshake lines. RC controlled 1 Mhz clock.

Complete documentation. I/O lines use 50 pin edge connector. Data and address lines are not accessible. Mod. for 2532 is included. EPROM is not included. 1K RAM, 2K EPROM, 2 I/O ports.

80-153 Assm.	$110.95
80-153 Kit	$ 89.95
80-153 Bare Board	$ 19.95

Z-80 MICROCOMUTER






Z-80 MPU, Z-80 PIO, 2716 EPROM, 2114 RAM single board computer. Single 5 volt power supply at 300 Ma. Two independent 8 bit I/O ports with handshake lines. RC controlled 2Mhz clock.

Complete documentation. I/O lines use 50 pin edge connector. Data and address lines are not accessible. Mod. for 2532 is included. EPROM is not included. 1K RAM, 2K EPROM, 2 I/O ports.

80-280 Assm.	$129.95
80-280 Kit	$119.95
80-280 Bare Board	$ 19.95

JBE I MICROCOMPUTER



JBE's 7.75 x 11.75 6502 base Microcomputer has the capacity for 16K of EPROM, 4K of RAM, 8 Parallel Ports and 1 Serial Port. Monitor and Tiny Basic are also available. The fully populated version includes:

- 1 6502 CPU
- 4 6522 VIA (8 Parallel I/O Ports)
- 1 AY5-1013 (Serial I/O Ports)
- 8 2114 RAM (4K)
- 2 2716 EPROM (Monitor & Tiny Basic)

The partially populated version includes:

- 1 6502 CPU
- 1 6522 VIA (2 Parallel I/O Ports)
- 1 AY5-1013 (Serial I/O Port)
- 2 2114 RAM (1K)
- 1 2716 EPROM (with Monitor)

Both versions include sockets for 2716s or 2532s, 8 16 pin sockets for I/O interfacing and a DB25 connector for RS232.

All address and data lines are brought off the board to the 50 pin edge connector. (similar to the Apple II bus)

This board also features power on reset and cassette interface.

81-030 C Fully Populated	$349.95
81-030M Partially Populated	$249.95
81-030B Bare Board	$ 89.95
2716 EPROM (with Monitor)	$ 19.95
2715 EPROM (with Tiny Basic	$ 19.95



JOHN BELL ENGINEERING, INC.

MC

ALL PRODUCTS ARE AVAILABLE FROM **JOHN BELL ENGINEERING** • P.O. BOX 338 • REDWOOD CITY, CA 94064
ADD SALES TAX IN CALIFORNIA • ADD 5% SHIPPING & HANDLING 3% FOR ORDERS OVER $100
10% OUTSIDE U.S.A.
SEND FOR CATALOG **(415) 367-1137**

VISA




SPECIALS on INTEGRATED CIRCUITS

6502	7.45	10/6.95	50/6.55	100/6.15
6502A/6512A	8.40	10/7.95	50/7.35	100/6.90
6520 PIA	5.15	10/4.90	50/4.45	100/4.15
6522 VIA	6.45	10/6.10	50/5.75	100/5.45
6532	7.90	10/7.40	50/7.00	100/6.60
2114-L200		3.75	25/3.50	100/3.25
2114-L300		3.15	25/2.90	100/2.65
2716 EPROM		7.00	5/6.45	10/5.90
2532 EPROM				14.50
6116 Hitachi 2K x 8 CMOS RAM				**14.50**
4116				**8 for 17**
Zero Insertion Force 24 pin Socket				2.00
6550 RAM (PET 8K)				12.70
S-100 Wire Wrap Socket				2.40

A P Products 15% OFF
A P Hobby-Blox 15% OFF





MODEM SPECIAL $99

SIGNALMAN Mk1 from Anchor Automation

DIRECT CONNECT Modem with RS232 Cable and Connector included. Fully compatible with all Bell 103 modems. 0 to 300 bps. full duplex. frequency shift keyed modulation. automatic ANSW/ORIG selection. direct connect. audible tone carrier detect indicator. self-contained battery powered.


PET/CBM Version (Mk1P) $169

For Commodore Computers. the Signalman Mk1P includes connector. cable. and machine language software

STAR MODEM Prentice/Livermore Data Systems

RS232 MODEM	**SALE**	**$128**
IEEE 488 MODEM	**SALE**	**$199**
RS232 CCITT		**$170**
IEEE 488 CCITT		**$270**

We carry Apple II+ from Bell & Howell



CASH MANAGEMENT SYSTEM $45
Easy to use. Keeps track of cash disbursements, cash receipts, cash transfers, expenses for up to 50 categories.

FORTH for PET by Cargile/Riley **$50**
Full FIG model with all 79 Standard extensions.
Metacompiler for FORTH for independent object code **30**

KMMM PASCAL for PET/CBM $85
Includes translator for true machine language object code.

EARL for PET/CBM 65
Editor, Assembler, Relocator, Linkeditor.

SuperGraphics - BASIC Language Extensions 30
Fast Machine Language Graphics routines for PET/CBM.

SM-KIT - Super PET/CBM ROM based Utilities 40

commodore



CBM-PET SPECIALS

	list	SALE
8023 Printer – 136 col, 150cps bi-directional	(995)	775
8300 Daisy Wheel – 40 cps bi-directional	(2250)	1750
8032 80 x 25 CRT, business keyboard	(1495)	1100
Super Pet	(1995)	1650
8096 Board (extra 64K RAM for 8032)	(500)	400
8050 Dual Disk Drive - 1 megabyte	(1795)	1345
8250 Dual Disk Drive - 2 megabyte	(2195)	1760
CBM IEEE Modem	(395)	199
4016 full size graphics keyboard	(995)	795
4032 full size graphics keyboard	(1295)	999
4040 Dual Disk Drive - 330,000 bytes	(1295)	999
2031 Single Disk Drive - 165,000 bytes	(695)	550
4022 Tractor Feed Printer	(795)	630
C2N External Cassette Deck	(75)	65
VIC 20 Color Computer	(299)	259
VIC 1515 Graphic Printer	(395)	335
Used CBM/PET Computers		CALL
8024-7 High Speed Printer	(1995)	1345

WE WILL MATCH ANY ADVERTISED PRICE

***** EDUCATIONAL DISCOUNTS *****
Buy 2 PET/CBM Computers, receive 1 FREE

VIC 20 Color Computer	259
VIC 1515 Graphics Printer	335
VIC 3K RAM	36
VIC 8K RAM	54
VIC 16K RAM	112
VIC 1540 Disk Drive	525
VIC Avengers (Invaders)	24
VIC Jupiter Lander	24
VIC Superslot	24
VIC Super Alien	24
VIC Maze (Victory Software)	12
VIC Cosmic Debris (Victory Software)	9
VIC Amok (UMI)	17
TNW 1000 Serial Interface	110
TNW 488/103 with DAA	450
Compute!'s First Book of PET/CBM	11
WordPro 3 Plus - 32K CBM, disk, printer	195
WordPro 4 Plus - 8032, disk, printer	300
OZZ Data Base System for CBM 8032	335
VISICALC for PET, ATARI, or APPLE	190
SM-KIT - PET ROM Utilities	**40**
Programmers Toolkit - PET ROM Utilities	35
PET Spacemaker II ROM Switch	36
2 Meter PET to IEEE or IEEE to IEEE Cable	40
Dust Cover for PET	8
IEEE-Parallel Printer Interface for PET	110
IEEE-RS232 Printer Interface for PET	120
The PET Revealed	12
Library of PET Subroutines	12

RAM/ROM for PET/CBM
4K or 8K bytes of soft ROM with optional Battery Backup.
Adds extra RAM which can be write protected like ROM.
4K Version - $85 8K Version - $120 Battery Backup - $30

EPROM Programmer for CBM/PET 79
Branding Iron with software/hardware for 2716 and 2532.

DISK SPECIALS



SCOTCH (3M) 5"	10/2.45	50/2.35	100/2.30
SCOTCH (3M) 8"	10/2.60	50/2.45	100/2.40
Verbatim 8" Doubled Dens.	10/3.65	50/3.55	100/3.40
Verbatim 5" Datalife	10/2.65	50/2.60	100/2.55
(Add 1.00 for Verbatim 5" plastic storage box)			
BASF 5" soft	10/2.10	20/2.00	100/1.90
Wabash 5"	10/2.30	50/2.25	100/2.15
Wabash 8"	10/2.40	50/2.35	100/2.25

WE STOCK MAXELL DISKS

Diskette Storage Pages		10 for 3.95
Disk Library Cases	8" - 2.85	5" - 2.15
Disk Hub Rings	8" - 50 for 7.50	5" - 50 for 6.00

CASSETTES - AGFA PE-611 PREMIUM
High output, low noise, 5 screw housings.

C-10	10/.56	50/.50	100/.48
C-30	10/.73	50/.68	100/.66

All other lengths available. Write for price list.

SPECIALS

EPSON MX-80 Printer
EPSON MX-80 F/T Printer
EPSON MX-70 Printer
EPSON MX-100 Printer

Centronics 739 Printer with dot graphics	575
STARWRITER Daisy Wheel Printer	**1445**
Zenith ZVM-121 Green Phosphor Monitor	119
Amdek Color Monitor	355
DC Hayes Smartmodem	240
Watanabe Intelligent Plotter	1195

ALL BOOK and SOFTWARE PRICES DISCOUNTED
OSBORNE/McGraw-Hill, HAYDEN, SYBEX, etc.


Synertek Systems

SYM-1 Microcomputer SALE	**199**
SYM BAS-1 BASIC or RAE 1/2 Assembler	85
KTM-2/80 Synertek Video and Keyboard	349
KTM-3/80 Synertek Tubeless Terminal	385



Z90-80 64 K	2170
Z90-82 64K, 1 double dens. drive	2395
Z89-0 48K	1950
Z89-1 48K, 1 drive	2150
Z67 10 Megabyte + Floppy Drive	4495
Z37 1.3 Megabyte Dual Floppy	1495
Z25 High Speed Printer	1195
Z19 Video Terminal (VT-52 compatible)	670
ZVM-121 Green Phosphor Monitor	119
All Zenith Software discounted	





SPECIALS

800 Computer	695	Microsoft BASIC	72
400 - 16K	339	**MISSILE COMMAND**	**32**
810 Disk Drive	449	**ASTEROIDS**	**32**
825 Printer	629	**STAR RAIDERS**	**32**
850 Interface	175	Space Invaders	36
822 Printer	359	Music Composer	45
Paddle Pair	19	Chess	30
Joystick Pair	19	Super Breakout	30
16K RAM	85	**PAC-MAN**	**36**
Assembler/Editor	46	**CENTIPEDE**	**36**
Pilot	68	First Book of Atari	11

Write for prices on other Atari items.

252 Bethlehem Pike
Colmar, PA 18915
215-822-7727


A B Computers

WRITE FOR CATALOG
Add $1.25 per order for shipping. We pay balance of UPS surface charges on all prepaid orders. Prices listed are on cash discount basis. Regular prices slightly higher. Prices subject to change.

Circle 4 on inquiry card.

PRIORITY ONE ELECTRONICS

S-100 CPU



CPU-Z - COMPUPRO
2/4 MHZ Z80 CPU 24 Bit Addressing WOW!

PART NO.	DESCRIPTION	LIST PRICE	OUR PRICE
BDGBT 160A	A & T	$295.00	$199.00
BDGBT 160C	CSC 3-6 MHZ	$395.00	$375.00

DUAL PROCESSOR 8085-8088 - COMPUPRO
6 or 8 MZ Provides true 16 Bit Power with a standard 8 bit S-100 bus.

BDGBT 1612A	A & T 6 MHZ	$425.00	$399.00
BDGBT 1612C	CSC 6/8 MHZ	$525.00	$498.00

SOLID STATE DISK DRIVE, 3500% FASTER!
Not Really, But the Next Best Thing For Godbout 8085/88 Users. Call for Details on M-Drive. See Page 340 of November **BYTE**

BDGBT MD 128K	$1,550.00
BDGBT MD 256K	$3,000.00

2810 Z80 CPU-CA. COMP. SYST.
2/4 MHZ Z80A CPU with RS232C Serial I/O Port complete with Monitor PROM for 2422 Disk Controller

BDCCS 2810A	A & T	$350.00	$280.00

CB2 Z80 CPU - S.S.M.
2/4 MHZ will accept 2716, or 2732, or RAM RUN/STOP and single step switches

BDSSMCB2K	Kit		$260.00
BDSSMCB2A	A & T	$344.00	$310.00
BDSSMZ80M	SSMZ80 Monitor		$89.00

CBIA 8080 CPU - S.S.M.
8080 CPU, 1K RAM, Holds 1 2708, 1 Bit parallel input port.

BDSSMCB1K	Kit		$183.00
BDSSMCB1A	A & T	$252.00	$225.00
BDSSM8080M	SM 8080 Monitor		$59.00

S-100 I/O BOARDS

SYSTEM SUPPORT I - COMPUPRO
Serial port (software prog baud), 4K EPROM OR RAM provision, 15 levels of interrupt, real time clock, optional math processor

PART NO.	DESCRIPTION	LIST PRICE	OUR PRICE
BDGBT162A	Assembled & Tested	$399.00	$360.00
BDGBT162C	CSC	$495.00	$460.00
BDGBT8231	Math Chip		$195.00
BDGBT8232	Math Chip		$195.00
BDGBT162AM1	A&T with 8231 Math Chip		$555.00
BDGBT162CM1	CSC with 8231 Math Chip		$655.00
BDGBT162AM2	A&T with 8232 Math Chip		$555.00
BDGBT162CM2	CSC with 8232 Math Chip		$655.00

MPX CHANNEL BOARD - COMPUPRO
I/O Multiplexer, using 8085A-2 CPU on board

With 4K RAM

BDGBT166A4	A & T	$495.00	$445.00
BDGBT166C4	CSC	$595.00	$535.00

With 16K RAM

BDGBT166A16	A & T	$649.00	$585.00
BDGBT166C16	CSC	$749.00	$675.00

INTERFACER I - COMPUPRO
Two Serial I/O

BDGBT133A	A & T	$249.00	$219.00
BDGBT133C	CSC	$324.00	$298.00

INTERFACER II - COMPUPRO
Three parallel, one serial I/O board

BDGBT150A	A & T	$249.00	$219.00
BDGBT150C	CSC	$324.00	$289.00

INTERFACER III - COMPUPRO
Eight channel multi-use serial I/O board

BDGBT1748A	A & T	$699.00	$629.00
BDGBT1748C	CSC 200 hr. Burn In	$849.00	$750.00

INTERFACER 3 WITH 5 SERIAL PORTS

BDGBT1745A	A & T	$599.00	$559.00
BDGBT1745C	CSC 200 hr. Burn In	$699.00	$629.00

MULTI I/O - MORROW DESIGNS
Three Serial, Two parallel

BDMDSMB3200	A & T	$359.00	$329.00

SWITCHBOARD - MORROW DESIGNS
Two serial I/O, four parallel I/O, one status port, one strobe port

BDMDSSB2411	$299.00	$269.00

I/O4 - SSM
Two serial I/O, two parallel I/O

BDSSMIO4K	Kit		$210.00
BDSSMIO4A	A & T	$290.00	$260.00

I/O 5 - SSM
2 Serial, 3 Parallel including 1 Centronics

BDSSMIO51	A & T	$329.00	$309.00

I/O 8 - SSM
8 Port Serial I/O with Timer

BDSSMIO8A	A & T	$550.00	$495.00

2710 4 PORT SERIAL - CCS
4 Full handshaking RS232 ports and optional 2K ROM

BDCCS271001	A & T	$360.00	$310.00

2719 2 SERIAL & 2 PARALLEL - CCS
2 RS232 C ports, 2 8 bit parallel ports, & optional 2K ROM


BDCCS271901	A & T	$360.00	$325.00

2720 4 PORT PARALLEL - CCS
4 8 bit parallel ports and optional 2K ROM

BDCCS272001	A & T	$250.00	$225.00

S-100 10 MHZ STATIC RAM
NEW LOW PRICES!

RAM 20 - 32K
SALE $299.00



32K STATIC RAM - COMPUPRO
RAM 20 10 MHZ, 4K byte block disable, bank select or 24 bit addressing available 8, 16, 24 or 32K

PART NO.	DESCRIPTION	LIST PRICE	OUR PRICE
BDGBT164AA8	8K A&T	$210.00	$190.00
BDGBT164AC8	8K CSC	$280.00	$260.00
BDGBT164AA16	16K A&T	$285.00	$260.00
BDGBT164AC16	16K CSC	$355.00	$325.00
BDGBT164AA24	24K A&T	$355.00	$325.00
BDGBT164AC24	24K CSC	$425.00	$385.00
BDGBT164AA32	32K A&T	$425.00	$299.00
BDGBT164AC32	32K CSC	$495.00	$450.00

CMOS STATIC RAM
For a complete analysis of the advantages of CMOS memory, see the "Product Description" on page 416 of the January Issue of **BYTE.**

64K CMOS STATIC RAM - COMPUPRO
RAM 17, 10 MHZ, 2 Watt, DMA Compatable 24 Bit Addressing

BDGBT175A48	48K A&T	$650.00	$619.00
BDGBT175C48	48K CSC 200hr.	$750.00	$710.00
BDGBT175A64	64K A&T	$795.00	$755.00
BDGBT175C64	64K CSC 200hr.	$895.00	$850.00

NEW! 32K x 16 BIT CMOS STATIC RAM - COMPUPRO
RAM 16 10 MHZ, 32K x 16 or 64K x 8 IEEE/696 16 BIT 2 Watt, 24 Bit Addressing

BDGBT1BDA	64K A&T	$895.00	$850.00
BDGBT180C	64K CSC	$995.00	$945.00

NEW! 128K NMOS STATIC RAM - COMPUPRO
RAM 21 10MHZ 128K X 8 OR 64K x 16 IEEE/696 8 or 16 Bit 1.2 Amps 24 Bit Addressing

BDGBT167A	128K A&T	$1695.00	$1610.00
BDGBT167C	128K CSC	$1895.00	$1795.00

S-100 PROM

PBI PROM PROGRAMMER - SSM
Programs 2708 or 2716's, operates as a 4K/8K EPROM BOARD AS WELL.

BDSSMPB1K	Kit		$179.00
BDSSMPB1A	A & T	$265.00	$220.00

ECONOROM 2708 - COMPUPRO
16K x 8 EPROM Board using 2708, Power on jump to any 256 byte

BDGBT125A	A & T	$135.00	$120.00
BDGBT125C	CSC	$195.00	$175.00

MB8A - SSM
1K/16K 2708 EPROM board, disable in 1K increments

BDSSMMB8AK	Kit		$114.00
BDSSMMB8AA	A & T	$179.00	$159.00

S-100 VIDEO BOARDS

SPECTRUM - COMPUPRO
Color Graphics board with Parallel I/O

BDGBT144A	A & T	$399.00	$349.00
BDGBT144C	CSC	$449.00	$399.00
BDGBT20	Sublogic Universal Graphics Interpreter Software		$35.00

VB - 3 S.S.M.
80 x 25 or 50 character video display Memory Mapped, Parallel Keyboard port

BDSSMVB3K24	80 x 24 Kit		$425.00
BDSSMVB3A24	80 x 24 A&T	$499.00	$440.00
BDSSMVB3UP	80 x 50 Line Upgrade		$ 39.00

VB2-S.S.M.
I/O Mapped Video Board, with Parallel Keyboard port 64 x 16

BDSSMVB2K	Kit		$199.00
BDSSMVB2A	A & T	$269.00	$229.00


VBBB - S.S.M
Memory Mapped Video Board 64 x 16 character display or 64 x 16 graphics display

BDSSMVB1K	Kit		$179.00
BDSSMVB1A	A & T	$242.00	$220.00

S-100 MOTHERBOARDS - COMPUPRO
Active termination, 6-12-20 slot

BDGBT153A	A&T 6 slot, 2 lbs	$140.00	$126.00
BDGBT153C	CSC 6 slot, 2 lbs.	$190.00	$175.00
BDGBT154A	A&T 12 slot, 3 lbs.	$175.00	$155.00
BDGBT154C	CSC 12 slot, 3 lbs.	$240.00	$220.00
BDGBT155A	A&T 20 slot, 4 lbs.	$265.00	$235.00
BDGTB155C	CSC 20 slot, 4 lbs.	$340.00	$310.00

S-100 DYNAMIC RAM



THE EXPANDABLE 1
PRIORITY 1 ELECTRONICS

THE EXPANDABLE 1™ 64K Dynamic Ram board provides your S-100 system with 64K of reliable, high-speed dynamic RAM. Compatable with most of the major S-100 systems on the market, including those with front panels, it supports DMA operations and requires no Wait states with current microprocessors.
• User expandable from 16 to 64K • Supports DMA • Designed to IEEE proposed S-100 bus standards • 2 or 4 MHz operation • Operates with either an 8080 or Z-80 based S-100 system, providing processor-transparent refreshes with both • Supports IMSAI-type front panels • Jumper-selectable Phantom input • Uses Popular 4116 RAMS • All ICs in sockets • Any 16K block can be made bank-independent • Fully buffered address and data lines • Fail-safe refresh circuitry for extended Wait states • Board configuration with reliable, easy-to-configure Berg jumpers

BDPRIEXP116	16K Assembled & Tested	$299.00
BDPRIEXP132	32K Assembled & Tested	$339.00
BDPRIEXP148	48K Assembled & Tested	$379.00
BDPRIEXP164	64K Assembled & Tested	$409.00

S-100 DISK CONTROLLERS

2422A - CA. COMP. SYST.
I/O Mapped, controls 8", single or double density A&T with CPM 2.2 8" S.D.

	LIST PRICE	OUR PRICE
BDCCS2422A	$475.00	$375.00

DISK JOCKEY 2D - MORROW
Memory Mapped, controls 8", single or double density, serial I/O

BDMDIDJ2208	A&T with CP/M 2.2	$399.00	$375.00

S-100 DISK SUBSYSTEMS


DJ2B DISCUS SINGLE SIDED MORROW
8" DBL Density drives with cabinet, power supply controller, with CP/M 2.2 and Microsoft Basic

BDMDSF1218	Single Drive System	$1095.00	$950.00
BDMDSF122B	Dual Drive System	$1875.00	$1598.00

DJ2B DISCUS DOUBLE SIDED - MORROW
8" DBL Density/sided drives with cabinet Power supply controller, with CP/M 2.2 and Microsoft Basic

BDMDSF2218	Single Drive System	$1395.00	$1250.00
BDMDSF2228	Dual Drive System	$2495.00	$2050.00

S-100 HARD DISK - MORROW



5.25" 5MB, 8" 10 & 20MB, 14" 26MB formatted hard disk complete with cabinet, P.S., Controller, CP/M 2.2 and Microsoft MBASIC 80

		LIST PRICE	SALE PRICE
BDMDSDMAM5	5 MB	$2495.00	$1995.00
BDMDSM10S	10 MB	$3695.00	$2950.00
BDMDSM20S	20 MB	$4795.00	$3825.00
BDMDSM26S	26 MB	$4495.00	$3495.00

WOW!




OUTPERFORMS MONITORS OF TWICE THE PRICE
USI has the competition buckling at their knees! You can have a professional performing Video Monitor for a **fraction of the cost!** *The USI EV2131N is a 12" Green, high resolution data display compatable with 80 x 24 computer formats*

BDUSIEV2131N	24 lbs.	$149.00

Circle 334 on inquiry card.

PRIORITY ONE ELECTRONICS

COMPUPRO DMA DISK 1 WITH FREE CP/M 2.2 SALE $450.00



SAVE $220.00

Priority 1 Electronics is pleased to offer the GODBOUT DISK 1 High Performance Disk Controller at our regular low price with CP/M 2.2 and BIOS at no additional cost. That's a savings of $220.00 of the manufacturer's list price.

- Third generation INTEL 8272/NEC 765A LSI floppy disk controller.
- High speed cycle stealing DMA interface for processor independent data transfer between system memory and flexible disk.
- Handles up to four 8 or 5.25 inch floppy disk drives
- Single or double density/single or double sided capability.
- Supports IBM 3740 soft sectored formats.
- 24 bit DMA addressing with data transfer across 64K boundaries for data transfer throughout the 16Mbyte memory map.

PART NO.	DESCRIPTION	LIST PRICE	OUR PRICE
BDPDB171ACPM	A&T w/CP/M 2.2 & BIOS	$670.00	$450.00
BDGBT171C	CSC	$595.00	$555.00
BDGBTCPM80*	CP/M 2.2 for Z80/8085 with manuals & BIOS 8" S/D disk		$175.00
BDGBTOAS8S	Oasis 8 bit single user 8" S/D disk		$500.00
BDGBTOAS8M	Oasis 8 bit multiuser, 8" S/D disk		$850.00

S-100 SYSTEMS
SUPERSIXTEEN — COMPUPRO
HERE IS WHAT EACH PACKAGE INCLUDES:

BDGBT1612A 6 MHz 8085/8088 Dual Processor Board
BDGBT171A High Speed DMA Disk Controller
BDGBT162A System Support 1 Multi-Function Board
BDGBT133A Interfacer 1 Dual Serial I/O
BD128K 10MHz Low Power Static Ram
BDGBTCP/M 86 16 Bit Operating System Ready to Load & Go
Cables and Documentation Three interfacer cables one disk I/O cable, complete documentator for all hardware, and manuals for both CP/M operating systems.
Compu Pro's famous 1 Year limited warranty.

Now to the best part of all. If purchased separately, these quality components would list for $4,344.00. BUT SuperSixteen's low package price is an amazing $3,495.00. You save $849.00!(For boards qualified under the Certified System Component high-reliability program - with extended 2 year warranty, 200 hour burn-in and 6/8 MHz processors - add $600.00 to the package price. Sh. Wt. 15 lbs.

BDPDBGBTSJ	SuperSixteen A&T	$3495.00
BDPDBGBTSX	SuperSixteen CSC	$4095.00

PRINTERS





MICROLINE — OKIDATA
WITH FRICTION AND TRACTOR FEED

- BI-DIRECTIONAL - 120 CPS
- 9/9 Matrix (Alphanumeric)
- 6/9 or 12 Matrix for Graphics
- 5,8.3, 10, 16 Charactrsp/Inch
- 6 or 8 Lines per Inch
- 80 CPL @ 10 CPI for 82A
- 132 CPL @ 10 CPI for 83A
- Parallel and Serial I/O
- 100 Thru 1200 Baud
- Self Test
- Out of Paper Switch
- Friction or Tractor Feed
- 3" to 14" Top of Form (Switch Selectable)
- 10 Different Character Sets

PART NO.	DESCRIPTION	LIST PRICE	SALE PRICE
BDDKIDAT82AT(26 lbs)	8 80 CPL @ 10 CPI	$ 799.00	$539.00
BDDKIDAT83AT (37 lbs)	132 CPL @ 10 CPI	$1195.00	$750.00
BDDKISER2KBF	9600 baud with 2K Serial Buffer upgrade with X-on Y-off		$159.00
BDDKIGRAPH	High Resolution Graphics Prom		$99.00

CALL FOR THE NEW MICROLINE 84

MX80 — EPSON
NEED WE SAY MORE?

BDEPNMX80	Tractor Feed 17 lbs	$645.00	$450.00
BDEPNMX100	132 Col. Tractor Feed 24 lbs		$725.00

PRINTER INTERFACES - MICROBYTE
RS232 Serial Conversion for MX80 & MX100

BDMBSSEI1	A & T	$55.00
	Apple Centronics 8 bit parallel interface for Centronics, Epson & OKIDATA printers	
BDMBSAEI1	A & T	$55.00
BDMBSAEC1	Cable for above	$14.95

Printer interfaces & cables sold only with printer purchase

S-100 MAINFRAMES



S-100 MICROFRAME - TEI
110V 60HZ CVT Mainframes, the best money can buy!
12 Slot ±8V 17A±16V @ 2A
22 Slot ±8V @ 30A± 16V @ 4A

PART NO.		LIST PRICE	OUR PRICE 1-9	10-24
BDTEIMCS 112	12 Slot Desk	$685.00	$615.00	$570.00
BDTEIMCS 122	22 Slot Desk	$825.00	$760.00	$705.00
BDTEIRM 12	12 Slot Rackmount	$725.00	$720.00	$619.00
BDTEIRM 22	22 Slot Rackmount	$875.00	$850.00	$750.00

Shipping Weight: On 12 Slot Mainframe 45 lbs.
On 22 Slot Mainframes 55 lbs.

TEI S-100 FRAMES 3 - 5" DISK CUTOUTS
±8V @ 17±16V @ 1.2A, Internal Cables

			1-9	10-24
BDTEITF12	12 Slot desk	$675.00	$625.00	$580.00
BDTEIRF12	12 Slot Rackmount	$795.00	$715.00	$665.00

Shipping Weight: On 12 Slot Desk 40 lbs.
On 12 Slot Rackmount 45 lbs.

DUAL 8" DISK DRIVE CHASSIS - TEI
For Shugart 800/801R or 850/851R with internal power cables provided
+24V @ 1.5A+5V @ 1.0A - 5V @ .25A

			1-9	10-24
BDTEBCFDD	Desk Top	$535.00	$485.00	$455.00
BDTEIRFDD	Rack Mount	$720.00	$670.00	$630.00

CALL FOR NEW TEI PRICES APRIL 1st



S-100 MAINFRAME - COMPUPRO
110V 60HZ CVT Mainframe uses famous 20 slot GODBOUT Motherboard. 55 lbs.

BDGBTENC20RM	20 Slot Rack Mount	$895.00	$825.00
BDGBTENC20DK	20 Slot Desk Top	$825.00	$760.00

S-100 MAINFRAME - CCS
12-slot motherboard with removable termination card

BDCCS220001	Office Cream	35 lbs	$575.00	$535.00
BDCCS220002	Blue	35 lbs	$575.00	$535.00

SOFTWARE - MICROPRO
All software is supplied on 8" Single Density IBM 3740 CP/M Compatable Diskettes

WORDSTAR
Screen-Oriented, integrated word processing system specifically designed for non-technical personnel
BDMPRWRDSTAI $495.00 $300.00

MAIL MERGE WORD STAR OPTION
Powerful file merging tool
BDMPRMLMRGAI(Requires Word Star 2.1 or later) $250.00 $100.00

SPELLSTAR WORD STAR OPTION
One Step "Proofreader" with compressed 20,000 word dictionary and user-created supplemental dictionaries
BDMPRSPLSTAI (Requires Word Star 3.0 or later) $250.00 $150.00


SUPERSORT
Sophisticated program that will select and re-arrange variable length information from data files
BDMPRSPRSRAI $250.00 $150.00

CALC STAR
Sophisticated, easy-to-use, electronic spread sheet and financial planner
BDMPRCLCSTAI $295.00 $200.00

DATA STAR
Office-Oriented Data Entry, retrieval, and updating system
BDMPRDATSTAI $350.00 $200.00

FLOPPY DISC DRIVES

Tandon TM-800 Thinline is exactly half the size of conventional 8" floppy disk drives.



Exactly one-half the height of any other model.
Propietary, high-resolution, read-write heads patented by Tandon
D.C. only operation - no A.C. required
Industry standard interface.
Three millisecond track-to-track access time 9 lbs.

BDTNDTM8481	Single Sided $425.00	2 or more	$395.00
BDTNDTM8482	Double Sided $575.00	2 or more	$550.00
BDTNDTM8M	Manual - not included with drive		$ 10.00

801R - SHUGART
Single sided double density most popular 8" drive

BDSHU801R	$425.00 ea or 2 or more (16 lbs) for	$395.00 ea.
BDSHUSA801RM	Manual for 801R drives	$ 10.00

DT-8 - QUME

DT-8 - QUME
2 OR MORE $499.00

Data track 8 double sided, double density 8"

BDQMEDT8WH	Sh. Wt. 16 lbs	$525.00 ea.

2 or more $499.00 each

BDQMEDT8M	Manual for DT-8	$ 10.00

5¼" DRIVES - TANDON

BDTNDTM1001	Single Sided, 250KB (5 lbs)	$310.00
BDTNDTM1002	Double Sided, 500KB	$370.00
BDTNDTM1003	Single Sided, 500KB	$375.00
BDTNDTM1004	Double Sided, 1000KB	$495.00
BDTNDTM5M	Manual, not included with drive	$ 10.00

DISK CABINETS



V-100 - VISTA
- Desk or rack mountable • Internal power and data cables
- Drives pull out for easy service and maintenance

BDVISV100 Disk Drive Cabinet (43 lbs) $495.00 $449.00

SINGLE 8" - Q.T.
Single 8" cabinet with power supply
BDQTCDDC8 (22 lbs) $249.00 $225.00

DUAL 8" - Q.T.
Dual 8' cabinet with power supply
BDQTCDDC88 (24) $395.00 $349.00

5" CABINETS - VISTA

BDVIS 9801	Single 5" with P.S.	$75.00
BDVIS 9802	Dual 5" with P.S.	$95.00

TERMINALS



VIEWPOINT — ADDS
Detachable keyboard, RS232 interface and auxiliary port, 80 x 24 display, tiltable screen
BDADDVWPR Shipping Weight 40 lbs $699.00 SALE $525.00

VT200 — VISUAL TECHNOLOGY
THE MOST RELIABLE TERMINAL WE'VE EVER USED!
Detachable keyboard, RS232C or 20MA interface, 110 to 19200 baud, 12" non glare 80 x 24 display, RS232 Aux. port and composite video out.
BDVSL200 Shipping Weight 55 lbs. $995.00









9161-B DEERING AVE ● CHATSWORTH, CA 91311

ORDER TOLL FREE (800) 423-5922 CA, AK, HI CALL (213) 709-5464

Terms U.S. VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs. plus 25¢ for each additional pound. Orders over 50 lbs. sent freight collect. Just in case, please include your phone no. Prices subject to change without notice. We will do our best to maintain prices through April, 1982. Credit Card orders will be charged appropriate freight. See November **BYTE** for 60 page Catalog or send $1.00 for your copy today. Sale prices are for prepaid orders only.


Circle 334 on inquiry card.

PRIORITY ONE ELECTRONICS

PROTECT YOUR INVESTMENT
PROTECT YOUR DATA WITH

GSC ISOBAR

With Built-In Noise Filters and Surge Suppressors



ISOLATES SENSITIVE AND VALUABLE EQUIPMENT FROM: *Equipment interaction - Damaging High Voltage Spikes - AC line noise and hash.*
PROTECTS AGAINST: *Voltage transients caused by lightning, contact switching, turn-off of inductive components, noise due to electromagnetic coupling.*
USE THE GSC ISOBAR TO ISOLATE: Microprocessor from peripherals - Lab instruments from noisy equipment - Sensitive pre-amp or tape deck from power amplifier.
THE GSC ISOBAR ELIMINATES: Equipment interaction - Equipment damage from power line spikes and surges - Errors - False printouts - Disk Skips - Audio or video hash.
FEATURES: Inductive isolated ground- Sockets individually filter isolated - Circuit breaker protected at 15A
VOLTAGE TRANSIENT SPIKE PROTECTION: 2000 A peak for up to 6 Sec duration spikes. 1000A, 8/20 Sec protection from repeated spikes.
LOAD HANDLING: 1875 W max. total load; 15A per socket.
INPUT: 125 VAC, 15 amps; standard 3-prong plug.

IBAR 3 Three common outlets built-in circuit breaker, pilot light, hang-up bracket and a 6 foot cord.

		LIST PRICE	OUR PRICE
BDGOFIBAR3	SH. WT. 3 lbs.	$59.95	**$39.95**

IBAR 46- Four independently isolated outlets. Built-in 15A circuit breaker, pilot light, switch, and 6 foot cord.

BDGOFIBAR46	SH. WT. 4 lbs.	$79.95	**$49.95**


IBAR 86 - 8 outlets, grouped to form 4 independently isolated sets of two. Built in 15A circuit breaker, on/off switch, pilot light.

BDGOFIBAR86	SH. WT. 5 lbs.	$84.95	**$54.95**

IBAR 9RM- Eight rear-mounted outlets grouped to form four independently isolated sets of two, plus one non-isolated convenience outlet on front face. 19" rack mount cabinet. Built in 15A circuit breaker, pilot light, on/off switch, and 6 foot cord.

BDGOFIBAR9RM	SH. WT. 6 lbs.	$99.95	**$74.95**

RS232 Breakout Box



A must for every technician, repair man or systems integrator

The Breakout Box contains 24 Dual-In-Line Switches which allow any of the interface signals (except Pin 1, which is not used) to be interrupted. The switches are located in the center of the main control panel. A 25 way female connector for connecting the box to the DTE is fitted to the left hand side via a ribbon cable and a 25 way male connector for connection to the DCE is similarly connected to the right hand side.

DTE and DCE interface connection pins are located on both sides of the Dual-In-Line switches. Using the jumpers supplied, these pins permit monitoring of any of the interface lines with either or both the positive and negative test indicators on the front panel. These pins also permit cross-patching or the connection of an external test meter or oscilloscope.

The Breakout Box contains indicators which monitor the following signals

Pin	Function
2	Transmitted Data
3	Received Data
4	Request to Send
5	Ready for Sending (clear to send)
6	Data Set Ready
8	Data Channel Received Line Signal Detector
15	Transmitter Signal Element Timing
17	Receiver Signal Element Timing
20	Connect Data Set to Line/Data Terminal Ready
21	Signal Quality
22	Ring Indicator
25	Busy

Breakout box is contained in a tough plastic case and is powered by two 1.5 volt penlight batteries. No power is consumed by the tester when not in use. Dimensions 2.9" x 5.55" x 1.45" Weight 10 ounces, with batteries

BDDNW232BOX	$199.00	**$159.00**

GLOBAL SPECIALTIES LOGIC PROBES

SPECIFICATIONS *Shipping Wt. 2 lbs*

MODEL	LP1	LP2	LP3
Response	50 ns. 80 ns. single shot event, 10MHz pulse train	500 ns. 1.5MHz pulse train	6 ns typical. tested at 10 ns. 70MHz pulse train
Pulse Mode	High Speed Train or Single Event		

Part No.	Description	List Price	Our Price
BDGSCLP1	Standard 10MHz w/Memory	$50.00	**$45.00**
BDGSCLP2	Economy 1.5MHz	$32.00	**$30.00**
BDGSCLP3	High Speed 70MHz w/Memory	$77.00	**$69.00**
BDGSCOP1	High speed Digital Pulser 100 PPS or single shot	$83.00	**$76.00**
BDGSCLTC1	LP1, DP1 and LM1 in molded case	$240.00	**$220.00**
BDGSCLTC2	LP3, DP1 and LM1 in molded case	$270.00	**$245.00**

MICROCOMPUTER PRODUCTS

MEMORY

PART NO.	PRICE
BD4116AC20	8/$18.00
BD2016P3	8/$72.00
BD2114N3L	8/$28.00
BD5257N3L	8/$50.00
BD2732	8/$120.00
BD2716	8/$50.00
BD2708	8/$20.00

Z80 SERIES

BDZ80A	$14.95
BDZ80AP10	$14.95
BDZ80ACTC	$13.95
BDZ80ADMA	$45.00
BDZ80AS100	$59.95
BDZ80AS101	$59.95
BDZ80AS102	$59.95

UARTS

BDAY51013A	$5.95
BDTR1602B	$5.95
BDTR1863	$6.95
BDIM6402	$7.95

8080 SERIES


PART NO.	PRICE
BDINS 8080A	$5.50
BDINS 8085A	$19.95
BDDP8212N	$2.95
BDDP8214N	$5.25
BDDP8216N	$2.95
BDDP8224N	$3.25
BDDP8224-4N	$9.95
BDDP8226N	$3.50
BDDP8228N	$5.55
BDDP8238N	$5.55
BDINS8250N	$15.00
BDINS8251N	$7.50
BDINS8253N	$17.95
BDINS8255N	$6.80
BDINS8257N	$16.45
BDINS8259N	$18.00
BDINS8275N	$59.95
BDINS8279N	$49.95

FLOPPY DISC CONTROLLER

BDFD1771B-01	$24.95
BDFD1791B-01	$44.95

KEITHLEY

Handheld DMMs For Every Application and Budget



Easy-to-use Rotary Switches
Large 0.6" LCD displays
dc Voltage
ac Voltage
dc Current
ac Current
Resistance
Diode Test
3½ or 4½ Digit Accuracy
Overload Protection
Externally Accessable Battery & Fuse
Rugged 0.1" ABS Plastic Case
Shock-Mounted PC Board

4½ Digits $235.00


BDKTH130	**#0.5% DCV accuracy, 10M input** impedence auto polarity and current measurement through 10A	**$124.00**
BDKTH131	Same as BDKTH130 except 0.25% accuracy and enhanced band with on top ACV ranges	**$139.00**
BDKTH128	See/hear display includes both over/under threshold indicator arrows, audible tone that operates on all ranges & functions, and adjustable threshold	**$139.00**
BDKTH135	4½ digit, 0.05% accuracy	**$235.00**
BDKTH870	Thermocouple(TC)based themometer	**$199.00**
BDKTH1304	Soft Carrying Case & Stand(handhelds)	**$ 10.00**
BDKTH1306	Deluxe Carrying Case (handhelds)	**$ 25.00**

LCD & LED Bench DMMs

BDKTH169	3½ Digit, LCD Display	**$189.00**
BDKTH176	4½ Digit, LCD Display	**$269.00**
BDKTH179A	4½ Digit, LED Dispay, TRMS	**$359.00**
BDKTH1793	IEEE-488 Interface(Model 179A)	**$325.00**


See pp. 42-43 of our Engineering Selection Guide in the November **BYTE** for a complete list of specifications and accessories.

SPECIAL PURCHASE
16 PIN LOW PROFILE IC. C95 SOCKETS
GOLD



BCTIG16LP pkg of 100 .... **$16.00**
BCTIG16LP pkg of 1000 .... **$120.00**
OEMS Stock up at this LOW PRICE!

ZERO INSERTION FORCE TEST SOCKETS



	1-9	10-24
BCZIP16 DIP	$ 5.50	$5.35
BCZIP24 DIP	$ 7.50	$7.25
BCZIP40 DIP	$10.25	$9.85

ANCHOR AUTOMATION — THE SIGNALMAN MK I

MODEM PRICE BREAKTHROUGH!




PRODUCT FEATURES
- Direct Connect Modem
- Built-in RS232C Cable and Connector
- Self-contained 9V Battery — Wall plug transformer available.
- Audible carrier detect signal.
- Automatic mode selection.
- Talk/Data switch.
- CONNECTS IN SERIES WITH MODULAR *HANDSET* JACK ON TELEPHONE
- Complete with RS232C and Modular Handset Cables, eliminates need to buy cables — save $20.00 -$30.00, assures correct fit.
- Uses low cost 9V battery. Eliminates unsightly cords and need for "another" AC outlet. Optional plug-in transformer available.
- Audio Transducer eliminates need to view LED to confirm connection — can be placed anywhere (velcro tape provided)
- Advanced IC Circuitry eliminates confusion of who is originator — ends need to manually switch from Originate to Answer and Vice/Versa.
- Permits you to listen/talk on phone or switch to data communications mode.
- Permits you to communicate with most other computer networks.
- Small size, light weight permits you to install the SIGNALMAN anywhere.
- Lowest priced modem available.

ROBINSON-NUGENT ICN SERIES GOLD 3 LEVEL WIRE WRAP SOCKETS

- 10 μ in GOLD Plated Pins
- Deep Chamfered Closed Entry Contacts
- RN Side Wipe Contact Design
- Phosphor Bronze Contact Material
- Terminal Barbs Allow Self-lock into PC Board
- Rugged Socket Body Design
- Deep Chamfered Closed Entry Contacts

PART NO.	PINS	PRICE 1-9	10-24	25-99	100-249	250-999
BDRNS08WWG	8	.60	.55	.49	.45	.41
BDRNS14WWG	14	.75	.70	.65	.55	.48
BDRNS16WWG	16	.85	.75	.70	.60	.52
BDRNS18WWG	18	1.00	.90	.80	.75	.71
BDRNS20WWG	20	1.20	1.05	.96	.91	.87
BDRNS22WWG	22	1.35	1.25	1.15	1.05	.99
BDRNS24WWG	24	1.35	1.25	1.15	1.05	.99
BDRNS28WWG	28	1.70	1.55	1.40	1.34	1.25
BDRNS40WWG	40	2.20	2.05	1.85	1.60	1.50

GOLD PLATED CONTACTS



TIN PLATED TAILS

NEW!
SELECTIVE PLATED PINS THAT WILL SAVE YOU MONEY BY HAVING GOLD ONLY WHERE IT COUNTS!
Same as above except pins are selectively plated.

PART NO.	PINS	PRICE 1-9	10-24	25-99	100-24	250-99
BDRNS08TWW	8	.55	.50	.45	.41	.37
BDRNS14TWW	14	.65	.55	.50	.47	.44
BDRNS16TWW	16	.75	.65	.52	.51	.46
BDRNS18TWW	18	.90	.79	.75	.70	.65
BDRNS20TWW	20	1.10	.95	.91	.87	.82
BDRNS22TWW	22	1.25	1.15	1.05	.94	.89
BDRNS24TWW	24	1.25	1.15	1.05	.96	.89
BDRNS28TWW	28	1.50	1.45	1.35	1.25	1.15
BDRNS40TWW	40	2.00	1.80	1.60	1.40	1.30

D-SUBMINIATURE CONNECTORS

25 Pin Solder Type

BDCNDDB25P	25 Pin Male	$3.00	$2.75	$2.25

★ ***BDCNDDB25P*** *100 pcs at* ***$1.95 ea*** ★

BDCNDDB25S	25 Pin Female	$4.00	$3.75	$3.00

★ ***BDCNDDB25S*** *100 pcs at* ***$2.95 ea*** ★

BDCNDDB51226	2 Pc. Black Hood	$1.90	$1.65	$1.45
BDCNDDB51212	1 Pc. Grey Hood	$1.60	$1.45	$1.30
BDCNDP25H	2 Pc. Grey Hood	$1.50	$1.25	$1.10

Call for other D-Subminiature connectors




9161-B DEERING AVE ● CHATSWORTH, CA 91311

ORDER TOLL FREE (800) 423-5922 CA, AK, HI CALL (213) 709-5464

Terms U.S. VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs. plus 25¢ for each additional pound. Orders over 50 lbs sent freight collect. Just in case, please include your phone no. Prices subject to change without notice. We will do our beest to maintain prices through April, 1982. Credit Card orders will be charged appropriate freight. See November **BYTE** for 60 page Catalog or send $1.00 for your copy today. Sale prices are for prepaid orders only.

HARD DISK FOR LESS THAN FLOPPIES



DISCUS M5 by MORROW DESIGNS

PRIORITY 1 ONE ELECTRONICS

INTRODUCTORY PRICE: $1995.00

LIST PRICE: $2495.00

PRIORITY 1 ELECTRONICS is pleased to announce Morrow Designs' DISCUS M5, the lowest cost 5 megabyte Winchester sub-system and the fastest. Now you can afford a hard disk for the price of floppies. Morrow Designs is the largest supplier of hard disk sub-systems to the S-100 market. With the new DMA Hard Disk Controller and the ST506 mini-Winchester drive, Morrow has attained speeds over 600,000 bytes per second.

As with all Morrow Designs' systems, Morrow delivers it complete. Drive, controller, cabinet, power supply, fan, transformer, cables, *CP/M 2.2*™ operating system, *Microsoft*™ Basic 80 and a ninety day warranty.

The DISCUS M5 regularly sells for $2495.00. *Priority 1 Electronics* is proud to offer the DISCUS M5 for a limited time at only $1995.00. Winchester speed, 5Mb capacity and reliability for only $1995.00. Three additional drives may be daisy-chained to the controller for future expansion. Perfect to back up each other at the end of each day. Takes seconds, is more reliable than tape and with the outside lock can be unplugged and removed (after the locking screw has been put in place.)

A few facts about the ST506 drive which is being used in the Discus M5:

Key Features:

- Storage Capacity of 6.38 megabytes unformatted, 5.0 megabytes formatted as shipped
- Same physical size and mounting as the mini-floppy
- Same DC voltages as the minifloppy
- Band actuator and stepper motor head positioning
- 5.0 megabit/second transfer rate
- Same track capacity as a double density 8 inch floppy
- 170 millisecond random average access time, reduceable to 95 ms via a simple software algorithm
- The only single S-100 DMA Hard disk controller board on the market today
- Fully compatable with high speed 6MHz and 8 MHz CPUs of today and tomorrow
- DMA bus arbitration as outlined by the IEEE 696 standard
- Controls 1 to 4 soft sectored Winchester drives
- Supports both 5¼" and 8" drives

CPM is a registered Trademark of Digital Research.

- ST506 or SA 1000 interface compatable
- Variable sector length (256, 512, 1024, or 2048 byte sectors)
- Automatic CRC generation and checking
- Addresses 1 to 16 heads
- Addresses an infinite number of tracks
- Contains its own on-board microprocessor
- 24-bit address burst DMA transfers
- Channel driven
- All disk driver routines resident on the controller
- Variable format
- No buffering required
- Maximum transfer rate 5,000,000 bits per second
- Due to this high transfer rate, a minimum CPU speed of 2.5MHz is required

Pure Speed

The speed of this Winchester controller is enhanced by Morrow's channel driven concept. This DMA hard disk controller (DMAHDC) picks up its commands from the host processor via memory on the system bus. The host processor writes commands into memory and then picks them up during DMA cycles from this memory. The channel, commands and transfers may be located anywhere in the 24-bit address range. At the completion of the command, the controller returns appropriate status and can generate an interrupt. Commands may be chained together by the CPU to allow the controller to execute many commands in succession, generating an interrupt at the end of each command and/or at the end of the completed command chain.

Communications

An imbedded microprocessor enables the user to easily communicate with this intelligent device. All low level disk drive routines are resident on the controller itself.

These include:

format	write a sector
seek	return status
read a header	set DMA address
read a sector	set channel address

Variable sector lengths are available. On Morrow Designs system products 512 byte sector lengths are standard. This is being done to maximize the capacities available on current drive units but may be varied by independent system integrators when desired.

The DMAHDC has been designed for expansion. One to four drives can be attached directly and controlled. One to sixteen drive heads may be addressed. Any number of tracks may be specified during the seek routine by specifying one to two hundred and fifty-six tracks one or more times. Each of the expansion abilities prepare the user to upgrade his system as technology advances to additional platters and tracks.

The controller has no peer today in the S-100 bus market.

Systems Interfaced:

1. North Star
2. Cromemco
3. Vector Graphics
4. Dynabyte
5. Micromation
6. Exidy
7. Imsai
8. Sol
9. California Computer
10. Godbout
11. Ithaca Intersystem

Look to Morrow for answers!

Look to PRIORITY 1 for the best price!

Priority 1 Electronics, as the world's largest stocking distributor of Morrow Designs' products committed to buy an entire production run of DISCUS M5 sub-systems so we can offer them at a special introductory low price. The DISCUS M5 is a good buy at the list price of $2495.00. The DISCUS M5 is an *excellent* value at our introductory low price of:

$1995.00

BOMOSDMAM5	*Software suplied on 8" IBM3740 disk with blank I/O and INSTALL program*
BOMOSDMAM52B	*Software configured for Morrow DJ/2B controller and Mult I/O as console*
BOMOSDMAM5DMA	*Software configured for Morrow DJ/DMA controller and Mult I/O as console*
BOMOSDMAM55S	*Software supplied on 5¼" soft sector (IBM/Cromemco disk w/blank I/O and INSTALL program)*
BOMOSDMAM5NS	*Software supplied on 5¼" 10 sector North Star disk with blank I/O and INSTALL program*







PRIORITY ONE ELECTRONICS

ORDER TOLL FREE (800) 423-5922


Include $10.00 for UPS Ground Shipping


Sale prices are for prepaid orders only. Orders on open account will be accepted at $2250.00 each.

PRIORITY ONE ELECTRONICS

1 ONE

COMPARE HITACHI





Until now, if you wanted a 50MHz or 100MHz dual trace oscilloscope of uncompromising quality, there was only one choice. Now there is a second . . . outstanding new delay sweep with an established name — the Hitachi V550B and the V1050.

HITACHI Oscilloscopes are innovative oscilloscopes designed and manufactured by Hitachi Denshi Ltd. The wide experience gained by HITACHI electronic specialists in producing oscilloscopes has resulted in this line of modern oscilloscopes featuring wider band width, more compact design and light weight. Through adopting circuitry with linear IC's and logic IC's plus modern manufacturing techniques. including automatic component-insertion machines. These oscilloscopes offer increased stability, improved reliability, excellent performance and enhanced operating ease.

BDHITV1050 100 MHz, List $2375.00

Sale $1595.00

All HITACHI Scopes come complete with 2, 10 to 1 Probes

SPEC	TEK 2215	HITV1050	HITV550B	HITV352	HITV202
PRICE	$1400.00	$1595.00	$1250.00	$795.00	$595.00
BANDWIDTH	60 MHz/50 MHz‡	100 MHz	50 MHz	35 MHz	20 MHz
SENSITIVITY	20 mV/DIV - 5mV/DIV‡	5mV/DIV	5mV/DIV	5mV/DIV	5mV/DIV
SWEEP SPEED SELECTION	50 ns/DIV to .5 s/DIV x 10 pull	20 ns/DIV to .5 s/DIV x 10 pull	50 ns/DIV to .5 s/DIV x 10 pull	.2 μ s/DIV to .2 s/DIV x 10 pull	.2 μ s/DIV to .2 s/IDV x 10 pull
VERTICAL MODES	CH 1, CH 2, ALT CHOP, ADD	CH 1, CH 2, ALT CHOP, ADD TRIG A VIEW TRIG B VIEW	CH 1, CH 2, ALT CHOP, ADD TRIG A VIEW	CH 1, CH 2 DUAL, ADD DIFF	CH 1, CH 2 DUAL, ADD DIFF
WIDE RANGE VERT. SENSITIVITY	2 mV to 100 V /DIV*	500 μ V to 50V /DIV†	1 mV to 50 V /DIV†	1 mV to 50 V /DIV†	1 mV to 50 V /DIV†
DELAYED OR INTENSIFIED SWEEP	YES	YES	YES	NO	NO
DELAY TIMES	.5 μ s to 4 ms	10 ns to 5 s/DIV	25 ns to 5 s/DIV	FIXED	———
DUAL TIME BASE MEASUREMENTS	A, B, ALT w/B INTENSIFIED	A, B, ALT w/B INTENSIFIED B INTENSIFIED	A, B, ALT w/B INTENSIFIED	——— ———	——— ———
TRIGGER "A" MODES	AUTOMATIC TV FIELD VERT MODE LINE EXTERNAL	AUTOMATIC TV VERTICAL TV HORIZONTAL LINE EXTERNAL SINGLE SWEEP	AUTOMATIC TV VERTICAL TV HORIZONTAL LINE EXTERNAL SINGLE SWEEP	AUTOMATIC TV (+, -) LINE EXTERNAL	AUTOMATIC TV (+, -) LINE EXTERNAL
TRIGGER "B" MODES	+, - SLOPE INTERNAL ONLY	+, - SLOPE INTERNAL EXTERNAL	+, - SLOPE INTERNAL EXTERNAL	———	———
SCALE ILLUMINATION	NONE	YES	YES	YES	YES
CHANNEL 2 INVERT	YES	YES	YES	NO	NO

*USING X10 PROBE
† USING X 10 PROBE WITH MAGNIFIER

Circle 336 on inquiry card.

‡ *We had to obtain this specification by phone from Tektronics because it was not listed in the literature.*

ORDER NOW! TOLL FREE:—

PRIORITY ONE ELECTRONICS

TO TEKTRONIX . . .
. . . THEN DECIDE!

ONE

BDHITV550B 50 MHz, List $1745.00

Sale $1250.00


BDHITV352 35 MHz, List $1150.00

Sale $795.00

BDHITV202 20 MHz, List $850.00

Sale $595.00

All HITACHI Scopes come complete with 2, 10 to 1 Probes



SPEC	TEK 2215	HITV1050B	HITV550B	HITV352	HITV202
TRIGGER VIEW	NONE	A, B	A	NONE	NONE
HF REJECTION	NONE	SWITCHABLE YES	SWITCHABLE YES	NONE	NONE
LF REJECTION	NONE	SWITCHABLE YES	SWITCHABLE YES	NONE	NONE
BAND WIDTH LIMIT	NONE	YES 20 MHz	NONE	NONE	NONE
X - Y MEASUREMENTS	YES	YES	YES	YES	YES
CAMERA BEZEL	YES	YES	YES	NO	NO
MULTI POSITION HANDLE	YES	YES	YES	YES	YES
JITTER	10,000:1	20,000:1	20,000:1	———	———
Z AXIS BANDWIDTH 0 - 5 Vpp	DC to 5 MHz	DC to 3.5 MHz	DC to 3.5 MHz	DC to 2 MHz	DC to 2 MHz
POWER CONSUMPTION	50 WATTS	60 WATTS	45 WATTS	45 WATTS	45 WATTS
PROBE CALIBRATOR	YES	YES	YES	YES	YES
MTBF	NOT GIVEN	20,00 HRS TARGET VALUE	20,000 HRS TARGET VALUE	20,000 HRS TARGET VALUE	20,000 HRS TARGET VALUE
A, B CHANNEL GATE OUTPUT	NO	YES	NO	NO	NO
POWER-ON INDICATOR	NO	YES	YES	YES	YES
WARRANTY	1 YEAR	2 YEARS	2 YEARS	2 YEARS	2 YEARS
ALTERNATE SWEEP SEPARATOR	YES	YES	NO	———	———
CRT	8 x 10 OIV INT. GRATICULE P31 PHOSPHOR 10KV ACCEL. V	8 x 10 OIV INT. GRATICULE P31 PHOSPHOR 20KV ACCEL. V.	8 x 10 OIV INT. GRATICULE P31 PHOSPHOR 10KV ACCEL. V	8 x 10 OIV INT. GRATICULE P31 PHOSPHOR 5.2KV ACCEL V.	8 x 10 DIV INT. GRATICULE P31 PHOSPHOR 2KV ACCEL. V
CRT CONTROLS	BRIGHTNESS, AUTO FOCUS BEAM FINDER TRACE ROTATION	BRIGHTNESS AUTO FOCUS BEAM FINDER TRACE ROTATION	BRIGHTNESS AUTO FOCUS TRACE ROTATION	BRIGHTNESS FOCUS TRACE ROTATION	BRIGHTNESS FOCUS TRACE ROTATION

ACCESSORIES

BDHITAP5010	*Accessory pouch for BDHITV550B & BDHITV1050 Oscilloscopes*	$40.00
BDHITDC2035	*Vinyl Dust Cover for BDHITV202 & BDHITV352 Oscilloscopes*	$35.00
BDHITFC5010	*Front Cover For BDHITV550B & BDHIT1050 Oscilloscopes*	$18.00

PRIORITY ONE ELECTRONICS










TERMS U.S : VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA residents add 6% Sales Tax. **INCLUDE $15.00 FOR EACH OSCILLOSCOPE** for UPS Surface Shipping and Handling. Just in case, include your phone number. Prices subject to change without notice. We will do our best to maintain these prices through March, 1982. For complete specifications, see our 60 page catalog in the November issue of **BYTE** or send $1.00 for your copy today. Sale Prices are for prepaid orders only. Circle 336 on inquiry card.

—(800) 423-5922 or (213) 709-5464

JADE Computer Products

Sunnyvale • Woodland Hills • Hawthorne • San Diego

Printers



BETTER THAN EPSON ! - Okidata

Microline 82A *80/132 column,* **120 CPS**, *9 x 9 dot matrix, friction feed, pin feed, adjustable tractor feed (removable), handles 4 part forms up to 9.5" wide, rear & bottom feed, paper tear bar, 100% duty cycle/200,000,000 character print head, bi-directional/logic seeking, both serial & parallel interfaces included, front panel switch & program control of 10 different form lengths, uses inexpensive spool type ribbons, double width & condensed characters, true lower case descenders & graphics*

PRM-43082 *with FREE tractor* **$544.95**

Microline 83A *132/232 column, 120 CPS, handles forms up to 15" wide, plus all the features of the 82A.*

PRM-43083 *with FREE tractor* **$774.95**

Microline 84 *132/232 column, 200 CPS, full dot graphics built in, handles forms up to 15" wide, plus all the features of the 83A.*

PRM-43083 *with FREE tractor* ... **$1249.95**

PRA-27081 *Apple card* **$39.95**
PRA-27082 *Apple cable* **$19.95**
PRA-27087 *TRS-80 cable* **$24.95**
PRA-43081 *Hi speed 2K serial board* **$169.95**
PRA-43080 *Extra ribbons pkg. of 2* ... **$9.95**

INEXPENSIVE PRINTERS - Epson

MX-70 *80 column, 80 CPS, 5 x 7 dot matrix, adjustable tractor feed, & graphics*

PRM-27070 *List $459* **$399.95**

MX-80 *80 column, 80 CPS, bi-directional/logic seeking printing, 9 x 9 dot matrix, adjustable tractor feed, & 64 graphics characters*

PRM-27080 *List $645* **$469.95**

MX-80FT *same as MX-80 with friction feed added.*

PRM-27082 *List $745* **$559.95**

MX-100 *132 column, correspondence quality, graphics, up to 15" paper, friction feed & adjustable tractor feed, 9 x 9 dot matrix, 80 CPS.*

PRM-27100 *List $945* **$759.95**

PRA-27084 *Serial interface* **$69.95**
PRA-27088 *Serial intf & 2K buffer* .. **$144.95**
PRA-27081 *Apple card* **$74.95**
PRA-27082 *Apple cable* **$22.95**
PRA-27086 *IEEE 488 card* **$52.95**
PRA-27087 *TRS-80 cable* **$32.95**
PRA-27085 *Graftrax II* **$95.00**
PRA-27083 *Extra ribbon* **$14.95**

Modems

SMARTMODEM - Hayes

Sophisticated direct-connect auto-answer/auto-dial modem, touch-tone or pulse dialing, RS-232C interface, programmable

IOM-5400A *Smartmodem* **$249.95**
IOK-1500A *Hayes Chronograph* ... **$199.95**

CAT MODEMS - Novation

CAT *300 baud, acoustic, answer/orginate*

IOM-5200A *List $189.95* **$149.95**

D-CAT *300 baud direct connect, answer/orginate*

IOM-5201A *List $199.95* **$169.95**

AUTO-CAT *Auto answer/orginate, direct connect*

IOM-5230A *List $299.95* **$239.95**

Apple-CAT - Novation

Software selectable 1200 or 300 baud, direct connect, auto-answer/auto-dial, auxiliary 3-wire RS232C serial port for printer.

IOM-5232A *Save $50.00!!!* **$325.00**

Accessories for Apple

16K MEMORY UPGRADE

Add 16K of RAM to your TRS-80, Apple, or Exidy in just minutes. We've sold thousands of these 16K RAM upgrades which include the appropriate memory chips (as specified by the manufacturer), all necessary jumper blocks, fool-proof instructions, and our 1 year guarantee.

MEX-16100K *TRS-80 kit* **$25.00**
MEX-16101K *Apple kit* **$25.00**
MEX-16102K *Exidy kit* **$25.00**

16K RAM CARD - for Apple II

Expand your Apple to 64K, 1 year warranty

MEX-16500A *Save $70.00 !!!* **$129.95**

Z-80* CARD for APPLE

Two computers in one, Z-80 & 6502, more than doubles the power & potential of your Apple, includes Z-80 CPU card, CP/M 2.2, & BASIC-80*

CPX-30800A *A & T* **$299.95**

8" DISK CONTROLLER

New from Vista Computer, single or double sided, single or double density, compatible with DOS 3.2/3.3, Pascal, & CPM 2.2, Shugart & Qume compatible

IOD-2700A *A & T* **$499.95**

2 MEGABYTES for Apple II

Complete package includes: Two 8" double-density disk drives, Vista double-density 8" disk controller, cabinet, power supply, & cables, DOS 3.2/3.3, CP/M 2.2, & Pascal compatible.

1 MegaByte Package *(Kit)* **$1495.00**
1 MegaByte Package *(A & T)* **$1695.00**
2 MegaByte Package *(Kit)* **$1795.00**
2 MegaByte Package *(A & T)* **$1995.00**

DISK DRIVES - Micro Sci

Inexpensive disk drives for your Apple

A2 *Direct replacement for Apple Disk II, works with Apple II controller as first or second drive.*

MSM-123101 *Micro Sci A2* **$429.95**

A40 *40 track drive for Apple II. Improved storage capacity and speed over Apple Brand drives - requires Micro Sci controller.*

IOD-2340A *Micro Sci A40* **$399.95**

A70 *70 track drive for Apple II. Twice the storage capacity and three times faster than Apple Brand drives - requires Micro Sci controller*

IOD-2370A *Micro Sci A70* **$499.95**

Micro Sci Controller *Disk controller for up to two Micro Sci A40 or A70 disk drives, DOS 3.2, 3.3, Pascal, and Z-80 SoftCard compatible, includes utility disk and 40/70 track patch.*

IOD-2300A *Micro Sci controller* **$95.00**

VISION 80 - Vista Computer

80 column x 24 line video card for Apple II, 128 ASCII characters, upper and lower case, 9 x 10 dot matrix with 3 dot descenders, standard data media terminal control codes, CP/M Pascal & Fortran compatible, 50/60 Hz

IOV-2400A *Vista Vision 80* **$375.00**

AIO, ASIO, APIO - S.S.M.

Parallel & serial interface for your Apple (see Byte pg 11)

IOI-2050K *Par & Ser kit* **$139.95**
IOI-2050A *Par & Ser A & T* **$169.95**
IOI-2052K *Serial kit* **$89.95**
IOI-2052A *Serial A & T* **$99.95**
IOI-2054K *Parallel kit* **$69.95**
IOI-2054A *Parallel A & T* **$89.95**

CPS MULTICARD - Mtn. Computer

Three cards in one! Real time clock/calendar, serial interface, & parallel interface - all on one card.

IOX-2300A *A & T* **$199.95**

Single Board Computer

Z-80 STARTER KIT - SD Systems

Complete Z-80 microcomputer with RAM, ROM, I/O, keyboard, display, kludge area, manual, & workbook

CPS-30100K *KIT* **$299.95**
CPS-30100A *A & T* **$469.95**

SYM-1 - Synertek Systems

Single board computer with 1K of RAM, 4K of ROM, key-pad, LED display, 20ma & cassette interface on board.

CPK-50020A *A & T* **$249.95**

VIC 20 - Commodore

Complete personal computer with 5K RAM, full color, 61 key keyboard, 4 dual special-function keys, serial ports, cassette port, composite video output (connects to standard color TV set), BASIC language, & expansion port.

COM-VIC20 *VIC-20* .... **Under $300.00**

PERSONAL COMPUTERS

Also available from Jade - Call for Price and Info

AIM-65, Altos, Apple II, Atari, Commodore, California Computer Sys Hewlett-Packard, Intersystems Jade, NEC, Novell, SD Systems SYM-1, Xerox, and more...

Video Monitors

HI-RES 12" GREEN - Zenith

15 MHz bandwidth, 700 lines/inch, P31 green phosphor, switchable 40 or 80 columns, small, light-weight & portable.

VDM-201201 *List price $150.00* **$118.95**

12" GREEN SCREEN - NEC

20 MHz, P31 phosphor video monitor with audio, exceptionally high resolution - A fantastic monitor at a very reasonable price

VDM-651200 *Special Sale Price* **$199.95**

12" COLOR MONITOR - NEC

Hi-res monitor with audio & sculptured case

VDC-651212 *Color Monitor* **$479.95**

NEC-1202D *RGB color monitor* ... **$1045.00**

Leedex / Amdek

Reasonably priced video monitors

VDM-801210 *Video 100 12" B&W* .. **$139.95**
VDM-801230 *Video 100-80 12" B& W* **$179.95**
VDM-801250 *12" Green Phospor* **$169.95**
VDC-801310 *13" Color I* **$379.95**
VDC-801320 *Color II* **$895.00**
IOV-2300A *DVM board for Apple* .. **$199.95**

Video Terminals

TELEVIDEO 910

Full featured - inexpensive terminal

VDT-901210 *List 795.00* **$695.00**

TELEVIDEO 950

VDT-901250 *List $1195.00* **$995.00**

AMBER SCREEN - Volker Craig

Detachable keyboard, amber on black display, 7 x 9 dot matrix, 10 program function keys, 14 key numeric pad, 12" non-glare screen, 50 to 19,200 baud, direct cursor control, auxiliary bi-directional serial port

VDT-351200 *List $795.00* **$645.00**

VIEWPIONT - ADDS

Detachable keyboard, serial RS232C interface, baud rates from 110 to 19,200, auxiliary serial output port, 24 x 80 display,

VDT-501210 *Sale Priced* **$639.95**

DIALOGUE 80 - Ampex

VDT-230080 *List $1195.00* **$895.00**

Circle 222 on inquiry card.

SD Systems ExpandoRAM III

256K RAM $879.95

Single User System

SBC-200, 64K ExpandoRAM II, Versafloppy II, CP/M 2.2

$1095.00


4 MHz Z-80A CPU, 64K RAM, serial I/O port, parallel I/O port, double-density disk controller, CP/M 2.2 disk and manuals, system monitor, control and diagnostic software.

Add $100.00 for upgrade to ExpandoRAM III 64K (expandable to 256K)

-All boards are assembled and tested-

SBC-200

2 or 4 MHz single board computer




• S-100 bus compatible • Powerful 4MHz Z-80A CPU • Synchronous/asynchronous serial I/O port with RS-232 interface and software programmable baud rates up to 9600 baud • Parallel input and parallel output port • Four channel counter/timer • Fourmaskable, vectored interrupt inputs and a non-maskable interrupt • 1K of on-board RAM • Up to 32K of on-board ROM • System monitor PROM included

The SBC-200 is an excellent CPU board to base a microcomputer system around. With on-board RAM, ROM, and I/O, the SBC-200 allows you to build a powerful three-board system that has the same features found in most five-board microcomputers. The SBC-200 is compatible with both single-user and multi-user systems.

CPU-30200A *A & T with monitor* **$299.95**

Versafloppy II

5¼" & 8" double density controller




• S-100 bus compatible • IBM 3740 compatible soft sectored format • Controls single and double-sided drives, single or double density, 5¼" and 8" drives in any combination of four simultaneously • Drive select and side select circuitry • Analog phase-locked loop data seperator • Vectored interrupt operation optional • Standard CP/M 2.2 disk operating • Control/diagnostic software PROM included

The Versafloppy II is faster, more stable and more tolerant of bit shift and "jitter" than most controllers. All control and diagnostic software included.

IOD-1160A *A & T* **$359.95**
For CP/M 2.2 and manual set add **$99.95**

ExpandoRAM III

64K to 256K expandable RAM board




SD Systems has duplicated the famous reliability of their ExpandoRAM I and II boards in the new ExpandoRAM III, a board capable of containing 256K of high speed RAM. Utilizing the new 64K x 1 dymanic RAM chips, you can configure a memory of 64K, 128K, 192K, or 256K, all on one S-100 board. Memory address decoding is done by a programmed bipolar ROM so that the memory map may be dip-switch configured to work with either COSMOS/MPM-type systems or with OASIS-type systems.

Extensive application notes concerning how to operate the ExpandoRAM III with Cromemco, Intersystems, and other popular 4 MHz Z-80 systems are contained in the manual.

MEM-65064A *64K A & T* **$495.00**
MEM-65128A *128K A & T* **$639.95**
MEM-65192A *192K A & T* **$769.95**
MEM-65256A *256K A & T* **$879.95**

ExpandoRAM II

16K to 64K expandable RAM board



• S-100 bus compatible • Up to 4MHz operation • Expandable from 16K to 64K • Uses 16 x 1 4116 memory chips • Page mode operation allows up to 8 memory boards on the bus • Phantom output disable • Invisible on-board refresh

The ExpandoRAM II is compatible with most S-100 CPUs. When other SD System' series II boards are combined with the ExpandoRAM II, they create a microcomputer system with exceptional capabilities and features.

MEM-16630A *16K A & T* **$345.00**
MEM-32631A *32K A & T* **$365.00**
MEM-48632A *48K A & T* **$385.00**
MEM-64633A *64K A & T* **$399.95**

PROM-100

Versatile EPROM Programmer

• S-100 bus compatible • Programs 2708, 2758, 2716, 2732, 2516 EPROMs • DIP switch selection of EPROM type • 25 VDC programming pulse generated on-board • Very fast programming and verification • Zero insertion force socket • Programming software included on 8" diskette

MEM-99520K *Kit w/software* **$189.95**
MEM-99520A *A & T w/software* ... **$249.95**

Multi-User System

SBC-200, 256K ExpandoRAM III, Versafloppy II, MPC-4 COSMOS Multi-User Operating System, C BASIC II


$1995.00

Two Z-80A CPUs (4 MHz), 256K RAM, 5 serial I/O ports with independently programmable baud rates and vectored interrupts, parallel input port, parallel output port, 8 counter/timer channels, real time clock, single and double sided/single or double density disk controller for 5¼" and 8" drives, up to 36K of on-board ROM, CP/M 2.2 compatible COSMOS interrupt driven multi-user disk operating system, allows up to 8 users to run independent jobs concurrently, C BASIC II, control and diagnostic software in PROM included.

-All boards are assembled and tested-

MPC-4

Intelligent communications interface



• Four buffered serial I/O ports • On-board Z-80A processor • Four CTC channels • Independently programmable baud rates • Vectored interrupt capability • Up to 4K of on-board PROM • Up to 2K of on-board RAM • On-board firmware

This is not just another four-port serial I/O board! The on-board processor and firmware provide sufficient intelligence to allow the MPC-4 to handle time consuming I/O tasks, rather than loading down your CPU. To increase overall efficiency, each serial channel has an 80 character input buffer and a 128 character output buffer. The on-board firmware can be modified to make the board SDLC or BISYNC compatible. In combination with SD's COSMOS operating system (which is included with the MPC-4), this board makes a perfect building block for a multi-user system.

IOI-1504A *A & T with COSMOS* .. **$495.00**

Place Orders Toll Free

Continental U.S.	*Inside California*
800-421-5500	800-262-1710

For Technical Inquires or Customer Service call:
213-973-7707

JADE
Computer Products

4901 W. Rosecrans, Hawthorne, Ca 90250

TERMS of SALE: Cash, checks, credit cards, or Purchase Orders from qualified firms and institutions. **Minimum Order $15.00.** California residents add 6% tax. Minimum shipping & handling charge $3.00. Pricing & availibility subject to change

Circle 223 on inquiry card.

Centronics 730



Same as Radio Shack Line Printer II


Once $995

Brand New

Now $ 399

While they last

Plus $10 for shipping & insurance



5¼ Disc Drives

For TRS-80 Mod. 1 35 or 40 track capability

$ 279

Single or double density (with proper interface)

Choice of MPI or Tandom drives

Add $7.50 for shipping

5¼ Discs for TRS-80 and Apple

Prime First Quality

MEMOREX Discs as low as **$1.89 per disc** In lots of 100

Limited time only
Subject to availability

Part No.	10 or More	50 or More	100 or More
3401	**$2.09**	**$1.99**	**$1.89**
3431 with Hubring	**$2.35**	**$2.25**	**$2.15**

All prices, F.O.B. shipping point, subject to change. All offers subject to withdrawl without notice. Advertised prices reflect a 2% cash discount (order pre-paid prior to shipment). C.O.D.'s and credit cards are 2% higher.

MiniMicroMart, Inc



943 W. Genesee St. Syracuse, N.Y. 13204 (315) 422-4467




Circle 281 on Inquiry card.

California Digital

Post Office Box 3097 B • Torrance, California 90503

California Digital STATIC • 64



RELIABILITY OF STATIC ... PRICE OF DYNAMIC

Sixteen Bit Memory

$595

February Price $850

30% Price Reduction

Utilizing the new Hitachi 6167/2167 ram chip, the Static 64 is the most current technology available is S-100 memory products.
24 bit extended addressing, 8 or 16 bit data paths along with 16 bit request and acknowledge make this unique board completely compatable with the IEEE 696 S-100 buss standard.

The Static 64 has been engineered to allow each 16K segment of memory to be bank selectable supporting multiuser systems. Other selectable features allow the board to fully integrate with all current bank selecting schemes including Cromex and Alpha-Micro. Operates with all 16 bit computers including Seattle Computers, Tecmar and Lomas. Designed for DMA operations at clock frequencies in excess of 10 MHz. Standby power consumption less than one Amp.

To add to the total integrity of the product, each board is subjected to extensive high temperature burn-in and test procedures. CAL-6400



ZENITH $119

GREEN PHOSPHOR MONITOR

The new Zenith ZVM-121 monitor features a P-31 green phosphor tube along with 15 MHz bandwidth.
Switch selectable for 40 and 80 character per line screen formats.
Accepts composite video and is fully compatable with 80 column Apple cards.
VDM-121 20 lbs.

EPSON MX80 $450

Epson MX80FT friction/tr	$595.00
Epson MX100 132 column	
Graftrax 80 option	70.00
Apple I/O & cable (8131)	129.00
Serial interface (8141)	79.00
Serial Inter., 2K buf. (8151)	145.00
Cable for TRS-80	35.00
IEEE 488 interface (8161)	65.00
Replacement head	45.00
Replacement Ribbon	14.00
Paper 3500 sheets 9 1/2"	35.00

NEC PC-8023A $535

Dot-matrix, bi-directional, logic-seeking, friction or tractor feed, impact printer. Complete graphics, upper and lower case ASCII, Greek, mathematics long with the ability to print dot graphic screen images directly onto paper.

Proportional spacing and 132 column compressed print make this low cost machine the best value in todays printer market.

PRINTRONIX



P-300 $4500

P-600 $6150

IBM 3101 Display Terminal



IBM Direct Price $1395

California Digital discount price $1295

AMPEX DIALOGUE 80



REDUCED PRICE

$795

New from the Ampex Corporation. The Dialogue 80 features removable keyboard, displayable two pages (four optional) dual program keys, half intensity protected fields and status line. Transmits data either block, line or character mode. Excellent value. VDT-D80 shipping 47 lbs.

ACCESSORIES FOR THE APPLE COMPUTER



CALIFORNIA COMPUTER SYSTEMS	
Arithmetic Processor 7811 B/C	$319
Asynchronous serial Interface 7710	129
Centronics Interface card 7728	95
12K PROM Module 7114	69
Calender/Clock, Bat. back-up 7424	99
Parallel Interface 7720A	99
Programable Timer 7740A	99
Analog/Digital converter 7470A	99
MICROSOFT PRODUCTS	
Apple to Z-80 CPU card	379
D.C. HAYES PRODUCTS	
Micromodem for Apple	319
COMPUTER STOP PRODUCTS	
Double Vision / 80 Column Video	250
INTERACTIVE STRUCTURES	
16 Channel A/D card AIO/2	275
MOUNTAIN COMPUTER PRODUCTS	
Intro X-10 system for BSR	$239
Intro X-10 card only	165
16 channel AD/DA 8 bit	319
Apple Clock battery back-up	225
Supertalker SD200	245
ROM Plus with filter	165
ROM Writer/Programmer	149
APPLE BRAND PRODUCTS	
Apple Language card	450
Floppy disk with controller	560
Floppy disk wit but controller	495
Apple parallel interface	175
SSM MICROCOMPUTER	
Dual serial parallel interface AIO	
SORRENTO VALLEY ASSOCIATES	
8" floppy controller (Pascal)	360

PRINTERS

Epson MX80	PREMX80	$475
Epson MX80FT	PREMX80F	595
Epson MX100	PREMX100	
Anadex 9500	PRA9500	1295
Anadex 9501	PRA9501	1295
Anacom 150	PRA150	1075
IDS Paper Tgr.	PRG460G	1095
IDS Tiger 560	PRG560G	1350
Diablo 630	PRD630	2150
Diablo 1650	PRD1650	2850
Diablo 1640	PRD1640	2496
Datasouth 180	PRD180	1350
Printronix 300	PRP300	4500
Printronix 600	PRP600	6150
NEC/Sellum 1	PRN5510ps	2695
NEC/Sm 16K	PRN5516ps	2795
TEC/Starwrit.	PRV300	1395
Okidata 80	PRO80	419
Okidata 82	PRO82	619
Okidata 83	PRO83	895
Teletype 43K	PTT4320K	1095
Texas Ins. 810	PRT810B	1450
Tex. Ins 810C	PRT810C	1795
Centronics 730	PRC730P	529
Centronics 737	PRC737P	695
Centronics 739	PRC739P	795
Centrnx 704-9	PRC704-9	
Centrnx.704-11	PRC704-11	


VIDEO TERMINALS

ADDS Viewpoint	VDT-RVP	595
ADDS Regent 25 numeric cluster	VDT-R25	850
ADDS Regent 30 25th status line	VDT-R30	950
ADDS Regent 40 limited graphics	VDT-R40	1195
ADDS Regent 60 Block mode	VDT-R60	1495
Ampex Dialouge 80 two page, detatch	VDT-D80	
Digital Equipment VT-100	VDT-V100	1595
Digital Equipment VT-132	VDT-V132	1895
IBM 3101-10 character mode green	VDT-3101	1195
IBM 3101-20 block mode	VDT-31012	1395
Visual 200	VDT-V200	995
Televideo 910C (new)	VDT-T910	595
Televideo 912C	VDT-T912	665
Televideo 920C	VDT-T920	745
Televideo 950C detatchable keybd.	VDT-T950	985
Zenith Z-19	VDT-Z-19	

S-100 BOARDS


Assembled • Tested • Burned-in





CPU BOARDS		
Calif. Computer 2810A Z-80 DMA, 4MHz	BDC-C2810	$250
Godbout Z-80 24 bit, 4MHz	BDC-GZ80	239
Godbout 8085/8088 dual 16 bit processor	BDC-G88	375
Measurement Systems Z-80 4 serial 2 parallel real time clock, 8 vector	BDC-MZ80	395
SD Systems SBC-200 Z-80 with serial & parallel I/O ports	BDC-SBC2	385
Teletek FDC-1 single board CPU & floppy disk controller plus I/O	BDC-FDC1	695
MAINFRAMES		
Calif. Computer 2200A 12 slot & power supply	ENM-C2200	
TEI 12 slot table	ENM-T12	
TEI 22 slot table	ENM-T22	
Godbout mainfrm.	ENM-GMF	
MEMORY BOARDS		
Calif. Computer 2065A 64K dyamic memory	BDM-C2065	
Calif. Computer 2016 16K static memory	BDM-C2016	259
Calif. Computer 2032 32K static memory	BDM-C2032	585
Godbout Ram 17 64K static memory 16 bit	BDM-G17	1025
SD Systems Exbandoram II 16K dynamic	BDM-EX16	295
64K dynamic	BDM-EX64	375
Measurement Systems DMB6400 for Alpha Micro	BDM-M6400	685
EPROM BOARDS		
Digital Research 32K, 2716 proms extra	BDM-DP32	99
SD Systems Prom-100 programmer	BDM-P100	250
FLOPPY DISK CONTROLLER		
Calif. Computer 2422A with 2.2 CPM	BDF-C2422	329
Godbout "Disk One" features the NEC 765 controller, DMA arbitration	BDF-GD1	395
Measurement Systems 765 chip, single & double density, Error recovery	BDF-MF	419
SD Systems Versafloppy II double density	BDF-VF2	419
Tarbell D/D	BDF-TF2	419
Morrow Design Disk Jockey I single density	BDF-DJ1	195
Morrow Design Disk Jockey II double density	BDF-DJ2	345
INTERFACE BOARDS		
Calif. Computer 2718 I/O 2 serial/2 par'l	BDT-C2718	
Morrow Designs Switchboard 2 serial/4 par'l	BDT-MSB	219
Morrow Designs Multiboard 3 serial/3P, +++	BDT-MMB	275
Godbout Interfacer One 2 serial/2 par'l	BDS-GB1	199
Godbout Interfacer Two 1 serial/3 par'l	BDS-GB2	199
SPECIALITY BOARDS		
QT Computer real time clock/calendar	BDS-QCK	135
Artec Elec. Wire wrap prototype board	BDS-AWW	25
Artec Elec. General Purpose proto board	BDS-AGP	25
Godbout Spectrum color board	BDS-GSC	295
D.C. Hayes S-100 Micromodem	BDS-HMI	350
Mullen Products extender board & logic probe kt	BDS-MTB1	49
Mullen Products Opto-contro board kit	BDS-MOC	139

SYSTEMS



HEWLETT PACKARD

HP 85 COMPUTER

BELOW OUR COST

$2295






apple

48K Memory

$1150

VIDEO MONITORS



BMC KG-12C 20 MHz P31 green phosphor	$169
NEC gm. 1201	189
Zenith gm ZVM121	119
BMC color composit	339
Zenith color 13"	395
NEC RGB 1202DH	895

EPROM ERASER

Ultra Vilot Products

$65



UVP-11E

Rotron Muffin Fan



$14.77 $12.00 @ 100; 10.50 @ 1000

115 VAC. 7 Watts WR2A1

Factory fresh Muffin fans

NOT pull-outs. EMF-4M

VISA



All merchandise sold by California Digital is premium grade.
Shipping: First five pounds $2.00; each additional add $.40
Foreign orders 10% shipping. Excess will be refunded.
California residents add 6% sales tax. COD's discouraged.
Open accounts extended to state supported educational institutions and companies with a "Strong Dun & Bradstreet."
Warehouse: 15608 Inglewood Blvd. Visitors by appointment.

Circle 73 on inquiry card.

TOLL FREE ORDER LINE

(800) 421-5041

TECHNICAL & CALIFORNIA

(213) 679-9001

TWX 910 325-6212

California Digital

Post Office Box 3097 B • Torrance, California 90503

DISKETTES

FREE PLASTIC LIBRARY CASE INCLUDED WITH THE PURCHASE OF EVERY BOX OF DISKETTES

$24.95



Private labeled for California Digital by one of the most respected producers of magnetic media. Each diskette is certified double density at 40 tracks. To insure extended media life each diskette is manufactured with a reinforced hub-hole. And of course, a plastic library case is included with every box of diskettes. MMD-CD5(01)(10) Please specify computer or required sectors.

Ten boxes $22.75 One hundred boxes $21.50

5¼" DISKETTES WITH LIBRARY CASE

$26.50

Scotch
iskettes
minidisks
Verbatim

Your Choice
SCOTCH MEMOREX VERBATIM

	Soft Sector	10 Sector	16 Sector	
SCOTCH	744-0	744-10	744-16	$26.50
MEMOREX	3401	3403	3405	26.50
VERBATIM	525-01	525-10	NA	26.50
DYSAN	104/1	107/1	NA	39.50
Single Side Double Density				
DYSAN	104/1D	107/1D	NA	45.00
Double Side Double Density				
SCOTCH	745-0	745-10	745-16	42.50
DYSAN	104/20	107/20	NA	49.50
DYSAN 96	204/20	NA	NA	59.50

EIGHT INCH DISKETTES

Single Side Single Density			Single Side Double Density		
SCOTCH	740-0	29.50	SCOTCH	741-0	39.00
MEMOREX	3060	29.50	MEMOREX	3090	35.00
DYSAN	3740/1	39.50	DYSAN	3740/D	57.50
Thirty Two Sector			**Double side Double Density**		
SCOTCH	740-32	29.50	SCOTCH	743-0	47.50
Scotch Head Cleaning Kits 5¼ & 8"		$24.95	MEMOREX	3114	39.50
Plastic Library Cases 5¼ & 8"		2.95	DYSAN	3740/2D	65.00
Diskette Flip Tubs fifty diskettes 5¼"		24.95			
Diskette Flip Tubs fifty diskettes 8"		29.95			

PLEASE PHONE FOR VOLUME PRICING.



BSR SYSTEM X-10

The new BSR timer runs your home just like clockwork. Turns on lamps and appliances while your away from home. Completely compatible with your existing System X-10 devices.

BSR Timer eight channel	$65.00	Appliance Module 500 W.	$13.95
Master control console	34.95	Lamp Module 300 Watts	13.95
Ultrasonic Controller	19.95	NEW full control wall switch	14.50

WINCHESTER SUBSYSTEM

$1250

Includes seven megabyte Winchester hard disk, dual enclosure and power supply.
Floppy backup drive $199.00 additional.



MEMORY

64K DYNAMIC $9.95	16K STATIC $13.95
4164 100+	2167 70ns.
16K DYNAMIC $2.10	**2716 EPROM $4.95**
4116 100+ $1.85	100+ $4.50 1K+ $4.00



2732 EPROM SALE $7.95

STATIC

		ea.	32+	100+	1K+
21L02	1K	1.19	1.09	1.05	.99
2114	300ns.	2.95	2.75	2.50	1.99
4044-4	450ns.	4.50	4.19	4.00	3.75
4044-2	250ns.	4.95	4.65	4.50	4.25
6116	16k 24 pin	7.95	7.50	6.75	6.45
2167/6167	20 pin	11.95	10.75	9.65	9.25

EPROM

2708	450ns.	3.95	3.50	3.25	3.00
2716	5V.	4.95	4.00	3.75	3.60
2716	tri-volt	8.50	7.95	7.65	7.25
2732	Intel/Hitac.	7.95	7.50	7.00	6.65
2532	Texas Inst	12.95	11.50	10.00	9.50
2764	64K Eprom	29.95	27.00	25.00	23.50



direct connect MODEM

Your Choice **$169**

Direct connect modems eliminate loss of information due to the carbon compression associated with acoustic modems. Choose either of these two great units.

The Universal Data Systems 103LP is switch selectable between answer and originate modes. Fully Bell 103 compatable. Directly connects to the new modular telephone jack. 100% powered from the telephone line. No need to locate modem in proximity to A.C. power recepticle. MOD-103LP 2 pounds.

Novation "D" Cat connects to most of the new "Bell" modular handsets. Ideal for multiple line office telephones. Requires external A.C. power. MOD-DCAT 2 Lb.

SWITCHES



DIP SWITCHES

pos.	ea.	100+	1K+
4	.88	.75	.69
7	.99	.83	.79
8	1.05	.91	.87
12	1.19	.99	.91

TOGGLE

		ea.	100+
7101	on/on	1.19	.98
7103	on/off/on	1.39	1.19
7107	mnt. on	1.39	1.19
7108	mnt. on	1.39	1.19
7205	dpdt mnt	1.85	1.65

CONNECTORS



GOLD EDGE CONNECTORS

S-100 .125" centers	each	10+
Imsai solder .250" row	$2.95	$2.50
Imsai wire wrap (TI)	3.95	3.50
Sullins Hi-Rel. .250"	4.50	4.00
Sullins Hi-Rel. W/W	5.35	4.90
Sullins / Altair .140"	4.95	4.50
.156" Centers (standard)		
22/44 Kim Eyelet	2.50	2.15
36/72 Digital Group S/T	5.95	5.50
36/72 Digital Group W/W	6.60	6.15
43/86 Motorola 6800 S/T	6.60	6.15
43/86 Moto. 6800 W/W	7.00	6.85

INTEGRATED CIRCUIT SOCKETS

	Low Profile each	Low Profile 100+	Wire Wrap each	Wire Wrap 100+
8 pin	$.10	$.09	$.46	$.41
14 pin	.10	.09	.46	.41
16 pin	.12	.11	.50	.45
18 pin	.15	.13	.68	.61
24 pin	.26	.24	.94	.87
40 pin	.42	.40	1.60	1.47

"D" Type	each	10-24	25+
DE9P male	$1.60	$1.40	$1.30
DE9S female	2.25	2.00	1.90
DE hood	1.50	1.35	1.20
DA15P male	2.35	2.15	2.00
DA15S female	3.25	3.10	2.90
DA hood 2/P	1.60	1.35	1.30
DB25P male	2.50	2.35	2.25
DB 25S female	3.35	3.15	3.05
DB hood 2/P	1.35	1.15	1.05
DC37P male	4.20	4.00	3.70
DC37S female	6.00	5.75	5.50
DC hood 2/P	2.25	2.00	1.75
DD50P male	5.50	5.10	4.75
DD50S female	9.40	8.60	8.00
DD50 hood 2/P	2.60	2.40	2.10
CENTRONICS			
57-30360	7.95	6.75	5.75
RIBBON CABLE CONNECTORS			
17/34 5" disk	4.85	4.15	3.95
20/40 TRS-80	5.65	5.05	4.70
25/50 8" disk	5.90	5.15	4.90



NEW OLIVETTI 801 Eight Inch Disk Drive $295

		ONE	TWO	TEN
★ OLIVETTI 801	single	$319	309	295
★ OLIVETTI 802/851	double	425	419	410
SHUGART 801/R	single	395	385	375
SHUGART 851/R	double	525	495	475
QUME DATA TRACK 8	double	525	495	475

★ The 8" Olivetti drives are aprox. ½" wider than the Shugarts.

Five Inch Disk Drives

OLIVETTI 501/400	single	199	185	175
OLIVETTI 502/451	double	235	225	215

Upon request, all drives are supplied with power connectors and one manual per order.

230 volt 50Hz. 8" add $50.00 per drive.



$995 *Eight Inch Subsystem*

Two Olivetti 801 disk drives with power supply, 4" exhaust fan complete in dual enclosure with all necessary power cables. Documentation included. 50 Lbs. CAL-2801

Signal cable add $35.00 WCA-650D

Same as above but with:

Shugart 801R	MSD2801	$1195
Shugart 851R	MSD2851	1450
Olivetti 802	CAL2802	$1250
Qume DT8	MSD8DT	1450

SPECIAL $895

Volumn Pricing Upon Request

Seagate Compatable 7.5 MEGABYTE Winchester Hard Disk Drive

We have priced this so low that the manufacturer has asked not to use their brand name in our advertising.
Industry standard Seagate plug compatable. Drive fits into the same space as a 5¼" floppy disk drive. CAL-561/2

S-100 MOTHER BOARD

$35

IMSAI 18 Slot CAL-M18


The Quiet Buss from California Digital is quality engineered. No short cuts have been taken to produce this mother board. Active termination circuitry prevents noise and crosstalk. Manufactured from extra heavy epoxy glass.



All merchandise sold by California Digital is premium grade.
Shipping: First five pounds $2.00; each additional add $.40
Foreign orders 10% shipping. Excess will be refunded.
California residents add 6% sales tax. COD's discouraged.
Open accounts extended to state supported educational institutions and companies with a "Strong Dun & Bradstreet."
Warehouse: 15608 Inglewood Blvd. Visitors by appointment.

TOLL FREE ORDER LINE (800) 421-5041
TECHNICAL & CALIFORNIA (213) 679-9001
TWX 910 325-6212


Circle 73 on inquiry card.



15381 CHEMICAL LANE ★ HUNTINGTON BEACH, CA 92649
★ (714) 891-2677 ★

OPEN FRAME POWER SUPPLIES

DISK POWER SUPPLIES				
PRIAM—SHUGART—CENTURY—MICROPOLIS				
+5V @ 9A	−5V @ .8A	+24V @ 7A	US-384	89.00
SHUGART — SIEMANS — MPI 5¼″				
+5V @ .5A	+12V @ .9A		US-340	33.50
+5V @ 2A	+12V @ 4A		US-323	56.25
SHUGART — SIEMANS — CDC 8″				
+5V @ 1A	−5V @ .5A	+24V @ 1.5A	US-205	52.50
+5V @ 2A	−5V @ .5A	+24V @ 3A	US-206	69.00
+5V @ 3A	−5V @ .6A	+24V @ 5A	US-162	89.00
+5V @ 1.7A	−5V @ 1.5A	+24V @ 2A	US-272	69.00
+5V @ 2A	+12V @ .4A	−12V @ .4A	US-HTAA	37.50



If you can beat these prices we will be truly amazed. OEM's at 500 lot pay more than this. Call or write for full spec. sheets.

SOFTWARE SOFTWARE SOFTWARE

CP/M 2.2 $150
WORDSTAR $250
SUPER VYZ $95

DATA BASE DBII $595
MICROSOFT BASIC 80 $299

CROSSTALK MODEM $150

COMING NEXT MONTH — HARD DISK!

BREAK THE COST BARRIER!

GRAND OPENING SPECIAL


THIS OFFER ONLY GOOD THRU MAY 1982
NOW IS YOUR CHANCE TO GET THAT COMPUTER
LOOK AT THESE FEATURES!

- 4MHZ Z-80 CPU with 2 Programmable Serial and 3 Parallel Ports
- 64K Dynamic Ram w/Extended Addressing to 1MB
- Floppy Disk Controller with WD1795. Runs 8" or 5" Floppys Error Free
- 30 Amp Power Supply with S-100 MOD 12 Slot Mother with Regulated Floppy Supplies as Shown Below
- Tan and Charcoal Sturdy Steel Cabinet with Space for 2 Floppy Drives at Left (8" or 5")

$1750 Retail

ONLY $975.00


CP/M $150*
MP/M $350
CABLE SET $30



(Less Drives, Cables Pick-up Price)
*CP/M is a Trademark of Digital Research

★ DUAL DRIVE SUBSYSTEMS ★


HORIZONTAL


VERTICLE


MINI

- Power Supply for 2 801/851 DT8 etc.
- 50 Pin Ribbon Cable, 36"
- AC Cord Fuse Internal Wiring

w/2 801R Shugart	$1045.00
w/2 851R Shugart	$1395.00
w/2 QUME DT-8	$1295.00
w/2 MPI B-51	$ 675.00
w/2 MPI B-52	$ 830.00
w/2 MPI B91	$ 850.00
w/2 MPI B92	$ 995.00
w/2 Empty 5"	$ 87.00
w/2 Empty 8"	$ 95.00

★ DELTA PRODUCTS ★

S-100 MOD KIT $199.00



For test or hobby applications complete S-100 12 Slot Sub-System power for up to 4 Floppy Disk Drives.

SPECIFICATIONS:


UNREGULATED	REGULATED
• 12 Slots S-100	+5 at 5 Amps
• +8VDC at 30Amps	+24 at 4 Amps
• ±16VDC at 6 Amps	−5 at 1 Amp

DP-CPU	Z-80 4MHZ, Prom 2 Serial 3 Par	**$255**
DP-DSK	WD-1795 MINI and 8"	**$275**
DP-64K	Bank SW Memory up to 1 Meg	**$389**
DP-32K	Static Ram (Kit)	**$199**
DP-MPM	IO MPM Interface Card	**$335**
DP-DTC	Hard Disk and DTC Tape	**$225**
DP-SMS	Hard Disk Controller	**$750**

★ MODEMS ★





Ask About Our Low Cost Modem Software



Hayes - Micro Modem	**$275.00**
Hayes - Smart Modem	**$250.00**
NOV. - DCAT 300 Baud Direct Con. Ans./Orig.	**$165.00**
NOV. - AUTOCAT Auto/Ans./Orig. Direct Con.	**$235.00**
NOV. - APPLECAT 300/1200 Baud Direct Con.	**$350.00**
PMMI - MM103 300/600 Baud (S-100)	**$359.00**

★ IBM AND APPLE ★





APPLE - 16K Ram Expansion Card, works with Microsoft Basic	**$99.50**
APPLE - Z-80 CPU Direct replacement for Z-80 Softcard	**$149.50**
IBM-PC Ram Expansion Card with 64K (256K available	**$475.00**

Circle 420 on inquiry card.

PRINTERS

- C-ITOH PROWRITER $625.00
- C-ITOH Comet I 9 x 7 Dot Matrix ...$450.00
- C-ITOH Comet II...$810.00 132 Column Printer 9 x7 Dot Matrix
- MPI-88G $725.00
- EPSON MX 80 ......CALL
- EPSON MX 100 .....CALL
- Anadex 9501 ....$1,235.00 Graphic Printer
- OKIDATA 82A $465.00
- Microline 80 ......$329.00

MONITORS

ZENITH VIDEO MONITOR—
ZVM $145.00

AMDEK MONITORS—
AMDEK Color 1 ...$399.00
AMDEK Video 300 .$229.00
w/Green Screen

California Computer Systems



- 2810 CPU Only — $255.00
- 2422 Dsk Cont Only — $330.00
- 2065C 64K Only — $510.00
- 2200A Mainframe Only — $450.00
- CCS Apple Boards Call for prices
- CCS 2200 System Tested and Assembled Only — $1,695.00

★SPECIAL★SPECIAL★SPECIAL★

CCS SYSTEM 2410

FEATURES

* DMA Disk Controller
* 2-Real Time Clocks
* 2-Serial/1-Parrell Port
* Hardware Vectored Interupts
* Supports C/PM, M/PM, OASIS

Comes with C/PM
only-$2200.00



MICRO SALES

11 EDISON DRIVE ★ NEW LENOX ★ ILLINOIS 60451
CALL TOLL FREE: 1-800-435-9357 ★ MONDAY thru SATURDAY
(ILLINOIS RESIDENTS CALL: 815-485-4002) ★ 8:00 a.m. to 6:30 p.m.

TERMS: Prepayment — C.O.D. up to $100.00 — M/C Visa
$5.00 Processing and Handling added to each order PLUS
Shipping Charges. Please allow personal check to clear before shipment.
15% Restocking Charge

SSM

CB2-CPU	$295.00
MB10A-16K	$295.00
MB64-64K	$845.00
I/05-2SER 3PAR	$329.00
I/O8-8SER	$550.00

Apple

A-I/O II	$225.00
A-SI/O	$149.00

COMMUNICATIONS PACKAGES

TRACEND I	$89.00
TRACEND II	$149.00

DISK DRIVES

- Shugart 801's — $395.00
- Shugart 851's — $575.00
- Qume DT-8's — $540.00
- Shugart 400's — $255.00
- Tandom 5¼ — $255.00

TERMINALS

- Adds Regent 20 — $570.00
- Televideo 910 — $575.00
- Televideo 912C — $665.00
- Televideo 925C — $740.00
- Televideo 950 — $950.00
- Ampex Dialog 80—$895.00
- Zenith Z19 — $745.00


Zenith data systems

CALL FOR PRICES

FEATURES!

TERMINAL

- Feather Touch Capacitance Keyboard
- 60 Key Standard ASCII PLUS + Hex Keypad PLUS + 8 Special Function Keys PLUS + 20 Screen Editing Keys
- SOROC Type Screen Attribute Set
- Half Intensity



COMPUTER

- 8 Slot S-100
- 64K Dynamic Ram
- 4MHZ Z-80
- Double Density Disk Controller
- Programmable Baud Rate
- Programmable Keyboard Set
- Serial Printer Port (150-19.2K)

S-100-8

INCLUDING CP/M 2.2®
AND WORDSTAR®

WITH: 8" SS/DD Drives Only $2850.00
5¼" SS/DD Drives Only $2700.00

CALL FOR QUOTE ON DIFFERENT DRIVE OPTIONS

WORDSTAR is a TM of Micropro Inc. – CP/M 2.2 is a TM of Digital Research Inc.

Circle 420 on inquiry card.

16K Memory 4116-200ns 8/15.95

ALL MERCHANDISE 100% GUARANTEED! **CALL US FOR VOLUME QUOTES**

EPROMS

			Each	8 pcs
1702	256 x 8	(1ns)	4.95	4.50
2708	1024 x 8	(450ns)	2.99	2.75
2758	1024 x 8	(5V) (450ns)	9.95	8.95
TMS2516	2048 x 8	(5V) (450ns)	6.95	5.95
2716	2048 x 8	(5V) (450ns)	5.50	4.95
2716-1	2048 x 8	(5V) (350ns)	9.00	8.50
TMS2716	2048 x 8	(450ns)	9.95	8.95
TMS2532	4096 x 8	(5V) (450ns)	12.95	11.95
2732	4096 x 8	(5V) (450ns) (200ns)		CALL
2764	8192 x 8	(5V) (450ns)		CALL

DYNAMIC RAMS

				100 pcs
4027	4096 x 1	(250ns)	2.50	2.00
4116-120	16,384 x 1	(120ns)	8/29.95	CALL
4116-150	16,384 x 1	(150ns)	8/18.95	1.95
4116-200	16,384 x 1	(200ns)	8/15.95	1.80
4116-300	16,384 x 1	(300ns)	8/14.95	1.75
4164	64,536 x 1	(200ns)		CALL

STATIC RAMS

				100 pcs
2101	256 x 4	(450ns)	1.95	1.85
2102-1	1024 x 1	(450ns)	.89	.85
21L02-4	1024 x 1	(LP) (450ns)	1.29	1.15
21L02-2	1024 x 1	(LP) (250ns)	1.69	1.55
2111	256 x 4	(450ns)	2.99	2.49
2112	256 x 4	(450ns)	2.99	2.79
2114	1024 x 4	(450ns)	8/16.95	1.95
2114L-2	1024 x 4	(LP) (200ns)	8/19.95	2.35
2114L-3	1024 x 4	(LP) (300ns)	8/18.95	2.25
2114L-4	1024 x 4	(LP) (450ns)	8/17.95	2.10
2147	4096 x 1	(55ns)	9.95	CALL
TMS4044-4	4096 x 1	(450ns)	3.49	3.25
TMS4044-3	4096 x 1	(300ns)	3.99	3.75
TMS40L44-2	4096 x 1	(LP) (200ns)	4.49	4.25
TMM2016	2048 x 8	(200ns) (150ns)		CALL
HM6116	2048 x 8	(200ns) (150ns) (120ns)		CALL

LP = LOW POWER

74LS00 SERIES

				74LS166	2.40	74LS293	1.85
74LS00	.25	74LS85	1.15	74LS168	1.75	74LS295	1.05
74LS01	.25	74LS86	.40	74LS169	1.75	74LS298	1.20
74LS02	.25	74LS90	.65	74LS170	1.75	74LS324	1.75
74LS03	.25	74LS91	.89	74LS173	.80	74LS352	1.55
74LS04	.25	74LS92	.70	74LS174	.95	74LS353	1.55
74LS05	.25	74LS93	.65	74LS175	.95	74LS363	1.35
74LS08	.35	74LS95	.85	74LS181	2.15	74LS364	1.95
74LS10	.25	74LS96	.95	74LS189	9.95	74LS365	.95
74LS11	.35	74LS107	.40	74LS190	1.00	74LS366	.95
74LS12	.35	74LS109	.40	74LS191	1.00	74LS367	.70
74LS13	.45	74LS112	.45	74LS192	.85	74LS368	.70
74LS14	1.00	74LS113	.45	74LS193	.95	74LS373	.99
74LS15	.35	74LS114	.50	74LS194	1.00	74LS374	1.75
74LS20	.25	74LS122	.45	74LS195	.95	74LS377	1.45
74LS21	.35	74LS123	.95	74LS196	.85	74LS378	1.18
74LS22	.25	74LS124	2.99	74LS197	.85	74LS379	1.35
74LS26	.35	74LS125	.95	74LS221	1.20	74LS385	1.90
74LS27	.35	74LS126	.85	74LS240	.99	74LS386	.65
74LS28	.35	74LS132	.75	74LS241	.99	74LS390	1.90
74LS30	.25	74LS136	.55	74LS242	1.85	74LS393	1.90
74LS32	.35	74LS137	.99	74LS243	1.85	74LS395	1.65
74LS33	.55	74LS138	.75	74LS244	.99	74LS399	1.70
74LS37	.55	74LS139	.75	74LS245	1.90	74LS424	2.95
74LS38	.35	74LS145	1.20	74LS247	.76	74LS447	.37
74LS40	.35	74LS147	2.49	74LS248	1.25	74LS490	1.95
74LS42	.55	74LS148	1.35	74LS249	.99	74LS668	1.69
74LS47	.75	74LS151	.75	74LS251	1.30	74LS669	1.89
74LS48	.75	74LS153	.75	74LS253	.85	74LS670	2.20
74LS49	.75	74LS154	2.35	74LS257	.85	74LS674	9.65
74LS51	.25	74LS155	1.15	74LS258	.85	74LS682	3.20
74LS54	.35	74LS156	.95	74LS259	2.85	74LS683	2.30
74LS55	.35	74LS157	.75	74LS260	.65	74LS684	2.40
74LS63	1.25	74LS158	.75	74LS266	.55	74LS685	2.40
74LS73	.40	74LS160	.90	74LS273	1.65	74LS688	2.40
74LS74	.45	74LS161	.95	74LS275	3.35	74LS689	2.40
74LS75	.50	74LS162	.95	74LS279	.55	81LS95	1.69
74LS76	.40	74LS163	.95	74LS280	1.98	81LS96	1.69
74LS78	.50	74LS164	.95	74LS283	1.00	81LS97	1.69
74LS83	.75	74LS165	.95	74LS290	1.25	81LS98	1.69

CRYSTALS

32.768 KHZ	3.95
1.0 MHZ	4.95
1.8432	4.95
2.0	3.95
2.097152	3.95
2.4576	3.95
3.2768	3.95
3.579545	3.95
4.0	3.95
5.0	3.95
5.0688	3.95
5.185	3.95
5.7143	3.95
6.5536	3.95
8.0	3.95
10.0	3.95
14.31818	3.95
18.0	3.95
18.432	3.95
20.0	3.95
22.1184	3.95
32.0	3.95

MISC.

AY5-2376	12.50
11C90	13.95
XR2206	4.95
3242	7.95
3480	9.00
MC4024	3.95
MC4044	4.50
7103	9.50
7106	9.95
7107	12.95
76477	3.95
8038	3.95
95H90	7.99
9602	1.50

DISC CONTROLLERS

1771	24.95
1791	36.95
1793	44.95
1797	54.95
UPD765	39.95

UARTS

AY3-1014	6.95
AY5-1013	3.95
TR1602	4.95
IM6402	7.95

INTERFACE

8T26	1.69
8T28	2.49
8T95	.99
8T96	.99
8T97	.99
8T98	.99
DM8131	2.95
DS8836	1.29

CLOCK CIRCUITS

MM5369	3.95
MM5375	3.95
MSM5832	7.45
7207	7.50
7208	15.95

CONVERTERS

MC1408 L8	4.95
DAC-0800	4.95
ADC-0804	4.95

April Specials

4116-250NS	**8/13.95**
Z-80A CPU	6.00
Z-80A PIO	6.00
D3242 Intel	6.95
2532	8/75.00
2732	8/70.00

LM1310	50/ 95.00	LM1488	.75
LM1800	50/125.00	LM1489	.75
MC1330	50/ 70.00	DM8131	2.75
MC1350	50/ 50.00		

16PIN IC Sockets 100/$12.00

SUPER SPECIAL

Hitachi HM6116LP ***2048 x 8 CMOS Static Ram*** pin compatible with the 2716 EPROM. ***Super low power*** data retention characteristics: 2.0 volts at only 50ua yes ***50 microamps.***

		1-31 pcs.	*32 pcs.*
HM6116LP-2	120ns	19.95ea	18.95ea
HM6116LP-3	150ns	16.95ea	15.95ea
HM6116LP-4	200ns	15.95ea	14.95ea

STANDARD POWER RAMS

HM6116P-2	120ns	18.95ea	17.95ea
HM6116P-3	150ns	11.95ea	10.95ea
HM6116P-4	200ns	10.95ea	9.95ea

Specials end April 30, 1982. Please state "April Specials" when ordering.

6502

6502	6.95
6502-A	12.95
6504	6.95
6505	8.95
6507	9.95
6520	4.35
6522	9.95
6532	14.95
6551	11.85

Z80

Z80-CPU	8.95
Z80A-CPU	6.00
Z80-P10	6.50
Z80A-P10	6.00
Z80-CTC	5.95
Z80A-CTC	8.65
Z80-DART	15.25
Z80A-DART	18.75
Z80-DMA	17.50
Z80A-DMA	27.50
Z80-S10/0	23.95
Z80A-S10/0	28.95
Z80-S10/1	23.95
Z80A-S10/1	28.95
Z80-S10/2	23.95
Z80A-S10/2	28.95
Z80-S10/09	17.95
Z80A-S10/9	22.95
Z80B-CPU	18.95
Z80B-CTC	17.95
Z80B-P10	17.95
Z8671	39.95
Z6132	34.95

CMOS

74C00	.35	74C374	2.75	4019	.45	4098	2.49
74C02	.35	74C901	.80	4020	.95	4099	1.95
74C04	.35	74C902	.85	4021	.95	14409	12.95
74C08	.35	74C903	.85	4022	1.15	14410	12.95
74C10	.35	74C905	10.95	4023	.35	14411	11.95
74C14	1.50	74C906	.95	4024	.75	14412	12.95
74C20	.35	74C907	1.00	4025	.35	14419	4.95
74C30	.35	74C908	2.00	4026	1.65	4502	.95
74C32	.50	74C909	2.75	4027	.65	4503	.65
74C42	1.75	74C910	9.95	4028	.80	4508	1.95
74C48	2.10	74C911	10.00	4029	.95	4510	.95
74C73	.65	74C912	10.00	4030	.45	4511	.95
74C74	.85	74C914	1.95	4034	2.95	4512	.95
74C76	.80	74C915	2.00	4035	.85	4514	1.25
74C83	1.95	74C918	2.75	4040	.95	4515	2.25
74C85	1.95	74C920	17.95	4041	1.25	4516	1.55
74C86	.95	74C921	15.95	4042	.75	4518	1.25
74C89	4.50	74C922	5.95	4043	.85	4519	1.25
74C90	1.75	74C923	5.95	4044	.85	4520	1.25
74C93	1.75	74C925	6.75	4046	.95	4522	1.25
74C95	1.75	74C926	7.95	4047	.95	4526	1.25
74C107	1.00	74C927	7.95	4049	.55	4527	1.95
74C150	5.75	74C928	7.95	4050	.55	4528	1.25
74C151	2.25	74C929	19.95	4051	.95	4531	.95
74C154	3.25	74C930	19.95	4053	.95	4532	1.95
74C157	1.75	4000	.35	4060	1.45	4538	1.95
74C160	2.00	4001	.35	4066	.75	4539	1.95
74C161	2.00	4002	.25	4068	.40	4543	2.70
74C162	2.00	4006	.95	4069	.35	4555	.95
76C163	2.00	4007	.29	4070	.35	4556	.95
74C164	2.00	4008	.95	4071	.30	4581	1.95
74C165	2.00	4009	.45	4072	.30	4582	1.95
74C173	2.00	4010	.45	4073	.30	4584	.95
74C174	2.25	4011	.35	4075	.30	4585	.95
74C175	2.25	4012	.25	4076	.95	4702	12.95
74C192	2.25	4013	.45	4078	.30	4724	1.50
74C193	2.25	4014	.95	4081	.30	80C07	.95
74C195	2.25	4015	.95	4082	.30	80C95	.85
74C200	5.75	4016	.45	4085	.95	80C96	.95
74C221	2.25	4017	1.15	4086	.95	80C97	.95
74C373	2.75	4018	.95	4093	.95	80C98	1.20



JDR MICRODEVICES, INC.
1224 So. Bascom Ave.
San Jose, CA 95128
800-538-5000 • 800-662-6279 (CA)
(408) 995-5430 • Telex 171-110

TERMS: For shipping include $2.00 for UPS ground, $3.00 for UPS Blue Label air. $10.00 minimum order. Bay Area residents add 6½% sales tax. California residents add 6% sales tax. We reserve the right to limit quantities and substitute manufacturer. Prices subject to change without notice. Send SASE for complete list.

2716 EPROMS 450NS (5V) 8/4.95 ea.

ALL MERCHANDISE 100% GUARANTEED! **CALL US FOR VOLUME QUOTES**

8000

8035	16.95
8039	19.95
8080A	3.95
8085	12.95
8085A-2	16.95
8086	99.95
8088	39.95
8155	11.95
8156	11.95
8185	29.95
8185-2	39.95
8741	39.95
8748	29.95
8755	44.95

8200


8202	45.00
8205	3.50
8212	1.85
8214	3.85
8216	1.80
8224	2.50
8226	1.80
8228	4.90
8237	19.95
8238	4.95
8239	4.85
8243	4.45
8250	14.95
8251	4.75
8253	9.25
8253-5	9.85
8255	4.75
8255-5	5.25
8257	8.75
8259	6.90
8272	39.95
8275	29.95
8279	9.50
8279-5	10.50
8282	6.65
8283	6.65
8284	5.70
8286	6.65
8287	6.50
8288	25.00
8289	49.95

TV CIRCUITS

MC1330	1.89
MC1350	1.29
MC1358	1.79
LM380	1.29
LM386	1.50
LM565	.99
LM741	.29
LM1310	2.90
LM1800	2.99
LM1889	2.49

APPLE FAN $69.00

- EXTRA PLUG-IN CARDS CAN CAUSE YOUR APPLE TO OVERHEAT
- ULTRA-QUIET APPLE FAN DRAWS COOL AIR THROUGH YOUR COMPUTER
- ELIMINATES DOWN TIME
- SAVES REPAIR CHARGES
- INCREASES RELIABILITY
- CLIPS ON — NO HOLES OR SCREWS
- COLOR MATCHES APPLE
- LONG LIFE, LOW NOISE MOTOR



*APPLE IS A TRADEMARK OF APPLE COMPUTER INC.

IC SOCKETS

	1-99	100
8 pin ST	.13	.11
14 pin ST	.15	.12
16 pin ST	.17	.13
18 pin ST	.20	.18
20 pin ST	.29	.27
22 pin ST	.30	.27
24 pin ST	.30	.27
28 pin ST	.40	.32
40 pin ST	.49	.39

ST = SOLDERTAIL

8 pin WW	.59	.49
14 pin WW	.69	.52
16 pin WW	.69	.58
18 pin WW	.99	.90
20 pin WW	1.09	.98
22 pin WW	1.39	1.28
24 pin WW	1.49	1.35
28 pin WW	1.69	1.49
40 pin WW	1.99	1.80

WW = WIREWRAP

CONNECTORS

RS232 MALE	3.25
RS232 FEMALE	3.75
RS232 HOOD	1.25
S-100 ST	3.95
S-100 WW	4.95

DIP SWITCHES

4 POSITION	.85
5 POSITION	.90
6 POSITION	.90
7 POSITION	.95
8 POSITION	.95

EPROM ERASERS

PE-14	78.50
PE-14T (with timer)	108.50
PE-24T (with timer)	154.50

ALL ARE HIGH QUALITY UNITS ENCLOSED IN A BLACK ANODIZED ALUMINUM ENCLOSURE.

6800

6800	5.70
6802	10.95
6808	9.95
6809	24.95
6809E	29.95
6810	4.60
6820	4.95
6821	4.95
6828	14.95
6834	16.95
6840	14.95
6843	42.95
6844	44.95
6845	16.95
6847	15.95
6850	4.75
6852	5.75
6860	10.95
6862	11.95
6875	6.95
6880	2.95
68B00	10.95
68B21	12.95
68B50	12.95

800-538-5000
800-662-6279
(CALIFORNIA RESIDENTS)

CALL JDR BEFORE YOU BUY!
WE WILL BEAT ANY COMPETITORS' PRICES

TRANSISTORS

PN2222	10/1.00	100/ 8.99
2N2222	.25	50/10.99
2N2907	.25	50/10.99
2N3055	.79	10/ 6.99
2N3904	10/1.00	100/ 8.99
2N3906	10/1.00	100/ 8.99
1N4148 (1N914)		25/ 1.00
1N4004		10/ 1.00

LEDS

Jumbo Red	10/1.00
Jumbo Green	6/1.00
Jumbo Yellow	6/1.00
5082-7760 .43'CC	.79
MAN74 .3'CC	.99
MAN72 .3'CA	.99

VOLTAGE REG's

7805T	.79	7905T	.89
7808T	.99	7912T	.89
7812T	.79	7915T	1.19
7815T	.99	7924T	1.19
7824T	.99		
7805K	1.39	7905K	1.49
7812K	1.39	7912K	1.49
7815K	1.39	79LO5	.79
78LO5	.69	79L12	.79
78L12	.69	79L15	.79
78L15	.69		
		LM317K	3.95
LM309K	1.49	LM323K	4.95
LM317T	1.95	LM337K	3.95

T = TO-220 K = TO-3 L = TO-92

LINEAR

LM301V	.34
LM308V	.98
LM309K	1.49
LM311	.64
LM317T	1.95
LM317K	3.95
LM318	1.49
LM323K	4.95
LM324	.59
LM337K	3.95
LM339	.99
LM377	2.29
LM380	1.29
LM386V	1.50
LM555V	.39
LM556	.69
LM565	.99
LM566V	1.49
LM567V	1.29
LM723	.49
LM733	.98
LM741V	.29
LM747	.79
LM748V	.59
LM1310	2.90
MC1330V	1.89
MC1350V	1.29
MC1358	1.79
LM1414	1.59
LM1458V	.69
LM1488	.99
LM1489	.99
LM1800	2.99
LM1889	2.49
LM3900	.59
LM3909V	.98
LM3914	3.95
LM3915	3.95
LM3916	3.95
75451V	.39
75452V	.39
75453V	.39

74S00 SERIES

74S00	.44	74S74	.69	74S163	3.75	74S257	1.39
74S02	.48	74S85	2.39	74S168	4.65	74S258	1.49
74S03	.48	74S86	1.44	74S169	5.44	74S260	1.83
74S04	.79	74S112	1.59	74S174	1.09	74S274	19.95
74S05	.79	74S113	1.98	74S175	1.09	74S275	19.95
74S08	.48	74S114	1.50	74S181	4.47	74S280	2.90
74S09	.98	74S124	2.77	74S182	2.95	74S287	4.75
74S10	.69	74S132	1.24	74S188	3.95	74S288	4.45
74S11	.88	74S133	.98	74S189	14.95	74S289	6.98
74S15	.70	74S134	.69	74S194	2.95	74S301	6.95
74S20	.68	74S135	1.48	74S195	1.89	74S373	3.45
74S22	.98	74S138	1.08	74S196	4.90	74S374	3.45
74S30	.48	74S139	1.25	74S197	4.25	74S381	7.95
74S32	.98	74S140	1.45	74S201	14.95	74S387	5.75
74S37	1.87	74S151	1.19	74S225	8.95	74S412	2.98
74S38	1.68	74S153	1.19	74S240	3.98	74S471	9.95
74S40	.44	74S157	1.19	74S241	3.75	74S472	16.85
74S51	.78	74S158	1.45	74S244	3.98	74S474	17.85
74S64	.79	74S161	2.85	74S251	1.90	74S482	15.60
74S65	1.25	74S162	3.70	74S253	7.45	74S570	7.80
						74S571	7.80

7400 SERIES

7400	.19	7451	.23	74136	.50	74186	18.50
7401	.19	7453	.23	74141	.65	74190	1.15
7402	.19	7454	.23	74142	2.95	74191	1.15
7403	.19	7460	.23	74143	2.95	74192	.79
7404	.19	7470	.35	74144	2.95	74193	.79
7405	.22	7472	.29	74145	.60	74194	.85
7406	.22	7473	.34	74147	1.75	74195	.85
7407	.22	7474	.35	74148	1.20	74196	.79
7408	.24	7475	.49	74150	1.35	74197	.75
7409	.19	7476	.35	74151	.65	74198	1.35
7410	.19	7480	.59	74152	.65	74199	1.35
7411	.25	7481	1.10	74153	.55	74221	1.35
7412	.30	7482	.95	74154	1.40	74246	1.35
7413	.35	7483	.50	74155	.75	74247	1.25
7414	.55	7485	.65	74156	.65	74248	1.85
7416	.25	7486	.35	74157	.55	74249	1.95
7417	.25	7489	4.95	74159	1.65	74251	.75
7420	.19	7490	.35	74160	.85	74259	2.25
7421	.35	7491	.40	74161	.70	74265	1.35
7422	.29	7492	.50	74162	.85	74273	1.95
7423	.29	7493	.49	74163	.85	74276	1.25
7425	.29	7494	.65	74164	.85	74279	.75
7426	.29	7495	.55	74165	.85	74283	2.00
7427	.29	7496	.70	74166	1.00	74284	3.75
7428	.45	7497	2.75	74167	2.95	74285	3.75
7430	.19	74100	1.00	74170	1.65	74290	.95
7432	.29	74107	.30	74172	5.95	74293	.75
7433	.45	74109	.45	74173	.75	74298	.85
7437	.29	74110	.45	74174	.89	74351	2.25
7438	.29	74111	.55	74175	.89	74365	.65
7440	.19	74116	1.55	74176	.89	74366	.65
7442	.49	74120	1.20	74177	.75	74367	.65
7443	.65	74121	.29	74178	1.15	74368	.65
7444	.69	74122	.45	74179	1.75	74376	2.20
7445	.69	74123	.55	74180	.75	74390	1.75
7446	.59	74125	.45	74181	2.25	74393	1.35
7447	.69	74126	.45	74182	.75	74425	3.15
7448	.69	74128	.55	74184	2.00	74426	.85
7450	.19	74132	.45	74185	2.00	74490	2.55

HOURS: Mon. - Fri., 9 to 5; Sat. 11 to 3

VISIT OUR RETAIL STORE!




JDR MICRODEVICES, INC.
1224 S. Bascom Ave.
San Jose, CA 95128
800-538-5000 • 800-662-6279 (CA)
(408) 995-5430 • Telex 171-110

TERMS: For shipping include $2.00 for UPS Ground, $3.00 for UPS Blue Label Air. $10.00 minimum order. Bay Area residents add 6½% sales tax. California residents add 6% sales tax. We reserve the right to limit quantities and substitute manufacturer. Prices subject to change without notice. Send SASE for complete list.

Circle 225 on inquiry card.

Circle 224 on inquiry card.



Circle 224 on inquiry card.

ADVANCED COMPUTER PRODUCTS

TOLL FREE ORDER LINE
800-854-8230



apple computer
Sales and Service

COMPUTERS

	LIST	ACP
Apple II 16K	$1330 00	$102900
Apple II 48K	1530 00	109900
Apple II 64K	172900	122500
Apple II 64K w/Z80 Softcard & Vision 80	2519 00	177500
★ Apple III 128K	3495 00	★ 289500

AVAILABLE IN STORE ONLY

APPLE HARDWARE

AVAILABLE IN STORE ONLY

	LIST	ACP
Apple Disk II w/interface	$ 645 00	$ 52900
Apple Disk II w/o	52500	44900
Silentype Printer	39500	35500
Prototype Card	24 00	21 95
IEEE-488 Interface	45000	37500
1 year ext warranty	22500	17500
Parallel Printer Interface	18000	15995
Communications Card	22500	18900
Pascal Language System	495 00	42595
High Speed Serial Interface	19500	174 95
Applesoft II ROM Card	200 00	159 95
Language Card	195 00	174 95
12" Green Monitor III	320 00	275 00
★ Profile Hard Disk Subsystem	3495 00	2995 00
Graphics Tablet	795 00	695 00

APPLE COMPATIBLE HARDWARE

Microsoft Z80 Softcard©		$299 00
Microsoft 16K RAMcard©		169 00
SSM AIO Serial/Parallel		165 00
The Keyboard Company	Joystick	4500
	Numeric Pad	11900
Mountain Computer	ROMplus	16900
	ROM Writer	15900
	RAMPlus	call
	CPS Multifunction	22900
	Expansion Chassis	69900
	Thunderclock	125 00
	X-10 option	4900
	Pascaloption	2900
Versacard 4 in 1		22500
CCS Serial I/O		139 00
Parallel I/O		9900
M & R Enterprises	Apple Fan	4500
	Sup'R Mod	2995
	Aux Switcher Supply	19900
	Sup'R Term	29900
ALS Smarterm		29900
Corvus	5Mb Hard Disk	2995 00
	10Mb	432500
	20Mb	524000
Apple 16K Upgrade Kit		1595
Votrax Voice Box		call
Scott Voice Recognition		849 00

APPLE SOFTWARE

Visicalc	$ 16900
SuperCalc	19900
VisiTrend/VisiPlot	23900
VisiDex	16900
VisiTerm	12900
BPI General Ledger	32900
Accounts Receivable	32900
Inventory	32900
Microcourier	22900
Micro Telegraph	22900
Accounting Plus	119500
DB Master	17900
Wordstar	25900
Super Sort	14900
Mail Merger	8900
Data Star	19900
Spell Star	16900
VTS-80 CP/M	319 00
Fortran80	195 00
Cobol 80	699 00
PFS Filing System	75 00
PFS Report	75 00

NEW INSOFT "ELECTRIC DUET" $29.95

FLOPPY DISK DRIVES QUME DT/8 D/D D/S



Qume Only $569.95

QUME DT/8 D/D D/S	$ 569 95
Tandom TM100-1 5 1/4" Disk Drive	27900
MPI B5-1-5 1/4", 40 tracks	27900
Shugart SA400-5 1/4" 35 tracks	29500
Shugart 800/801R 8"	449 00
Siemens Shugart Compatible Model FDD-120-8D	429 00
PERSCI Model 277 Dual	1195 00
MPI B52 5 1/4" Dual	34800
WANGO SIEMENS 2	290 00
MPI 91 Double Track Density Single Side 80 Tracks	375 00
MPI 92 Double Track Density Double Side 160 Track	475 00

16K RAMCARD

- Compatible w Applesoft CP M and PASCAL
- Why pay more


$89.95 Complete

DEALER PRICING AVAILABLE

Vista

VISTA COMPUTER

	LIST	ACP
★ Vision 80 © 80x24 display card	$395 00	$299 00
Vision 40 © 40col enhancement	199 00	149 00
Vision 20© lower case ROM	29 95	25 00
★ A800 Double Density 8 Controllers	595 00	★ 499 00
MM9 9 voice music	195 00	99 00
GB75 IBM Regent Apple I O	195 00	169 00
PDS PROM development	595 00	399 00
TYPE AHEAD BUFFER	49 95	35 00



VISTA V-DRIVE

VISTA V-DRIVE
Model V-1000 8" floppy disk enclosures with Qume Datatrak 8

CABINET	$ 459 95
w/2 single-sided drives ps&c	$149500
w/2 double-sided drives ps&c	$199500
A800 Double density controller (for Apple computers)	$ 49900

VISTA V 80

MINI DISK DRIVE

V 80 Single drive, case ps	$299 00
V 80 Dual drive, case, ps	$589 00

D/S, D/D also available

APPLE COMPATIBLE DRIVES (MicroSci)

A2 series is plug-compatible
Save $300 on dual drive system
DOS software not included

	LIST	ACP
★ A2 5 1/4" 143K Drive	$47900	★ $38900
A2C controller	100 00	8900
A405 1/4" 160K Drive	449 00	36500
A70 5 1/4" 286K Drive	599 00	480 00
A40C controller for A40/A70	100.00	79 00

DISKETTES

VERBATIM & Maxell Diskettes
100% CERTIFIED ERROR-FREE!

• 35 TRACKS DOUBLE DENSITY SINGLE-SIDED 5¼

TYPE	DESCRIPTION	PRICE BOX 10
525-01	Soft Sectored TRS 80 etc	$29 95
525-10	10 Hole Hard NS Apple etc	$29 95
525-16	16 Hole Hard Micropolis	$29 95

• 40 & 77 TRACK DOUBLE DENSITY - SINGLE SIDED 5¼ W/HUB REINFORCEMENT RING

577-01	Soft Sectored TRS 80 etc	$32 25
577-10	10 Hole Hard NS Apple etc	32 25
577-16	16 Hole Hard Micropolis	32 25

• 40 TRACKS DOUBLE SIDED DOUBLE DENSITY 5¼

550-01	Soft Sectored SA 450 MPI 52	$39 95
550-10	10 Hole Hard BASF WANGCO	$39 95
550-16	16 Hole Hard Micro	$39 95

• 8" 100% CERTIFIED DISKETTES

FD800-01	Soft Single Density 3740	$33 50
FD800-32	32 Hard Single Density Shug	33 50
FD802-01	Soft Double Density 3740	44 80
FD850-21	Soft Double Sided Double Density 3740	49 80

ROBOTIC ARM

- Automation or Robotic Assembly
- Education in Robotic Priciples
- Artificial Inteligence Experiments
- Computer Art and Games

Microbot **$1695.00**

Microbot Minimover-5 Completely Assembled w/Applications Manual	$1695 00
ARMBASIC Software For TRS-80	39 95
Application/Reference Manual	16 95

HEWLETT PACKARD CALCULATORS



HP-41CV Only $256.00

HP-41CV w 2 2K memory	NEW!	325 00	256 00
HP-41C Calculator		25000	189 95
Memory Module for 41C			26 00
Quad RAM		95 00	83 95
CardReader for 41C CV		21500	169 95
Printer for 41C CV		38500	291 95
Optical Wand for 41C CV		12500	99 95
HP-11C Advanced Scientific	★ NEW!	135 00	149 95
HP-12C Financial		15000	129 95
HP-34C Prog Scientific		15000	119 00
HP-38C Prog Business		15000	119 00
HP-97 Programmable Printer		750 00	595 00

NOTE WE STOCK ACCESSORIES



PRINTERS

		LIST	ACP
EPSON/VISTA			
MX-80 Dot Matrix		$645 00	★ $429 00
★ MX-80 FT		74500	52900
MX-100		999 00	725 00
Apple I O & cable		110 00	8900
Graftrax option		95 00	89 00
IEEE I O & cable		13000	9500
Serial I O & cable		13000	9500
Serial w 2K & cable		175 00	14900
Universal Graphics Utility		3995	★ 3595
NEC			
8023 Dot Matrix		795 00	64900
DIABLO			
★ 630 Daisywheel		2965 00	★ 229500
Tractor		24900	169 95
C. ITOH/VISTA			
★ Starwriter V300	25cps	1895 00	★ 149500
	45cps	2195 00	179500
8510	100 cps	749 00	★ 675 00
ANADEX			
9500/9501		1650 00	1350 00
QUME			
9/45		329500	2995 00
IDS			
460G w/graphics		139500	89900
560G 14 75" carriage		1695 00	1199 00



TERMINALS

	LIST	ACP
TELEVIDEO		
910	$ 699 00	$ 59900
912C	95000	69900
920C	99500	79900
950C	119500	99900
SOROC		
IQ120		69900
IQ135		89900
IQ140		1149 00



MONITORS

	LIST	ACP
SANYO		
9" B&W	$235 00	$169 95
9" Green	259 00	199 95
12" B&W	340 00	249 00
12" Green	360 00	279 00
13" Color	550 00	429 00
13" RGB	1195 00	995 00



MODEMS

	LIST	ACP
NOVATION		
Cat	$19995	$14900
D-Cat	19995	16900
Apple-Cat	34995	30900
Auto-Cat	29995	239 95
HAYES		
Micromodem	$37900	$29900
Smartmodem	27900	249 00



MUFFIN TYPE FAN

115 VAC 7 watts WR2A1 $13 95

Factory fresh

IBM

IBM COMPATIBLE BOARDS

Top Quality 1 year warranty

	LIST	ACP
★ 256K Add-on memory	$1145 00	★ $899 00
PC Communications	295 00	269 00
Graphics		call
Wire Wrap kit w extender	95 00	89 00



ATARI®

ATARI COMPUTER

	LIST	ACP
400 w 16K RAM	$399 00	$339 95
400 Basic Language Module	49 00	47 00
800 w 16K RAM	899 00	699 00
410 Prog Recorder	9000	80 00
825 Printer	79995	699 00
830 Acoustic Modem	19995	159 00
850Interface Module	219 95	18995
MTK 16K RAM	9950	8400
MTK 32K RAM	19950	13900
ATARI VisiCalc	20000	160 00
ATARI Pac-Man	44 95	3695

ATARI "THE COMMUNICATOR" Kit

Package Deal

850 I O — Source Pkg
830 Modem — Dow Jones Pkg
Telelink 1 — Compuserve Pkg
Total Value $444 85


ACP **$379.95**

XEROX 820

"The Personal Computer"

FREE TCS BUSINESS SOFTWARE
w/purchase A R G L A P Payroll Inventory
$1100 00 VALUE 8" only

		LIST	ACP
820-1	5 1/4 system	$2995 00	$2496 00
★ 820-2	8 system	3795 00	★ 3195 00
CP/M		20000	169 95
SuperCalc		29500	23995
Word Processing		50000	429 95





HEWLETT-PACKARD COMPUTERS

★ New

	LIST	ACP
HP-87 Microcomputer	$2495 00	$2195 00
HP-125 CPM Microcomputer	3750 00	3090 00
HP-85 Microcomputer	2750 00	2375 00
HP-83 Microcomputer	2250 00	1889 00
82903A 16K Memory Module	195 00	174 95
7225 Graphics Plotter	2450 00	2125 00
7225 Personality Module	750 00	675 00
HP-125080 8" Disk	1210 00	1085 00
HP-9895A 8" Disk	6850 00	5750 00
HP-9111A Graphics Tablet	2050 00	1790 00

SINGLEBOARD COMPUTERS

ROCKWELL	
AIM 65 w/1K	$43500
AIM 65 w/4K	475 00
8K BASICROM	9900
4K Assembler ROM	84 00
Power Supply	64 95
Enclosure	49 95
Total system w 4K	66900
SYNERTEK	
SYM-1	239 00
SD SYSTEMS	
Z80 Starter Kit	36700
Z80 Starter A & 1	450 00
SBC 100 A & 1	367 00
SBC 200 A & 1	39900
RCA	
Cosmac VIP	19900

TERMS: MO Cashier's Check Bank Wire Personal checks allow 2 weeks for processing Include Driver's License and credit card #s Visa MC AMEX CB add3%servicecharge Add3% shipping & Handling or $2 whicheverisgreater Add 10% forforeignorders or US Parcel Post include Telephone number NO CODs Prices suject to change without notice Some items subject to prior sale We reserve the right to substitute manufacturer Retail prices may vary

☆ SUPER SPECIALS ☆

EPSON/VISTA MX-80

#1 Best seller
LOWEST PUBLISHED PRICE
Note: Supply Limited

LIST $645 00 — ACP **$429.00**

SAVE $300

Apple Board Set	LIST	ACP
Z80 Softcard (Microsoft)	$395 00	$289 00
16K Ramcard (Microsoft)	195 00	169 00
Vision 80 display card (Vista)	395 00	299 00

ALL THREE ONLY $679 save $306

ELPAC FD206 8"

Floppy Disk Power Supply
Drives 2 Drives
+24V @ 3A +5V @ 2 5A -5V @ 0 5A
LIST $159 00 — ACP $99 00

AMDEK

12" B&W Monitor (Super Value)

$89.95 ea.

Circle 10 on inquiry card.

BECKMAN DIGITAL MULTIMETERS

TECH 300 Digital Multimeter	$ 110 00
TECH 310 Digital Multimeter	140 00
TECH 330 Digital Multimeter	189 00
VC-201 Vinyl Carrying Case	10 00
DC-202 Deluxe Carrying Case	24 00
HV-211 High Voltage Probe	35 00
RP-221 RP Probe	35 00
CT-231 AC Current Clamp	42 00
DL-241 DeluxeTest Lead Kit	10 00
TL-242 Square Test Leads	6 00

NLS TOUCH TEST 20

Digital Multimeter	$349 95

S100 32K STATIC RAM BOARD

2 or 4 MHz Expandable uses 2114L's

16K 4 MHz Kit	$159 95
16K 4MHz A&T	217 95
32K MHz Kit	289 95
★ 32K 4 MHz A&T	★ 339 00
Bare Board	39 95
Bare Bd w/all parts less mem.	99 95

8080/8085 SUPPORT

8155/8156 I/O	$ 11 95
8755 I/O w/EPROM	44 95
8202 Dyn RAM Cont	34 95
8205/74S 138 Decoder	3 95
8212 8 bit I/O	2 75
8214 Priority Int	5 25
8216 Bus Driver	2 75
8224 Clock Gen	2 95
8224 4 MHz	9 75
8226 Bus Driver	2 95
8T26 Bus Driver	2 95
8228 Sys Con	4 50
8238 Sys Con	5 50
8243 I/O Exp	9 50
8250 Asyn Com	15 95
8251 Prog I/O	6 95
8253 Int Timer	12 95
8255 Prog I/O	4 50
8257 Prog DMA	9 95
8259 Prog Int	9 95
8275 CRT Con	29 95
8279 Prog Keyboard	9 95

Z80 SUPPORT

Z80-PIO	2 5 MHz	$ 6 75
Z80A-PIO	4 0 MHz	9 95
Z80-CTC	2 5 MHz	6 75
Z80A-CTC	4 0 MHz	9 95
Z80-DMA	2 5 MHz	19 95
Z80A-DMA	4 0 MHz	29 95
Z80A-SIO/0	2 5 MHz	24 95
Z80A-SIO/0	4 0 MHz	29 95
Z80-SIO/1	2 5 MHz	24 95
Z80A-SIO/1	4 0 MHz	29 95
Z80-SIO/2	2 5 MHz	24 95
Z80A-SIO/2	4 0 MHz	29 95

4K STATIC RAM SELL-OFF

for Z80 based systems

★ Zilog 6104-4 4Kx1 450ns ★ $1 49

PROTO BOARDS

PB-6	$ 19 95
PB-100	21 00
PB-101	28 00
PB-102	34 00
PB-103	59 00
PB-104	77 00
PB-203	130 00
PB-203A	170 00
PB-203A Kit	140 00

PROTO CLIPS

PC-14	14 Pin	$ 3 25
PC-16	16 Pin	3 50
PC-24	24 Pin	8 50
PC-40	40 Pin	13 95

6800 SUPPORT

6810 128x8 RAM	$ 4 75
6820	6 50
6821	6 50
6828 Priority Int	10 75
6834-1 512x8 Eprom	16 95
6845/HD46505 CRT Cont	29 95
6847 Color CRT	29 95
6850ACIA	5 95
6852 Serial Adapter	5 95
6860 Modem	10 95
6682 Modulator	11 95
6871A 1 0MHz OSC	25 95
6880 Bus Driver	2 19
MC68488	19 95
68047	24 95

6520PIA	$ 7 50
6522Mult	11 95
6530-002, 003, 004, 005	21 95
6532	19 95
6551	19 95

BIPOLAR PROMS

82S23/6330/5600/74S188	$ 4 25
82S115 (512x8) TS	12 95
82S123/5610/74S268 (32x8) TS	4 25
82S126/5603/74S387 (256x4) OC	4 25
82S129/5623/74S287 (256x4) TS	4 25
82S130/5604/74S570 (512x4) OC	6 50
82S131/74S571 (512x4) TS	6 95
82S137/74S573 (1024x4) TS	12 95
82S141/3624/74S474 (512x8) TS	12 95
82S147/74S472 (512x8) TS	12 95
74S471/6309 (256x8) TS	7 95

MOS PROMS

2764 (8Kx8) TS	$89 95
2732 (4Kx8) TS	16 95
2716/2516, 5V (2Kx8) TS	8 95
TMS2716, ±5V, 12V	17 95
2758, 5V, (450ns)	7 50
2708 (450ns)	5 75
2708 (650ns)	5 25
1702A	5 75
MM5203AQ	14 50
MM5204Q	9 95

IC SPECIAL PURCHASE

82S09 64x9 RAM	$ 8 95
OP8304 Octal Driver	2 95
DAC86EX D/A Conv	6 95
MC1650 Hi Speed A/D	7 95
SN75136	46
MC10210	89
LM339	79
LM710CN	29
LM711CN	29
78M06	49
79M06	49
74157	49
74161	49
74C74	39
MC14433P 3 5 Digit A/D	13 95
ICL8211 Volt Ref	1 95
LM1850N Gr Fault	3 for 1 00
LM2900N Quad Amp	2 for 1 00
LM2917N Freq to Volt Conv	2 for 1 99
MEM4963 Mosfet Smoke Detector	7 95
27S08 32x8 PROM (IM5600)	2 95
ULN2003A 7ch dr	99
MCM14505 64 bit SI RAM	6 95
MOC1003 Opto Cap (4N28)	3 for 1 00
SPX33 Opto Coup	3 for 1 00
IH5045 CMOS Sw OPST	4 50
UA3045 Trans Array	1 25
TR1402A UART	1 95
MK1007 Dyn Mem Shift Req	3 95
5318 TV Ch Disp Circuit	4 50
8700 CJ 8 bit A/D	9 95
7520/25	50
1488/1489	2 for 1 99
MC1372	8 95
MM5298-4A/B	2 95
LM377	1 25
LM380	1 25
LM387	1 25
LM4558	3 for 1 99
RC4136	2 for 1 99
RC4131	2 for 1 99
COM 5027	39 95
COM 5037	49 95
TMS 4060 4K RAM (22 Pin)	1 49
TMS 4050 4K RAM (18 Pin)	1 49
MCM 6604 4K RAM (16 Pin)	1 49

416/4116 16K (16 Pin)	$ 2 49
416 200 ns Set of 8	15 95
4115 8K (16 Pin)	2 49
4050 4Kx1 (18 Pin)	4 95
4060 4Kx1 (22 Pin)	4 95
4096 4Kx1 (16 Pin)	3 95
2104 4Kx1 (16 Pin)	4 75
4027 4Kx1 (16 Pin)/UPD414	4 95
5261	1 95
5262	1 95
5270	4 95
5280	4 95
1103	95
4008L	4 95
6605	7 95
6804	4 95
6602	1 50
64K RAM	9 95

MICROPROCESSORS

Z8001 16 bit to 8Mb	$ 110 00
Z8002 16 bit to 64K	75 00
Z80	9 95
Z80A	11 95
F-8 (3850)	16 95
2650	16 95
CD1802	9 75
8080A	4 75
8080A-4MHz	19 95
8085	14 95
8008-1	14 95
2901	9 90
2901A	14 95
TMS 9900JL	49 95
6502	9 95
6502A	16 95
IM6100	29 95
6800	11 75
6800B 2 0 MHz	19 95
6802P	14 95
8035	14 95
8039	12 95
INS 8073N	34 95
8755	49 95
8748	49 95
6809	30 00
8086	49 95
68000	129 95

2513-001 (5V) Upper	$ 9 50
2513-005 (5V) Lower	10 95
2513-ADM3 (5V) Lower	14 95
MCM667 10 Ascii Shifted	12 95
MCM66740 Math Symbol	13 95
MCM66750 Alpha Control	13 45

DB25P (RS232)	$ 3 25
DB25S Female	3 75
Hood	1 25
Set w/Hood, Sale	7 50
22/44 W/W, S/T, KIM	2 95
43/86 W/W, S/T, MOT	6 50
50/100 S-100 Connector w/w	4 95
50/100 S-100 Connector s/t	3 95

BARE PC BOARDS

S-100 Sound Board	$ 34 95
8080A CPU	34 95
32K Static RAM (2114)	34 95
8K Eprom (2708)	24 95
2708/2716 Eprom	34 95
ACP Proto Bd	22 95
Vector 8800 Proto	22 20
Vector 8803 11 slot MB	29 95
ACP Extender w/Conn	18 95
13 Slot Mother Board (WMC)	32 95
9 Slot Mother Board (WMC)	29 95
8 Slot Mother (Expandable)	34 95
Floppy PCB (8" SHUGART)	39 95
S100 (AY5-8910) Sound Bd	34 95
Apple Sound Bd	24 95

UV "EPROM" ERASER

Model UVs-11E $79.95
Holds 4 Eproms at a time
★ Model S-52T ★ $325 00

16K MEMORY EXTENSION KITS

for Apple/TRS-80

★ 8 pcs 4116 16K 200/250ns ★
Specify computer $ 15 95
CALL FOR VOLUME PRICING

KEYBOARD ENCODERS

AY5-2376	$13 75
AY5-3600	13 75

MOSTEK

4K Dynamic RAM (16 Pin)
MK 4015 20 pcs @ 1 99
(Pin Equiv. MR 4027 w/ 1 ms refresh)
16K RAM SALE (4116) 100 pcs @ $1 15 ea
64K RAM SALE (4164 10 pcs @ 9 95 ea ★
16K STATIC RAM (TMM 2016) 8 pcs @ 9 95 ea

2708 EPROM

Prime 450 ns
8/29 95
2716 SALE 8/$9 95
2732 SALE 8/69 95

NEW! from Zilog

★ Z-8 CPU w/Tiny Basic & debug program $69 95 w/data
Plus 6132 companion quasi-static RAM $34 95 ea

★ NEW LOW PRICES

8255 Prog I/O	Only $ 1 95
8259 Prog Int	Only 6 95

STATIC RAMS

	1-24	25-99	100
21L02 450ns	$ 1 30	$ 1 25	$ 99
21L02 250ns	1 59	1 55	1 15
2111	3 75	3 65	3 55
2112-1	2 95	2 85	2 65
2101-1	2 90	2 70	2 55
2114N (450ns)	3 75	3 50	3 25
2114L-250ns (4045)	6 50	5 95	5 50
2114L-450ns (4045)	4 75	4 25	3 95
4044 250ns	8 95	7 50	6 90
4044450ns	5 95	5 95	4 75
EMM4200A	9 75	8 75	7 95
EMM4402	7 95	7 25	6 25
AMD9140/41	10 95	10 25	9 25
AMD9130/31	12 95	11 95	10 25
1101	1 95	1 75	1 25
P2125/93425 (45ns)	9 95	8 35	8 25
6513 1Kx1 CMOS	7 95	7 95	7 25
2147 Low Power 4 K Static	9 95	8 95	6 95
93415	9 95	8 95	8 50

SOCKETS

WireWrap 3 Level

# Pins	Lo-Pro Soldertail	Tin	Gold
8	15	$ 32	$ 45
14	19	36	59
16	20	38	62
18	24	59	64
20	29	69	99
22	24	79	1 10
24	38	85	1 20
28	43	1 10	1 49
36	58	1 25	1 59
40	60	1 40	1 89

FLOPPY DISK I/O

1771-01B" & Minifloppy	$ 24 95
1781 Dual Floppy	29 95
1791-01 Dual Floppy	36 95
1791-02 Dual Floppy	44 95
1793 DD, DS Floppy	44 95
1797 DD, DS Floppy	54 95
1691 Data Separator	18 95
2143 Clock Gen	18 95

A/D CONVERTERS

8700 8 bit Binaray	$ 13 50
8701 10 bit Binary	22 00
8703 8 bit TS	13 50
9400 Volt to Freq Conv	7 25
8750 3 1/2 Digit BCD	13 95
1408L6 6 bit	3 95
1408L8 8 bit	5 95
DAC01 D to A	5 95
DAC08	9 95
DAC 100	9 95

8038 Function Gen	$ 4 50
MC4024VCO	2 95
LM566VCO	1 95
XR2206 Function Generator	5 25

SHIFT REGISTERS

2504V	$ 1 49	MM500H	$ 50
2507V	1 49	MM5056N	2 95
2517V	1 49	MM5060N	2 95
2524V	1 49	2510A	1 95
2525	1 49	2847	4 95
2527	1 49	3341	4 95
2528	1 49	3351	17 95
2529	1 49	3357	6 95
2533	1 49	9403	24 95
3347	5 95	9408	9 95

CTS DIPSWITCHES

CTS206-2	$ 1 75	CTS206-7	$ 1 75
CTS206-4	1 75	CTS206-8	1 95
CTS206-5	1 75	CTS206 9	1 95
CTS206-6	1 75	CTS206-10	1 95

UARTS BAUD RATE

TR1602B (5V, 12V)	$ 3 95
AY51013 (5V, 12V)	4 95
AY51014A/1612 (5-14V)	6 95
AY51015A/1863 (5V)	6 95
IM6402	7 95
IM6403	8 95
2350 USRT	9 95
1671B Astros	24 95
MC14411	11 95
4702	14 95
WD1941	9 95
COM 5016	16 95
INS 8250	15 95

ZERO INSERTION FORCE

16 Pin $5 50 24 Pin $7 50 40 Pin $10 25

7400

SN7400N	$ 19	SN74123N	$ 59
SN7401N	22	SN74125N	39
SN7402N	22	SN74126N	44
SN7403N	22	SN74128N	59
SN7404N	22	SN74132N	69
SN7405N	23	SN74136N	75
SN7406N	23	SN74139N	95
SN7407N	23	SN74141N	79
SN7408N	26	SN74142N	2 95
SN7409N	23	SN74143N	2 95
SN7410N	22	SN74144N	2 95
SN7411N	29	SN74145N	62
SN7412N	29	SN74147N	1 95
SN7413N	39	SN74148N	1 20
SN7414N	59	SN74150N	1 09
SN7416N	29	SN74151N	67
SN7417N	29	SN74152N	67
SN7420N	22	SN74153N	67
SN7421N	35	SN74154N	1 19
SN7422N	29	SN74155N	78
SN7423N	29	SN74156N	78
SN7425N	29	SN74157N	69
SN7426N	29	SN74158N	1 65
SN7427N	25	SN74160N	88
SN7429N	45	SN74161N	88
SN7430N	23	SN74162N	89
SN7432N	29	SN74163N	87
SN7437N	25	SN74164N	87
SN7438N	29	SN74165N	87
SN7439N	29	SN74166N	1 20
SN7440N	19	SN74167N	1 95
SN7441N	79	SN74170N	1 69
SN7442N	57	SN74172N	4 75
SN7443N	95	SN74173N	79
SN7444N	95	SN74174N	89
SN7445N	79	SN74175N	85
SN7446N	79	SN74176N	75
SN7447N	65	SN74177N	75
SN7448N	79	SN74179N	1 34
SN7450N	19	SN74180N	75
SN7451N	19	SN74181N	1 75
SN7453N	19	SN74182N	75
SN7454N	19	SN74184N	2 25
SN7459N	25	SN74185N	2 25
SN7460N	23	SN74186N	9 95
SN7470N	29	SN74188N	3 90
SN7472N	29	SN74190N	1 15
SN7473N	34	SN74191N	1 15
SN7474N	34	SN74192N	85
SN7475N	38	SN74193N	85
SN7476N	34	SN74194N	85
SN7479N	4 60	SN74195N	68
SN7480N	49	SN74196N	85
SN7482N	95	SN74197N	85
SN7483N	55	SN74198N	1 39
SN7485N	65	SN74199N	1 39
SN7486N	35	SN74221N	1 19
SN7489N	1 75	SN74251N	95
SN7490N	39	SN74273N	1 05
SN7491N	57	SN74279N	75
SN7492N	45	SN74283N	1 40
SN7493N	45	SN74284N	3 90
SN7494N	69	SN74285N	3 90
SN7495N	65	SN74290N	1 25
SN7496N	69	SN74298N	95
SN7497N	2 90	SN74365N	68
SN74100N	1 20	SN74366N	68
SN74107N	32	SN74367N	68
SN74109	37	SN74368N	68
SN74116N	1 95	SN74390N	1 45
SN74121N	29	SN74393N	1 90
SN74121N	29	SN74393N	1 90
SN74122N	39	SN74490N	1 90

74LS00

74LS00N	$ 26	74LS164N	$ 1 19
74LS01N	28	74LS165N	89
74LS02N	28	74LS166N	2 48
74LS03N	28	74LS168N	1 15
74LS04N	35	74LS169N	1 15
74LS05N	28	74LS170N	1 99
74LS08N	28	74LS173N	89
74LS09N	35	74LS174N	89
74LS10N	28	74LS175N	89
74LS11N	39	74LS181N	2 20
74LS12N	33	74LS190N	1 15
74LS13N	47	74LS191N	1 15
74LS14N	95	74LS192N	98
74LS15N	33	74LS193N	98
74LS20N	26	74LS194N	1 15
74LS21N	33	74LS195N	95
74LS22N	33	74LS196N	89
74LS26N	33	74LS197N	89
74LS27N	33	74LS21N	1 15
74LS28N	33	74LS240N	1 69
74LS30N	26	74LS241N	1 69
74LS32N	33	74LS242N	1 69
74LS33N	55	74LS243N	1 69
74LS37N	45	74LS244N	1 49
74LS38N	39	74LS245N	2 20
74LS40N	26	74LS247N	1 10
74LS42N	79	74LS248N	1 10
74LS47N	79	74LS249N	1 19
74LS48N	95	74LS251N	1 40
74LS51N	26	74LS253N	1 40
74LS54N	29	74LS257N	85
74LS55N	29	74LS258N	98
74LS73N	45	74LS259N	2 95
74LS74N	42	74LS260N	85
74LS75N	59	74LS261N	2 49
74LS76N	45	74LS266N	59
74LS78N	45	74LS273N	1 75
74LS83AN	79	74LS275N	4 40
74LS85N	1 19	74LS279N	59
74LS86N	45	74LS283N	99
74LS90N	57	74LS290N	99
74LS92N	75	74LS293N	99
74LS93N	75	74LS295N	1 10
74LS95N	88	74LS298N	1 19
74LS96N	98	74LS324N	1 75
74LS107N	45	74LS347N	1 95
74LS109N	45	74LS348N	1 95
74LS112N	43	74LS352N	1 19
74LS113N	43	74LS353N	1 19
74LS114N	43	74LS363N	1 49
74LS122N	55	74LS365N	69
74LS123N	1 19	74LS366N	69
74LS124N	1 35	74LS367N	69
74LS125N	89	74LS368N	69
74LS126N	52	74LS373N	1 69
74LS132N	79	74LS374N	1 69
74LS136N	49	74LS375N	69
74LS138N	85	74LS377N	1 95
74LS139N	85	74LS385N	1 95
74LS145N	1 25	74LS386N	65
74LS148N	1 49	74LS390N	1 95
74LS151N	79	74LS393N	1 95
74LS153N	79	74LS395N	1 70
74LS154N	1 70	74LS399N	2 35
74LS155N	1 19	74LS424N	2 95
74LS156N	99	74LS668N	1 75
74LS157N	85	74LS670N	2 29
74LS158N	75	81LS95N	1 69
74LS160N	1 05	81LS96N	1 69
74LS161N	1 15	81LS97N	1 69
74LS162N	1 05	81LS98N	1 69
74LS163N	1 05		

TOLL FREE ORDER LINE
800-854-8230
TWX: 910-595-1565

Mail Order: P.O. Box 17329 Irvine, CA 92713 (800) 854-8230
Retail: 1310 B E. Edinger, Santa Ana, CA 92705 (714) 558-8813
542 W. Trimble, San Jose, CA 95131 (408) 946-7010

ADVANCED COMPUTER PRODUCTS

Circle 10 on inquiry card.

Unclassified Ads

UNCLASSIFIED POLICY: Readers who are soliciting or giving advice, or who have equipment to buy, sell or swap should send in a clearly typed notice to that effect. To be considered for publication, an advertisement must be clearly noncommercial, typed double spaced on plain white paper, contain 75 words or less, and include complete name and address information.

These notices are free of charge and will be printed one time only on a space available basis. Notices can be accepted from individuals or bona fide computer users clubs only. We can engage in no correspondence on these and your confirmation of placement is appearance in an issue of BYTE.

Please note that it may take three or four months for an ad to appear in the magazine.

BOMB
BYTE's Ongoing Monitor Box

Article #	Page	Article	Author(s)
1	32	A Generic Word Processor	Schrodt
2	40	Use Infrared Communication for Remote Control	Ciarcia
3	50	How to Use Color Displays Effectively	Durrett, Trezona
4	56	A Human-Factors Case Study Based on the IBM Personal Computer	Cooper, Marston, Durrett, Stimmel
5	76	The Hewlett-Packard Interface Loop (HPIL)	Katz
6	96	Strawberry Tree's Dual Thermometer Card for the Apple	Murray
7	108	A Human-Factors Style Guide for Program Design	Simpson
8	134	The Atari Tutorial, Part 8: Generating Sound with Software	Fraser
9	158	A Po(r)tpourri of Ideas	Barden
10	186	The Input/Output Primer, Part 3: The Parallel and HPIB (IEEE-488) Interfaces	Leibson
11	212	User's Column: The Osborne 1, Zeke's New Friends, and Spelling Revisited	Pournelle
12	242	Designing the Star User Interface	Smith, Irby, Kimball, Verplank, Harslem
13	284	Designing a Text Editor? The User Comes First	Jong
14	302	Managing Words: What Capabilities Should You Have with a Text Editor?	Finseth
15	312	Two Word Processors for North Star	Coudal
16	322	A Disk Operating System for FORTH	Reece
17	371	Selector IV by Micro-Ap	Abbott
18	380	MOD III: TRS-80 Features for Your Model I	Rocke
19	398	Binary-Coded Text, A Text-Compression Method	Tropper
20	439	Career Opportunities in Computing	Johnston
21	447	Converting Apple DOS to Pascal Text Files	Matthews
22	464	A Simple Multiprocessor Implementation	Harrington
23	472	An Introduction to NSC Tiny BASIC	Handy

IBM Leads Ciarcia Two Sets to Love

Once again, our BOMB-card mail bin has overflowed with responses to an article on IBM's Personal Computer. "A Closer Look at the IBM Personal Computer" by Gregg Williams outstripped all other articles in the January issue and ran away with first place. Our congratulations to Gregg for a first-rate review. Second-place prize of $50 goes to Jerry Pournelle for his User's Column entitled "Operating Systems, Languages, Statistics, Pirates, and the Lone Wolf." Steve Ciarcia has to settle for third place this month. (Sorry, Steve, but no matter how we counted, you still came up third.)

Reader Service

To get further information on the products advertising in BYTE, fill out the reader service card with your name and address. Then circle the appropriate numbers for the advertisers you select from the list. Add an 18-cent stamp to the card, then drop it in the mail. Not only do you gain information, but our advertisers are encouraged to use the marketplace provided by BYTE. This helps us bring you a bigger BYTE. The index is provided as an additional service by the publisher, who assumes no liability for errors or omissions. *Correspond directly with company.

Reader Service

**Correspond directly with company.*

National Advertising Sales Representatives:

Northeast (617) 444-3946
ME, NH, VT, MA, CT, RI, DE, MD, VA, WV, OK, TX, Upstate NY, Eastern Canada

Hajar Associates
280 Hillside Ave.
Needham Heights, MA 02194

Mid Atlantic (201) 741-7744
NY, NYC, NJ, PA

Hajar Associates
321 Broad St.
Red Bank, NJ 07701

Southeast (305) 628-3525
NC, SC, GA, FL, AL, MS, TN, KY

Hajar Associates
Diplomate Bldg.
5400 Diplomate Circle
Suite 272
Orlando, FL 32810

Midwest (312) 966-0160
MN, WI, MI, IA, IL, IN, OH, MO, NE, KS, ND, SD, AR

Hajar Associates
5225 Old Orchard Rd.
Suite 50
Skokie, IL 60076

Northwest (415) 964-0706
AK, HI, WA, OR, ID, MT, WY, Northern California, Nevada Except Las Vegas, Western Canada

Hajar Associates
1000 Elwell Ct.
Suite 124
Palo Alto, CA 94303

Southwest (714) 540-3554
UT, CO, AZ, NM, Las Vegas, Southern California

Hajar Associates
3303 Harbor Blvd.
Suite H-4A
Costa Mesa, CA 92626

European Advertising Sales Representatives:

Simon Smith
McGraw-Hill
34 Dover St.
London W1X 3RA, England
01 493 1451

Andrew Karnig
Andrew Karnig & Associates
Kungsholmsgatan 10
112 27 Stockholm, Sweden

Hans Csokor
Publimedia
Velthgasse 6/3
A-1037 Vienna, Austria

Fritz Krusebecker
Liebigstrasse 27c
D-6000 Frankfurt/Main 1
West Germany

Michael Sales
17 rue Georges Bizet
F 75116 Paris, France

A. Fabio Guarnieri
Via Bracchini 1
20123 Milan, Italy

Mrs. Gurit Gepner
115 Yosephtal St.
Bat Yam, Israel

APRIL 1982
4142

BYTE READER SERVICE

For fastest service transfer mailer label from wrapper to coupon provided at the right. Requests cannot be honored unless zip code is given. This card valid for 90 days only. **NOTE**—If label is missing or defaced fill out coupon carefully—**PLEASE PRINT**—this is the only way to get requested material to you.

Name ______________________________

(Title) ______________ (Company) ______________

Address ______________________________

City ______________ State ________ Zip ________

1	21	41	61	81	101	121	141	161	181	201	221	241	261	281	301	321	341	361	381	401	421	441	461	481	501	521	541	561	581	601	621	641	661	681
2	22	42	62	82	102	122	142	162	182	202	222	242	262	282	302	322	342	362	382	402	422	442	462	482	502	522	542	562	582	602	622	642	662	682
3	23	43	63	83	103	123	143	163	183	203	223	243	263	283	303	323	343	363	383	403	423	443	463	483	503	523	543	563	583	603	623	643	663	683
4	24	44	64	84	104	124	144	164	184	204	224	244	264	284	304	324	344	364	384	404	424	444	464	484	504	524	544	564	584	604	624	644	664	684
5	25	45	65	85	105	125	145	165	185	205	225	245	265	285	305	325	345	365	385	405	425	445	465	485	505	525	545	565	585	605	625	645	665	685
6	26	46	66	86	106	126	146	166	186	206	226	246	266	286	306	326	346	366	386	406	426	446	466	486	506	526	546	566	586	606	626	646	666	686
7	27	47	67	87	107	127	147	167	187	207	227	247	267	287	307	327	347	367	387	407	427	447	467	487	507	527	547	567	587	607	627	647	667	687
8	28	48	68	88	108	128	148	168	188	208	228	248	268	288	308	328	348	368	388	408	428	448	468	488	508	528	548	568	588	608	628	648	668	688
9	29	49	69	89	109	129	149	169	189	209	229	249	269	289	309	329	349	369	389	409	429	449	469	489	509	529	549	569	589	609	629	649	669	689
10	30	50	70	90	110	130	150	170	190	210	230	250	270	290	310	330	350	370	390	410	430	450	470	490	510	530	550	570	590	610	630	650	670	690
11	31	51	71	91	111	131	151	171	191	211	231	251	271	291	311	331	351	371	391	411	431	451	471	491	511	531	551	571	591	611	631	651	671	691
12	32	52	72	92	112	132	152	172	192	212	232	252	272	292	312	332	352	372	392	412	432	452	472	492	512	532	552	572	592	612	632	652	672	692
13	33	53	73	93	113	133	153	173	193	213	233	253	273	293	313	333	353	373	393	413	433	453	473	493	513	533	553	573	593	613	633	653	673	693
14	34	54	74	94	114	134	154	174	194	214	234	254	274	294	314	334	354	374	394	414	434	454	474	494	514	534	554	574	594	614	634	654	674	694
15	35	55	75	95	115	135	155	175	195	215	235	255	275	295	315	335	355	375	395	415	435	455	475	495	515	535	555	575	595	615	635	655	675	695
16	36	56	76	96	116	136	156	176	196	216	236	256	276	296	316	336	356	376	396	416	436	456	476	496	516	536	556	576	596	616	636	656	676	696
17	37	57	77	97	117	137	157	177	197	217	237	257	277	297	317	337	357	377	397	417	437	457	477	497	517	537	557	577	597	617	637	657	677	697
18	38	58	78	98	118	138	158	178	198	218	238	258	278	298	318	338	358	378	398	418	438	458	478	498	518	538	558	578	598	618	638	658	678	698
19	39	59	79	99	119	139	159	179	199	219	239	259	279	299	319	339	359	379	399	419	439	459	479	499	519	539	559	579	599	619	639	659	679	699
20	40	60	80	100	120	140	160	180	200	220	240	260	280	300	320	340	360	380	400	420	440	460	480	500	520	540	560	580	600	620	640	660	680	700

BYTE'S BOMB is your direct line to the editor's desk. Each month, the two top-rated authors receive bonuses based on your votes. To cast your vote, first look at the list of this month's articles and corresponding article numbers (located in the unclassified ads section on the page preceding the Reader Service list), then rate each article as **Excellent, Good, Fair,** or **Poor** by circling the appropriate number in each column below. Your feedback helps to produce the best possible magazine each month.

Article No.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
Excellent	801	805	809	813	817	821	825	829	833	837	841	845	849	853	857	861	865	869	873	877	881	885	889	893	897
Good	802	806	810	814	818	822	826	830	834	838	842	846	850	854	858	862	866	870	874	878	882	886	890	894	898
Fair	803	807	811	815	819	823	827	831	835	839	843	847	851	855	859	863	867	871	875	879	883	887	891	895	899
Poor	804	808	812	816	820	824	828	832	836	840	844	848	852	856	860	864	868	872	876	880	884	888	892	896	900

Comments ______________________________

APRIL 1982
4142

BYTE READER SERVICE

For fastest service transfer mailer label from wrapper to coupon provided at the right. Requests cannot be honored unless zip code is given. This card valid for 90 days only. **NOTE**—If label is missing or defaced fill out coupon carefully—**PLEASE PRINT**—this is the only way to get requested material to you.

Name ______________________________

(Title) ______________ (Company) ______________

Address ______________________________

City ______________ State ________ Zip ________

1	21	41	61	81	101	121	141	161	181	201	221	241	261	281	301	321	341	361	381	401	421	441	461	481	501	521	541	561	581	601	621	641	661	681
2	22	42	62	82	102	122	142	162	182	202	222	242	262	282	302	322	342	362	382	402	422	442	462	482	502	522	542	562	582	602	622	642	662	682
3	23	43	63	83	103	123	143	163	183	203	223	243	263	283	303	323	343	363	383	403	423	443	463	483	503	523	543	563	583	603	623	643	663	683
4	24	44	64	84	104	124	144	164	184	204	224	244	264	284	304	324	344	364	384	404	424	444	464	484	504	524	544	564	584	604	624	644	664	684
5	25	45	65	85	105	125	145	165	185	205	225	245	265	285	305	325	345	365	385	405	425	445	465	485	505	525	545	565	585	605	625	645	665	685
6	26	46	66	86	106	126	146	166	186	206	226	246	266	286	306	326	346	366	386	406	426	446	466	486	506	526	546	566	586	606	626	646	666	686
7	27	47	67	87	107	127	147	167	187	207	227	247	267	287	307	327	347	367	387	407	427	447	467	487	507	527	547	567	587	607	627	647	667	687
8	28	48	68	88	108	128	148	168	188	208	228	248	268	288	308	328	348	368	388	408	428	448	468	488	508	528	548	568	588	608	628	648	668	688
9	29	49	69	89	109	129	149	169	189	209	229	249	269	289	309	329	349	369	389	409	429	449	469	489	509	529	549	569	589	609	629	649	669	689
10	30	50	70	90	110	130	150	170	190	210	230	250	270	290	310	330	350	370	390	410	430	450	470	490	510	530	550	570	590	610	630	650	670	690
11	31	51	71	91	111	131	151	171	191	211	231	251	271	291	311	331	351	371	391	411	431	451	471	491	511	531	551	571	591	611	631	651	671	691
12	32	52	72	92	112	132	152	172	192	212	232	252	272	292	312	332	352	372	392	412	432	452	472	492	512	532	552	572	592	612	632	652	672	692
13	33	53	73	93	113	133	153	173	193	213	233	253	273	293	313	333	353	373	393	413	433	453	473	493	513	533	553	573	593	613	633	653	673	693
14	34	54	74	94	114	134	154	174	194	214	234	254	274	294	314	334	354	374	394	414	434	454	474	494	514	534	554	574	594	614	634	654	674	694
15	35	55	75	95	115	135	155	175	195	215	235	255	275	295	315	335	355	375	395	415	435	455	475	495	515	535	555	575	595	615	635	655	675	695
16	36	56	76	96	116	136	156	176	196	216	236	256	276	296	316	336	356	376	396	416	436	456	476	496	516	536	556	576	596	616	636	656	676	696
17	37	57	77	97	117	137	157	177	197	217	237	257	277	297	317	337	357	377	397	417	437	457	477	497	517	537	557	577	597	617	637	657	677	697
18	38	58	78	98	118	138	158	178	198	218	238	258	278	298	318	338	358	378	398	418	438	458	478	498	518	538	558	578	598	618	638	658	678	698
19	39	59	79	99	119	139	159	179	199	219	239	259	279	299	319	339	359	379	399	419	439	459	479	499	519	539	559	579	599	619	639	659	679	699
20	40	60	80	100	120	140	160	180	200	220	240	260	280	300	320	340	360	380	400	420	440	460	480	500	520	540	560	580	600	620	640	660	680	700

To get further information on the products advertised in BYTE, fill out the reader service card with your name and address. Then circle the appropriate numbers for the advertisers you select from the list. Add a 13-cent stamp to the card, then drop it in the mail. Not only do you gain information, but our advertisers are encouraged to use the marketplace provided by BYTE. This helps us bring you a bigger BYTE. The index is provided as an additional service by the publisher, who assumes no liability for errors or omissions. *Correspond directly with company.

PLACE
STAMP
HERE



READER SERVICE
PO BOX 298
DALTON, MA 01226
USA

PLACE
STAMP
HERE

BYTE

READER SERVICE
PO BOX 298
DALTON, MA 01226
USA

BYTE SUBSCRIPTIONS

For a subscription to BYTE, please complete this card.

Name ______________________________

Address ______________________________

City ______________________________

State __________ Zip ________ Country ______________

Card No. ______________________________

Expiration date ______________________________

Four digits above name—Master Charge only ______________

Signature ______________________ Date __________

Please allow eight weeks for processing. Thank you.

	USA	Canada Mexico
☐ 1 year	☐ $19	☐ $21
☐ 2 years	☐ $34	☐ $38
☐ 3 years	☐ $49	☐ $55

☐ $43 Europe (air delivery) payment enclosed
☐ $35 Elsewhere (surface mail) payment enclosed
(Air mail rates available upon request)

Please remit in US funds drawn on a US bank. Thank you.

☐ Check enclosed (**Bonus:** [North America only] one EXTRA issue—receive 13 issues for the price of 12)

☐ Master Charge ☐ VISA

☐ Bill me (North America only)

4142

BYTE SUBSCRIPTIONS

For a subscription to BYTE, please complete this card.

Name ______________________________

Address ______________________________

City ______________________________

State __________ Zip ________ Country ______________

Card No. ______________________________

Expiration date ______________________________

Four digits above name—Master Charge only ______________

Signature ______________________ Date __________

Please allow eight weeks for processing. Thank you.

	USA	Canada Mexico
☐ 1 year	☐ $19	☐ $21
☐ 2 years	☐ $34	☐ $38
☐ 3 years	☐ $49	☐ $55

☐ $43 Europe (air delivery) payment enclosed
☐ $35 Elsewhere (surface mail) payment enclosed
(Air mail rates available upon request)

Please remit in US funds drawn on a US bank. Thank you.

☐ Check enclosed (**Bonus:** [North America only] one EXTRA issue—receive 13 issues for the price of 12)

☐ Master Charge ☐ VISA

☐ Bill me (North America only)

4142

Note our special offer! Send cash with your order and receive 13 issues for the price of 12 for each year you subscribe. (North America only, please)

Don't Miss An Issue!

Have BYTE delivered to your door.

Each month BYTE will bring you the latest in microcomputer technology.

DISCOVER and IMPLEMENT new ideas. Don't miss the original information presented in the pages of BYTE.

With BYTE you'll always be among the first to know about the important breakthroughs, worthwhile new equipment, and innovative projects in the world of computing.

CHALLENGE US to deliver the very best ideas in microcomputers and advanced technology to you. Return the attached card today!


Subscribe to BYTE—the world's leading computer magazine.

PLACE
STAMP
HERE



PLACE
STAMP
HERE





On the new, slicked-up, trimmed-down Starwriter F-10.

It's C. Itoh's latest generation of letter-quality printers.

It cranks out flawless copy at 40 cps; and its full 15″ carriage lets it double in brass for both letter processing and business applications. You can plug it into almost any micro on the market (serial or parallel) simply by plugging it in. And then make it keep on trucking with inexpensive, easily available Diablo compatible daisy wheels and ribbons.

In its serial mode, it can print just about anything (including boldface, underlines, subscripts and superscripts), and snap the carriage back to start the next line in less than a second. In its line mode, it prints in both directions, for even faster throughput.

(While making about as much noise as a cat walking on Kleenex.)

It's a nice, portable 30 pounds—about 10 pounds lighter than the Starwriters before it. And it stands exactly as tall (or precisely as small) as a dollar bill.

Speaking of which:

Incredibly, the Starwriter F-10 sells for about the same preposterously low price as its predecessors. Which is to say, about $800 less than a lot of other printers that don't even come close to measuring up. Or even better...

Measuring down.

Distributed Exclusively by Leading Edge Products, Inc., 225 Turnpike Street, Canton, Massachusetts 02021. Call: toll-free 1-800-343-6833; or in Massachusetts call collect (617) 828-8150. Telex 951-624.

LEADING EDGE.

Circle 232 on inquiry card.

Radio Shack Has Everything You Need for Your TRS-80®



A **File Boxes for Your Diskettes.** Two open and shut cases for protecting 5¼″ or 8″ floppies. Holds 50-60, with index dividers. Durable acrylic.
For 5¼″ Diskettes. #26-1453, **$29.95**
For 8″ Diskettes. #26-4953, **$39.95**

B **Disk Drive Head Cleaning Kit.** Helps prevent read/write errors. Easy and safe — just apply solution to a cleaning diskette (two included) and run it in drive for 30 seconds.
For 5¼″ Drives. #26-407, **$29.95**
For 8″ Drives. #26-4909, **$29.95**

C **Genuine TRS-80 Diskettes.** Best you can buy. Certified error-free. Extra-long life, double density, soft sector.
5¼″ Single Diskette. #26-305, **$4.95**
5¼″ Three-Pack. #26-405, **$13.95**
5¼″ Ten-Pack. #26-406, **$39.95**
8″ Single Diskette. #26-4905, **$7.50**
8″ Ten-Pack. #26-4906, **$59.95**

D **Diskette Library Cases.** Protection against dust and curling. An easel insert pops-up for easy selection. Holds ten floppies. Polystyrene.
For 5¼″ Diskettes. Gray. #26-1452, **$3.95**
For 8″ Diskettes. Brown. #26-4952, **$4.95**

E **Anti-Glare Mask.** Solves reflection problems. No loss of resolution. For TRS-80 Models I, II and III. Not for color monitors. #26-511, **$16.95**

F **Anti-Static Spray.** Prevents static electricity build-up that can attract dust and damage equipment. Apply to accessories, video display and carpet. 16 ounces. #26-515, **$5.95**

G **Printviewer.** Magnifies and highlights a single line of your printout. Reduces errors. Clear plastic with yellow "line window." Includes 10 and 12 cpi scales. #26-1313, **$2.95**

H **Logic Flowchart Template.** This durable, clear-plastic "stencil" with ANSI flowchart symbols and 1/10″ lay-out grid makes it easy to draw pro-quality charts. #26-1312, **$3.95**

I **Stacking Data Trays.** For standard 14⅞″-wide printouts. Eliminates damage to paper caused by using an undersized tray. #26-1309, **each $6.95**

Radio Shack®
The biggest name in little computers™
A DIVISION OF TANDY CORPORATION

Prices may vary at individual stores and dealers. Some items may require special order.

And there's much more! Send for your free Radio Shack TRS-80 Computer Catalog today!

Mail To: Radio Shack, Dept 82-A-129
1300 One Tandy Center, Fort Worth, Texas 76102

NAME ____________________
ADDRESS ____________________
CITY ________ STATE ________ ZIP ________

Circle 352 on inquiry card.